APRIL 12, 1979

ELECTRO 79: A GLIMPSE OF THE 1980s/162

A versatile design component: analog divider ICs/120

How to use PROMs for sequential controllers/134

FOUR DOLLARS A McGRAW-HILL PUBLICATION

50 YEARS

Electronics®

SPECIAL REPORT

LITHOGRAPHY AIMS AT VLSI



Bourns SIP Trimmers Come in Small Packages...

And save you valuable space.

Model 20 SIP trimmers save you precious PC board space, yet don't cost a fortune. Only .785" X .185" X .079" in size, the Model 20 SIP trimmer occupies just 25% of the board space used by comparable DIP configurations and 50% of that used by conventional ¾-inch rectangular trimmers. The low board profile of .185-inches and .100-inch spacing are ideal for meeting all of your high density PC board trimmer needs.

Priced at only 75¢* in 1,000 to 4,999 quantities, Model 20 SIP trimmers are available in 18 standard resistance values ranging from 10 ohms to 5 megohms. Options of either hand or machine insertion, plus compatibility with automatic test equipment add up to more cost savings yet.

There's no sacrifice in performance either. Sealed to withstand industrial cleaning processes,

Model 20 SIP trimmers have a low tempco of 100 ppm/°C over −55°C to +125°C temperature range. Power rating is 0.50 watts at 70°C. The stable cermet element offers infinite resolution. The wiper assembly idles at both ends of travel, eliminating damage from forced adjustment.

Put these little jewels to work for you. Dramatic space savings, the ring of Bourns quality, and sparkling performance, too. Contact your local Bourns representative for evaluation samples or send today for complete details. Or, see EEM directory, Volume 2, pages 3804, 3805.

TRIMPOT PRODUCTS DIVISION, BOURNS, INC., 1200 Columbia Avenue, Riverside, CA 92507. Phone: 714 781-5050. TWX: 910 332-1252.

European Headquarters: Bourns AG, Zugerstrasse 74 6340 Baar, Switzerland. Phone: 042 33 33 33. Telex: 78722.

*Domestic U.S.A. price only.



BOURNS®

For Immediate Application—Circle 120 For Future Application—Circle 220

Step up to excellence. Step up to Series E.

Why settle for anything less than excellence. Especially now that it's available at a very affordable price in Series E from Hewlett-Packard—five precision calculators for science, engineering and business starting at just $60.*

EXCELLENCE BY DESIGN. Experience the HP difference in Series E: a new larger display with commas for easy reading; built-in diagnostic systems that help catch errors; RPN logic for ease-of-use and efficiency; a complete documentation system—Owners' Manual and Applications Books; plus a host of HP extras—low battery warning light, rechargeable batteries, positive feedback keys, sturdy impact-resistant case. In sum—excellence by design.

A SERIES E FOR EVERY NEED. Series E gives you more power and features at a lower price than any comparable calculator HP has ever offered. You'll find them all outstanding values:

HP-31E. Scientific. $60.*

HP-32E. Advanced Scientific with Statistics. $80.*

HP-33E. Programmable Scientific. $100.*

HP-37E. Business Management. $75.*

HP-38E. Advanced Financial with Programmability. $120.*

SEE YOUR HP DEALER. For details, send in the coupon or visit your nearest HP dealer. For the name and address, CALL TOLL-FREE 800-648-4711 except from Alaska or Hawaii. In Nevada, call 800-992-5710.

HEWLETT hp PACKARD

Dept. 214U, 1000 N. E. Circle Blvd., Corvallis, OR 97330

HEWLETT-PACKARD
Dept. 214U
1000 N.E. Circle Blvd.
Corvallis, OR 97330

Please send details on Series E:

_____ Business Calculators

_____ Scientific Calculators

Name _____

Address _____

City _____

State _____ Zip _____

*Suggested retail price excluding applicable state and local taxes—Continental U.S.A., Alaska and Hawaii.

Displays photographed separately to simulate typical appearance.

#619/03

Circle 1 on reader service card.



Now OEM's can draw high quality graphics even when the bottom line is price.

Graphics gives you the best way to analyze and communicate data. But cost has been keeping it out of the picture for many OEM systems. That's why Hewlett-Packard is offering the new Model 7225A Graphics Plotter.

The price: $1750 (domestic USA price with 17602A general purpose "personality" module), in quantities of five. With further OEM discounts from there.



Plug-in "personality modules" customize the plotter for you.

HP's versatile 7225A converts the output of processor based systems into high quality charts and graphs in any size up to 8½ x 11" (A4). A wide selection of plug-in "personality modules" lets you adapt the plotter to suit your needs. Different modules determine interface hardware, language, and capabilities such as internal character sets, axis generation, labeling and scaling.

Simple linear stepping motors eliminate many moving parts to assure reliability. Visually smooth, high resolution ink lines of any length and angle are generated, requiring only end point data.

And you give your customers the confidence of Hewlett-Packard's worldwide service network.

So if you want high quality graphics but you draw the line at price, look into the Model 7225A Graphics Plotter. For a detailed 24-page OEM brochure, contact Hal Phillips at Hewlett-Packard, 16399 West Bernardo Drive, San Diego, CA 92127; (714) 487-4100. 11901

HEWLETT hp PACKARD

1501 Page Mill Road, Palo Alto, California 94304

For assistance call: Washington (301) 948-6370, Chicago (312) 255-9800, Atlanta (404) 955-1500, Los Angeles (213) 877-1282

Circle 2 on reader service card

Electronics

The International Magazine of Electronics Technology

Vol. 52, No. 8 • April 12, 1979

39 **Electronics Review**
PACKAGING & PRODUCTION: New design doubles Multiwire density, 39
MEDICAL: Artificial arm checks on waveform of body's signals, 40
CAREERS: No razzle-dazzle, but lots of jobs at Electro79, 40
MILITARY: Navy tests Loral's radar warning unit, 41
PERIPHERALS: Displays head for under-$1,000 target, 42
COMMUNICATIONS: E-Systems readies a voice coder, 44
MEMORIES: Mostek's 64-K RAM pinout follows Motorola's, 46
TRADE: Message to Japan: open up the NTT market, 46
MICROWAVES: Test ranges stir citizens' ire, 48
COMPANIES: Intel sets up plants in Phoenix, 50
NEWS BRIEFS: 50
LASERS: RCA boosts stability of planar diode 52

63 **Electronics International**
WEST GERMANY: Trip computer gets smarter and more capable, 67
GREAT BRITAIN: Coding scheme sends data by tone signals, 68
FRANCE: Transpac starts up, wants small users, too, 70
GREAT BRITAIN: Sub hunter goes digital, 72

81 **Probing the News**
COLLISION AVOIDANCE: Can we prevent midair crashes? 81
MEDICAL: Microwaves help detect tumors, 85
CONSUMER: Auto stereo is a hot market, 88
SOLID STATE: Semiconductor makers reach a crossroads, 90
ABROAD: East, West meet at West German TV maker, 94

105 **Technical Articles**
PACKAGING & PRODUCTION: Lithography chases shrinking line, 105
COMPONENTS: Analog ICs perform accurate computations, 120
DESIGNER'S CASEBOOK: Regulator has low dropout voltage, 130
Missing-pulse detector handles variable frequencies, 131
Charge pump cuts compandor's attack time, 133
MICROSYSTEMS: PROM controller makes fast work of serial jobs, 134
TEST & MEASUREMENT: Monitoring chip-package bond quality, 141
ENGINEER'S NOTEBOOK: Circuit computes frequency differential, 148
8-channel scanner multiplexes data for strip-chart recorder, 149
Reducing a PLL's even-order harmonics, 150
ELECTRO79: Agenda for the 1980s, 162

179 **New Products**
ELECTRO79 PRODUCT PREVIEW:
RCA unveils first five computer boards, 179
System acquires 250,000 samples per second, 180
Adjustable bandpass filter has sharp cutoff, 182
Operational power supply works six ways, 182
Data-acquisition unit resolves 16 bits, 185
Low-cost analyzers test Z80s and 8085s, 187
V-f converters have small footprints, 188
Audio distortion analyzer is easy to use, 190
Handheld multimeter race gets tighter, 196
Single-step board speeds debugging, 198
Cinch gets into flat-cable market, 202
IN THE SPOTLIGHT: Array (processor) of hope for slow computers, 209
COMPONENTS: Triac driver is driven by logic, 215
INSTRUMENTS: LCD thermometer computes, too, 226
MICROCOMPUTERS & SYSTEMS: Small firm uses big bubbles, 238
DATA ACQUISITION: Z80-based system offers flexibility, 252
INDUSTRIAL: Weighing system displays five digits, 265
COMPUTERS & PERIPHERALS: System grows to fit big picture, 274
MATERIALS: 298

Departments

Publisher's letter, 4
Readers' comments, 6
News update, 8
People, 14
Editorial, 24
Meetings, 26
Electronics newsletter, 33
Washington newsletter, 57
Washington commentary, 58
International newsletter, 63
Engineer's newsletter, 154
Products newsletter, 297
New literature, 308

Services

Employment opportunities, 310
Reprints available, 337
Reader service card, 337

Highlights

Cover: In pursuit of the submicrometer line, 105
The chip density demanded by very large-scale integration is pushing the development of lithographic techniques. Mask making seems likely to remain the prerogative of electron-beam systems, but the X-ray approach is more promising for mass production, says this special report.

Cover is by Associate Art Director Charles Ciatto.

Can microprocessors stop midair collisions? 81
The Federal Aviation Administration is investigating new microprocessor-based airborne collision-avoidance systems that would be capable of cooperating with ground-based air traffic control.

Electro79 looks beyond the chip, 162
The technical sessions this year will focus on software manufacture, industrial control networks, personal computers—everywhere except on semiconductor technology, notes this special report.

Analog dividers attain hybrid status, 120
Profiting from the recent advances in integrated-circuit technology and design, analog dividers now come in dual in-line packages costing less than $20 each yet achieve great accuracy: error can be held to 0.1% over a 1,000/1 denominator voltage.

. . . and in the next issue
Two more special reports: the Electronic Components Conference previewed, and fast static random-access memories . . . an interface chip for the IEC bus.

Electronics

EDITOR-IN-CHIEF: Kemp Anderson

EXECUTIVE EDITOR: Samuel Weber

MANAGING EDITORS: Arthur Erikson, Gerald M. Walker

ASSISTANT MANAGING EDITORS: Howard Wolff, Alfred Rosenblatt

SENIOR EDITORS: William F. Arnold, Ray Connolly

ART DIRECTOR: Fred Sklenar

DEPARTMENT EDITORS
Aerospace/Military: Ray Connolly
Circuit Design: Vincent Biancomano
Communications & Microwave: Harvey J. Hindin
Components: Nicolas Mokhoff
Computers: Anthony Durniak
Consumer & Industrial: John Javetski
Instrumentation: Albert F. Shackil
Microsystems & Software: John G. Posa
New Products: Michael J. Riezenman, Richard W. Comerford
Packaging & Production: Jerry Lyman
Solid State: Raymond P. Capece

CHIEF COPY EDITOR: Margaret Eastman

COPY EDITORS: Mike Robinson, Charlotte Wiggers, Jeremy Young

ART: Charles D. Ciatto, *Associate Director*
Paula Piazza, *Assistant Director*

EDITORIAL SECRETARIES: Janet Noto, Penny Reitman, Maryann Tusa

EDITORIAL ASSISTANT: Marilyn B. Steinberg

REGIONAL EDITORS
New York: Ben Mason (212) 997-2245
Boston: James B. Brinton
Pamela Hamilton (617) 262-1160
Chicago: Larry Marion (312) 751-3805
Dallas: Wesley R. Iversen (214) 742-1747
Los Angeles: Larry Waller (213) 487-1160
Palo Alto: William F. Arnold
Robert Brownstein (415) 968-2712
Washington: Ray Connolly (202) 624-7592
Frankfurt: John Gosch
London: Kevin Smith
Paris: Arthur Erikson
Tokyo: Charles Cohen

McGRAW-HILL WORLD NEWS
Editor: Michael Johnson
Brussels: James Smith
Milan: Jeff Ryser
Moscow: Peter Hann
Paris: Kenneth Dreyfack
Stockholm: Robert Skole
Tokyo: Robert E. Lee

PUBLISHER: Paul W. Reiss

GENERAL MANAGER, DIRECT MARKETING OPERATIONS: Horace T. Howland

CIRCULATION MANAGER: Herbert A. Hunter

RESEARCH MANAGER: Margery D. Sholes

READER SERVICE MANAGER: Frances M. Vallone

Publisher's letter

With this issue *Electronics* enters its 50th year of publication, marking a half century in which the industry has grown from essentially a radio and broadcast business into the most pervasive and influential technology in the world.

The design shown above and on the cover symbolizes our pride in having been a part of this history. It will appear on the magazine for the next 12 months, leading up to our commemoration next April of the 50th anniversary of *Electronics*.

Dan McMillan, for 10 years the publisher of *Electronics*, has become our corporate boss: he's been promoted to a group vice president of the McGraw-Hill Publications Co. During his time as publisher Dan earned an international reputation as an incisive industry observer and a superb manager.

It's customary in taking over a successful operation to say that it will be a tough act to follow—and it will indeed. However, Dan leaves behind him a topnotch team. Together, we intend to carry on the high standards he set as we move into the next 50 years.

Lithography is undoubtedly the foundation of the VLSI age, as the special report (p. 105) by packaging and production editor Jerry Lyman underscores. He has been following the development of fine-line lithography and reporting on it since VLSI was merely a gleam in device designers' eyes. In the course of preparing this article, Jerry donned more white gowns, hats, and shoes to enter the clean rooms than he had ever expected. Our bureau managers in Europe and Japan had similar white room experiences preparing their contributions to this report.

As he passed through those dust-defying rooms, Jerry was struck by the change in lithographic techniques in just two years. Step-and-repeat equipment, which was only being discussed a few years ago, is now firmly entrenched. He sees this type of equipment turning up everywhere.

"One point I heard over and over," Jerry reports. "The 1-micrometer production processing nut may take much longer to crack than the lithography nut. Except for chip processing going on at a couple of R&D labs, we are not quite there yet."



April 12, 1979 Volume 52, Number 8 100,295 copies of this issue printed

Electronics (ISSN 0013-5070). Published every other Thursday by McGraw-Hill, Inc. Founder: James H. McGraw 1860-1948. Publication office 1221 Avenue of the Americas, N.Y., N.Y. 10020; second class postage paid at New York, N.Y. and additional mailing offices.

Executive, editorial, circulation and advertising addresses: Electronics, McGraw-Hill Building, 1221 Avenue of the Americas, New York, N.Y. 10020. Telephone (212) 997-1221. Teletype 12-7960 TWX 710-581-4879. Cable address: M C G R A W H I L L N E W Y O R K.

Subscriptions limited to professional persons with active responsibility in electronics technology. No subscriptions accepted without complete identification of subscriber name, title or job function, company or organization, and product manufactured or services performed. Based on information supplied, the publisher reserves the right to reject non-qualified requests. Subscription rates: in the United States and possessions $17 one year, $29 two years, $43 three years; company addressed and company libraries $23 one year, $41 two years, $58 three years; APO/FPO addressed $35 one year only; Canada and Mexico $19 one year, $32 two years, $47 three years; Europe $46 one year, $78 two years, $110 three years; Japan, Israel and Brazil $70 one year, $115 two years, $165 three years; Australia and New Zealand $95 one year, $170 two years, $240 three years, including air freight; all other countries $50 one year, $85 two years, $125 three years. Limited quota of subscriptions available at higher-than-basic rate for persons allied to field served. Check with publisher for these rates. Single copies: $4.00. Please allow four to eight weeks for shipment.

Officers of McGraw-Hill Publications Company: Gordon L. Jones, President; Group Vice-President: Daniel A. McMillan, Senior Vice-Presidents: Russell F. Anderson; Ralph R. Schulz, Editorial; Vice-Presidents: James E. Hackett, Controller; Thomas H. King, Manufacturing; Robert L. Leyburn, Circulation; John W. Patten, Sales; Edward E. Schirmer, International.

Officers of the Corporation: Harold W. McGraw, Jr., President, Chief Executive Officer, and Chairman of the Board; Robert N. Landes, Senior Vice President and Secretary; Ralph J. Webb, Treasurer.

Title registered in U.S. Patent Office; Copyright© 1979 by McGraw-Hill, Inc. All rights reserved. The contents of this publication may not be reproduced in whole or in part without the consent of copyright owner.

Where necessary, permission is granted by the copyright owner for libraries and others registered with the Copyright Clearance Center (CCC) to photocopy any article herein for the base fee of $0.50 per copy of the article plus $0.25 per page. Payment should be sent directly to the CCC. Copying done for other than personal or internal reference use without the express permission of McGraw-Hill is prohibited. Requests for special permission or bulk orders should be addressed to the publisher.

ISSN 0013-5070/79$0.50+.25.

Subscribers: The publisher, upon written request to our New York office from any subscriber, agrees to refund that part of the subscription price applying to copies not yet mailed. Please send change-of-address notices or complaints to Fulfillment Manager; subscription orders to Circulation Manager, Electronics, at address below. Change-of-address notices should provide old as well as new address, including zip codes. Attach address label from recent issue. Allow one month for change to become effective. Subscriber Service: call (609) 448-8110, 9 a.m. to 4 p.m. EST.

Postmaster: Please send form 3579 to Fulfillment Manager, Electronics, P.O. Box 430, Hightstown, N.J. 08520.

KEPCO/TDK switchers have guts!



RMX Size D Switching Power Supply cover removed to expose its guts.

The KEPCO/TDK Series RMX, Size D Power Supply offers a lot of guts neatly arranged in a compact, 270-cubic-inch box that will fit nicely into your project. Ask your local Kepco man to let you try it on for size.

MODEL	VOLTS	AMPS @ 50°C
RMX 05-D	3.5-5.5	60A
RMX 09-D	6.3-9.9	32A
RMX 12-D	8.4-13.2	27A
RMX 15-D	10.5-16.5	23A
RMX 24-D	16.8-26.4	16A
RMX 28-D	19.6-30.8	13.7A



Typical for Model RMX 05-D, 5-Volt Switching Power Supply

KEPCO® For complete specifications write Dept. BWF 14

KEPCO, INC. · 131-38 SANFORD AVENUE · FLUSHING, N.Y. 11352 U.S.A. · (212) 461-7000 · TWX #710-582-2631 · Cable: KEPCOPOWER NEWYORK

SIGNAL GENERATOR AMPLIFIER

Our Model 603L is the ultimate in RF signal generator amplifiers. Just plug this low cost unit into any signal or sweep generator in its 0.8 to 1000 MHz range and this completely solid state unit will provide you with the maximum in power flexibility.



With a flat frequency response and 3 watts of linear Class A output (up to 5 watts saturated), the 603L will provide constant forward power, making it ideal for driving reactive or resistive loads.

Priced at $1895*, the versatility and usefulness of this outstanding power amplifier can best be demonstrated in your own applications.

For detailed specifications or a demonstration, please contact:

ENI
3000 Winton Road South
Rochester, New York 14623
Call: 716-473-6900 or
Telex: 97-8283 ENI ROC

* U.S.A.

ENI

The World's Leader in Power Amplifiers

Readers' comments

Some friend?

To the Editor: Leo Young's defense of the Professional Activities Committee workshops run by the Institute of Electrical and Electronics Engineers' U. S. Activities Board [Readers' Comments, Feb. 1, p. 6] is not unexpected, given his long record as an apologist for the IEEE's establishment.

There is another action that reveals the bankruptcy of the U. S. Activities Board. This board, of which Dr. Young is so proud, has refused a request from 62 Sperry engineers, who were fired as a result of alleged age bias, that it file a "friend of the court" brief in their lawsuit.

We working American EEs deserve far better from our professional society.

Irwin Feerst
Committee of Concerned EEs
Massapequa Park, N. Y.

Not ready

To the Editor: Contrary to the impression conveyed by your story "Wiring system rivals multilayer, Multiwire" [Feb. 1, p. 74], representatives of Laboratoire d'Electronique et de Technologie de l'Informatique (LETI) have informed us that they have not yet reached a point where the K6 process is ready for commercial development.

Furthermore, a recent meeting with them confirmed our considered opinion that the K6 process and concept depend on the use of technology covered by certain claims in Kollmorgen's Multiwire patents. Accordingly, we are conducting discussions with LETI that we hope will lead to a satisfactory resolution of the proprietary issues.

William P. Sharpe
PCK Technology Division
Kollmorgen Corp.
Glen Cove, N. Y.

1978 Index ready

The index of articles published in Electronics *in 1978, which was previously announced in the March issues, is now available. For a free copy, please circle 340 on the reader service card.*

bel delay lines

- Digital
- Programmable
- DIP

TTL DTL Compatible

BEL FUSE INC.
203E Van Vorst st. Jersey City N.J.
07302 (201) 432-0463
TWX 710-730-5301

Circle 78 on reader service card

FORECLOSURE
AUCTION

TELENEUTRONICS
Whitefish, Montana
TUESDAY, APRIL 24th
12:30 P.M.

Thousands of Dollars Valuation of Rectifiers, Capacitors, Resistors & Other Electronic Components, Parts & Supplies.

Patent Pending #808,865 for the "Extension I" telephone system & 7 "Extension I" telephones in various stages of completion.

Specialized Electronic Tools

Shop & Office Equipment & More

"Phone or Write for Brochure"

RADCLIFFE AUCTION COMPANY
6525 N. FEDERAL — DENVER, COLO. 80221 — (303) 428-7568

Circle 79 on reader service card

Last year, this $1000 device convinced over 300 companies they could cut the high cost of digital troubleshooting.

Company after company is becoming convinced that it can significantly reduce the huge costs involved in microprocessor troubleshooting by using HP's signature analysis technique. The savings on board inventories alone can run into hundreds of thousands of dollars. In brief, it is now possible for a modestly trained technician to accurately troubleshoot microprocessor boards right down to the component level in the field or on the production line.

A simple concept.
Subtle errors in the lengthy bit streams of microprocessor-based products are definitive clues to component failures which cause them. But lengthy bit streams are very tedious and costly to examine by traditional means.

HP's 5004A Signature Analyzer solves this problem by compressing lengthy bit streams into short, four-digit, hexa-decimal signatures that quickly and accurately lead right to the failed component.

Just activate a digital exercise routine in the circuit under test and compare the bit stream signature at each data node with the known good signatures previously written into your service manual. Digital signal tracing now becomes as simple as analog tracing used to be. But more accurate. So accurate that it catches almost every possible fault, including many that can be detected in no other way. It once again becomes realistic to think of field or production troubleshooting to the component level by technicians.

Design it in or retrofit.
The savings in service costs and spare circuit board inventory are well worth the effort of designing with signature analysis in mind. It could possibly eliminate the need to partition your product for modular service. In some cases, it could even pay you to "retrofit" by developing exercise circuitry and a signature manual for your existing equipment. It's a fascinating—and very workable—concept. Amazingly the price of the HP 5004A Signature Analyzer that makes all this possible is a low $990.*

To help you make the most of this breakthrough we've prepared Application Note 222—"A Designer's Guide to Signature Analysis." Contact your nearest HP field sales office or write for your copy today. *price, domestic U.S.A. only

HEWLETT hp PACKARD

1507 Page Mill Road, Palo Alto, California 94304

02823

For assistance call: Washington (301) 258-2000, Chicago (312) 255-9800, Atlanta (404) 955-1500, Los Angeles (213) 877-1282

New possibilities for your Printed Circuit Board

WIMA Miniature Capacitors



WIMA MKS 2 with a PCM of 5 mm

The new miniatures from WIMA help you to save space on your Printed Circuit Boards and can be utilised everywhere. They are the smallest plastic cased, metallised polyester Capacitors available.

Capacitance values 0.01 — 0.47 µF (1 µF with 7.5 mm PCM.)

WIMA FKS 2 from 1000 pF.

All capacitors are resistant to moisture.

Please ask for our special catalogue.

WIMA®

WILH. WESTERMANN

Spezialvertrieb elektron. Bauelemente
P. O. Box 2345 · D-6800 Mannheim 1
Fed. Rep. of Germany

U.S. Sales Offices:
BOSL & ROUNDY · 3333, Delray Drive
Ft. Wayne · Indiana 46815
(219) 483-3378

THE INTER-TECHNICAL GROUP INC.
North Dearman Street · P. O. Box 23
Irvington · New York 10533
(914) 591-8822

TAW ELECTRONICS CO.
4215 W. Burbank Blvd., Burbank
California 91505 · (213) 846-3911

8 Circle 8 on reader service card

News update

■ Downtown Boston has a fine, new retail store. Surburban Framingham, Mass., also has a new shopping place. But the merchandise in each of these stores is unusual for the average window-shopper. Digital Equipment Corp. of Maynard, Mass., is displaying small-business computer systems in the Boston store, whereas The Computer Store Inc. in Framingham has Apple computers for personal use and Data General microNovas for business applications. Although not the first attempts at computer retailing, these stores do mark a growing trend to take computers directly to the user [*Electronics*, March 31, 1977, p. 89].

DEC opened its first retail store in a mall in Manchester, N. H., last August, and business has been booming ever since, according to Jonah Kalb, merchandising manager for retail products. "We're essentially selling computer systems for small businesses and professional offices. Computer systems range from $11,400 to $13,000," he says. The second store, in Boston, opened in February, and "early results are encouraging."

Richard Brown, president of The Computer Store Inc. in Burlington, Mass., notes that his store does very little hobbyist business, "although many of my customers are first-time users." The latest store opening, in Framingham in March, coincides with a growing trend to personal computer sales. Brown opened his first store in February 1976 and now has three stores and several franchise outlets operating.

Out West. Not all the action is on the East Coast, however. The first retail computer store to open is still doing a brisk business in Santa Monica, Calif.

Dick Heiser, president of the Computer Store—no relation to the eastern stores with the same name—has been in business since July 1975 and thinks he will be for quite a while. "The personal computer business is growing" fast, he notes.

"We'll keep adding new products as they become available," he says. The store now carries products from 50 companies. **-Pamela Hamilton**

DON'T GET BENT OUT OF SHAPE OVER QUARTZ CRYSTALS.

WRITE OR CALL

SE

Savoy Electronics, Inc.

Manufacturers of Quality Quartz Crystals Since 1937

Dept. EM. P.O. Box 5727
Fort Lauderdale, Florida 33310
305/563-1333 • TWX 510 955 9766
IN CALIFORNIA:
714/968-5166 • TWX 910 595 2259

Circle 81 on reader service card

PROFESSIONAL DISCOUNTS

TEXAS INSTRUMENTS electronic calculators

TI-25	$27.95	TI-5025	$74.95
TI-50	33.50	TI-5040	89.95
TI-55	43.95	TI-5100	39.95
TI-57	49.95	Programmer	48.95
TI-58	95.79	MBA	57.95
TI-59	219.95	Business Analyst II	39.95
TI-58/59 Libraries	28.95	Speak and Spell	48.95
TI-30-SP	17.95	Spelling Bee	28.95
SR-40	21.95	DataMan	18.95
PC-100C	146.95	DataCard	24.95
TI-1030	16.95	DataClip	27.95
TI-1750-LCD	19.95	Little Professor	12.59
TI-1790	39.95	Alarm Clock	28.95
TI-5015	62.95	Chrono Alarm	89.95

Ask for TI Digital Watches!

HEWLETT hp PACKARD

HP-10	$139.95	HP-97	$600.00
HP-19C	184.95	HP-31-E	49.95
HP-29C	144.95	HP-32-E	65.95
HP-67	360.00	HP-33-E	82.95
HP-92	399.95	HP-37-E	61.95
		HP-38-E	110.00

We are HP's authorized franchise dealer — all accessories are professionally discounted

Also Casio, Canon, APF, Sharp, Lexicon (NEW), NSC Seiko, Citizen, Craig, Sanyo, Norelco-Phillips, Pearlcorder SCM, Olivetti, Record-a-Call, Code-a-Phone Apple, Atari, Boris, Chesschallenger Randix Midex

ALL AT GREAT PRICES!

WE WILL BEAT OR MEET ANY COMPETITOR'S PRICE IF HE HAS MERCHANDISE ON HAND. *All units shipped in original factory cartons with accessories according to manufacturers' specifications.* **CALL TOLL FREE (800) 854-0523)** (outside CA) or (714)549-7373 (within CA). BankAmericard, Visa and MasterCharge; money order; pers. ck. (2 Wks. to clear); COD accepted. Add $4.95 for shipping in USA. We ship AIR on request. CA residents add 6% sales tax. All merchandise subject to availability. Prices good only with this ad for limited time only. Send mail orders to DEPT. EL-d 12 **WRITE OR CALL FOR FREE CATALOG.**

computique

3211 South Harbor Blvd., Santa Ana, CA 92704
4 Stores in California – CALL:
(714) 549-7373 (800) 854-0523

Circle 82 on reader service card

"Talk about

OPEN FRAMES

NUMBER 1 IN OPEN FRAMES



ONLY POWER-ONE OFFERS THESE EXCLUSIVE FEATURES:

QUALITY • Two-Year Warranty — fully transferable to your customer • Two-Hour Burn-in — plus *two* full functional tests on every unit • UL Recognized, CSA Certified
SERVICE • 83 Standard Stocked Models — the industry's largest selection • Local Stocking Centers Nationwide — stocked for immediate delivery
ECONOMY • The industry's most cost-effective D.C. power supplies • Liberal discounts for quantity buyers

SINGLE OUTPUT — STANDARD

±.02% REGULATION • REMOTE SENSING

VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9
5	3.0	B5-3	$24.95	12	1.7	B15-1.5	$24.95	18	1.3	B24-1.2	$24.95	24	1.2	B24-1.2	$24.95
	6.0	C5-6	44.95		3.4	C15-3	44.95		2.6	C24-2.4	44.95		2.4	C24-2.4	44.95
	12.0	D5-12	74.95		6.8	D15-6	74.95		5.2	D24-4.8	74.95		4.8	D24-4.8	74.95
	18.0	E5-18	104.95		10.2	E15-9	104.95		7.8	E24-7.2	104.95		7.2	E24-7.2	104.95
6	3.0	B5-3	$24.95	15	1.5	B15-1.5	$24.95	20	1.3	B24-1.2	$24.95				
	6.0	C5-6	44.95		3.0	C15-3	44.95		2.6	C24-2.4	44.95	—	—	—	—
	12.0	D5-12	74.95		6.0	D15-6	74.95		5.2	D24-4.8	74.95				
	18.0	E5-18	104.95		9.0	E15-9	104.95		7.8	E24-7.2	104.95				

SINGLE OUTPUT — HI-VOL

115/230 VAC INPUT • OVP ON 5V MODELS

VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9	VOLTS	AMPS	MODEL	PRICE 1-9
2	3.0	HB2-3	$29.95	12	0.5	HA15-0.5	$22.95	24	1.2	HB24-1.2	$24.95	48	0.5	HB48-0.5	$29.95
	6.0	HC2-6	49.95		1.7	HB12-1.7	24.95		2.4	HC24-2.4	44.95		1.0	HC48-1	49.95
	12.0	HD2-12	79.95		3.4	HC12-3.4	44.95		3.6	HN24-3.6	64.95		3.0	HD48-3	79.95
	18.0	HE2-18	109.95		5.1	HN12-5.1	64.95		4.8	HD24-4.8	74.95		4.0	HE48-4	109.95
5	1.2	HA5-1.2/OVP*	$22.95		6.8	HD12-6.8	74.95		7.2	HE24-7.2	104.95				
	3.0	HB5-3/OVP*	24.95		10.2	HE12-10.2	104.95								
	6.0	HC5-6/OVP*	49.95	15	0.5	HA15-0.5	$22.95	28	1.0	HB24-1.2	$24.95	180, 200	0.12	HB200-0.12	$34.95
	9.0	HN5-9/OVP*	69.95		1.5	HB15-1.5	24.95		2.0	HC28-2	44.95				
	12.0	HD5-12/OVP*	79.95		3.0	HC15-3	44.95		3.0	HN28-3.0	64.95				
	18.0	HE5-18/OVP*	114.95		4.5	HN15-4.5	64.95		4.0	HD28-4	74.95				
					6.0	HD15-6	74.95		6.0	HE28-6	104.95	250	0.1	HB250-0.1	$34.95
					9.0	HE15-9	104.95								

SINGLE OUTPUT — HIGH POWER

115/230 VAC INPUT • OVP ON 5V MODELS

VOLTS	AMPS	MODEL	PRICE 1-9
5	25.0	F5-25/OVP*	$149.00
	35.0	G5-35/OVP*	185.00
12	16.0	F15-15	$149.00
15	15.0	F15-15	$149.00
24	12.0	F24-12	$149.00
28	10.0	F24-12	$149.00

SINGLE OUTPUT — HIGH EFFICIENCY

EFFICIENCY UP TO 66% • RELIABLE LINEAR DESIGN

VOLTS	AMPS	EFFICIENCY @ NOMINAL LINE	MODEL	PRICE 1-9
5	9	66%	RD5-15/OVP*	$ 99.95
	12	63%		
	15	60%		
5	14	63%	RE5-23/OVP*	$130.00
	18	60%		
	23	57%		
5	25	63%	RG5-40/OVP*	$220.00
	32	60%		
	40	57%		

DUAL OUTPUT — STANDARD

TRACKING REGULATORS • ±.02% REGULATION

MODEL	OUTPUT #1	OUTPUT #2	PRICE 1-9
AA15-0.8	12V @ 1.0A or 15V @ 0.8A	−12V @ 1.0A or −15V @ 0.8A	$42.95
BB15-1.5	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A	$53.95
CC15-3.0	12V @ 3.4A or 15V @ 3.0A	−12V @ 3.4A or −15V @ 3.0A	$84.95

DUAL OUTPUT — HI-VOL

115/230 VAC INPUT • OVP ON 5V MODELS

MODEL	OUTPUT #1	OUTPUT #2	PRICE 1-9
±12 to 15V			
HAA15-0.8	12V @ 1.0A or 15V @ 0.8A	−12V @ 1.0A or −15V @ 0.8A or −5V @ 0.4A	$39.95
HBB15-1.5	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A or −5V @ 0.7A	49.95
HCC15-3.0	12V @ 3.4A or 15V @ 3.0A	−12V @ 3.4A or −15V @ 3.0A	79.95
±18 to 24V			
HAA24-0.6	18-20V @ 0.4A or 24V @ 0.6A	(−)18-20V @ 0.4A or −24V @ 0.6A	$39.95
±5V			
HBB5-3/OVP	5V @ 3.0A*	−5V @ 3.0A*	$61.95
HCC5-6/OVP	5V @ 6.0A*	−5V @ 6.0A*	92.95
5V and 9-15V (Isolated Outputs)			
HAA512	5V @ 2.0A*	9-15V @ 0.5A	$44.95
HBB512	5V @ 3.0A*	9-15V @ 1.25A	54.95
HCC512	5V @ 6.0A*	9-15V @ 2.5A	86.95

TRIPLE OUTPUT — STANDARD

TRACKING REGULATORS • ±.02% REGULATION

MODEL	OUTPUT #1	OUTPUT #2	OUTPUT #3	PRICE 1-9
BAA-40W	5V @ 3.0A	12V @ 1.0A or 15V @ 0.8A	−12V @ 1.0A or −15V @ 0.8A	$ 69.95
CBB-75W	5V @ 6.0A	12V @ 1.7A or 15V @ 1.5A	−12V @1.7A or −15V @ 1.5A	$ 91.95
DBB-105W	5V @ 12.0A	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A	$126.95

TRIPLE OUTPUT — HI-VOL

115/230 VAC INPUT • OVP ON 5V MODELS

MODEL	OUTPUT #1	OUTPUT #2	OUTPUT #3	PRICE 1-9
HTAA-16W	5V @ 2.0A*	9-15V @ 0.4A	(−)9-15V @ 0.4A or −5V @ 0.2A	$ 49.95
HBAA-40W	5V @ 3.0A*	12V @ 1.0A or 15V @ 0.8A	−12V @ 1.0A or −15V @ 0.8A or −5V @ 0.4A	$ 69.95
HCBB-75W	5V @ 6.0A*	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A or −5V @ 0.7A	$ 91.95
CP-131	5V @ 8.0A*	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A or −5V @ 0.7A	$110.00
HDBB-105W	5V @ 12A*	12V @ 1.7A or 15V @ 1.5A	−12V @ 1.7A or −15V @ 1.5A or −5V @ 0.7A	$126.95
HDCC-150W	5V @ 12A*	12V @ 3.4A or 15V @ 3.0A	−12V @ 3.4A or −15V @ 3.0A	$149.00

FLOPPY-DISK SERIES

SINGLE/DUAL DRIVE MODELS • FOR 5.25" & 8.0" MEDIA DRIVES

DISK-DRIVE MODEL	OUTPUT RATINGS				PRICE 1-9
	+5V*	−5V*	+12V AVG./PK	+24V AVG./PK	
+5V and +12V					
CP-249	0.7A		1.1A/1.7A		$ 39.95
+24V and ±5V					
CP-205	1A	0.5A		1.5A/1.7A	$ 69.95
CP-206	2.5A	0.5A		3.0A/3.4A	$ 91.95
CP-162	3A	0.6A		5A/6A	$120.00

*INCLUDES BUILT-IN OVP, SET @ 6.2V ±0.4V.

NEW CATALOG!

Get Your FREE Copy Now!

Phone us direct or circle the reader service number below.

"Think about

power-one INC.

D.C. POWER SUPPLIES

Power One Drive • Camarillo, CA 93010 • (805) 484-2806 • TWX 910-336-1297

Circle 9 on reader service card

SIMPLE ANSWERS TO COMPLEX PROBLEMS

MORE ANSWERS FROM INTERSIL

Better applications of proven circuits. Applications that offer lower circuit cost, increased reliability and simplified circuit design. Make your own comparison from the diagrams below.

LOW COST 12-BIT μP A/D CONVERTER



At $10 a copy, the ICL7109 A/D converter offers a price breakthrough in true 12-bit performance. Interfacing directly with a μP or UART, the ICL7109 can provide on-location conversion of analog signals. And, power requirements are typical of CMOS. Low.

PART #	100 PIECE PRICE
ICL7109CPL	$10.00
IM6402-1IPL	$ 4.50

CMOS 6-DIGIT STOPWATCH



The ICM7215 is a totally integrated stopwatch that directly drives LED's. The circuit provides for four modes of timing function. Applications include sports timing, darkroom timers, process control timers and elapsed time accumulation. Available in 24-pin plastic DIP only.

PART #	100 PIECE PRICE
ICM7215IPG	$9.29

12-BIT SUCCESSIVE APPROXIMATION REGISTER



Convert 12 bits fast. With the AD7521/AM2504 chip pair. 8-bit SAR's are also available. Specify AM2502 for parallel outputs or AM2503 for serial applications.

PART #		100 PIECE PRICE
AM2504PC	12-bit SAR	$ 7.00
AM2502PC	8-bit parallel SAR	$ 4.75
AM2503PC	8-bit serial SAR	$ 4.75
AD7521LN	12-bit DAC	$12.50

70V MONOLITHIC POWER DRIVER



Chop the cost of a complete servo amplifier to ≈$7.95. Increase reliability. Reduce parts count. With the ICL8063, you can build a high performance, output protected amplifier with minimum board space at reduced cost.

PART #	100 PIECE PRICE
ICL8063CPE	$2.13

TRIPLE LOW POWER OP AMP



Save power and space with the ICL8023 triple OP AMP. Each amplifier is individually programmable and will operate down to ±1.0V and 8μA per amplifier. Available in single, dual or triple OP AMPs.

PART #		100 PIECE PRICE
ICL8021CPA	(Single)	$1.34
ICL8022CPD	(Dual)	$4.25
ICL8023CPE	(Triple)	$4.80

LOW COST ANALOG SWITCHES



The IH5009 through IH5024 are a complete family of low cost 1, 2, 3 and 4-channel analog switches capable of interfacing with either 15V or TTL logic. No external power supplies are required.

PART #		100 PIECE PRICE
IH5009CPD	(Quad SPST, high level logic)	$3.25
IH5010CPD	(Quad SPST, TTL logic)	$3.25
And many more...		$2.25 up

CMOS REFERENCE GENERATOR



Drawing only 0.25mA, the ICM7213 CMOS crystal-controlled clock generates 1 pulse per second and 1 pulse per minute. The circuit is excellent for low speed system timing, clocks, industrial sequencing and other timing applications. Available in 14-pin plastic DIP only.

PART #	100 PIECE PRICE
ICM7213IPD	$3.15

DIELECTRICALLY-ISOLATED MATCHED FETs



Dielectrically-isolated dual FETs (DIFETS) combine the low parasitic leakage current and interdevice capacitance of discrete duals with the tight offset matching and tracking of monolithics. Available in quantity. Now.

PART #	100 PIECE PRICE
IMF5911	$4.95
IMF5912	$3.75

THE PROBLEM WITH PROBLEMS IS ANSWERS

At Intersil, we know there are better ways to do things. You're looking for them. We're looking for them. Devices and applications that cut system cost, reduce design time and board population while increasing reliability. If you'd like more information on any of the devices above, or all of them, call your Intersil Sales Office or Franchised Distributor. Or, return the coupon below.

INTERSIL SALES OFFICES

CALIFORNIA: Sunnyvale (408) 744-0618, Long Beach (213) 436-9261 • COLORADO: Aurora (303) 750-7004 • FLORIDA: Fort Lauderdale (305) 772-4122 • ILLINOIS: Hinsdale (312) 986-5303 • MASSACHUSETTS: Lexington (617) 861-6220 • MINNESOTA: Minneapolis (612) 925-1844 • NEW JERSEY: Englewood Cliffs (201) 567-5585 • OHIO: Dayton (513) 866-7328 • TEXAS: Dallas (214) 387-0539 • CANADA: Brampton, Ontario (416) 457-1014

INTERSIL FRANCHISED DISTRIBUTORS

Advent/Indiana • Alliance Electronics • Arrow Electronics • Bell Industries/Century Electronic Division • CESCO • Component Specialties Inc. • Components Plus • Diplomat Electronics Inc., (FLA) • Diplomat Electronics Inc., (NJ) • Harvey Federal Electronics • Intermark Electronics • Kierulff Electronics • LCOMP • Parrott Electronics • R.A.E. Ind. Elect. Ltd. • RESCO/ Raleigh • Schweber Electronics • Sheridan Associates • Summit Distributors Inc. • Wyle Distribution Group • Zentronics Ltd.

E41279

INTERSIL

Analog Products
10710 No. Tantau Ave., Cupertino, CA 95014
Tel: (408) 996-5000 TWX: 910-338-0171
(800) 538-7930 (Outside California)



Gentlemen:

Problems I've got. Answers I need. Please send me product information on the following devices: _____, _____, _____, _____, _____, _____, _____, _____

_____ Please send me your Victor Hugo Poster.

Name _____

Company _____

Address _____

City _____ State _____ Zip _____

23 YEARS OF REASONS TO LOOK TO FLUKE FOR PRECISION MEASUREMENTS.

Calibration is a sophisticated business, and it requires sophisticated instrumentation and proven techniques. At the same time, instrumentation must bring greater efficiency to the calibration task.

Fluke has been a leader in the calibration and standards business for 23 years. During that period, we have not altered the integrity of our line of precision measurement instruments, while introducing instruments to make your calibration tasks easier.

* *

1955: Fluke introduces the world's first DC differential voltmeter.

Over 23 years ago, we began building differential voltmeters — in most instances setting new standards for the industry. Here are four.

The 893A is an AC/DC differential voltmeter routinely used as a secondary lab standard. DC accuracy is ±0.01% with infinite input impedance from 0 to ±1100 VDC. AC accuracy is ±0.05%.

The 887AB and 895A differential voltmeters both achieve a DC accuracy of 25 parts per million for 60 days, and both offer a resolution of 1μV. The 887AB also has outstanding AC specifications.

The 931B is a true RMS differential voltmeter designed for rapid measurements of AC waveforms to within ±0.05% regardless of their shape. Frequency response extends to 2MHz.



"I wouldn't expect anything less than a long and distinguished history."

1957: Fluke introduces ultra-stable DC calibrator.

Two years after introducing differential voltmeters, we expanded our precision measurement line to include DC calibrators. Now Fluke provides a full range of instruments for all DC calibration needs. Here are three.

The 343A is a seven-dial, 20 ppm DC calibrator that provides parameters of stability, temperature range and response time required by a wide range of applications.

The 382A operates as a combination ±0.01% voltage calibrator and a ±0.02% current calibrator. It offers voltage outputs to 50V and current capabilities to 2A.

The 335D provides 10 ppm accuracy as both a DC voltage standard and a differential voltmeter.

1963: Fluke introduces standards.

We started it all in 1963; now the 540B stands by itself in the industry. It is a primary standard thermal transfer device for NBS traceable measurement and calibration of AC voltage and current. Measurement capability is 0.25V to 1000 Vrms over 14 ranges, with a frequency range from 5 Hz to 1 MHz.

The 510A is a precision fixed-frequency sinewave voltage source suited to calibration or test applications. Outputs are 10 Vrms at 10 mA with available frequencies from 50 Hz to 100 kHz.

The 731B DC transfer standard is an electronic standard cell designed to give metrology people a portable working DC standard. The 731B can be hand-carried anywhere and subjected to severe environmental conditions.

And look at the 515A portable calibrator. This lightweight precision calibration source is ideal for on-site calibration of measuring instruments. With four DC voltage ranges, three AC ranges, resistance capability from 10Ω to 10 MΩ and a rechargeable battery pack, you can perform eight hours of field calibration.

1966: Fluke introduces DC calibration systems.

Eleven years after we introduced our first precision measurement instrument, we offered the Fluke-designed 7105A system.

Accuracy to 5 ppm is standard in this DC voltage and ratio calibra-



893A, 931B, and 895A differential voltmeters.



335D, 343A, and 382A DC calibrators.

tion system, with resolution and ratio accuracy to 0.1 ppm.

In a functional self-contained enclosure, the 7105A offers voltmeter and power supply calibration capability, a differential voltmeter, ratio calibrator and a null detector.

The system is self-calibrating, and is supplied with certificates of traceability to the NBS.

1972: Fluke introduces AC calibration system.

We entered the market with a fully programmable AC calibration setup. Together, the 5200A precision ±0.02% AC calibrator and the 5205A precision power amplifier can calibrate AC devices up to 1200 Vrms. Frequency range is 10 Hz to 1.2 MHz.

The calibrators interface easily with almost any system. Field installable IEEE 488 and parallel isolated programming options are available.

1977: Fluke introduces the cal lab in a box.

In this year, we introduced the first "calibration laboratory in a box."

Our new 5100A/5101A calibrators can calibrate VTVMs, VOMs, 3½- and 4½-digit DMMs in a fraction of the time it takes you now, unless — of course — you're already using one!

The heart of these calibrators is a microprocessor, eliminating mechanical switch failure and providing large systems flexibility at a fraction of the previous cost.

Both calibrators supply AC and DC to 1100 volts, with a DC accuracy of 50 ppm and AC bandwidth of from 50 Hz to 50 kHz standard. AC/DC current to 1.99999 amps and decade resistance values from 1Ω to 10 MΩ at cardinal points.

Optional IEEE interface puts either calibrator in your total calibration systems. The 5101A's built-in cassette tape deck lets you store calibration and test programs and perform them error-free under microprocessor control.

The microprocessor also provides error computation in percent or dB, full scale or fraction of full scale.

1978: Fluke introduces the most advanced DMM.

Our 8502A microprocessor-based DMM, a total systems instrument, has uniquely enhanced bench capability as well.

The 8502A measures DC volts and amps, AC volts and amps (RMS or averaging), resistance (two or four terminal measurements) and performs AC or DC ratio. The 8502A has microprocessor control, computational capability, 6½-digit resolution, 6 ppm accuracy (DC volts), limits, peak reading, cal-memory, zero memory, digital filtering, diagnostic routines and IEEE 488, RS232C, and full parallel interfaces. The 8502A has them all; other DMMs only have some!

All functions are front panel controlled as well as remotely (systems) programmable.

NOW: For more information, contact one of the more than 100 Fluke offices and representatives worldwide, or CALL (800) 426-0361*, TOLL FREE. In the U.S. and countries outside Europe, write: John Fluke Mfg. Co., Inc., P.O. Box 43210, Mountlake terrace, WA 98043, U.S.A.

In Europe, contact Fluke (Nederland) B.V., P.O. Box 5053, Tilburg, The Netherlands. Telephone: (013) 673973. Telex: 52237.

*Alaska, Hawaii, Washington residents — please call (206) 774-2481.

The 8502A μP-controlled DMM.



7105A DC calibration system.

5200A AC calibrator and 5205A power amplifier.



731B, 510A, 540B standards.

515A meter calibrator and the 5101A "cal lab in a box."

COMMAND PERFORMANCE: DEMAND FLUKE.

FLUKE®

Circle #13 for demonstration

Circle #12 for literature



NEW JEDEC Standard "Chip Carrier" Test Sockets

VERSATILE TEXTOOL SERIES ACCEPTS ALL JEDEC STANDARD CHIP CARRIERS

This versatile new TEXTOOL "chip carrier" test socket series includes off-the-shelf models to accept all JEDEC Standard carriers with from 16 to 84 leads and body sizes up to and including 1.250" square on .050" centers.

In addition, only minor tooling changes allow the socket also to accept JEDEC Standard .040" center packages or virtually any other non-standard chip carrier.

A positive locking system enables loading and unloading literally with the fingers.

A new lid design allows the same socket to accept packages ranging from .050 to .100" thick, interchangeably.

Other significant features of TEXTOOL'S new "chip carrier" sockets include a lid design that eliminates shorting against contacts or P.C. board and which will not separate from the socket body under normal usage, integral mounting holes and minimum lid overhang at the back of the socket to permit maximum P.C. board mounting density.

All TEXTOOL "chip carrier" sockets are ideally suited for both test and burn-in applications and are available in a wide variety of materials to meet specific test requirements.

Detailed information on these and other products in a wide choice of materials from TEXTOOL . . . IC, MSI and LSI sockets and carriers, power semiconductor test sockets, and custom versions . . . is available from your nearest TEXTOOL sales representative or the factory direct.

TEXTOOL

PRODUCTS, INC.
1410 W. Pioneer Drive • Irving, Texas 75061
214/259-2676

People

Motorola's Jarrat to decide on fast Schottky logic

Henri Jarrat of Motorola Inc.'s Integrated Circuits division, Phoenix, admits to sitting in a pretty good spot for dealing his firm into what looks like a big-stakes semiconductor pot for the 1980s. The pot involves fast Schottky logic, and the situation is this: two firms, Texas Instruments and Fairchild Camera and Instrument, are taking the lead, each with a somewhat different type of fast Schottky logic for computers [*Electronics*, Feb. 1, p. 88].

"Both lines have merit," Jarrat says diplomatically, but neither can prevail yet, an opinion neutral observers also hold. What will tip the scale decisively is another major semi house—Motorola, for instance—backing one or the other by second sourcing. Until then, "it could be a mess, with the industry heading in different directions," comments the director of Motorola's bipolar operations.

As for his fast-Schottky trump card, he notes, "We have the technology base in our hands to do either one and crank out devices in a matter of weeks." So what is holding up the decision? "We are still talking to key fast-Schottky customers," answers the French-born Jarrat. "Then we will decide, for certain before the second half is over."

Analysis. If it's TI, the issue will be settled quickly, he predicts, but if the Fairchild parts win, then the Texas firm's vaunted staying power could make it a horse race for a while. Generally, evaluation shows TI with somewhat better performance specs, but Fairchild with a manufacturing edge in getting them into the field.

In TI's case, the youthful-looking, 40-year-old Jarrat surely knows whereof he speaks. He came from Texas Instruments in 1977 shortly after Alfred J. Stein also came from there to take over Motorola's integrated-circuit operations. A hard-driving executive out of Stein's mold, he has pushed his bipolar troops hard since being named to his job in early 1978. As he also holds three master's degrees (in electrical engineering, solid-state physics, and business), the result is a resurgence for Motorola. The company now has large-scale integrated logic and memory parts for all the major technologies, most notably the transistor-transistor-logic area in which it struck out in the past.



Choosey. Both lines have merit, says Henri Jarrat of TI's and Fairchild's fast Schottky.

Coming along soon are such unheard-of things for them as 8-K random-access memories and 16-K programmable read-only memories. At the same time, the linear business, featuring converters, is also on a steep upward curve, due to Jarrat's urging.

This reflects Stein's philosophy of making "Motorola a supplier with a full portfolio," as Jarrat puts it. Jarrat's success in broadening the product range has propelled him into the front rank at Motorola Semi. "He's the one who made all these [bipolar] things happen," complimented Stein recently to financial analysts visiting Phoenix.

Dataproducts' Wieselman looks toward ink jets

Printers, like so much else in electronics, have felt the onslaught of large-scale integration. With LSI replacing functions previously performed with mechanical parts, the latest printers are smaller, many

Biomation's K100-D-- no other logic analyzer even comes close.

No wonder the K100-D is our fastest selling new logic analyzer ever. It gives you 16 channels, 1024 word memory, clock rates up to 100 MHz, signal timing resolution to 10ns-plus a built-in display and keyboard control.

Biomation's K100-D puts it all right at your fingertips — more performance and features than any logic analyzer ever.



It starts with the microprocessor-controlled keyboard and interactive video display. To give you fast, precise control, the display serves as a comprehensive control status menu, with all selectable parameters in reverse video. There's a single, labelled key for each function, corresponding directly to status display choices. So guesswork is eliminated.

For example, in the data domain, you can direct the display to read in hexadecimal, octal, binary or ASCII, or any combination, by selecting one of four control buttons. There's also a unique "sequence" key that enables you to rearrange the order in which channels are displayed, to aid in data decoding, to simplify side-by-side comparison of timing signals and to enable you to cancel any channels you're not interested in seeing. A separate key controls horizontal expansion.

That gives you an idea of the K100-D's display versatility. Here's a picture of its astounding capture capability.



By providing timing analysis of signals as fast as 100 MHz, you can capture logic signals with resolution to 10ns. And the 100 MHz clock rate protects against obsolescence as the speed of your systems gets faster and faster. The K100-D also has a latch mode that can capture glitches as narrow as 5ns.

With the 32-channel input adapter, the K100-D is ideal for exploring the new world of 16-bit microprocessors. To give you unprecedented analysis capability, there's a built-in Auto Stop capability you can use to detect, record and display any match (or mismatch) between incoming data and previously recorded data held in a reference memory. Or using Search Mode you can key in a specific word and the K100-D will find it in memory.



To get the full impact of the K100-D, you really do need to have it at your fingertips. That's why we would like to arrange a demonstration. Call us at (408) 988-6800. Or, for more information, write: Gould Inc., Biomation Division, 4600 Old Ironsides Drive, Santa Clara, CA 95050.

GOULD

Circle 15 for information

short Story



About a 0.4" regulated 6 watt DC-DC Converter

Here's a short story with a happy ending. Tecnetics' new 100 Series low profile DC-DC converter packs 6 watts of power into a very short 0.4" case.

It's a perfect fit for tight places like between rack-mounted PC boards in computers, communications equipment, instruments, or anywhere height space is limited. This new converter is available with single or dual outputs, boasts efficiencies as high as 60%, and offers full isolation and regulation to eliminate pick-up of noise or feedback.

Tecnetics wrote the book on state-of-the-art converters. We've been producing and improving them since 1959, so that today our catalog contains over 1000 converters, each a tale in itself. So write for our catalog and get the whole story.

And now for the happy ending we promised you: prices for the 100 Series start at $60.00.

100 SERIES DC TO DC REGULATED CONVERTER

Output (VDC): 5-15
Input (VDC): 5,12,24,28
Terminals: PC type pins
Case: Black glass fiber-filled Diallyphthalate

Dimensions: 2.35"L x 2.125"W x 0.40"H
Weight: 3.0 ounces Typ.
Operating Temp.: −25°C to +71°C (Case)

tecnetics® The Power Conversion Specialists P.O. Box 910, 1625 Range Street, Boulder, Colorado 80302
(303) 442-3837 TWX 910-940-3246

Circle 16 on reader service card

College dollars need time to grow.

Take stock in America.
With higher paying U.S. Savings Bonds.

People

times more reliable, and programmed for much greater flexibility. Now the printing technology itself is beginning to receive close attention.

At Dataproducts Corp., Woodland Hills, Calif., the largest independent supplier of computer-driven printers, attention is on nonimpact, ink-jet printing. "Anyone who wants more than 3,000 lines per minute had better look at something other than impact printing," says industry veteran Irving L. Wieselman, vice president for technology assessment. At Wieselman's urging, Dataproducts recently entered into a joint research venture with a company that has mastered the ink-jet technology, A. B. Dick Co., Chicago, a maker of business equipment, including ink-jet printers.

With ink jets, already established in the marketplace by IBM Corp., "printed characters can be formed on any surface by projecting minute ink droplets through the air at very high speeds," Wieselman explains. Until recently, the cost of memory needed to obtain high enough resolution with dot-matrix techniques would have been prohibitive, he continues. But LSI can help lower costs and enhance the kind of control that is possible.

Low end. Dataproducts' agreement with A. B. Dick is intended initially to push the state of the art. But Wieselman indicates Dataproducts will consider applying the technique to the low end of the printing range. (IBM's 6440, for example, prints at a high-quality 54-line-per-minute rate and sells for $5,000; a very high-speed, low-resolution unit leases for $5,800 a month.)

Around Dataproducts' campus-like complex, Wieselman is called the "in-house guru" because of his scholarly bent and some 20 years in the business, 17 at the company. Outside, he is a well-known expert on computer printers, appearing on numerous panels and the author of many papers. Part of his responsibility is to help direct a $10 million research and development budget, considered high for a firm with $155 million in annual sales. □

SSR UPDATE

Now we've put Teledyne technology in this popular SSR package



If you have been designing around this solid state relay package simply because of multi-source availability, this is important news. You don't have to settle for less than the best anymore. Now you, too, can reap the benefits of Teledyne SSR technology.

For instance, the Teledyne 615 features a 40% reduction in component count. We don't need to spell out the cost and reliability advantages that gives you.

No black magic. We do it by using ICs to replace a significant part of the discrete circuitry. We designed the ICs ourselves. We build them ourselves. That gives us an exceptional degree of quality control. And it gives you reliability and performance you can really count on.

The Teledyne 615 Series is available in 10, 25 and 40 amp versions. Contact us for full technical details or see your local Teledyne distributor for off-the-shelf delivery.

TELEDYNE RELAYS

12525 Daphne Avenue, Hawthorne, California 90250 • (213) 777-0077

Circle 17 on reader service card



"How can I get Mil spec quality from coax connectors without paying for features I don't need?"

Easy. New AMP

Take the AMP Commercial BNC connector. It's smaller. Lighter in weight. And lower in price than other BNC's. Yet it is fully intermateable with all of your BNC UG/U type jacks. That's because AMP engineers completely redesigned the connector to cut out expensive parts. The result? The Commercial BNC features a totally new collar design, a fully captive center contact, and tin-, silver- or gold-plated contacts. The whole connector operates within −55°C to +85°C. And electrically it performs to MIL-C-3912.

AMP engineers carried out this same kind of thinking when they designed the Commercial TNC series, N series and pc board jacks. They're the perfect complement to the broad range of RF coaxial connectors available from AMP.

AMP RF Connectors. They're worth a look. They're worth the price. Find out for yourself. Just telephone the RF Connector Information Desk at (717) 564-0100, Ext. 8400.

AMP has a better way.



RF Connectors.







Some facts worth knowing about AMP Commercial BNC Connectors

Electrical Characteristics

Impedance: 50 ohms

Rated working voltage: 500 volts RMS

VSWR: Less than 1.3

Contact Resistance:
3.0 milliohms max., gold contact

Insulation Resistance: 5000 megohms min.

Dielectric Withstanding Voltage:
1500 volts min.

Environmental Characteristics

Temperature Range: −55°C to +85°C

Tooling Available: Hand tool with replaceable dies, and semi-automatic bench machine with combination dies.
Where to telephone: Call the AMP RF Connectors Information Desk at (717) 564-0100, Ext. 8400.
Where to write: AMP Incorporated, Harrisburg, PA 17105.

AMP is a trademark of AMP Incorporated.

AMP


INTELLEC
ice-86
MODULE
intel

Sixth Sense for 8086 Users.

Intel delivers ICE-86™ emulator, the designer's direct diagnostic connection to 8086 system development.

Intel's new 8086 sets the standard for 16-bit microcomputers. It delivers the Architecture of the Future today, high-level languages for programming and the Intellec® development system for unsurpassed support.

Now that support moves even further out in front. Introducing the ICE-86 module. Experienced microcomputer designers have learned that having a development system with in-circuit emulation—ICE—is like having a vital sixth sense. Only ICE emulation provides designers with the real insight in actual system operation absolutely necessary for cost effective, efficient product development. Now Intel delivers that sixth sense for 8086 users.



ICE-86™ puts the future in your hands

The 8086's early availability provides the opportunity to get your new products to market a year or more ahead of your competitors who wait for follow-on 16-bit microprocessors. Only Intel delivers the future today.

The Intellec development system with in-circuit emulation enables you to seize that opportunity. You can actually begin software development and debugging in an 8086 environment before any prototype hardware exists. Or you can use the ICE-86 module to begin simultaneous hardware and software development and integration while your system is little more than an 8086 cpu and system clock.

The ICE-86 cable plugs into your system cpu socket to provide emulation of system operation, up to the full megabyte of memory the 8086 can address.

Communicate in English, or symbolic references.

The ICE-86 emulator is actually a complex breakpoint and logic trace system supporting the most advanced symbolic debugging techniques. English-like statements or symbolic references entered at the Intellec keyboard eliminate the need to search memory maps, keep track of address changes or get bogged down in the details of system operation.

And the ICE-86 emulator's powerful logic analysis capability helps find the cause and correct the problem when bugs do appear.

PL/M-86 for the Architecture of the Future.

The most powerful microcomputer ever deserves the most powerful microcomputer programming language. That's PL/M-86, an extension of the world's most widely used development language.

PL/M-86 is an ideal example of the block-structured languages the 8086's futuristic architecture can support. It gives you 32-bit floating point arithmetic and 16-bit signed integer arithmetic. And it takes full advantage of the program-compacting features of the 8086, such as hardware multiply and divide and byte-string operations.

PL/M-86 is best for fast composition of large and complex programs. For those who prefer the efficiency of assembly language, there's ASM-86. And CONV-86 converts 8080/8085 code to the 8086.

The future is even brighter. Planned expansion of the Intellec system promises programming in Pascal and FORTRAN and the added flexibility of a macro assembler. It's true today and will be true long into the future—the 8086 is the best supported 16-bit microcomputer you can buy.

Modular programming is here.

The Intellec system gives you the flexibility of modular programming. You can develop routines in small, manageable modules, choosing the best language for each. Then using the Intellec system's powerful relocation and linkage capabilities, you can merge modules using symbolic references.

We optimized Intellec hardware for 8086 development, providing a dual diskette, expandable to four drives and 2.5 megabytes of memory. And we'll be expanding the Intellec system with a 7-megabyte hard disk, enough memory to extend the 8086's capabilities into the realm of large mainframe computers.

A manual for your success.

We've compiled an in-depth Success Manual for 8086 Users, detailing the Intellec Microcomputer Development System, ICE-86 and the full software package for 8086 program development. For your copy, contact your local Intel sales office. Or write: Intel Corporation, Literature Dept., 3065 Bowers Avenue, Santa Clara, CA 95051.

intel® delivers.

Circle #21 for information

"See us at Computer Caravan,

How Litronix' opens a new world



Norand® Sprint 100™ Order entry terminal

Now designers have a communications peripheral perfectly matched in size and cost to the world of microcomputers.
Litronix invented the Intelligent Display* to give microcomputers a new way of "talking" to users in words, numbers or even sentences. And not surprisingly, these displays are already beginning to create a new class of microcomputer-based products.

Part Number	Features	Character Height	Horizontal Row Spacing	Vertical Row Spacing	Viewing Angle	Character Positions	Character Segments
DL-1416	Standard General Purpose Display	.160"	.250"	1.200"	±25°	4	16
DL-1414	Compact Display For Hand Held Equipment	.112"	.175"	.800"	±50°	4	16
DL-2416	Premium Display New Rugged Package	.160"	.250"	.800"	±50°	4	17

*Intelligent Display is a trademark of Litronix, Inc.

The Intelligent Display is an alphanumeric LED readout that incorporates ASCII decoder, multiplexer, memory and LED driver in a built-in CMOS IC. It interfaces simply and directly to any microprocessor bus, much like a RAM. Power is from a single +5V supply, and operating current is low enough for any battery powered device.

Litronix puts intelligent communications in the palm of your hand or anywhere panel space is limited. Three versions of the Intelligent Display are already available to fit a wide variety of applications. The smallest lets you fit 20 characters side by side in a space of only 3.5 inches.

Litronix' Intelligent Displays are already being used in the portable terminal, the low cost microcomputer and electronic translator above. They're also ideally suited for applications like control panel readouts. Handheld computer

Intelligent Display™ of microcomputer applications.

Lexicon LK-3000™ Electronic translator

terminals. "Smart" games and appliances. Educational products, and more.

Use Intelligent Displays in any product that calls for alphanumerics. They'll reduce component count and cut costs dramatically. Since everything is encapsulated in a single package, design and production costs are minimal. And because no display interface PC board is needed, component costs are typically reduced by 25%. Typical OEM volume pricing per digit will range from $2 to $5 per digit, depending on display type. For easy breadboarding with Intelligent Displays, ask about our inexpensive, prewired Evaluation Kit. To get data sheets and a copy of our applications note

on Intelligent Displays, or for a demonstration, phone or write Litronix, Inc., 19000 Homestead Road, Cupertino, CA 95014. Telephone (408) 257-7910.



litronix
AN AFFILIATE OF SIEMENS

Circle 23 on reader service card

Editorial

Electronics can help prevent more nuclear accidents

In the wake of the March 28 reactor accident at Middletown, Pa., it is necessary to note that the United States still faces a major commitment to nuclear power. Ever-increasing oil prices, stagnant Government energy policy, and a dearth of usable alternative energy sources will tend to force nuclear power upon us. The only things that might prevent this are an unlikely sudden shift to the use of coal or massive forced conservation, also unlikely with elections due in 1980.

Nuclear power is therefore almost certainly going to be with us, and we must try to minimize the risk, for in the words of the president of the utility that runs the ill-fated Pennsylvania power plant, "Anything that man makes will not operate perfectly." Nevertheless, what's needed for the immediate future is a reactor design that people can trust, and, while electronic technology cannot supply all the answers to such a design problem, it can certainly help. Electronics might even be able to help improve the safety potential of existing equipment.

Present nuclear plants are, at best, based on the technology of the late 1960s and early 1970s; early design freezes are a way of life in this industry, with its decade-long lead times. Thus, the plants coming on line today are technically dated in most cases. But use of modern electronic technology could make possible a new, safer generation of reactors.

Because of the massive improvement of the past few years in the price/performance ratio of small computers, it is feasible to consider seeding hundreds of micro- or minicomputers throughout nuclear power stations to monitor events; to predict temperature, pressure, and radiation trends; and to control critical systems. One solid reason for using small computers lavishly is their high reliability compared with analog or mechanical control systems. Any computer system maker with an eye for reliability will do a job with silicon rather than mechanical devices if possible. His payoff is in lower maintenance cost, but for nuclear power the payoff would be increased safety.

Although computer control is already used in modern nuclear plants, its technology is normally a generation or two behind current capability; further, it is usually centralized in one or two mainframe-type systems, making graceful degradation problematic. The problems of distributed data processing having already been solved for some commercial, military, and space applications, it seems appropriate to distribute information about a nuclear plant by microprocessor.

Because microprocessors are so inexpensive, it should be feasible to use them in voting blocks of three to five. Multiprocessor controllers could react almost immediately to potentially dangerous temperature, radiation, or pressure fluctuations, using majority voting to assure proper response. Such units could continually monitor all important parameters and project near-term trends, making it possible to actuate or deactivate critical systems before failures could occur. Of course, the know-how in radiation hardening acquired from years of fabricating devices for the military would have to be applied.

Electronics cannot solve all the problems associated with nuclear power, but it should certainly be able to enhance the safety of such systems by putting machine intelligence in charge of the most minor details. More cooling-system redundancy, tighter containment, and other engineering changes may be necessary before the public will accept the reactor as a neighbor. But putting in 1979's advanced computer-control capabilities is cost-effective now. Manufacturers who fail to take full advantage of this inexpensive aid to improved safety are rolling dice with their market, the nation's future energy supply, and perhaps with lives.

Ooops-free PROM programming with the CMOS buffered programmer.

Avoid lost or altered data, misprogrammed PROMs, ruined master PROMs with the M900B, the only programmer with built-in CMOS buffer.

Our new M900B has a buffer of 2048 8-bit words with capacity to 4096 words. It's CMOS with power-backup so you can shut off or lose AC power for up to 60 seconds and not lose data. That's plenty of time to replace one PROM personality module with another. Thus you can transfer data from one PROM type to an entirely different PROM type (UV eraseable to bipolar, for instance) or transfer from several small PROMs to a single large one. A Data-Shift feature lets you change data locations when transferring data between PROM and memory.

Helps prevent misprogramming.

The M900B lets you check, correct and verify your data in the buffer before you commit it to a PROM.

CMOS technology with power-backup guards against transients that can alter data stored in a cheaper but volatile bipolar RAM.

Use it with or without the buffer. Two-socket personality modules guard your master PROMs.

With the buffer switched out, the M900B gives you direct PROM to PROM copying. We use two sockets, one for the master PROM, one for the copy PROM. Operator error can't alter a PROM in our master socket because that socket contains no programming voltages.

The M900B, like all our control units and PROM personality modules, comes U.L. listed, designed and built to U.L. electrical safety standards.

The M900B with standard 2K buffer costs only $2,100. With full 4K buffer, it costs only $2,400.

Write for our PROM User's Information Package.

Pro-Log Corporation, 2411 Garden Road, Monterey, CA 93940, phone (408) 372-4593.

PRO-LOG CORPORATION

Microprocessors at your fingertips.

COME ON UP TO...

"SIL-PADS 400": THE SUPERB SOLID STATE HEAT SINK INSULATORS . . . TEST 'EM!

U.L. FILE #E59150

Overcome your heat-sink problems by using "SIL-PADS 400". Eliminate messy grease and fragile mica or plastic film by using this exclusive development of the Bergquist Company.

"SIL-PADS 400" are thin but tough layers of thermally-conductive silicone rubber and fiberglass (laminated together). Cut-through, tearing, and breaking problems are gone. Assembly time is reduced; no more solder contamination; consistent heat transfer performance.

"SIL-PADS 400" are successfully used in thousands of applications.

Many standard configurations; also custom capability.

FREE SAMPLES, TECHNICAL DATA, and LITERATURE!

BERGQUIST

5300 Edina Industrial Blvd.
Minneapolis, MN 55435
Phone (612) 835-2322
TWX 910-576-2423

Meetings

1979 Photovoltaic Solar Energy Conference, IEEE and the Commission of the European Communities (Brussels), Kongresshalle, West Berlin, April 23–26.

Electro79 Show and Convention, IEEE, Coliseum and Americana Hotel, New York, April 24–26.

Reliability Physics Symposium, IEEE, Airport Hilton Hotel, San Francisco, April 24–26.

International Microwave Symposium and Workshops, IEEE, Sheraton Twin Towers, Orlando, Fla., April 30–May 4.

Newcom—The 1979 Electronic Distribution Show, Electronic Industry Show Corp. (Chicago), Las Vegas Convention Center and Hilton Hotel, Las Vegas, Nev., May 1–4.

25th International Instrumentation Symposium, Instrument Society of America, Sheraton Hotel, Anaheim, Calif., May 7–10.

ISS '79—International Switching Symposium, Colloque International de Commutation (Paris), PLM St. Jacques Hotel, Paris, May 7–11. For information in the U. S., contact A. E. Joel Jr., Bell Laboratories, Holmdel, N. J.

1979 SID International Symposium, Society for Information Display (Los Angeles), Chicago Marriott Hotel, Chicago, May 7–11.

29th Electronic Components Conference, EIA and IEEE, Hyatt House, Cherry Hill, N. J., May 14–16.

Electrical and Electronic Measurement and Test Instrument Conference, IEEE, Skyline Hotel, Ottawa, May 15–17.

Naecon—National Aerospace and Electronics Conference, IEEE and Naecon (Dayton, Ohio), Dayton Convention Center, Dayton, May 15–17.

Advances in Systems Technology: Trends and Applications, 1979, IEEE and NBS, National Bureau of Standards, Gaithersburg, Md., May 17.

Huntsville Electro-Optical Technical Symposium and Workshop, Society of Photo-Optical Instrumentation Engineers (Bellingham, Wash.), Huntsville Hilton and Von Braun Civic Center, Huntsville, Ala., May 22–25.

Failure Avoidance Seminar, Integrated Circuit Engineering Corp. (Scottsdale, Ariz.), Hilton Inn, Jamaica, N. Y., May 23–24.

1979 International Summer Consumer Electronics Show, EIA, McCormick Place, Chicago, June 3–6.

Conference on Laser Engineering and Applications, IEEE and Optical Society of America, Washington Hilton Hotel, Washington, D. C., May 30–June 1.

NCC '79—1979 National Computer Conference, IEEE, American Federation of Information Processing Societies, *et al.*, New York Hilton and Americana Hotels, New York, June 4–7.

Machine Vision, Automatic Assembly, and Productivity Technology, summer session, Massachusetts Institute of Technology, Department of Electrical Engineering and Computer Science, MIT, Cambridge, Mass., June 11–15.

Second Joint Intermag—Magnetism and Magnetic Materials Conference, IEEE and American Institute of Physics, Statler Hilton Hotel, New York, July 17–20.

Second International Fiber Optics and Communications Exposition, Information Gatekeepers Inc. (Brookline, Mass.), Hyatt Regency O'Hare Hotel, Chicago, Sept. 5–7.

Wescon/79 Show and Convention, IEEE and Electronic Conventions Inc. (El Segundo, Calif.), Brooks Hall and St. Francis Hotel, San Francisco, Sept. 18–20.

MOSTEK 3870

Three of them together make flying a breeze.

"Our OC-1401 navigation computer uses three Mostek 3870s to distribute the complex processing tasks. While one controls the keyboard and display, all three operate independently, calling on each other to perform the mathematical functions and subroutines necessary for computing in-flight navigational data." *Bruce Trump, Project Engineer, and Rod Brahman, Software Engineer, Heath Company.*

Toledo Scale: "We use Mostek's 3870 three ways: (1) to perform all the logic functions associated with A/D conversion; (2) to provide selectable operating features using multiple program switches; (3) to generate bit serial output in ASCII format." *Roger Williams, Engineering Manager for Electronic Products.*

Tokheim: "Using the 3870's 2K ROM memory, we incorporated two separate software programs. Now we can use the 3870 in a control console or individual gasoline pumps, depending on mechanical connections." *Earl Langston, Project Manager.*

There are hundreds of applications using Mostek's 3870 single-chip microcomputer. Get information for your design by contacting Mostek, 1215 West Crosby Road, Carrollton, Texas 75006; phone (214) 242-0444. In Europe, contact Mostek Brussels; phone (32) 02/660.25.68.



MOSTEK®

© 1979 Mostek Corporation



Only Gould recorders can give you a trace this accurate, clear and permanent over the entire frequency range of the recorder.

Because only Gould offers this unique direct writing recording system.







This system has many features that work together to produce traces of the highest quality.

Patented pressurized fluid supply, invented by Gould, and rectilinear pen linkage provide clear, crisp, dry and error-free rectilinear traces with a uniform width of 0.01 inch at all writing speeds. The high-stiffness servo penmotor with exclusive Metrisite® noncontact position feedback ensures high frequency response, fast rise time and linearity of 99.65% full scale.

No other recorder can equal this advanced technology designed into each and every Gould recorder. Technology

that makes Gould recorders versatile, reliable and the performance leaders in analog recording. Gould Inc., Instruments Division, 3631 Perkins Ave., Cleveland, Ohio 44114.

Writes dry. Pressurized fluid writing utilizes a completely closed system which forces ink into paper, not just on it. Pen tip writes in any position, even upside down.



Constant trace width... even corners of sq. waves.

When shut down ink is drawn back into pen to prevent puddling.

System never clogs; writes instantly.

Cartridge holds enough ink for up to a year of normal recording.



It's transparent, making it easy to check ink supply; disposable; and easy to replace.

A parallel-motion mechanism keeps the pen tip travel perpendicular to the direction of the chart paper in Gould's true rectilinear trace presentation. A unique pen linkage converts rotary motion of the pen motor shaft into straight line motion of the pen tip without geometric error. Allows recording of even small signals anywhere on the chart with equal accuracy and perfect fidelity.



Find out more about Gould recorders today.
For brochure, Call toll free:
800-325-6400 Ext. 77
(In Missouri: 800-342-6600)

GOULD

An Electrical/Electronics Company



We've accepted
of

Cinch connectors, like Dura-Con,(TM) are whe they belong. Near you. On our distributors shelves, and in the factory back-up stock to make sure you have Cinch connectors at you convenience . . . not ours.

We know that if versatile Cinch Dura-Con Connectors are available, you'll choose one of our hundreds of rugged, highly adaptable designs for your systems. From the newest micro-miniature Metal Shell Dura-Con D for commercial/military applications when shock, vibration and RF interference specs must be met . . . to the proven plastic shell Dura-Con D and strip connectors for less demanding jobs.

Dura-Con contacts, with a unique seven wire helical spring construction, deliver constant contact stability even under the toughest environments.



Getting Cinch Connectors to you, on time, is one commitment to you from the NEW Cinch. Responding to your specific system needs from our full connector line is another. Call us! We'll accept your challenge!

Contact your TRW Cinch Connector Distributor or sales office listed in EEM. TRW Cinch Connectors, 1501 Morse Avenue, Elk Grove Village, Illinois 60007. (312) 439-8800.

the challenge delivery.

TRW CINCH CONNECTORS

ANOTHER PRODUCT OF A COMPANY CALLED TRW

Circle 31 on reader service card

There's a little tiger in every Cherry switch

...but we're pussycats to do business with

Our products are tough, but our people aren't... and that's the beauty of dealing with Cherry.

You see, we can control the quality of our switches because we fabricate most of our own parts (moldings, stampings, springs, printed circuits, etc.) And we can keep the price down because we're loaded with automatic equipment to handle high volume.

But the real difference is in the *people* you work with at Cherry...from your first contact with a technically trained sales representative...through careful analysis and recommendations by engineers who are really concerned about *your* problem... to production scheduling and customer service men who follow-up and expedite to make sure we keep our delivery promise to you.

Of course we're proud of our modern facilities and equipment...but what we're proudest of is our reputation for customer service. Try some.

Test a free sample "tiger" from the pussycats at Cherry. Ask for our latest catalog which contains complete information on all our switches and keyboards, and we'll include a free sample switch. Just TWX 910-235-1572...or PHONE 312-689-7700... or circle the reader service number below.

CHERRY®

CHERRY ELECTRICAL PRODUCTS CORP. • 3608 Sunset Avenue, Waukegan, Illinois 60085

SWITCHES and KEYBOARDS — Available locally from authorized distributors.

See Us At
ELECTRO '79/NYC
April 24–26
CHERRY BOOTHS 2825–29

Circle 32 on reader service card

Electronics newsletter

AMI bows with 16-K static RAM while Zilog changes mind . . .

Not content to let Texas Instruments Inc. hog microcomputer applications calling for a 2,048-by-8-bit static random-access memories, American Microsystems Inc. of Santa Clara, Calif., has samples available of a fully static device that is designed for both 8- and 16-bit systems. Made with AMI's V-groove MOS technology, **the S4028 features access times of 200 to 300 ns, requires only 370 mW for operation over the commercial temperature range,** has a die size less than 32,000 mil^2, and is pin-compatible with equivalent read-only memories and erasable programmable ROMs. Last year, TI described a similar n-MOS part [*Electronics*, July 20, 1978, p. 39], but production problems delayed its delivery. Now the company says it is building inventories for distributor introduction in late spring.

Zilog Corp., however, is concentrating its guns on the pseudostatic 4,096-by-8-bit RAM announced two months ago [*Electronics*, Feb. 15, p. 40]. Consequently, the Cupertino, Calif., company, which is dropping new clocked static RAMs, **has decided not to make the 6166 2-K-by-8-bit or any other 16-K static devices** [*Electronics*, Feb. 15, p. 33]. Also opting out of the 2-K-by-8-bit level of the static RAM market is National Semiconductor Corp., also of Santa Clara, which considers that part to be short-lived. It thinks a better building block will be an 8,192-by-8-bit fully static RAM with power down that it hopes to unveil in 1980.

. . . as Mostek prepares 16-K RAM with single supply

With a 2-K-by-8 single-supply part already under its belt, Mostek Corp. is making plans to go after the market for 16-K dynamic random-access memories using a 1-bit configuration and a single 5-V power supply. The MK4516, an improvement over conventional 16-K RAMs requiring three power supplies, is scheduled to be available in sample amounts in the fourth quarter. That's about the same time that the Carrollton, Texas, firm's 64-K RAM is expected. But the 4516 will get to production much faster than the 64-K, says Mostek marketing official Sam Young. **He declares that 5-V 16-K parts will be the industry's "next major project,"** before the emerging generation of 64-K RAMs become commodity devices. Other manufacturers with single-supply 16-K parts planned or announced include Intel and National Semiconductor.

Polyimide substrate breaks the ice

Normally, the coldest environment any circuit board will see is $-55^{\circ}C$ when operating or $-65^{\circ}C$ in storage. But in an unusual application, Pactel Corp. of Newbury Park, Calif., is supplying one of its aerospace customers with a five-layer, polyimide printed-circuit board [*Electronics*, July 22, 1976, p. 101] **that is slated to operate at absolute zero ($-273^{\circ}C$).** Prototype boards have been cycled 10 times from ambient to liquid helium temperatures ($-246^{\circ}C$) without opens or any other failure mode developing. This could be the first multilayer board to pass such a severe test.

More U. S. firms being sought by Thomson-CSF

Thomson-CSF, following its acquisition in early March of Solid State Scientific Inc. in suburban Philadelphia, is looking toward further U. S. expansion. Pierre Mestre, deputy director general of the Paris-based group and head of its components division, says **passive components are just one area where the company is shopping** for additional acquisitions. Meanwhile, it has reorganized its U. S. operations into the Thomson-CSF Components Corp., with SSS becoming SSM, the Solid-State RF and

Microwave division. Two divisions are in Clifton, N. J.: the Dumont division, responsible primarily for special cathode-ray tubes and photomultipliers, and the Electron Tubes division, producing standard professional tubes. The other divisions, both in Canoga Park, Calif., are NPC, which makes diodes, transistors, and power supplies, and Socapex, whose main business is connectors. Mestre says Thomson's U. S. subsidiaries last year sold $40 million worth of components.

Motorola ready to complete codec phone set

The last two LSI chips to complete Motorola Semiconductor Group's codec-based telephone subscriber channel unit should be ready by mid-year, predicts Neil Wellenstein, manager of communication systems engineering. Samples of the pulse-code-modulated (PCM) filter chip, manufactured in metal-gate C-MOS, are already being shipped and the subscriber loop interface circuit is being fabricated in sample quantities, he says. The PCM codec, on the market since early this year, and three discrete components **signal the Phoenix firm's entry into the rapidly heating-up codec business.** It is expected to sell for about $20 in quantity.

Two-chip set reduces noise for low-end audio

Eyeing a market in noise-reduction systems for low-end consumer audio products, National Semiconductor Corp., Santa Clara, Calif., is introducing a two-chip approach for applications where the industry-standard Dolby encoding technique might be too expensive. Called the NR-2 adaptive noise processor, **the chip set is aimed at products such as car stereos or entertainment centers drawing 20 W or less.** National employs a dynamic filtering approach where a high-pass filter controls two low-pass filters to reduce noise. This compares with the complementary or encoding-decoding technique popularized by Dolby.

Addenda

Rockwell International Corp.'s Microelectronic Devices operation has its version of the Pascal computer language off and running on its System 65 microprocessor development system. **Within a few months it will be ready for users of 6500 devices,** says Rockwell. . . . National Semiconductor Corp., running into problems with its patent suit against Digital Equipment Corp. over software protection of DEC's PDP-11-34 minicomputer [*Electronics*, Jan. 18, p. 88], has shelved plans for a competing System/200. **But National plans to go ahead with its plug-compatible System/400** to compete with IBM's System/370 and recently announced 4300 series even though first System/400 shipments are running three to six months late. . . . Masatoshi Shima, designer of the Z8000 16-bit microcomputer [*Electronics*, Dec. 21, 1978, p. 81], **is leaving Zilog to return to Intel Corp.** While at Intel from 1970 to 1975, Shima was instrumental in the design of the industry-standard 8080 8-bit microprocessor. . . . Memorex Corp. plans to use Fairchild charge-coupled-device memories in its new 3770 disk cache unit. But faced with uncertain supply, the Santa Clara, Calif., peripherals maker **has built a prototype using bipolar random-access memories.** . . . An optical-fiber transmission line is being installed by New York Telephone Co. **for network color TV broadcasts of the 1981 Winter Olympics in Lake Placid.** The 2½-mile line will link the Olympic broadcast center to the local phone switching office. At the same time, New York Tel is running a 30-mile link between White Plains and Manhattan for regular voice and data service.

Cut the cost of digital system checkout with Biomation's DTO-1.

There's a whole new approach to test, calibration and maintenance of digital systems. It's Biomation's DTO, the first Digital Testing Oscilloscope. Here's how it works. The DTO's front panel functions very much like a traditional oscilloscope but provides additional capabilities. It automates testing without having to worry about software implementation. Simply step through your test sequence once using the DTO to record the entire program on a tape cartridge. Then DTO plays it back to guide technicians, even setting up the instrument's front panel to match the reference program. All in all, DTO provides a faster, easier, far more accurate approach to the otherwise time-consuming, error-prone task of system checkout.

DTO-1: For production test.

Now there's a better way to move new products out of engineering and into production accompanied by a comprehensive production test program. Just use DTO to record the test sequence you want technicians to follow. Step by step, it enables them to compare the system under test with your "known good" system, automatically flagging any discrepancies. Compare DTO with the test equipment you're now using.

SYSTEM TEST CAPABILITY COMPARED

Testable system elements	Oscilloscope	Signature analyzer	In-circuit emulation with signature analysis	DTO-1
Power supplies	yes	no	no	yes
System clocks	yes	no	no	yes
Processor/control logic	no	no/yes	yes*	yes
Digital input/outputs	no	yes	yes*	yes
Analog I/O	yes	no	no	yes

*System must have a processor.

DTO-1: For calibration & repair.

The most sophisticated calibration and repair labs are using DTO to "document" digital systems they must service.



By developing a tape for each new piece of equipment and instrumentation, troubleshooting and recalibration is faster and more precise. The DTO's screen displays both reference traces and test traces simultaneously, highlighting any disagreement and enabling technicians to zero in on faults.

DTO-1: For facility maintenance.

When it may be weeks or months between repair and maintenance of complex digital systems, DTO brings technicans back up to speed in a hurry. DTO can be used to make a record of the system operation, so it remembers exactly how a perfectly functioning system operates. By following the test procedures and adjusting the system signals to match recorded logic traces, maintenance is virtually automated.

For details on how Biomation's DTO-1 can cut the cost of digital system checkout for you, write Gould Inc., Biomation Division, 4600 Old Ironsides Dr., Santa Clara, CA 95050.

Or, call for a demonstration. (408)988-6800

GOULD



Head off trouble

at the bandpass.

Our DTMF Bandpass Filters are priced about 40% less than our competitors'. So, in addition to eliminating misunderstandings between Touchtone® telephones and decoders, our filters eliminate confrontations between designers and comptrollers.

They eliminate something else, too. Aggravation. By replacing discrete approaches to filtering problems, they get you out of a a lot of painstaking tweaking and tuning. All while providing higher circuit stability than available before.

We offer you two models. The AF121. Which filters extraneous signals from the low groups between 697 Hz to 941 Hz. And the AF122. Which is discriminating in the high range from 1209 Hz to 1633 Hz.

The filters are compatible with commercial digital detector circuits. And no external components are needed.

We'd like to let you know more about these and other items in National's growing telephone line. Give your National rep a ring. Or clip out the coupon below.



National Semiconductor
Corporation
2900 Semiconductor Drive
Santa Clara, CA 95051

☐ Send me the scoop on your DTMF Bandpass Filters.
☐ Also send your free Active Filter Handbook. (I've enclosed a copy of my company letterhead to qualify.)

Name_____
Title_____
Company_____
Address_____
City_____ State_____ Zip_____

E4/129-8

National Semiconductor

Harris shatters the Op Amp speed barrier:



The first true Op Amp with performance compatible with high-speed Data Acquisition and Display systems.

Harris sets a new benchmark for high-speed amplifiers.

The Harris HA-5190 wideband, fast-settling Op Amps provide the high-speed performance of costly hybrids—with the economy of monolithic bipolar construction.

Result: The industry's highest performing true Op Amps for as little as $8.60 (100-up).

You get the advantages of Harris' unique Dielectric Isolation technology—6.5 MHz full power bandwidth, ±200 V/μs slew rate and settling time of 70 ns (0.1%, 5 V output step). Plus excellent input characteristics of 5 mV offset voltage and 15 nV/√Hz input voltage noise at 1 kHz, and the facility of inverting and non-inverting mode operation.

Now you have an economical, true Op Amp to match the performance of high-speed DACs. The natural choice for data acquisition, pulse and wideband video amplifiers, avionic and military equipment, and a variety of graphic displays.

For fast facts, check the specs below . . . then call the Harris Hot Line. Or write: **Harris Semiconductor Products Division, Box 883, Melbourne, Florida 32901.**

PERFORMANCE PARAMETERS

INPUT OFFSET VOLTAGE	5 mV
BIAS CURRENT	5 μA
FULL POWER BANDWIDTH	6.5 MHz
RISE TIME	11 ns
SLEW RATE	±200 V/μs
SETTLING TIME	
5 V to 0.1%	70 ns
5 V to 0.01%	100 ns
POWER DISSIPATION	600 mW

TYPICAL APPLICATION
(Output Amplifier for DAC)



HARRIS HOT LINE!
1-800-528-6050, Ext. 455
Call toll-free (except Hawaii & Alaska) for phone number of your nearby Harris sales office, authorized distributor or expedited literature service.

Harris Technology ...Your Competitive Edge

HARRIS
SEMICONDUCTOR PRODUCTS DIVISION
A DIVISION OF HARRIS CORPORATION

Circle 38 on reader service card

New design doubles wiring density of Multiwire process

by Jerry Lyman, Packaging & Production Editor

Machines put down 80 wires per square inch of pc board and are available now; 110 wires/in.^{2} are on the way

Multiwire, one of the more successful competitors of multilayer printed-circuit boards, is getting a new look. In response to the need for ever denser wiring as integrated circuits both shrink in size and sprout more leads, the PCK Technology division of Kollmorgen Corp. has developed what it calls High Conductivity Multiwire. The new machine it offers can "write" wire in a pattern based on a 25-mil-grid, instead of Multiwire's 50-mil grid, creating the equivalent of roughly four layers of multilayer board interconnection.

"We have been under constant pressure to raise our interconnection density," says Page Burr, president of PCK Technology, which is in Glen Cove, N. Y. "Our customers now want automatic wiring machines capable of packing more interconnections in fewer layers of wiring."

Packing wires on. With the emergence of chip carriers, for example, a square inch of circuit board may require as much as 200 inches of wiring, whether printed conductor or round wire. Just a few years ago, however, boards loaded with dual in-line packages needed only about 35 inches of wiring per square inch of surface.

High Conductivity Multiwire is built around a new machine for laying down an insulation-covered wire onto an adhesive-coated printed-circuit board. As with the older Multiwire, ultrasonic energy is then used to heat the wire as it is laid out and bond it to the board.

By "writing" 6.3-mil-diameter wires on the 25-mil grid, the machine produces an interconnection density of 80 in. of wire per square inch of wiring level—double that of Multiwire. And, as with the older Multiwire, terminations are formed by drilling through the wires and the board and plating the walls of the holes. A layer of adhesive can be placed over the wired surface and the process repeated to build up multiple levels of wiring on a single side of a board.

New styles. PCK Technology, which leases its Multiwire and HC Multiwire machines and also makes circuit boards to order, obtained the higher density by redesigning the machine's wiring stylus and wire-feeding mechanism. The results are tighter wire placement control and an ability to handle finer wires.

The company also made the energy from the ultrasonic bonding head proportional to the motion of the table on which the circuit pattern is laid out. This ensures uniform bonding energy regardless of the wiring complexity, resulting in a more reliable board, Burr says.

Even though HC Multiwire is new, PCK Technology has already modified it to build a prototype machine that can put down 4-mil wire on an 18-mil wiring grid. The prototype—slated, says Burr, for delivery to "a large data-processing firm"—has a connective capacity of 110 in. of wire per in.^{2} of board.

The potential of HC Multiwire can best be illustrated by visualizing a pc board with a regularly spaced array of 24-pin chip carriers. A conventional pc board on a 50-mil grid would require 11 conductive layers to interconnect the carriers. The same packages could be interconnected on three levels of HC wiring using 6.3 mil wire on a 25-mil grid. With the even finer wire size and the smaller wiring grid of the prototype

New and old. High Conductivity Multiwire, right, packs more wires on a pc board by using a smaller grid than the original Multiwire, shown at the same scale to the left.



machine, chip carrier interconnection would only require two levels of HC Multiwire.

According to Burr, Multiwire is already competitive with all multilayer boards except at the highest production volumes. The new machines will lease at higher rates than the old, although he will not specify by how much. However, since the new machines will do more, users will save money, he says.

Medical

Artificial arm's processor recognizes different body signal waveforms

Building a control system around a microprocessor, researchers have developed an artificial arm that decodes the waveform of the slight electrical signals generated when a person tries to move a limb. The result is an arm more sensitive to control signals than any so far and more easily used by amputees with severely damaged nerve endings at the stubs of their limbs.

Developed at the Illinois Institute of Technology in Chicago, the new arm controls small electric motors that manipulate elbow, wrist, and hand joints. Because the system is so sensitive, it can be used with relatively little practice, unlike existing artificial arms, says Daniel Graupe, the 45-year-old project leader and a professor of electrical engineering at the institute.

The attempt to move a limb generates in the brain a faint electrical impulse of about 10 millivolts known as a myoelectric signal. Such signals, generated as well by those who have lost limbs, have been used for a number of years to control artificial devices. However, what Graupe's researchers have done is develop a processing system that looks for more than the presence of the signal. Rather, the system compares the myoelectric signal waveform with standard waveforms stored in memory, in this way determining exactly which joint movements are intended.

Detection. One electrode, or at most two, placed on the shoulder stump will detect the 10-mV myoelectric signals, according to Graupe. In more conventional arms, at least one electrode is needed for each joint. In some cases, depending on the extent of nerve damage, as many as 10 electrodes could be required, he points out. Not only can it be difficult to place so many electrodes on a stump but they are also hard to keep in place.

In the new arm, myoelectric signals sensed by the electrodes are amplified, converted by a 12-bit analog-to-digital converter, and compared by the microprocessor to the characteristics of the reference waveforms. Commands are transferred to transistor-transistor logic, which controls solid-state dc relays for the three joint motors powered by rechargeable nickel-cadmium batteries.

In the research model, Graupe uses an Intel 8080 microprocessor and 2 kilobytes of random-access memory. The system can recognize a command and activate the motors within 0.2 second. A simplified circuit design based on a 16-bit processor is under consideration.

The Israeli-born and educated Graupe says that the major challenge in the project was in developing the software to recognize and respond quickly to varying impulses. A series of algorithms for identifying different joint functions was prepared to change myoelectric signals into instructions.

A prototype model is undergoing tests on disabled veterans at a Veterans Administration hospital in Hines, Ill. The shakedown testing and further streamlining of the algorithms, funded by the National Science Foundation, are expected to lead to a device ready for the market within two years, says Donald Gustafson, vice president of Scientific Systems Inc., Cambridge, Mass., a software consulting firm hired to develop the programs. **-Larry Marion**

New arm. Artifical arm being developed by IIT's Daniel Graupe relies on internal microcomputer to control motors that operate joints in the elbow, wrist, and hand.



Careers

No razzle-dazzle, but lots of jobs

Boom times in the electronics business, a shortage of electronics engineers, and the start of the season for the major electronics shows: if that

familiar combination seems to promise razzle-dazzle recruiting, think again. The Institute of Electrical and Electronics Engineers annual show, Electro79, may be just around the corner, but all involved swear they are going in without a single promotional stunt in mind.

Two recruiting firms planning major efforts in New York City environs say they plan nothing more than their typical career-days sessions. An admittedly selective poll of companies known to be beating the bushes for EEs discloses no plans other than the now-typical low-key hospitality suite—and frequently not even that.

Moreover, the show's management, aware that there will be plenty of recruiters around, is determined to do all possible to forestall any lurch towards the showmanship recruiting of the past.

Changes. Of course, plans can change between now and the April 24 opening of Electro. It doesn't take long to round up special buses ferrying showgoers from the Coliseum to their hotels (and to the hospitality suites) or to charter a skywriting plane. And, of course, other attractions are available on a pickup basis.

Still, it is no less a seller's market for job-hunting EEs than it was last year, and last year's shows were not marked by high-pressure recruiting, says Bob Akers, president of Akers & Associates. His Santa Ana, Calif., firm has sent out 5,000 fliers to EEs living in the New York metropolitan region seeking resumes and inviting recipients to stop by during the show for a talk.

Akers says there will be companies interviewing his prospects, as well as companies doing their own recruiting. But he expects no return to high pressure, partly because the show management is hostile to it and partly because the companies recruiting have decided they do not like its associations.

Also, the individual EE is more sophisticated these days, less likely to be attracted by a show-business approach, says A. C. Sugalski, president of Interstate Staffing Inc. His Narbeth, Pa., firm plans to start the applicants' interviews with specific companies after the show closes, besides opening its suite well after the show opens.

No one could approve more of these low-pressure tactics than William C. Weber of Electronic Conventions Inc., the show management organization. He speaks without fondness of the days when the show "became a headhunter's paradise," and says, "We do everything in our power to discourage recruiting"—including policing the Coliseum floor and tearing down recruiting signs.

Still, Weber reports that already the show newspaper put out by his staff has a rash of recruiting ads. Moreover, Akers and Sugalski report a wide range of companies looking for qualified applicants. They say this June's college graduates with such credentials as microprocessor experience can command at least $20,000, while EEs with perhaps five years experience might go $10,000 above that. **-Ben Mason**

Military

Navy tests Loral's radar warning unit

These days, tactical aircraft meet a growing tangle of hostile radar signals. Moreover, the increasingly varied frequencies of radar-guided weapons are overwhelming aircraft defense systems.

Fighting electronics with electronics, the U. S. Navy's Air Development Center, Warminster, Pa., and Loral Corp.'s Electronic Systems division, Yonkers, N. Y., have come up with the AN/APR-43, a microprocessor-controlled, dual-receiver radar-warning system. The Navy's Air Systems Command has begun flight tests of the system and has set an initial procurement for the current fiscal year.

The APR-43 can detect a wide range of threatening signals in two different frequency bands and tell the pilot what direction they are coming from. Perhaps most important, however, is the fact that the system is reprogrammable. This means it may be altered in the field with relative ease to react to different frequencies and other threat parameters if new weapons suddenly appear—as when U. S. planes in Vietnam and Israeli planes in the Yom Kippur war faced radar-guided weapons that used new frequencies.

Smaller. The new system uses the militarized version of Texas Instruments' TMS 9900 16-bit microcomputer. The usual benefits of large-scale integration—such as smaller size, lighter weight, and lower power consumption—are crucial to the new system, for it is intended as an adjunct to the host plane's tactical warning radar, the AN/ALR-45. Also, the LSI solution fits the digital processor on one board instead of the three used in a hardwired setup, says Loral.

The hazards of the hardwired airborne defense system were particularly apparent to Israel, which lost many fighters to a Russian missile using a continuous-wave guidance signal. Other radar-guided weapons use pulsed frequencies in what is known as the guidance band.

The new Loral system packs in two receivers: a crystal video unit for the guidance-band signals and a tunable superheterodyne unit for the cw band. The digital processor, based on the integrated-injection-logic SBP 9900, operates the receivers on a time-shared basis, processes the incoming signals, and sends the results to the ALR-45's cockpit

Connections. Dual-receiver radar warning system has a back studded with connectors for incoming i-f and rf signals, outgoing control signals, and more.



display for the pilot.

However, the processor does not send all the processed signals to the display. Rather it winnows out threats to the aircraft from other signals, arranges them by priority, and sends strobe symbols to the display. It finds direction by calculating the amplitude ratios of the incoming signal.

Development. Loral says the 9900's instruction set is well suited to handle the data storage and manipulation input/output interfaces. A hardwired approach would have an unwieldy design and a complex solution.

Loral and the Navy have designed the APR-43 with an eye to the future. Its 5½-inch-diameter antenna disk actually contains three antenna assemblies: one for the guidance band, one for cw signals, and one to work with the forthcoming AN/ALQ-162 jamming system, giving signals to confuse incoming projectiles detected by the APR-43. Also, the digital processor of the APR-43 could send data to the Harms airborne missile system, under development to knock out ground radars.

Loral Electronics Systems has big plans for its new digital processor. Already, the division is supplying one version for the forthcoming AN/APR-23 (V-2), a radar warning system the U. S. Army is testing for its helicopters. **-Ben Mason**

Marching into distributed processing

In the computer business, all roads are leading toward distributed processing, and Advanced Digital Data Systems Inc. is marching right toward that destination. Its new Regent 300 terminal-cluster system (below) essentially is an intelligent terminal for original-equipment manufacturers, and its new System 75 is aimed at the OEM who will be selling systems to users like small businesses. Both units offer asynchronous or synchronous binary communications hardware.

The heart of the Regent 300 is the terminal-cluster controller, which incorporates the 8080 and two diskettes giving ½ megabyte of storage and 52 kilobytes of random-access memory. Its assembly language software includes the RDOS operating system (a CPM derivative), macro-assembler, editor, debugging package, and other utilities.

The controller can support up to four buffered editing terminals (the Regent 200) and has an interface for a serial printer. With the four terminals, it costs $8,080 per unit for 25 and up, a price that gives OEMs the controller and diskettes for little more than many firms charge for the smart terminals alone, maintains ADDS marketing vice president Alan M. Dziejma.

Aimed at OEMs who program small, stand-alone systems in Fortran or Basic, the System 75 has a controller similar to the 300's, but with 1.5 megabytes of storage on three double-sided floppies. It uses the ADOS II operating system and has a full complement of utilities with per-unit prices for 25 or more of $7,645 or $5,525 with two floppies.

The 75 will cost about 30% less than the ADDS System 70, yet it has three times as much program storage and more editing capabilities. The system shares many of its attributes with the Tandy 10, which Advanced Digital manufactures for Radio Shack.



Displays head for under-$1,000 tag

Sparked by the availability of single-chip CRT controllers, the makers of cathode-ray-tube terminals are scrambling to dive below the magic $1,000 price barrier. Advanced Digital Data Systems Inc. of Hauppauge, N. Y., for one, is launching its Regent 20, with a price of $995 for one unit and considerably less for quantity orders. Moreover, Hazeltine Corp. of Greenlawn, N. Y., already established in the under-$1,000 terminal market, is bringing out the 1420, an upgrade of the existing two models.

The electronics in the low-end Regent 20 include an 8085A microprocessor, National Semiconductor's DP8350 CRT controller and INS8250 asynchronous communications element, and a 2,048-bit program in a read-only memory. Two more models also bowing at the Interface '79 show in Chicago this week, the Regent 40 and 60, use the 8085A and Intel's 8275 CRT controller, which gives greater display capability. The 40 has a 6,144-bit program, the 60 an 8,192-bit program; both the 40 and the 60 are asynchronous, as is the 20.

The asynchronous 1420 from Hazeltine follows in the footsteps of the 1400 and 1410. It uses the 8049 single-chip microprocessor, faster than and with twice the memory of the others' 8048. All three use National's 8350 and 8250.

The new controllers take advantage of their chip's capabilities to incorporate features found in higher-priced, earlier-generation terminals. The features differ from line to line and from model to model, as does pricing. Prices for the Regent 20 are $695 each for 100 or more; for simi-

There's only one way to have the newest and most unique top-value electronic products...choose and build from the nearly 400 fascinating kits you'll find in this new

FREE HEATHKIT® CATALOG!

See the world's first Electronic Weather Computer It indicates, stores and retrieves all temperature, pressure and wind data ...even computes wind chill factors for home, farm or office.



See the very finest, most advanced oscilloscope Heath has ever developed. Compare this DC-35 MHz Dual Trace, Delayed Sweep Scope with others costing hundreds of dollars more.

See the first and the best electronic digital bathroom scale with a strain-gauge transducer like the most expensive laboratory scales.

See the new GC-1415 deluxe Digital Car Clock with trip timer and stopwatch. Useful and practical for car, van or truck.

The R/C'ers dream — Heath's Pack 17 8-channel open gimbal R/C transmitter with instant plug-in frequencies ...at big kit savings!

A super coin-shooter! Heath's 'Cointrack' Metal Locator with adjustable discrimination and pushbutton tuning.

See the world's first and finest fully computerized and programmable color TV that lets you program an entire evening's viewing.



See Heath's newest and finest 'rack-mount' series of audio components — professional performance for discriminating audiophiles and music lovers who want the best.

Plus hundreds of top-performing, value-priced electronic kit products for home, hobby or business. See the most powerful personal computer systems you can buy with complete software and peripherals. See the Heathkit Continuing Education Self-Learning Programs in Basic and Advanced Electronics, Automotive Electrical, Test Instruments and Novice and General Amateur Radio Licenses — the most efficient and economical way to stay on top of our electronics world! FILL-IN COUPON AND SEND TODAY.

If coupon is missing, write Heath Co., Dept. 510-520, Benton Harbor MI 49022.

Every Heathkit product is backed by world-famous technical service and counsel — plus sales and service facilities at 54 Heathkit Electronic Centers* coast-to-coast (*units of Schlumberger Products Corporation). See the white pages of your phone directory for the center nearest you.

SEND FOR YOUR FREE COPY TODAY!

HEATH
Schlumberger

Heath Company, Dept. 510-520
Benton Harbor, Michigan 49022

FREE CATALOG

Please send me my FREE Heathkit Catalog. I am not now receiving your catalogs.

Name_____

Address_____

City_____ State_____

CL-689 Zip_____

lar lots, the Hazeltine 1400 goes for $630, the 1410 for $660. For 51–99, the new 1420 costs $750, $10 less than the 1410 in similar quantities.

In comparison, the Bantam from Perkin-Elmer Corp.'s Terminals division costs $599 each for 100 or more. It uses a custom chip that combines the functions of a microprocessor and a CRT controller [*Electronics*, Oct. 26, 1978, p. 52].

One more. Still to be heard from is a fourth major terminal maker: Lear Siegler Inc.'s Data Products division. It is likely to introduce a new model with a CRT controller chip, although no date is set.

To some extent, these makers of low-cost CRT displays are playing a features game, each offering a mix of basic editing capabilities and other keyboard functions they hope will snare orders from original-equipment manufacturers.

For example, the new Hazeltine machine adds a program-function key mode to its numeric pad and incorporates a set of cursor control keys, some of which are on the 1400 and some on the 1410. It also has high- and zero-intensity and blinking display modes and has upper- and lower-case letters, whereas the other two have only capitals.

The Regent 20 also has upper and lower cases and adds to its RS-232-C/CCITT V.24 communications interface a switch-selectable 20-milliampere current loop. It can communicate with a serial printer through an auxiliary output without disturbing its own display.

Transformable. The 20 also has a mode that turns it into a line monitor displaying the data stream sent to the terminal. This mode will aid program debugging for OEMs and applications debugging after installation, says Frank Zelis, marketing manager for displays.

Nor is Advanced Digital neglecting customers who need more sophisticated CRT displays. With its more powerful chip set, the 40 offers more editing capabilities, and the 60 adds to that buffered transmission.

The three terminals do offer upward software compatibility, and their applications programs can also run on other ADDS terminals, such as the Regent 100 and 200, which continue in production. The 40 can be seen as an update of the 100, costing $950 apiece in hundreds, while the 60 is in effect an update of the 200, costing $1,240 in hundreds. These prices, slightly less than the earlier models, owe much to production economies ADDS achieves by new vertical integration of its manufacturing. **-Ben Mason**

Communications

E-Systems readies a voice coder

Though requiring lots of computational hardware, linear predictive coding (LPC) techniques have been recognized since the mid-1960s as a useful method for digitally analyzing speech and producing high voice quality at fairly low data rates—under 2,400 bits per second. But the compact number-crunching capabilities of high-speed microprocessors are bringing equipment costs and size down, and new machines designed for narrowband commercial applications are expected to emerge soon from various firms.

One such unit—the LPC-24 speech processor—was demonstrated by E-Systems Inc. of Dallas at the International Conference for Acoustics, Speech and Signal Processing held in Washington, D. C., April 2–4. The processor is designed to boost the efficiency of long-distance telecommunications networks.

Using LPC techniques to sample and analyze audio input from conventional telephones, the unit produces a 2,400-b/s synchronous bit stream that can then be mutliplexed with up to 7,200 b/s of data over a common circuit. A second LPC-24 at the receiving end then reverses the process to convert the serial data back into an audio signal. Separate devices for encrypting and deciphering the digital stream may also be added at each end to make the line secure.

E-Systems engineers use Advanced Micro Devices Am2900-series bit-slice microprocessors to perform the high-speed computation of the complex LPC algorithms. Typical of the benefits to be expected from using the latest chip technologies, the new machine contains only five 6-by-12-inch circuit cards, compared with the 13 cards of previous-generation voice coders using a different method of analysis that E-Systems sells to the military.

Dollars. Available this fall, the LPC-24 will sell for some $2,000 to $3,000 less than the $14,000 machine sold to the military, says D. P. Fulghum, manager of speech processing at E-Systems' Garland division.

E-Systems has also carried the quest for improved voice quality and intelligibility one step further. A separate front-end processor suppresses background noise and automatically adjusts gain so as to present an optimized voice signal to the analog-to-digital converter in the unit's speech processor. Using an Intel 8085, the LPC-24's voice-oper-

Vogad. Voice-operated gain-adjusting circuit relies on 8085 microprocessor to suppress background noise and adjust gain to present optimized voice signal to LPC processor.



Technological leadership.



Isolate anything from AC to output with 7.5 kV linear & digital couplers.

Now you've got a choice—a fast, low-cost digital coupler for 5 V logic applications—or a state-of-the-art analog unit for linear designs.



Both offer tested and spec'd 7,500 kV peak isolation for top-drawer transient protection. Both are in standard, easy-to-design-with, 6-pin DIP packages. Both are stamped with a quality-ensuring Motorola trademark.

And they offer you the capability to isolate just about any input from any output, digital or linear.

High speed for low cost

If you can't afford ultra-fast, $6 digital couplers, try one with slightly less speed and a huge saving in cost... the MOC5005/6 for $2, 1K-up.

It turns on in 225 ns, is TTL-compatible, and fits right into interfacing computer terminals to peripherals, MPUs, digital power supply control, motors and other servo machine applications.

Actually an optically isolated gate, the units combine IRED, linear amp and output transistor to furnish faster-than-4N speed between high and low output modes. The circuit is current, voltage and temperature compensated and will sink an eight-gate fan-out (13 mA) from DTL, TTL, or CMOS with 5 V applied to the detector and 16 mA to the input.

It offers built-in hysterisis and internal pull-up resistor. And it's UL-recognized.

What if you're into linear?

We've got the MOC5010, the very first optically isolated AC amplifier in 6-pin DIP. Combining IRED and bipolar monolithic amplifier, it greatly simplifies circuit designs.

The MOC5010 maintains a 4 to 8 V output with V_{out} directly proportional to input current. All you do is bias the IRED, tie in V_{CC} at 12 V, capacitively couple out and let it go. It's a one-way street to simplicity.

AC information is passed from input to output, but the input is completely isolated from the output circuit, eliminating ground loop problems and preventing transfer of dangerous circuit conditions.

It offers 250 KHz typical bandwidth, 200 mV/mA gain and low-impedance emitter output of $< 200\Omega$. Use it for telephone coupling, peripheral equipment isolation, audio and other designs.

Send for MOC5005/5010 data sheets and isolate just about anything. Motorola Semiconductor Products Inc., P.O. Box 20912, Phoenix, AZ 85036.

Turning state-of-the-art discrete semiconductors and linear and digital ICs into high-volume standards for every application and industry is our forte. Technology, time after time, for your

Innovative systems through silicon.

MOTOROLA INC.

Reduced. E-Systems' LPC-24 speech processor knocks about $2,000 to $3,000 off the price of older generation military units.

ated gain-adjusting circuit is believed by Fulghum to be the first to be microprocessor-controlled.

Different. Current LPC speech processors have not used front-end gain-adjusting devices. Instead, they depend on 12-bit accuracy in sampling the voice waveform to take care of the differences between users who speak more loudly or softly than the average. Noise-canceling microphones might be one way to attack the problem. But this approach breaks down when the mike is not held within ¼ to 1 inch of the speaker's lips, Fulghum says.

E-Systems front-end intelligent Vogad (for voice gain-adjusting device) is programmed to drive its own analog-to-digital converter to sample the audio input waveform at 8,000 hertz. The 8085 can then determine whether the input is noise, speech, or a combination of both. If the input is noise only, it is suppressed. For a combination of speech and noise, a gain factor is calculated to optimize the signal-to-noise ratio going to the LPC-24 and to avoid overdriving its a-d converter. **-Wesley R. Iversen**

Memories

Mostek 64-K pin 1 follows Motorola's

A showdown may be looming as Southwestern semiconductor makers stake their claims for pinouts on 64-K dynamic random-access memories. Flash point is the use of pin 1—Mostek Corp. is joining Motorola Inc. in using it for refresh, but Texas Instruments Inc. has a no-connect on pin 1 of its 65,536-bit RAM.

Mostek's MK4164 will incorporate a pin 1 refresh function that the company says is functionally compatible with one of two refresh modes provided on the Motorola 64-K RAM introduced early this year [*Electronics*, Feb. 15, p. 141]. With samples this fall, the Mostek part will fit into systems designed for the automatic refresh function on Motorola's MCM6664—so long as the activating pulse lasts the entire refresh cycle. A self-refresh function like Motorola's for power-down operation will not be provided.

The automatic refreshing capability on the 4164 is patterned after the Carrollton, Texas, firm's recently introduced MK4816, a 2-K-by-8-bit pseudostatic RAM designed for the microprocessor market. The 4816's self-refresh mode was eliminated because it would have increased die size and power dissipation. Such shortcomings do not matter in small-system microprocessor applications but would be a major drawback in large mainframe memory banks where the new 64-K-by-1-bit RAMs are expected to find major use, says marketing manager Sam Young.

Others. TI says the no-connect approach in its TMS4164 introduced last fall is geared to mainframe and minicomputer makers. Main-memory users cannot benefit by a pin 1 refresh function, the firm says, adding that the feature also restricts flexibility as well as contributing to a larger die size. Motorola, on the other hand, says it designed its refresh functions only after extensive talks with the same users.

Other firms planning similar 16-pin, 5-volt parts include Intel, National Semiconductor, Fujitsu, Nippon Electric Co., and Hitachi—all reportedly with no-connect pin 1. (Mostek officials say they are not ready to announce detailed pricing and availability).

With auto-refresh, the 4164 eliminates external row-address strobes and synchronization hardware by generating the addresses internally. It can substitute for the TMS 4164 and similar parts, though it would require external refresh circuitry.

Other features of the part include transparent refresh, allowing the output to remain valid during a refresh cycle and thus eliminating data output latches; a low 10-milliwatt typical standby power dissipation; and a 1980 access time under 100 nanoseconds.

Like Motorola's part, the 4164 has a 128-cycle, 2-millisecond refresh time, which requires 512 on-chip sense amplifiers. TI's part has a 256-cycle, 4-ms refresh, thus halving the sense amps and easing the way for 256-K RAMs, the firm claims. Young concedes the 512 sense amps will require a die of 37,000 to 38,000 square mils, compared to TI's 33,300 mil², but says they are necessary in order to produce a part that will provide good yields. **-W. R. I.**

Trade

Message to Japan: open up NTT market

The White House and U. S. trade officials are prepared to lay it on the line during the hastily arranged visit of Japanese foreign minister Sunao Sonoda scheduled for this week. Their object is to convince Japan that it must open its telecommunications market to competition from U. S. equipment makers.

Robert Strauss, U. S. special trade representative, broke off talks with Japan late last month, calling its offer to open $5 billion in government procurement to foreign competition "wholly inadequate." He singled out Japan's proposal for strictly limited procurement from U. S. bidders by the Nippon Telegraph and Telephone Public Corp.

The Japanese offer is less than half of the more than $10 billion worth of nonmilitary goods and services that the U. S. proposes opening to foreign bidders. Unless Japan improves its offer before June,

Spend less. Test more.

Integrated circuits are very private devices. When something goes wrong, they just don't work. Which is tough enough when part or all of *one* IC goes bad. But often worse, because a single bad IC usually means a large, complex system that won't function properly.

Until now, you could spend a lot of money and time—and still only be guessing what was happening at any point in a logic system.

Logic Probe LP-1. Captures pulses as fast as 50 nanoseconds, to 10MHz. Latching memory. Bargain-priced at only $44.95*.

CSC puts troubleshooting at your fingertips. Now, there's a quicker, surer, less expensive way to get the information you need. CSC multi-family Logic Probes. Their LEDs light to show you at a glance the logic state at any point—and more. Catch fast pulses, even store them if you like. A flashing light signals pulse trains. And you can even approximate the duty cycle of asymmetrical waveforms.

Nothing could be simpler. No complex settings, no sync, no wait. A switch selects the proper logic family. The probes derive their power from the circuit under test. High input impedance prevents circuit loading. And all you do is touch the tip to any pin, pad or path for an instant picture of circuit conditions.

Logic Probe LP-2. All the basic features of LP-1, with pulses as fast as 300 nanoseconds, to 1.5MHz. Doesn't have LP-1's memory feature . . . but features even lower price: $24.95*!

Laboratory quality. Economy price. High speed. High precision. Even memory. CSC Logic Probes deliver all the performance you need for design, development, debugging and servicing. Making digital work less of a chore, more of a bargain. CSC for yourself!

Logic Probe LP-3. Five times the speed of LP-1 at less than twice the price. Captures pulses as narrow as 10 nanoseconds, to over 50MHz. Latching memory. The new value standard, at $69.95*.

Call **1-800-243-6077** toll-free for details

CONTINENTAL SPECIALTIES CORPORATION

CSC

70 Fulton Terr., New Haven, CT 06509 (203) 624-3103, TWX 710-465-1227
OTHER OFFICES: San Francisco: (415) 421-8872, TWX 910-372-7992
Europe: CSC UK LTD. Phone Saffron-Walden 0799-21682, TLX 817477
Canada: Len Finkler Ltd., Ontario

* Suggested U.S. resale. Available at selected local distributors. Prices, specifications subject to change without notice. © Copyright 1979 Continental Specialties Corporation

when industrialized nations will hold a summit meeting in Tokyo to approve the treaty, the U. S. will sign with a reservation excluding the Japanese from any of the bilateral provisions.

The U. S. Government makes clear it is unhappy with more than the value of proposed Japanese buys. The rigid limitations in the proposed telecommunications procurements would restrict foreign suppliers to items like steel telephone poles and test equipment. "There should be no misunderstanding," says one U. S. official. "NTT will have to open a significant share of its transmission and terminal equipment markets," initially about 1% of its estimated $3.3 billion annual procurement budget.

The Government official says Strauss had little choice but to break off negotiations in view of rising congressional criticism of Japan's position on NTT equipment buys. He says Strauss suspects that, unless Japan relents on the NTT issue, the treaty might not pass Congress.

Limits. Angry U. S. telecommunications industry lobbyists are persuading Congress to limit Japanese imports into the growing and increasingly competitive domestic equipment market unless Japan complies. "The bedrock issue is that their market is closed and ours is open," says John Sodolski of the Electronic Industries Association, "and there are only two ways that problem can be resolved." This statement by the vice president of the EIA Telecommunications division reflects growing U. S. resentment of Japan's unbending trade stance.

Of NTT's reported concerns that foreign equipment might not meet Japanese standards and might thus damage the network, the Government official responds, "That sounds like an old AT&T argument a few years ago, one that they have long since dropped. There is a simple solution: NTT can draft its own equipment specifications in every category before it opens them to offshore competition, permitting only suppliers meeting them to participate." **-Ray Connolly**

Microwaves

Test ranges stir citizens' ire

Activist groups in Massachusetts have brought suit against two electronics firms to prevent them from installing microwave test ranges. The groups' concern is that the ranges—the kind used since the 1940s to map an antenna's beam pattern, a task done with 1 watt or so of power—will harm people's health by exposing them to microwaves.

"You can't fight emotion with logic," points out John M. Osepchuk, 59, a consulting scientist at Raytheon Co., Lexington, Mass., and an acknowledged expert on the biological effects of microwave energy. Raytheon, a $3-billion-a-year conglomerate, wants to install a range in nearby Wayland. The other company, Radant Systems Inc., a small consulting and antenna testing firm in Wayland, wants to build its range in Stow, also nearby.

It took months for Raytheon to get a permit from the town of Wayland to construct its range. Then, on March 9, both the town and Raytheon were slapped with a citizen's suit aimed at stalling or preventing construction of the range.

Unknown. It's what they don't know that bothers Wayland residents. George W. Faison, a 39-year-old English teacher, admits that he has little technical knowledge of the subject, but he backs the complaint against Raytheon. "Our major concern is that there are few standards for exposure, and those that exist differ and are arbitrary," he says.

Like many others, he worries about biological effects: "I am told that microwave exposure can increase the incidence of cancer, particularly of leukemia. But nobody can tell me what the certain effects of long-term, low-level irradiation are." If it is safe, "the burden of proof is on the industry, not on us," he concludes.

When Radant's plans for a range in Stow became known, handbills appeared saying: "Do you know: Microwaves are known to cause blindness and other harmful effects; radars are usually high power [sic] and dangerous at long range . . . such antennas have sidelobes in their radiation patterns [and] radiation will 'splash' in many directions." It also warns "Military contracts are anticipated. YOU will be subjected to microwave radiation!!!"

Figures. In response, Richard H. Park, president of Radant, did some math for Stow residents and showed that, 2,000 feet away on a road directly in front of the antenna, exposure would be about 0.1 microwatt per square centimeter, whereas exposure at a sidelobe would be only 0.003 microwatt.

In comparison, the Soviet Union's upper limit for exposure of civilians is 5 μW, though the exposure duration is not specified. The United States has no similar standard, but it is working on one; so far no nation has a standard for long-term low-level exposure.

The lack of standards, and Paul Brodeur's book, "The Zapping of America," which warns of an America awash in dangerous microwave radiation, have fueled the concern of many in the general public. (Scientifically educated reviewers have roundly criticized the Brodeur book for what they say are the questionable references on which it bases its hazard claims.)

The demonstration by Park did not assuage concern. "People are asking us questions that we engineers cannot answer—and shouldn't really," Park says. "The information they want has to come from the medical profession, and that's going to take upwards of 10 years."

Smaller. Radant has been hauled into court by two residents whose land abuts the company's and who are demanding a halt to the project. In response, Park insists that the power densities his firm will generate in Stow will be only one ninth those measured by the U. S. Environmental Protection Agency in the heart of Boston: "If Stow has a problem, which I doubt, then Boston has a bigger one." On the other hand,

5 DAY DELIVERY

Microcomputer Analog I/O Systems



For:

DEC LSI-11 & LSI-11/2 (FORTRAN SUBROUTINES AVAILABLE for RT-11)
DEC PDP-11 UNIBUS
INTEL SBC-80 Series & NATIONAL BLC-80 Series
ZILOG MCB Series (Z-80)
MOSTEK/PROLOG STD BUS
COMPUTER AUTOMATION LSI 2, 3, & 4 Series

Precise analog I/O for any micro.
Data Translation manufactures the largest array of analog I/O modules and systems in the industry.
Standard interfaces for every major microcomputer. From isolated inputs to extremely high-speed inputs. Designed to meet your most stringent data acquisition needs in a wide range of measurement and control applications.

Highly reliable systems in only 5 days.
Our goal is to ship the most reliable analog I/O systems available anywhere. That's why we go to such great lengths to ensure the highest reliability.

Delivery? We doubt that you'll find any company faster than **DATA TRANSLATION.**

We assure five-day delivery. When you order on Monday, we deliver by the next Monday.
No excuses. No delays.

SEND for Full Technical Data or Call us.
GSA Contract No. GS-00S-64219

DATA TRANSLATION INC
4 Strathmore Rd., Natick MA 01760
(617) 655-5300 Telex 948474

Circle 49 on reader service card

U.S. SALES OFFICES: AL (404) 455-7222; AZ (602) 944-5400; CA (408) 244-5508, (213) 681-5631; CO (303) 371-2422; CT (203) 622-9191; DC (301) 636-1151; FL (305) 274-4899, (813) 725-2201; GA (404) 455-7222; ID (801) 466-6522; IL (312) 297-2616; LA (713) 780-2511; MD (301) 636-1151; MN (612) 488-1129; NC (919) 723-8102; NJ (516) 488-2100, (609) 428-6060; NM (505) 292-1212, (505) 523-0601; NY (516) 488-2100; OK (405) 528-6071; PA (609) 428-6060, (412) 327-8979; SC (803) 233-1469; TN (404) 455-7222; TX (512) 451-5174, (214) 661-0300, (505) 523-0601, (713) 780-2511, (512) 828-2251; UT (801) 466-6522; WI (414) 567-0444; CANADA (416) 625-1907,

"We're being asked to prove a negative," Osepchuk says, "and it's almost impossible to prove that there will never be any long-term effect at all." **-James E. Brinton**

Companies

Intel sets up plants in Phoenix

The rush among Silicon Valley semiconductor firms to do their expanding outside of California picked up speed late last month when Intel Corp. officially announced its big move into the Phoenix area. The Santa Clara, Calif., firm says it is opening two new plants there.

A 150,000-square-foot facility in Deer Valley, northwest of Phoenix, will be operating as part of its Commercial Systems division by July, building memory boards for end users. The second is a single-chip microcomputer plant in Chandler, southeast of Phoenix, scheduled to start up in late summer.

Rumors circulating throughout the industry on the basis of Intel's first recruiting forays in Arizona hold that at peak employment possibly 5,000 personnel will be required across the board. Declining to comment more specifically, Intel's director of business development Jerry Diamond does make it clear that Intel's decision was influenced by the abundance of technical and assembly talent in Phoenix, compared with other areas.

"We're taking as few [with us] as possible," says Diamond of Intel's staffing plans. "By transplanting only a nucleus we can build around it from the Phoenix area and by recruiting from the entire U. S."

Intel's choice of Phoenix is an important sign for several reasons, in the opinion of a veteran industry consultant who counsels firms on moving (but not Intel). Recognition of the Arizona site's obvious advantages shows semiconductor firms are getting "smarter about such things," says Glen Madland, president of Integrated Circuit Engineering Corp., Scottsdale, Ariz. "Semiconductor firms have been very unsophisticated in terms of site selection." The result was that they often plunged into new geographical areas without fully weighing the pros and cons, he continues, and had to pay for the move in delays, personnel problems, and lost production.

An example is the way Motorola moved its microprocessor and memory operations to Austin, Texas, in 1975–77. "That was a mistake that other firms have learned by," Madland says. Motorola tried to transfer most of the people it needed, but turnover of more than 75% severely hampered getting the plant on stream. "They should have recruited them in Texas," says Madland, a lesson that Intel and others have learned well. Reportedly, Intel considered going not to Phoenix but to Colorado Springs, where Texas Instruments Inc. and Inmos Ltd. are opening plants. But Phoenix's obvious attraction tipped the scale. "Over the years Motorola has built a good labor pool of maybe 30,000 people," Madland says.

In addition to Intel and Motorola, other firms already in some form of the semiconductor business in the Phoenix area include: General Instrument, EMM Semi Inc., General Semiconductor, Northern Telecom, and Medtronics. There are also growing LSI commitments by California minimaker General Automation and the West German–based

News briefs

Dutch firm to test compatible 3-d TV system

With engineering help from American researchers, Digital Optical Technology Systems B. V. of Amsterdam has developed an optical/electronic system that allows TV broadcasters to beam three-dimensional pictures into the home. The system, to be installed next month at a TV station in Australia, is compatible with all existing broadcasting standards and TV sets, but the viewer must wear special glasses to see the 3-d effect.

Unlike existing 3-d systems, which create two images that simulate depth, the Dutch system uses lenses and color filters to color-code the extent a foreground or background object is out of focus relative to the camera's focal plane. A sophisticated digital electronic system then enhances the coloration, but restricts it to an amount unnoticeable without the special glasses, which contain two color filters to defocus color-coded objects to their original depth. Demonstration at U. S. TV stations is planned.

Hogan to retire from Fairchild

C. Lester Hogan, 59, whose career is practically synonymous with the rise of the semiconductor industry, is retiring as vice chairman of Fairchild Camera and Instrument Corp., Mountain View, Calif., effective with the company's May 4 annual meeting. He will continue as a member of the board and special consultant to president Wilfred Corrigan, whom he brought to Fairchild, and he will serve his second term as executive vice president of the Institute of Electrical and Electronics Engineers.

Sharp puts rolling displays into calculators

Filling the gap between hard-to-use programmable and expensive but limited-function scientific calculators, Sharp Electronics Corp. of Japan has introduced two new models with rolling alphanumeric displays. Each permits direct entry of algebraic and trigonometric equations that appear, as they are entered, on a liquid-crystal five-by-seven-dot matrix display of 24 or 16 characters. After the equations have been entered, the user switches to the compute mode and punches in constants and coefficients. The unit then solves for unknown variables or uses the equation as a subroutine in a larger expression of up to 80 steps. Both models use low-power complementary-metal-oxide-semiconductor circuits that allow the internal battery to store up to five expressions after the unit is turned off. When available in stores this August, the 24-character 5100 will retail for a price of $99; the 16-character 5101 will sell for $80.

EDUARD RHEIN PRIZE 1979

US $ 64.000 FOR TELEVISION RESEARCH

In agreement with the Advisory Council of the Eduard Rhein Foundation, the Board of Governors has issued the following guidelines for the Eduard Rhein Prize 1978:

1.

The Eduard Rhein Prize shall be awarded each year for outstanding work in the field of further development of television technology.

The special field of endeavour for the Eduard Rhein Prize 1979 shall be as written hereinafter:

For a significant contribution to the improvement in the performance of the total television system (picture quality or capability) that can be appreciated by the general viewer. This contribution can be both the improvement or development within the scope of present television or pointed to the future.

2.

The Eduard Rhein Prize 1979 shall be endowed with DM 100.000,-- (approx. US $ 54.000) at time of going to press.

3.

As a once-only special prize for a substantial improvement in the direction of the larger telescreen and higher performance, the Eduard Rhein Foundation makes a sum of US $ 10.000 available.

4.

Applicants for the Eduard Rhein Prize 1979 and the Special Prize shall only be nominated by experts, as well as by organizations or institutions, active in research in the field of television technology. Papers may be submitted from all over the world.

5.

a) The closing day for entries shall be August 15, 1979 (the date of the postmark shall be decisive).

b) The documents shall be sent to the Board of Govenors of the Eduard Rhein Foundation, Kloepperstieg 3, 2000 Hamburg 67, Federal Republik of Germany.

c) Said documents may include the following:
Research report.
Internal laboratory report.
Papers submitted for publication.
Papers which have already been published.

6.

a) The documents shall be in the German or English language.

b) The documents shall be submitted sevenfold, typewritten or printed.

c) The documents shall, as a rule, not exceed 20–30 typewritten pages. Should the contents of the research paper demand a more comprehensive exposition, then the documents shall be preceeded by a summary which shall not exceed 20 typewritten pages. In addition, each paper shall be accompanied by a summary of the significant research result; said summary shall not exceed one typewritten page in length.

d) A short curriculum vitae describing the applicant's scientific career shall be included with the documents.

7.

Upon the recommendation of the Advisory Council of the Eduard Rhein Foundation, the Board of Govenors of the Eduard Rhein Foundation shall decide as to the awarding of the Eduard Rhein Prize 1979 and the Special Prize.

In the event that no entry worthy of being awarded the Eduard Rhein Prize 1979 or the Special Prize respectively is submitted, that Prize shall not be awarded.

There shall be no legal means of redress against the decisions of the Board of Govenors.

8.

For the complete guidelines and rules applying to the Prize, write to the Board of Governors, Eduard Rhein Foundation, Kloepperstieg 3, 2000 Hamburg 67, Federal Republic of Germany.

The members of the Advisory Council of the Eduard Rhein Foundation are: Prof. Dr. Ing. E. h. Walter Bruch (Chairman), Hannover; James Hillier, Princeton, N.J.; Joseph Polonsky, Paris; Prof. Karl Tetzner, Munich; Dr. Frederik W. de Vrijer, Eindhoven.

Circle 51 on reader service card

MITEL

BI-DIRECTIONAL OCTAL BUS TRANSCEIVERS WITH 3-STATE OUTPUT DRIVERS

MITEL's ISO-CMOS™ 54C245/74C245
VS
THE TTL 54LS245/74LS245

SAVE on Power Supply Requirements
- Wider operating voltage range— 3V to 6.5V **VS** 5V±10%
- Lower current drain— 1 mA **VS** 100 mA

REDUCE Generated Noise
- Controlled output rise and fall times— >15nS **VS** <15nS

REDUCE dc Loading of Bus Lines
- Lower Input/Output leakages— 10μA **VS** 100μA

NO LOSS in System Performance
- Propagation delays— 15nS **VS** 12nS

SAME 20-Pin Packages

Contact the leader in CMOS technology for more information:

1745 JEFFERSON DAVIS HWY
SUITE 611
ARLINGTON, VA. 22202
TEL 703-243-1600

MITEL Semiconductor

Here are the choices

With several clients now involved in evaluating new plant locations, Integrated Circuit Engineering's Glen Madland is up to date on what they should be looking for. At the top, of course, is a good labor pool of not only engineers and scientists but assembly and support people as well. Schools at the university and vocational level are important, as are zoning, transportation, and local attitudes toward business. What should be obvious, but is often ignored at the expanding companies' peril, is a basic rule especially critical to semiconductor firms: "Never be the first into an area. In other words, don't be a pioneer."

All areas contemplated for expansion by semiconductor firms are in the Western United States. As summed up by Madland:

- Phoenix with all the ingredients in good supply "still has room left for semiconductors to grow in."
- Colorado Springs, Colo., with many new arrivals, and Albuquerque, N. M., just starting to take off, have many of the advantages of Phoenix and are right behind it.
- "San Diego is the last part of California with a chance and Texas is not all that bad." Also, Salt Lake City has some things to say for it, and several firms are going in.
- One previously well-thought-of place, Oregon, is dropping out as a site. "It's not as good as companies thought it would be," he remarks. Madland's information indicates that it is difficult to persuade people there to work overtime, especially on weekends, and also tougher to recruit working wives than elsewhere because they do not want to drive more than five miles.

giant Siemens. Other Silicon Valley firms with plans for operations elsewhere include Advanced Micro Devices in Austin, National Semiconductor in Salt Lake City, Signetics in Orem, Utah, and Zilog in Boise, Idaho. Intel already has operations in Aloha, Ore. **-Larry Waller**

Lasers

RCA boosts stability of planar diode

Stabilizing the power output of a laser diode is not easy, especially if the device is designed to have a planar construction. Yet planar is the preferred approach because it is the easiest to fabricate of all the semiconductor diode geometries. So recent research at RCA Laboratories in Princeton, N. J., to overcome the instability with a new planar geometry is particularly welcome.

The new diodes are stable even when their drive current increases much above the laser threshold operation level. This increase is necessary for signal modulation but has been difficult to achieve while maintaining stability. The lasers also combine "continous-wave operation in a single spatial and temporal mode," says Dan Botez, a member of the RCA technical staff. This combination enhances their stability even more.

Botez developed the diode, dubbed a "double-dovetail" constricted double-hetero laser, out of the same material—aluminum gallium arsenide—as other solid-state lasers. But before the needed epitaxial layers are deposited on the gallium-arsenide substrate, two adjacent dovetail-shaped channels are etched into its face. This geometry accurately locates and confines the generating spot of laser light to a space between the dovetails.

A superior device. The double-dovetail structure is easier to fabricate than other structures that lead to single-mode operation, Botez says. This is because the mesa and channel patterns are visible on the top surface of the device. Therefore, alignment of the laser contact stripe with the constricted active region is a simple task.

Optical power comes out of the diodes in the near-infrared region of

THIS IS KONTRON

Kontron's family of multimeters ranges from our $195 DMM 3020 to our unique Calculating Programmable Voltmeter (CPV 4). Our multimeters feature elegant craftsmanship and rugged metal cases that provide excellent EMI shielding.

Some standard features of our DMM 3020 include:

- Up to 3000 counts with full specs
- Built-in charger for standard Ni-Cad batteries
- Current measurement to 10 A

Get our data sheets for all the technical details and the name of a Kontron sales and service organization near you.

Write or call
Kontron Electronic Inc.,
700 South Claremont Street,
San Mateo, California 94402.

MULTIMETERS:

FOR DATA ON KONTRON® MULTIMETERS, COUNTERS, PROM PROGRAMMERS AND PRINTERS, CALL (800) 227-6854. IN CALIFORNIA CALL (415) 348-7291.

Circle 53 on reader service card

Another new Sigma relay

New Series 49 is a general purpose relay for both printed circuit and chassis mount applications. SPST or SPDT, it occupies just one cubic inch. Prices start at only $1.86 in 100 quantity and delivery is from distributor stock.

This versatile relay, available in a variety of terminal arrangements, is especially suitable where space, low cost and long life are important.

Send for new catalog describing the complete Sigma line of relays, opto-isolators and photo-electric controls.
Sigma Instruments Inc., Braintree, Mass., 02184.
(617) 843-5000.

SIGMA
INSTRUMENTS INC



Circle 54 on reader service card

1978 Electronics Buyers' Guide

The only book of its kind in the field. If you haven't got it, you're not in the market.

To insure prompt delivery enclose your check with this coupon.

1979 edition available in June.

Electronics Buyers' Guide
1221 Ave. of the Americas
New York, N.Y. 10020
Yes, please send me _____copy(ies) of 1978 EBG.
☐ I've enclosed $25 per copy delivered in the USA or Canada.
☐ I've enclosed $35 per copy for delivery elsewhere ($47 if shipped by Air). Full money-back guarantee if returned in 10 days.
Name
Company
Street
City State Zip

820 to 860 micrometers. In addition, the optical beamwidth is typically less than 0.009 μm, and this highly monochromatic signal ensures that the fiber-optic carrier frequency for any communications application is extremely well defined.

Applications. Future high-speed fiber-optic communication systems will use single-mode operation with as small a diameter fiber as possible (typically 4 to 5 μm) to keep attenuation low. The new laser diode will be useful here since the laser-light-emitting region is constricted by the novel geometry to a physically narrow beam only 10° to 35° wide.

What is more, Botez notes, "the light spot is only about 2.5 μm in diameter. This means that up to 70% of the optical power that's emitted can be put into a single-mode fiber with a numerical aperture of 0.1—a typical case."

Earlier diodes had their emitting region much larger than the fiber-core diameter, wasting much power. This was recognized as a problem early on, and, as Botez observes, "RCA is not alone in developing monochromatic narrow-beam single-mode diodes. Much work is going on in Japan. Those diodes, however, are more complicated to fabricate."

Dynamic range. Samples of the double-dovetail laser have shown linear variations in power output as a function of current drive level up to powers of 25 milliwatts. In a typical communication system, this translates into modulation capabilities and a dynamic range that are not available with conventional laser devices. At the higher power levels, operation is multimode and suitable for currently available multimode optical fibers.

The lasers operate both in the continuous-wave and pulsed modes, and at temperatures of up to 70°C to boot, without the usually expected kinks in the power-current curve. These distortions can cause system nonlinearities. Lifetime—that bugaboo of the fiber-optics industry—is not yet established by statistically significant data, but Botez says that "samples have been tested up to 3,000 hours." **-Harvey J. Hindin.**

THIS IS KONTRON

Model 6001 Autoranging Counter/Timer with a programming option.

Kontron offers you a variety of counter/timers from our $345 Model 6003 universal counter/timer to our high performance, autoranging Model 6001 that sells for only $695! All our counters are housed in elegantly-crafted metal cases. Some of our high-performance features include:

- Autoranging in all modes (Model 6001)
- 10 mV sensitivity to 1.2 GHz (Model 6002)
- Selectable frequency ranges to 1.2 GHz (Model 6003)

Get our data sheets for technical details and the name of the Kontron sales and service organization near you. Write or call Kontron Electronic, Inc., 700 South Claremont Street, San Mateo, California 94402.

COUNTERS:

FOR DATA ON KONTRON® MULTIMETERS, COUNTERS, PROM PROGRAMMERS AND PRINTERS, CALL (800) 227-6854. IN CALIFORNIA CALL (415) 348-7291.

Circle 55 on reader service card

Use the multimeter of tomorrow...

...today.



Free yourself for more creative tasks... the intelligent Calcumeter way.

Our custom CMOS microcomputer turns a handheld 3½-digit DMM into an automatic measurement processor... At the touch of a button you program the battery-powered Calcumeter™ to perform complex chores that can save you hours every week!

- Convert transducer signals automatically to engineering units of temperature, pressure, 20mA current loops, etc. (Mx + b key).
- Measure current without breaking into the circuit (Mx + b key), $I = \frac{V}{R}$
- Average away noise (AVG key).
- Sort components, using the HI-LO LIMITS mode (both "analog" display and audible alarm!).
- Use the LIMITS mode as a universal logic probe.
- Read out audio signals and amplifier gain in dB (dBV key).
- Test % tolerance or power supply regulation (% DEV key).
- Determine parallel or shunt resistance (xy/x + y key; xy/x-y key).

The Calcumeter offers you escape from much of the chore work connected with design, testing and maintenance, enabling you to spend more time in creative tasks. It pays for itself in a few months, often on the basis of one application alone. They are now available from regional distributors at the same low price of $389.



For the basic price of the Calcumeter you receive test probes and clips, handbook and storage/desktop case.

Calcumeter with accessory DataLogger—low cost, remote data processing system.

calcumeter $389 U.S.A.

The intelligent new way to measure V-Ω-A.

Call toll free for nearest distributor—
800-547-5637 or send for 12-page
full color brochure

esi ELECTRO SCIENTIFIC

Electro Scientific Industries, Inc.
13900 NW Science Park Dr.
Portland, Oregon, USA 97229
Telex 36-0273 • Telephone (503) 641-4141

See Calcumeter at Electro—Booth 2228

Circle 56 on reader service card

Washington newsletter

Consumer imports rise 18% in 1978 to $4.6 billion . . .

American imports of home entertainment electronics jumped sharply once more in 1978 to nearly $4.6 billion, 18% more than 1977's total $3.9 billion, with Japan accounting for almost 56% of the total with more than $2.5 billion. New Commerce Department figures show that, although imports of color television receivers from Japan dropped 29% to 1.4 million units as a result of Orderly Marketing Agreement controls, Japan earned $105 million more last year—a 4.3% gain from 1977. **The reason: sharp increases in unit shipments of color video cassette recorders and higher prices for a smaller number of audio tape recorder-players,** reflecting a continuing shift to top-of-the-line exports to the U. S. plus appreciation of the yen. Even though VCR imports rose 129% to 480,000 sets last year, there still are no domestic manufacturers. Audio tape equipment imports dropped nearly 30% to just under 20 million units, yet the dollar value rose 34% to $1.5 billion.

. . . Korean color TV shipments up 350%; Taiwan gains 94%

Taiwan and South Korea ranked second and third with growing import market shares of $733 million (16%) and $355 million (7.8%), respectively. Both registered major gains in color TV shipments. Orderly Marketing Agreements with those countries on color TVs just went into effect Feb. 1 after 1978 shipments from South Korea soared 350% to 430,000 sets, **largely from Japanese affiliates,** while Taiwan scored a 94% increase to 624,000 units.

U. S. is lazy in export competition, Strauss complains

U. S. industries are making "real bum" efforts compared with Japan and West Germany to expand export markets, says Robert Strauss, special trade representative for President Carter. He told a Senate subcommittee early this month that part of the reason this country's comparative lack of competitiveness in world trade is that **"we've gotten lazy because we've got a real fat, easy market right here."**

Responding to questions by the Senate select subcommittee on Government procurement, Strauss explained, "Today there are probably 12,000 to 15,000 very competent Japanese individuals in New York selling Japanese products against American products. They speak good English. In Japan, there are maybe 75 Americans, and maybe two speak Japanese." Given those circumstances, Strauss says, "you know how we'll come out."

Jamming of JTIDS seen possible threat to air traffic control

The possibility exists that intentional jamming of the triservice Joint Tactical Information Distribution System (JTIDS) now in development might interfere with international air traffic control functions sharing the same 960-to-1,215-MHz band. This prospect is causing concern among some member nations of the International Civil Aviation Organization (ICAO). But the Pentagon says that the **JTIDS spread-spectrum approach will use its antijam frequency-hopping techniques across only 190 MHz of the 255 MHz in the band and avoid civil aviation frequencies.** JTIDS is a multibillion-dollar integrated system that will provide navigation, communication, and identification functions for military aircraft, ships, land vehicles, and installations. In addition to military assignments in the 960-to-1,215-MHz band, the Federal Communications Commission says the band is used by distance-measuring equipment, which tells an aircraft the distance from radio beacons, and by the air traffic control radar-beacon system, which provides aircraft identification and altitude.

Washington commentary

Kicking a lazy Government

A number of U. S. electronics executives are, to say the least, unhappy with special trade representative Robert Strauss's generalization about U. S. industries. He said they are both lazy and incompetent when it comes to competing with Japan and West Germany in the world's export markets. A relative newcomer to the world of international trade negotiations, Strauss might have expressed himself more diplomatically in his Senate testimony (see p. 57). Yet his political instincts probably told him that any softer phrasing would have gone unnoticed outside the hearing room.

While Strauss is certainly correct in his observation that there are many more Japanese businessmen who speak English than there are Americans who speak Japanese, he overlooks the fact that Japanese public schools require a minimum of six years of English language training. There is no comparable program in U. S. schools because America was not subject to occupation by Japanese armed forces at the end of World War II.

Moreover, economic history shows that the United States has never ranked among the great trading nations because, as Strauss puts it, "We've got a real fat, easy market right here." Thus America, unlike Japan, has never cultivated a sense of urgency about trade.

It is not that many managers in U. S. industries have become lazy—rather, they have never recognized the need to trade in a global marketplace as other nations recovered from the wartime disaster of World War II and began challenging U. S. economic superiority. That may make those managers open to charges of shortsightedness and overconfidence, but no more so than the governments that have been elected to lead them.

The quick fixes

While Robert Strauss is negotiating hard to get Japan to open Nippon Telegraph and Telephone Public Corp.'s $3 billion annual market to U. S. bidders, as well as eliminate other inequities in the trade relationships between the two countries, his superiors in the White House need to do a great deal more at home to encourage domestic manufacturers to export more.

For the short term, the White House should immediately push for a realistic upgrading and simplification of computer export controls. As these are now, they tend to discourage direct U. S. exports while encouraging American computer makers to set up plants overseas. Though disagreeing on particular points, the manufacturers all agree that Government export procedures are both antiquated and overly long.

Similar problems exist when it comes to domestic enforcement of U. S. antidumping laws, as manufacturers of home entertainment electronic products have long insisted. "The long periods of time required to conduct investigations, and delays averaging 3 to 3½ years in assessing duties after findings of dumping, make it highly improbable that U. S. industry is being adequately protected" by its own Government, reports the General Accounting Office. What is left of the domestic television receiver industry learned that long ago, of course. Its complaints of Japanese dumping of color TV sets are still unresolved after 11 years.

As the investigative arm of Congress, the GAO also reported to legislators that even though the International Trade Commission and the Departments of the Treasury and Commerce all have roles in enforcement of antidumping laws, there is still no reliable data on the extent of dumping and its impact on national production and jobs. Worse yet, there is no Government program to assess the damage, much less take action to correct it.

Making a policy

What these criticisms say in sum is that the United States, the world's largest and richest marketplace, has no comprehensive trade policy. If the White House won't move to change that, then Congress should.

Perhaps the best recommendation thus far has emerged after a year of study from the Senate Banking subcommittee on international finance. It calls for the establishment of a new Department of Trade that would consolidate trade responsibilities now divided among the Departments of Agriculture, Commerce, State, and Treasury, as well as Strauss's office, the ITC and the Export-Import Bank. Citing the proposal's similarity to Japan's Ministry of International Trade and Industry, one electronics manufacturer smilingly concedes that "no one can say we are unable to learn from the Japanese."

-Ray Connolly

IN WAFER IMAGING SYSTEMS, "AUTOMATIC" IS THE NAME OF THE GAME.



THE ELECTROMASK MODEL 700SLR™ WAFER STEPPER™ HAS MORE AUTOMATIC FEATURES THAN ANY OTHER SYSTEM.

As circuits grow, densities increase, and line-widths shrink – wafer imaging systems must be advanced enough to meet the user's newest requirements. The Electromask Model 700SLR Wafer Stepper is the most sophisticated wafer-imaging system available today, and – like all Electromask systems – its key features and provisions for future enhancement have all been designed in from the start.

Just compare these features of the Model 700SLR with those of any other system. Then you be the judge.

(1) Automatic Reticle Loading that changes reticles without the operator opening the chamber door and manhandling the reticle.

(2) Automatic Reticle Alignment that provides better accuracy resulting from the consistent automatic performance.

(3) Automatic Reticle Masking of the portions of the reticle outside the scribe lines.

(4) Automatic Wafer Loading and Unloading of up to 25 wafers per cassette.

(5) Automatic Wafer Prealignment that accurately positions and orients the wafer for quick visual target acquisition during final alignment.

(6) Automatic Wafer Leveling to adjust for wafers having a gross wedge of up to four mils.

(7) Automatic Focus that employs a closed-loop air-gage system and allows exposures to be made to the wafer edge with no wasted surface.

(8) Through-the-lens Wafer-to-Reticle Alignment by remote-control with monitoring at 4000X magnification for higher resolution and greater accuracy.

(9) Provision for Automatic Wafer-to-Reticle Alignment designed into the system for future field retrofit.

(10) Fully Automatic Design Concept of Model 700SLR resulting in a stability that provides a machine-to-machine compatibility of less than 1 micron.

No other 10:1 wafer imaging system available today offers all these features. And, as the competition hurries to catch up, you can be sure that Electromask will continue always to stay one step ahead.

For the full story on today's most advanced wafer imaging system, call or write for our Model 700SLR brochure. Inquire now about a system demonstration.

Electromask, Inc., a subsidiary of the TRE Corporation, 6109 De Soto Avenue, Woodland Hills, California 91367. Phone: (213) 884-5050, Telex 67-7143.

TRE

ELECTROMASK

TM – Model 700SLR and Wafer Stepper are trademarks of Electromask, Inc.

Circle 59 on reader service card

Instant access to all American and International

Data Communications Standards



Data communications standards are undeniably necessary and helpful. But... the proliferation of standards by the many committees and groups has left the data communications equipment user and designer searching through numerous publications to find the applicable standards for each job.

Now: that time- and effort-wasting trial is over.

With the publication of this landmark resource, you can quickly and accurately determine exactly which standards apply to the project at hand, and speedily integrate those standards into your own network requirements.

Presents all relevant data communications standards promulgated by:

- Consultative Committee for International Telephone and Telegraph (CCITT)
- International Organization for Standardization (ISO)
- American National Standards Institute (ANSI)
- Electronic Industries Association (EIA)
- Federal Telecommunications Standard Committee (FTSC)

Need to know the latest standards for...

- data transmission over public data networks?
- computers and information processing systems?
- peripheral equipment?
- signal quality and analog and digital interfaces?

It's all here, and more, complete with introductory descriptions of the groups that promulgate the standards... and relational charts of similar interfacing standards produced by different groups.

Edited by
HAROLD C. FOLTS, data communications standards consultant; and
HARRY R. KARP, Editor-in-Chief, *Data Communications*, McGraw-Hill Publications Company
1133 pages

Design Engineers
Find the technical specs you need instantly.
Planning Engineers
Determine which standards apply to a vast range of networks and components.
Operations Managers
Learn whether the equipment you're buying will operate at all applicable standards.

Order today using this coupon!

Return coupon to:
Data Communications Standards
P.O. Box 669
Hightstown, New Jersey 08520

Send me _____ copy (copies) of **DATA COMMUNICATIONS STANDARDS** (099782-9) on a 10-day money-back guarantee. I understand that if I am not absolutely satisfied, I may return the book(s) within ten days at no further obligation. Otherwise, McGraw-Hill will bill me $165. for each copy, plus applicable sales tax, shipping and handling charges.

Name _____
Title _____
Company _____
Address _____
City _____ State _____ Zip _____

SAVE MONEY! Enclose payment in full, plus local sales tax, and McGraw-Hill pays all regular shipping and handling charges. Ten-day money-back guarantee still applies.

_____ Check enclosed _____ Bill me _____ Bill my company _____ Company purchase order #

This offer subject to acceptance by McGraw-Hill.

EL 1

CREATIVE 6800 ARCHITECTURE



In the future microcomputers will help extend architecture beyond our most extravagant visions. Buildings will actually be computers that are sensing, monitoring and controlling environments to an unprecedented degree of comfort and safety. Even today the possibilities are only limited by our imagination.



CREATIVE FLEXIBILITY

Creative Micro Systems manufactures a line of general purpose microprocessor support modules. These M6800-based devices are pin and outline compatible with the industry standard EXORciser* and Micromodule* bus. Original Equipment Manufacturers can benefit by the use of these modules as the building blocks for end products. Their flexibility and adaptability has been proven by applications in data acquisition, data communication, materials testing, process control and agriculture.

*Trade Mark of Motorola, Inc.

BEST OF BOTH WORLDS

Concentrate on the best solution for your product needs. Creative Micro Systems can provide the best hardware devices. Add the appropriate software and watch a unique personality develop for your application.

BUILDING WITH CMS



Start building with our 9600 MPU Module—a complete microcomputer system on a single board. It features the MC6802 processor, 6K of EPROM, 1.1K of RAM, 40 lines of parallel I/O, two full duplex serial I/O channels with BREAK detect, three 16-bit programmable timers, and a power failure protect/restart circuit.

If your requirements are more extensive the 9600 is supported by a variety of memory and I/O devices. The 9626 8K static RAM, the 9620 16 port parallel I/O, the 9650 8 port duplex serial I/O, the 9640 multiple programmable timer, the 96702 32 point contact closure and the 9610 utility prototyping board are all available now.

The line is fully supported with a card cage, mother boards, power supplies and accessories.

THE OEM ADVANTAGE

Original Equipment Manufacturers who specify Creative Micro Systems modules have found that system design is simpler, fabrication and testing is faster and costs are lower and more predictable. You can even compute in-place costs from our specifications and take advantage of immediate delivery. And our commitment doesn't stop here. New modules and subsystems are continually being announced to meet the requirements of advanced systems of the future.

The next time you feel creative give us a call. We'd like to supply your building materials.



Creative Micro Systems

CMS

11642-8 Knott Ave.
Garden Grove, CA 92641
(714) 898-9669

Circle 61 on reader service card

Now, a dual variable op amp that doesn't need extra devices for extended linearity.

Simply add 5 resistors to the circuit with the new RCA 3280 dual variable op amp and you get the same extended linearity (right) as with the more complicated circuit.

Costs are down, too. Because the 3280 is a dual, your "per device" costs are reduced about 25 percent over our previous 3080 design.

Other important features include low input offset voltage. (One fourth as much as previous designs.) And much lower noise which extends the range of applications by allowing operation with low input signals.

The new CA3280 also has a wide dynamic input voltage range, from 5mV to greater than 10 V.



And a low offset voltage drift.

Produced with the Gold CHIP process, the CA3280 is in stock and ready for immediate delivery.

Price for 1000 and up is $0.89 (optional with distributors).

For more information, contact your local RCA Solid State Distributor.

Or contact RCA Solid State headquarters in Somerville, New Jersey. Brussels, Belgium. Tokyo, Japan.





RCA

Circle 62 on reader service card

International newsletter

Data ring that transmits 1 Mb/s to go commercial

A packet-organized data ring and its associated operating system developed at Cambridge University's computer science department to link in-house mainframe and minicomputer resources is to be exploited commercially by the British software systems company Logica Ltd. **The closed loop operates at up to 1 Mb/s** over a simple twisted-pair cable and is currently accessed via a transistor-transistor-logic card. As part of a government-financed advanced computer techniques project, a two-chip version is to be developed over the next 12 months by Ferranti Semiconductors Ltd. using its uncommitted-logic-array technology. London-based Logica is a key member of the Nexos word-processing consortium of companies recently launched by the National Enterprise Board with $80 million funding, so the "portable" software could play a vital role in linking Logica's word processor to coming electronic office systems.

Siemens to introduce space-switched PBXs at Hanover fair

Microprocessor control, modular construction, and low power consumption are the prime features of a new family of space-switched private-branch-exchange (PBX) systems that Siemens AG will show for the first time at West Germany's Hanover Fair, April 18–26. The EMS (for electronic, microprocessor, and stored-program-controlled) family consists of five systems, the smallest for 10 subscribers and the largest expandable to handle an unlimited number. A 30-subscriber system is so compact it easily fits under a desk. Power consumption for a configuration handling 600 subscribers is only 1.5 kW.

Universal logic gate promises denser custom chips

Now being evaluated by one semiconductor company for use in custom microcircuits is a bipolar universal logic gate that can be **programmed to yield any three-input combinatorial function or a bistable device** by a choice of input/output connections. According to its developer, S. L. Hurst of the department of electrical engineering at Bath University in England, a chip array of such gates could be interconnected with a single masked metalization, thus achieving greater circuit densities and lower design costs than are possible with rival uncommitted logic arrays. That's because the metalization layers interconnect only gates and not the components within individual cells as in a ULA. The technique, says its developer, could perhaps also be applied to custom complementary-MOS circuits.

Antiskid control goes into high gear in West Germany

Robert Bosch GmbH, Stuttgart, is producing 1,000 antiskid control systems per month for Mercedes Benz and Bayrische Motoren Werke (BMW) automobiles in West Germany. The system uses six custom chips—two large-scale integrated p-MOS and four bipolar circuits—for separately monitoring the braking action of the rear wheels and each of the two front wheels [*Electronics*, July 20, 1978, p. 64]. Previous systems were shunned by consumers because of high cost and frequent breakdowns, but **the new unit has a fail-safe system, developers claim, to prevent accidental wheel locking** caused by electronic malfunctions. The logic chips are linked in a phase-locked loop for processing sensor signals, company officials explained at the Vehicular Technology Conference in Arlington Heights, Ill., at the end of March. Field tests indicate a failure rate of less than 0.5% per year while reducing braking distance on wet roads by 40%. A low-cost version is on the drawing boards for export that will use an off-the-shelf microprocessor rather than custom chips to keep the retail

price at less than $500; introduction is scheduled for 1983–84.

IEC proposes standards for medical equipment

The International Electrotechnical Commission, continuing its push for acceptance of medical equipment standards, has drawn up a series of norms for diagnostic X-ray equipment and electron accelerators used for radiation treatment of cancer patients. Adopted at a 10-day technical conference in Paris in late March, **the standards now go to the national committees in each of the 42 IEC member countries,** which include the U. S., the USSR, and virtually all other developed countries. In the past, only a handful of members have accepted IEC medical equipment norms. Still, the commission believes eventual acceptance is inevitable because it is expensive for each country to develop its own norms and international norms should facilitate international sales for manufacturers.

ITT Components will be first non-Sony firm to make Trinitron tubes

Watch for the ITT Components Group Europe to start producing Sony Corp.'s Trinitron color TV tubes for the Japanese company's TV plant in England. Sony and ITT have reached **an agreement that provides for the production initially of 60,000 22-inch tubes,** to be made at the group's tube-manufacturing facility in Esslingen, West Germany. This, an ITT representative says, would be the first time that Sony is having its Trinitron tubes produced in a plant other than its own. For the Japanese firm, the agreement spells a big savings in tube transportation costs; for the ITT group it means much-needed business for its Esslingen facility, which already makes TV tubes for other companies but has been operating significantly below capacity because of the decline in TV sales in Europe.

Grundig to make VCRs programmable for two TV shows

Seeking to enhance the versatility of its 4-hour video cassette recorder, the SVR4004, West Germany's Grundig AG is coming out with a modified version that can be preprogrammed to come on automatically at two different times, thus allowing the recording of two different TV shows, which may be on different channels. **The first European company to offer such "double-programmable" systems,** Grundig says this feature will also be available on its Secam VCRs intended for the French market. Like the standard SVR4004 [*Electronics*, June 8, 1978, p. 70], the new version, called the SVR4004EL, permits programming of turn-on and turn-off times as much as 10 days in advance of the show or shows to be recorded.

Addenda

Mostek Corp. has selected Blanchardstown, Ireland, near Dublin, for a wholly owned $80 million production facility that it says will employ 1,100 when fully operational after 1982. The two 100,000-square-foot buildings are planned for a 50-acre site, where the Carrollton, Texas, firm **will fabricate wafers and make microprocessor and memory products** for sale primarily to the European market. . . . Datasaab AB, the year-old Swedish computer firm, lost about $26 million last year, $9 million more than had been estimated when it was formed by the state and Saab-Scania AB. The owners are now kicking in $13 million each to cover the loss. Minister of Industry Erik Huss says the owners don't expect the company to be in the black for another three years, but he stresses that **the state is determined to support Datasaab in order to maintain domestic computer competence.**

Panasonic electrosensitive alphanumeric printers.

When you're this small, you don't have to make a lot of noise about your low price.

Print in silence and print at low cost with our electrosensitive alphanumeric-plus printer Model EUY-10E.

Naturally, you'll like the price. But that's not the major benefit.

It isn't even the fact that the package is small (4.33″L x 3.5″W x 1.5″H). That makes it great in tight applications like POS cash registers, electronic calculators, data loggers, home computers and general peripherals—anywhere, in fact, where inexpensive hard copy is required.

The real achievement was to pack so much character-forming flexibility in that tiny space. We did it, with a 5 x 7-dot matrix that prints up to 128 different characters or symbols (including a full ASCII character set) on either 15, 21, 32 or 40 characters per line at just 530 msec per line with legibility that's sharp and clear.

There are two versions to choose from, each with reliability designed-in by eliminating all moving parts except the print head and the paper.

To make it easier for you to get rid of noise, bulk and big price tags, we've also made the EUY-10E easy to talk to. For quick microprocessor compatibility, we supply a 4-bit 1-chip microcomputer on a pre-programmed plug-in board that meets a variety of interfacing requirements, including that 128-strong variety of character formations.

For specifics on how beautiful small can be, write for information and prices to: Panasonic Electronic Components, One Panasonic Way, Secaucus, NJ 07094; or call (201) 348-7282/7289



Optional Interface Board

Panasonic®

just slightly ahead of our time

Circle **701** on Reader Service Card

Relax!

We can get Microprocessor Development Systems from Zilog, Intel or Tektronix on their way to you in minutes.

Whether your requirement is for a week, a month, a year or longer, there's one way to get the latest in microprocessor development systems from Zilog, Intel or Tektronix without waiting. Rent it from Leasametric.

Instantly, AUTEX, our nationwide computerized inventory system, will check our dozens of regional inventory centers to pinpoint the unit closest to you. Within minutes, your order will be processed and moving on its way. In most cases, your development system will be in your hands in less than 24 hours.

Need more than one system? Don't waste time and energy calling everyone in the book. One phone call to Leasametric is the fast, simple way to end your equipment worries and start relaxing. And, rental means more than immediate possession.



It's the one effective way to get the new equipment you need without going back to management for more money. There's no major capital investment with a Leasametric rental.

Leasametric, of course, means more than development systems. We stock the latest terminals, acoustic couplers, modems, communications and general-purpose test equipment . . . just about anything you might conceivably need. Our growing inventory includes over 23,000 items from 500 of the top electronic manufacturers – including almost the entire HP catalog.

Need it now? Why wait? To order, or for our latest rental catalog, pick up the phone and call one of the relaxing, nationwide numbers shown below. They're toll free. Or call your local Leasametric office. There's one in every major city.

Leasametric/Rent it and relax.

In the West
Call 800-227-0280
In California, call (415) 574-4441

In the Central U.S.
Call 800-323-2513
In Illinois, call (312) 595-2700

In the East
Call 800-638-4009
In Maryland, call (301) 948-9700

A Trans Union Company
1164 Triton Drive, Foster City, CA 94404

Trip computer gets more functions and greater intelligence

by John Gosch, Frankfurt bureau manager

Interactive system from BMW, Siemens uses variable weighting to estimate time of arrival and range

Building computers that supply information on fuel economy, distance to a destination, estimated time of arrival, and other vehicle- and trip-related data into cars is a growing trend in the U. S., and European auto makers have begun to follow suit. Joining the lineup is West Germany's Bayrische Motoren Werke AG (BMW), a Munich-based company known as a builder of high-performance cars.

It is gearing up to fit its top-of-the-line models with an interactive microcomputer system that it claims has a level of intelligence unmatched by any system built thus far. Developed at Siemens AG in cooperation with BMW, the system is now in the prototype stage and will probably be installed in quantity next year. Its price, not yet determined, will be about that of a high-quality a-m/fm car radio.

Information plus. As Rüdiger Müller, head of the automotive electronic systems group in the Siemens Components division, explains it, the computer performs some 15 functions. These consist of purely informative indications like average speed, estimated time of arrival, and average and instantaneous gas consumption (either in miles per gallon or liters per 100 kilometers), as well as warnings on various travel- and car-related conditions.

In support of the claim of unmatched intelligence, Müller explains how the computer estimates, for example, the time of arrival and the miles to empty fuel tank, or range. For both, the indications of course depend on the figures used.

Undesirable. If the calculations are based on, say, instantaneous driving behavior, the results would be subject to considerable variations and would therefore be useless. If, on the other hand, they are based on the average driving behavior so far, the indications would be quasi-static and most likely highly inaccurate, because an overall average is not nearly so good a predictor of the future as is an average taken only over the recent past.

The Siemens-BMW solution is a compromise. The computer calculates the ETA using the car's average speed over the past 1 to 4 kilometers, depending on how fast the car is going—the slower the speed, the less distance it is averaged over. Similarly, the indicated range is based on an overall average value of fuel consumption weighted against the fuel consumed over the latest distance covered.

Of note, too, are the computer's warning features, items that, according to Müller, most other systems do not have. For example, if the outside temperature falls below 3°C, a light-emitting diode flashes and an alarm is sounded, warning the driver of the chance of icy roads. In the same way, the driver is warned when the car exceeds the keyed-in speed limit.

What's more, the driver can key in



Information, please. The central electronic unit of the BMW-Siemens interactive trip computer accepts analog and digital data to perform 15 functions that inform or alert the driver.

On the alert. Keyboard and display unit contains eight LEDs, to supply warnings (red), as well as information (green).

the distance to a desired highway exit and the system will alert the driver both optically and acoustically when he is approaching the exit. It also figures out the approximate exit-arrival time.

Locked. Then, too, there is a scheme that helps prevent theft or unauthorized use of the car. To start up, the driver unblocks the ignition system by keying into the computer an identification number of up to four digits. If a wrong number is keyed in three times in a row, the computer keeps the ignition blocked and triggers the horn.

Basically, the system consists of the dashboard-mounted keyboard and display (see photo) and the central electronic unit, which is 18.5 by 12 by 3.5 centimeters and installed in the passenger compartment. The keyboard contains a four-digit light-emitting-diode display and 12 double-function keys, as well as eight informative (green) and warning (red) LEDs.

Electronics. The central electronic unit is built around Intel's single-chip 8-bit 8049 microcomputer. Peripheral to it are an 8-bit analog-to-digital converter, complementary-metal-oxide-semiconductor clock and alarm circuits, a 256-by-4-bit random-access memory for all car-derived and keyed-in data, and a 2,048-by-8-bit read-only memory for program storage (see diagram) that supplements the 2-kilobyte ROM on the microcomputer chip.

Other peripheral components are input/output devices that interface with the keyboard display, the clock and alarm circuits, and the microcomputer. Finally, there is a type-selector switch that adapts the electronic unit to the various BMW models such that it takes into account the different speed sensors, wheel diameters, fuel tank geometries, and other parameters of the different models. The peripheral devices come from Siemens and other suppliers.

Inputs are such analog information as fuel level, battery voltage, and outside temperature, and digital data like the speedometer-derived speed pulses and the fuel-injection pulses. The latter come from the electronic injectors found on top-of-the-line BMW models. The battery voltage input is used to compensate for variations in voltage to the fuel injection system and the fuel sensor.

The only extra sensor required is for the outside temperature. For this purpose Siemens has developed a special high-accuracy negative-temperature-coefficient thermistor that responds to temperature variations within seconds.

Great Britain

Coding scheme sends data by tone signals

There's a new, highly reliable way of transmitting data over radio and telephone links, achieved by expanding the number of frequencies used and replacing the tunable filter generally employed in the decoder.

The coding technique is called HSC, for hexadecimal sequential code. It comes from Consumer Microcircuits Ltd., a small British company that has also designed complementary-metal-oxide-semiconductor circuits to perform the coding and decoding. The Witham, Essex–based firm specializes in the design and assembly of tone-signaling microcircuits for the mobile-telephone and radio-paging industry and exports over 80% of its production.

Its latest products build on the 5-tone (out of 12) sequential calling system that is already employed by the mobile-telephone industry to page a single receiver. The set, the company says, "would be ideal for a data link between microprocessor-based systems."

Integrity. Says Brian Hardy, Consumer Microcircuits' marketing director, "Tone signaling works well because of the integrating effect of detecting a tone over a long interval." In contrast, other popular data-communication transmission techniques like frequency shift keying have a far higher data rate (some 10 times as fast) but show poor integrity under heavy noise conditions. "It's the high-integrity market that we are after," Hardy says.

To transmit quadridecimal or hexadecimal data—say, a police car's status—Consumer Microcircuits has added 5 frequencies to the 12-frequency tone code. More importantly, it has redesigned the decoder to enable it to receive data.

Tuning in. In the existing set, a sequence of five tones, each typically 33 milliseconds long, is transmitted to address a particular mobile unit. Transmitting data is a problem, though. That is, says Hardy, "conventional decoders can decode their address and nothing else."

In operation, a tunable filter in the decoder is set to the tone representing the first digit of its address and will not shift till it hears that tone. Then it tunes to the second digit, and so on, till all five digits have been decoded.

To receive data, the decoder must respond to all possible tones, so Consumer Microcircuits has thrown out the tunable filter and chosen a digital autocorrelation technique to discriminate between tones.

The input signal is first digitized. Then it is passed to a tapped shift register and compared with a version of itself that has been delayed by passing through a second shift register. Periodic signals are reinforced, while nonperiodic random noise signals are "washed out." As a result, Hardy says, "a signal which is 6 decibels down in the presence of

E-MASK™

MASKMAKING SERVICES

E-Mask, the maskmaking services division of Electromask, has been serving the semiconductor manufacturers and the major semiconductor users for over 17 years. It is the only maskmaking company with its own equipment group – an equipment group that was developed for the express purpose of keeping E-Mask capabilities a step ahead with the latest state-of-the-art maskmaking equipment.

For immediate service,
call (213) 884-5050.



For more information,
send for our brochure.

TRE

ELECTROMASK

The Technology Leader in the Masking Industry

A subsidiary of TRE Corporation,
6109 De Soto Ave., Woodland Hills, Ca. 91367, Phone: (213) 884-5050, Telex 67-7143



By the tones. Principal members of Consumer Microcircuits' 003 tone-signaling set are the FX-003 tone decoder and the FX-503 tone encoder. They can interface directly with a microprocessor using 4-bit parallel hexadecimal data words.

wideband noise is lifted to +18 decibels above the background noise by the correlator."

Key device. The autocorrelation is performed by one chip, the FX-003, which puts out a 4-bit hex code. Several versions of this chip will be available for the various major national and international standards. Quadridecimal code set versions, too, will be made.

The FX-003 is the key circuit in the system and was "technically the most difficult," Hardy says. It will be available in the second half of the year. The other circuits making up the system, although simpler, all should be available by year-end.

The FX-103 performs the selective address function and compares the incoming 4-bit word with the address, stored in read-only memory, and beeps when the correct code sequence has been received. The FX-303 is a data store and display multiplexer, and the FX-503 a tone encoder that includes a frequency synthesizer capable of generating both the hexadecimal and quadridecimal tone sets.

The company is using Hughes Microelectronics Ltd. and General Instruments Microelectronics Ltd. to produce the circuits. **-Kevin Smith**

France

Transpac starts up, wants small users, too

People who want to converse by telephone in France often grumble about the quality of phone service, but those who want to converse by bits have nothing to complain about. With the inauguration late last month of Transpac, the French public packet-switching data-communications network, France now boasts Europe's most advanced digital telecommunications system.

The French postal and telecommunications administration, usually called the PTT, stresses that Transpac, a grid covering the entire country, is available to customers of any size, and at low cost.

The cost is based primarily on the volume of data transported, regardless of the distance between sending and receiving points, and speed ranges from 50 to 48,000 bits per second. Access to the system is based on the X.25 international data-communications protocol, the 128-byte packet and interfacing standard developed by the International Consultative Committee on Telephony and Telegraphy (CCITT).

The network consists of a series of switching nodes connected by a grid of high-speed links that handle up to 72,000 b/s. A national control system in Rennes monitors overall operations and changes routing if any link gives out. A customer plugs

WE'VE SHATTERED THE MYTH OF DOT MATRIX ALPHANUMERIC PRINTING

Full alphanumerics, without "needles"; with our line matrix impact drum printer.

Rugged, reliable, inexpensive—our alphanumeric printer uses "spanning hammers." Each hammer impacts the steel drum to form the characters in three columns. There are no needles to bend, break or jam. Only seven hammers for 21 columns. So it's simple *and* dependable. UL-listed. And, only $140 in 100's.

54 characters, two-color printing in all columns.

Our unique line matrix permits printing of "A" to "Z", "0" to "9", and eighteen other symbols in all columns at printing speeds to 90 lines per minute. Paper feed is fast—to 10 lines per second.

μP compatibility.

Drive the printer with our 8-bit pre-programmed μP-based interface controller. This unit accepts BCD, RS232 and parallel/serial ASCII, and provides signal conditioning, buffer storage, timing control, handshaking, character generation and solenoid drivers. Or, if you prefer, simply use the μP capability designed into your host system.



Tape, tickets, even multiple copies.

In addition to standard plain paper tape printers, we also offer ticket printing mechanisms with multiple-copy capability ideal for weighing systems, medical instruments, P.O.S. terminals, security monitors and data loggers.

Take the first step—evaluation.

For just $325, our engineering evaluation kit is yours. It includes journal printer, interface/control electronics, and custom power supply — everything you need to realize the benefits of drum printer performance in your alphanumeric application. Just return the coupon below, or write or call: SODECO, part of Landis & Gyr, 4 Westchester Plaza, Elmsford, NY 10523; (914) 592-4400.

Yes, I'd like to know more about your Alphanumeric Drum Printer

☐ Please send complete technical information

☐ I'd like a demonstration. Please have sales engineer call to arrange for an appointment.

Application _____

Estimated annual usage _____

NAME _____

TITLE _____

COMPANY _____

ADDRESS _____

CITY _____ STATE _____ ZIP _____

PHONE _____

SEE OUR PRINTER IN ACTION AT ELECTRO '79 BOOTH 1436

SODECO® LANDIS & GYR

"See our demonstration at Electro '79" Booth 1436

into the system in one of three ways: through a direct line; through the French telex network, for 50-b/s transmission; or through the switched telephone network, for up to 300 b/s.

Expanding. Experimental use of Transpac began in December [*Electronics*, Dec. 7, p. 107], and switches are now operating in 10 cities, with two more due to come on line shortly and plans for a total of 25 by the end of the year. The PTT believes the system will catch on quickly and foresees between 40 and 100 switching nodes by 1985. Eventually, no user will be more than 100 kilometers from a switching exchange.

When the network was inaugurated, 70 customers were linked directly to Transpac, and 60 others tied in through telex or telephone lines. The system is now capable of handling 1,500 customers, with the capacity projected at 4,500 next year and 25,000 by 1985.

The PTT believes much of the appeal of Transpac lies in the cost, and cites examples of savings ranging from 14% to 80%. The fact that customers pay basically only for what they send is aimed at attracting subscribers who might otherwise be unable to afford such an elaborate data-transport system.

Ad hoc. Transpac links depend on the use of virtual circuits, which permit simultaneous bidirectional exchanges of strings of packets regardless of the length of the messages transmitted. These virtual circuits may be either switched—links are activated on a correspondent's initiative—or permanent, at the customer's choice. They are employed in order to eliminate idle time, a key factor for a public telecommunications system. Transpac also offers multichannel access.

At the heart of the network are the switching nodes, each of which consists of a control unit and a switching module. The former is a general-purpose Mitra 125 minicomputer manufactured by the Thomas-CSF subsidiary, Société Européenne de Mini-informatique et de Systèmes (SEMS). It establishes and terminates calls, monitors operations, and recovers and retransmits any faulty messages. Two control units are located at each switching point, with the second serving as a stand-by. The error rate is put at less than 1 in 10^{10}.

Switches. The switching module handles line control and actual switching. Manufactured by Télécommunications Radioélectriques et Téléphoniques (TRT), a Philips subsidiary, each CP50 switching module can handle 256 X.25 ports. Asynchronous multiplexers provide 250 additional line interfaces. With two such modules at each switching point, the switching node has a maximum capacity of 16,000 lines.

The transit time of a packet, from input switch to output switch, depends on the routing; the PTT claims it is less than 200 microseconds at peak-usage hours 90% of the time. For switched access circuits, the connection time likewise depends on routing but is said to be less than 1.5 seconds in 90% of the cases.

Design and installation of the Transpac network was handled by the Société d'Etudes des Systèmes d'Automation (SESA) over a three-year period. Jacques Stern, president and director general of SESA, believes that with Transpac in operation his company is in a good position to compete for contracts for public data-communication systems elsewhere. He has his eye on markets in the U. S. and Latin America, as well as in Europe. **-Henry Dreyfack**

Sub hunter goes digital

In the cat-and-mouse defense game of measure and countermeasure, an Anglo-Australian venture headed by Marconi Avionics Ltd., Rochester, Kent, has come up with an all-digital airborne antisubmarine system to locate and identify nuclear submarines. The new system, designated the AQS901, counters the subs' quietness, deep-diving capability, and high speed with improved speed, sensitivity, and flexibility stemming from the use of microprocessors for signal processing.

The system teams the new Australian Barra, a passive directional sonobuoy, with the AQS901 listening equipment carried by Royal Australian Air Force P3-C Orion or British Royal Air Force Nimrod maritime patrol craft. Barra provides accurate target positioning by direct bearing, hyperbolic fix processing, or doppler fix processing.

Its acoustic signals, telemetered aloft, are processed extensively before being fed to the visual display and the chart recorder. From the display and the chart, the operator can, with training, identify the characteristic noise signatures of both surface and submarine vessels.

The signal-processing tasks are split among 30 Advanced Micro Devices Am2901 bit-slice microprocessors, each performing a specific function for speed and flexibility, says Paul Rayner, manager of Marconi's Maritime Aircraft Systems division. One processor, for example, is a fast Fourier analyzer used to plot the energy in different frequency bands, thus providing the noise signatures. It is capable of performing 2,048 complex transforms in 1.25 milliseconds. The hardware was developed by Marconi, and Computing Devices of Canada Ltd. provided the sonar signal-processing subsystems.

The whole system is controlled by Marconi's well-proven 920 ATC digital computer, which, by allowing the operator to call up a variety of analyzer techniques to pinpoint a submarine's location, makes it highly flexible. Thus the AQS901 can work with every other type of sonobuoy in the North Atlantic Treaty Organization inventory. **-K. Smith**



"Choosing Intel gave us a twelve month jump on the competition."

Dr. Wang: "We were first with a unique, new approach to word processing—using microcomputers to implement distributed intelligence in multiple station systems. That approach has enabled us to increase our market share 50% a year in a market that's growing 40% a year. This year our word processing sales will pass $100 million. In 1974 they were just $9 million.

"We decided on Intel's 8080 microprocessor for our distributed logic system. Only Intel offered PL/M, the microcomputer programming language we needed to get our software written quickly. So quickly that we introduced our system a year ahead of any competition. And Intel's tools for programming have continued to help us offer our customers the high quality software they expect from Wang."

Intel's extensive microcomputer design tools have helped hundreds of companies just like Wang Labs capture the marketing advantage with Intel microcomputers and semiconductor memory.

Our Intellec® Microcomputer Development System makes it possible and profitable for companies like yours to take full advantage of the promise and potential of the microcomputer. For example, the world's most advanced microcomputer, our new 16-bit 8086, is the first and only 16-bit microcomputer supported by a high-level programming language—PL/M, part of the total 8086 software development package available for the Intellec system.

To begin writing your own success story, contact Intel Corporation, 3065 Bowers Avenue, Santa Clara, CA 95051 408/987-8080.

Intel's Intellec® Development System

Circle #73 for information

intel® delivers.

IMAGINE

Zilog rockets out in front again to launch a new generation.

For the first time, the architectural sophistication and data processing capabilities of large, main-frame computers has been captured in the cost-effective, easy to use format of the microprocessor. Now you can have the freedom to create entirely new, innovative systems, unhindered by the primitive architectures of previous microprocessors.

A revolution in sophistication.

The Z8000 has been designed from the ground up with options to fit your application needs exactly. For the full 8 MB addressing capability, choose the 48 Pin DIP version. Its companion device, the Memory Management Unit, opens the way to dynamic relocation, memory protection and multi-tasking applications.

Flexibility soars to new heights.



The Z8000 allows you to directly address up to 8 MB of memory. All 16 registers are a full 16 bits wide and are completely general purpose. The powerful, problem-solving instruction set supports 7 different data types from bits to 32 bit words, has 8 addressing modes and 418 usable opcode combinations.

The general register architecture helps avoid the well-known bottlenecks inherent in dedicated register designs. When this architecture is combined with the powerful instruction set, the Z8000 system throughput is an explosive 50% greater than any other 16 bit microprocessor available today.



IMAGINE

A REVOLUTIONARY NEW WAY TO THINK ABOUT MICROPROCESSOR SYSTEMS. INTRODUCING ZILOG'S Z8000.

For smaller, less memory-intensive applications, select the 40 Pin version of the Z8000. It's software compatible with the 48 Pin Z8000 but addressing is limited to 64KB in each of its six address spaces. It comes in a standard 40 Pin package.

Wait 'till you meet the family.

We're starting off this new microprocessor era with a bang, but it's just the beginning. Soon to come are the Memory Management Unit, peripheral interfaces, FIFO buffer elements, universal peripheral controller and memories for any application you might have.

And, all the new I/O chips, memories and, of course, the companion Z8, take advantage of the flexible Z-BUS architecture to maximize performance, ease of interconnection and minimize PC board area.

Zilog delivers on the next generation of microprocessors. Again!

With the introduction of the Z8000, microprocessor technology explodes to new heights. Bursting with a rich and sophisticated architecture, the Z8000 not only opens the way to revolutionizing your next generation



of products, it has the built-in growth potential to carry your product development efforts out to totally new and unexplored horizons.

Imagine the possibilities, then light your own fuse!

Sound exciting? It is. Get your own fireworks blazing by placing your order today with your nearest Zilog distributor.

In the meanwhile, give your engineering staff a headstart on the fireworks by ordering the Z8000 literature package; in the U.S. order directly from Zilog, elsewhere from your Zilog distributor.

10460 Bubb Road, Cupertino, CA 95014
(408) 446-4666 TWX 910-338-7621
EASTERN REGION: (617) 667-2179
MIDWESTERN REGION: (312) 885-8080
SO. WESTERN REGION: (714) 549-2891
NO. WESTERN REGION: (408) 446-4666
EUROPE (ENGLAND): (0628) 36131/2/3
WEST GERMANY: (08106) 4035
JAPAN: 03-476-3010

An affiliate of
EXXON ENTERPRISES INC.

Zilog

SEE US AT ELECTRO
BOOTHS 1106, 1108.

Circle 75 on reader service card


Can you
supply
ten components?
a thousand?
ten thousand?



When it's TRW, the answer is yes.

Because...

TRW Electronic Components are available in small quantities (and large quantities, too) from a worldwide distributor network—in addition to their OEM availability. Most standard products are heavily stocked for immediate delivery, with factory back-up inventories.

With over 300 product lines, not every item can be stocked, but TRW markets more component types through distributors than any other electronic component manufacturer.

Whether you need TRW components for fast delivery, from your distributor, or for future use in OEM quantities, it's the same quality product, made to the same specifications and under the same production procedures.

The next time you want "yes" for an answer, call your TRW distributor, or your TRW/ECD sales office.

You'll find them listed in EEM, Electronics Buyers' Guide, Who's Who in Electronics, the Electronic Industry Telephone Directory and the Electronic Buyers' Handbook.

TRW *CAPACITORS*
TRW *CINCH CONNECTORS*
TRW *CINCH-GRAPHIK*
TRW *CINCH-MONADNOCK*
TRW *ELECTRONIC FUNCTIONS*
TRW *GLOBE MOTORS*
TRW *HOLYOKE WIRE & CABLE*
TRW *INDUCTIVE PRODUCTS*
TRW *IRC NETWORKS*
TRW *IRC RESISTORS*
TRW *LSI PRODUCTS*
TRW *POWER SEMICONDUCTORS*
TRW *RF SEMICONDUCTORS*

TRW ***ELECTRONIC COMPONENTS***
DIVISIONS OF TRW INC.

Circle 77 on reader service card

Who do you think of for a complete line of 8-bit microprocessors?

Next time,



If you haven't checked into our 8-bit line recently, take a look at what you've been missing.

We've got everything you need in 8-bit processors—plus a full assortment of industry standard peripherals and memories. And we've got them all in volume, ready to ship.

Not only do we support the entire 8080A family; we also offer the lower-cost single-chip 8048 family and the higher-performance 8085A series.

And for those with applications that require the capability of a Z80,™ we have the fully compatible μPD780—supported by the full family of 8080 peripherals.

Our 8-bit Families

μPD 8080AF	μPD 8085A	μPD 8048	μPD 780
μPD 8080AF μPD 8080AF-2 μPD 8080AF-1	μPD 8085A μPD8085A-2	μPD 8048 μPD 8049 μPD 8039 μPD 8035	μPD 780 μPD 780-1
μPD 8041 →			
	μPD 8155 → μPD 8156 →		
μPB 8212 →			
μPB 8214 →			
μPB 8216/26 →			
μPB 8224 μPB 8228/38		μPD 8243	
μPD 8251/A →			
μPD 8253 →			
μPD 8255/A-5 →			
μPD 8257 →			
μPD 8259 →			
μPD 8279-5 →			
	μPD 8355 →		
μPD 765 →			

TM Zilog

REPS: Action Unlimited, Arlington, TX; Spring, TX. Burton-Medley Associates, Grandview, MO. Cerco, San Diego, CA. Contact Sales, Inc. Burlington, MA. D/Z Associates, Inc., Denver, CO. Electronic Innovators, Inc., Minneapolis, MN. Eltron, Phoenix, AZ. HLM Assoc., Northport, NY; Parsippany, NJ. Imtech, Inc., Cleveland, OH; Dayton, OH. Kaytronics Limited, Ville St. Pierre, Quebec; Downsview, Ontario; Surrey, British Columbia. L & M Associates, Pikesville, MD; Montpelier, VA. Harry Nash Associates, Willow Grove, PA. R.C. Nordstrom & Company, Lathrup Village, MI. Perrott Associates, Inc., Fort Lauderdale, FL; Clearwater, FL; Orlando, FL. Santana Sales, Costa Mesa, CA. Stone Component Sales, Waltham, MA. Technology Sales, Inc., Palatine, IL. Trident Associates, Inc., Sunnyvale, CA. Tri-Tronix, Albuquerque, NM. Tri-Tronix, NW., Mercer Island, WA. 20th Century Marketing, Inc., Huntsville, AL; Greenville, TN. Wolff's Sales Service Company, Raleigh, NC.

DISTRIBUTORS: Almo Electronics Corp., Philadelphia, PA, Baltimore, MD. Bell Industries, Bellevue, WA. Century Electronics, Albuquerque, NM; Wheatridge, CO; Salt Lake City, UT. Norman Davis Electronics, South Euclid, OH. Diplomat/Westland, Inc., Sunnyvale, CA. Diplomat/Southland, Inc., Clearwater, FL. Diplomat/Lakeland, Inc., Elk Grove Village, IL. Diplomat/IPC of Mass., Chicopee Falls, MA. Diplomat, Holliston, MA. Diplomat/Northland, Inc., Farmington, MI. Diplomat/Electro-Com

think NEC.



We can also fill your needs for a wide range of high-performance peripherals, including our IBM-compatible, double-density, double-sided floppy disc controller, the μPD765.

NEC not only means advanced technology and volume delivery; we also offer remarkable product reliability—thanks to experienced designers and meticulous manufacturing techniques, backed up by 100% burn-in and testing with MIL-STD-883 methods.

What's more, we give you thorough support—including documentation, design assistance, and product development services. And our engineers are always available to help with specific application problems.

Our new catalog will give you a better idea of just how much we can do for you, not just in 8-bit products, but also in 4-bit single-chip processors and 1K, 4K and 16K memories.

For your free copy, clip your business card or letterhead stationery to this page and send to:
NEC Microcomputers, Inc.,
173 Worcester Street, Wellesley, MA 02181.

If you haven't thought of NEC before, you will.

Next time.

NEC

NEC Microcomputers, Inc.

Corp., Minneapolis, MN. Diplomat/St. Louis, Inc., St. Louis, MO. Diplomat/IPC Corp., Totowa, NJ; Mt. Laurel, NJ. Diplomat Electronics Corp., Woodbury, NY. Diplomat/Alta-Land, Inc., Salt Lake City, UT. Future Electronics Corp., Montreal, Quebec; Rexdale, Ontario; Ottawa, Ontario. Hughes-Peters, Inc., Cincinnati, OH; Columbus, OH. Intermark Electronics, Sunnyvale, CA; Santa Ana, CA; San Diego, CA. Kent Electronics, Houston, TX. G.S. Marshall, Sunnyvale, CA; Irvine, CA; El Monte, CA; San Diego, CA; Phoenix, AZ. Milgray Electronics, Inc., Freeport, NY; Orange, CT. Reptron Electronics, Inc., Livonia, MI. Resco/Raleigh, Raleigh, NC. Semiconductor Specialists, Inc., Chicago, IL; Burlington, MA; Farmington, MI; Minneapolis, MN; Hazelwood, MO; Pittsburgh, PA; Dallas, TX; Milwaukee, WI. Sterling Electronics, Phoenix, AZ; Sun Valley, CA; San Diego, CA; Baton Rouge, LA; Waltham, MA; Albuquerque, NM; Dallas, TX; Houston TX; Seattle, WA. Summit Distributors, Inc., Buffalo, NY. Summit Elec. of Roch., Inc., Rochester, NY. Technico, Inc., Columbia, MD; Roanoke, VA. Western Microtechnology Sales, Sunnyvale, CA.

REGIONAL SALES OFFICES: Western Region, NEC Microcomputers, Orange, CA (714) 633-2980. Eastern Region, NEC Microcomputers, Melville, NY (516) 293-5660.

E 1-5

Teradyne finds the practical solution.
No. 10 in a series.

The chroma generator



Converting a color television signal into a screen full of "The Muppets" is only slightly less complicated than unscrambling an egg. The rf signal appearing at the receiver front end is a jumble of modulated subcarriers and synchronizing signals, all of which must be delicately picked off and converted into information the picture tube can handle.

The toughest unscrambling job of all falls to the chroma demodulator, whose synchronous detectors must pull the color information out of a phase-modulated subcarrier and combine it with brightness information to create the proper mixtures of primary colors at the video output stage.

To test the chroma demodulator (in today's TV sets, integrated circuits), it is necessary to apply a modulated test signal at the appropriate subcarrier frequency and then accurately measure a number of phase-sensitive output voltages at the device output.

In practice, most of today's chroma demodulators are tested on Teradyne J273 Linear IC Test Systems equipped with a "chroma generator" specially designed to develop the convoluted waveforms that are required. The output of the chroma generator's output consists of 16 segments, each of which is programmable in time, dc level, and subcarrier level. In addition, three separate "event" outputs can be programmed to provide keying pulses wherever they are needed. Finally, a gated voltmeter can be programmed to measure, in any given segment, dc voltage, ac voltage, or phase (corresponding to brightness, color saturation, and color information, respectively). Since color information is actually transmitted in the form of phase angles, phase measurement is especially critical in chroma testing. The chroma voltmeter is more than equal to the task. First it measures the average values of the in-phase and quadrature components of the signal; then, from the ratio of the two values thus measured the voltmeter derives phase angle (ϕ = arc tan of the ratio of the two average voltages).

By writing a one-line software instruction for each of the 16 segments, the user can develop a periodic waveform that will simulate the desired range of chroma input signals. Also under software control are a number of other variables, including voltmeter operating modes, subcarrier frequency and amplitude, and scale factor and attenuation of the video waveform. Test procedures differ for the American and European systems (NTSC and PAL), and this choice is also made in software.

Thanks to the J273 and its chroma generator, today's chroma demodulator can be rigorously tested on the production line in well under a second. The story doesn't end there, of course, for device designers are now busy adding more circuits to the same chip, while Teradyne's linear-test engineers are just as busy developing new automatic test techniques.

After all, once you have unscrambled an egg, why not build a hen?

TERADYNE

 Circle 80 on reader service card

How can we prevent midair crashes?

FAA hopes microprocessors hold key as it seeks beacon-based collision-avoidance system that can work in heavy traffic

by Ray Connolly, Washington bureau manager

The Federal Aviation Administration is turning to microprocessors to solve a problem that has defied satisfactory resolution for more than a decade—that is, development of a workable airborne collision-avoidance system that can be used without sounding false alarms or interfering with ground-based air-traffic-control systems at heavily used terminals.

The FAA is calling this month for industry proposals for a full-capability beacon-based collision-avoidance system (BCAS). From those, it expects to select at least two contractors for 12-month design studies of an airborne system that can be integrated with its ground-based systems starting in 1983. The system would have both passive and active modes.

In passive operation, BCAS would listen on the 1,090-megahertz frequency used by surrounding aircraft to respond to interrogations from ground air-traffic-control radar beacons. A cockpit display would then show the relative position of other planes and, if necessary, present both horizontal and vertical collision-avoidance maneuvers. In the active mode, outside a radar-beacon coverage area, the system would use its directional antennas to scan the surrounding region, interrogating the transponders of other aircraft for potential threats.

Active only. At the same time, the FAA is preparing to award seed money for development of commercial models of more limited BCAS avionics that operate only in the active mode but could be available for use about 1981 outside higher-density traffic areas.

According to Norman Solat, assistant chief of the communications division in the FAA's system research and development service, the active BCAS will be able to issue only vertical maneuver commands (climb or dive) for collision avoidance, like its predecessors (see "CAS: past and present.)" Nevertheless, he notes that progress in airborne directional antennas may permit development of an active system that would provide some horizontal data in the form of a proximity display for pilots.

Three engineering models of an active system are being built for the FAA by the Massachusetts Institute of Technology's Lincoln Laboratory, and the FAA issued a draft national standard last December to permit equipment makers to begin designing marketable products.

Looming beyond what Solat calls the "very tough engineering problems" to be faced in taking the full-capability system through to a working model, the FAA clearly has budgetary problems as well. The numbers speak for themselves. Available money to be spent for work on both active and full-capability BCAS systems now stands at $4 million for the current fiscal year, although Congress is considering a $2 million supplemental appropriation being sought by the agency. For the fiscal 1980 year, which begins next October, the spending level for the system is a bit more than $3 million, Solat says.

As for the ground-based automatic traffic advisory and resolution service, or Atars—known earlier as IPC, for intermittent positive control—the agency is budgeted to spend approximately $2.25 million in each of those two fiscal years.

Compromises. The FAA has come around over the years from its earlier strong support of only ground-based air traffic control to



Two modes. Full-capability beacon CAS on commercial craft could operate passively, listening to transponders on other planes, or actively doing its own interrogation.

favoring a mix of airborne and ground CAS for all types of air space—controlled and uncontrolled, high density and low density. Now, however, it is also requiring that the system mix be compatible. But the agency has yet to convince the general aviation community that once new ground equipment for Atars–DABS (discrete address beacon system) is in place a small plane will be able to spend what the FAA calls "a modest cost increment" to replace its present air-traffic-control beacon transponder with a new DABS transponder and still use the existing altitude-encoding system.

On the other hand, airline operators are more favorably inclined toward the FAA's approach that—unlike the case with early systems—"will ensure that the first aircraft that equips will receive substantial protection immediately," since existing altitude-encoding beacon transponders are already widely used and required by law in some terminal areas for operation above 12,500 feet.

Control fight. Problems of air traffic control policy may be even more difficult for the FAA to resolve than those of technology. The reason: the mix of ground and air CAS would also involve putting air space now open to visual and instrument flight rules under what the FAA calls "positive control."

Citing new statistics on near midair collisions, especially in terminal control areas, from the National Aeronautics and Space Administration, the General Aviation Manufacturers Association (GAMA) is asking Congress, "Why is it thought that more controllers—with more potential for human error—can correct or improve conditions that cause near misses" that are in fact a function of human actions? (See "The numbers game.")

"We are genuinely convinced," argues GAMA vice chairman J. Lynn Helms, "that the FAA does not have the capability to provide the additional air-traffic-control services that would be required in a more restricted system without severely limiting access to that system. □

The numbers game

Statistics are flying in the dispute between the Federal Aviation Administration and its opponents in the general aviation community over how many near midair collisions occur in U. S. air space. At issue is whether the FAA's dramatically lower figures are valid compared with the sharply higher figures reported by the aviation safety reporting system set up in 1975 by the National Aeronautics and Space Administration to provide independent statistics. The issue is becoming increasingly important with the advent of the Civil Aeronautics Board's deregulation policy that has caused significant increases in competitive air traffic.

Whereas the FAA reports "approximately two per million operations in terminal control areas" for 1978 and part of 1977, new NASA data for the same period shows 24.3 near misses, or 12 times as many. FAA Administrator Langhorne Bond hints that the discrepancies may be attributable to the fact that NASA's system offers immunity from prosecution and anonymity to reporting pilots, whereas the FAA has authority to prosecute violators of flight rules that cause a near collision.

Though Bond says he favors maintenance of NASA's amnesty provision for pilots, he is distressed that it prevents prosecution of pilots "even if the violation was witnessed and subsequently reported by others." He cites the example of a Spokane, Wash., incident where "a DC-9 on a missed approach almost hit a DC-10 taking off on the same runway at the same time. Both the DC-9 pilot and a controller were in serious error—and we all knew about the near-miss as soon as it occurred. But the pilot filed a report with NASA, and the FAA was blocked from taking any action against either man."

CAS: past and present

U. S. efforts to develop an independent airborne collision-avoidance system (CAS) began in the early 1960s when McDonnell Douglas Corp., working primarily with the nation's airlines, came up with its EROS system based on the use of expensive and delicate atomic clocks in each aircraft. Later, RCA Corp. and Honeywell Inc. entered the market with potentially cheaper systems called Secant and Avoids, respectively.

Though the technology of the newer entrants differed from that of EROS, the concepts of the three were similar. None provided horizontal directional data for aircraft entering the so-called electronic shield surrounding the user, and all were limited to vertical escape maneuvers. The Federal Aviation Administration entered the act in 1971, awarding contracts to all three developers to come up with operating systems for flight testing. In its evaluation of the systems, the FAA found fundamental deficiencies.

Reacting to congressional pressure resulting from last year's midair collision over San Diego of a light plane and a commercial airliner that took some 150 lives, FAA Administrator Langhorne Bond presented Congress with an air traffic control plan for the future that is already generating controversy. His proposal to bring more aircraft operating by visual flight rules under "positive air traffic control" is being strongly opposed by the nation's 10 leading aviation organizations.

On the technology side, the FAA is being criticized for not moving faster with development and system procurement. Its principal ground-based system in high-density regions, now called Atars—for automatic traffic advisory and resolution service—and supported by the discrete address beacon system (DABS), is not expected to be widely operational for another decade. The FAA is just beginning tests this year on the three Atars systems.

Developmemt of active and passive beacon-based airborne collision-avoidance systems are regarded as interim steps to bridge this gap, although the BCAS hardware will be capable of working with DABS and Atars. The Atars package uses ground computers independent of normal air traffic control computers. The Atars computers work with the upgraded DABS radar transponder and provide an automatic data link in all weather conditions between aircraft transponder and the ground computers.

Spotlighting the Best



Spectrol Pots, Dials, Trimmers & Switches

If you're looking for high quality precision pots at competitive prices, you're looking for Spectrol. For digital or concentric turns-counting dials...for rectangular, round, or square trimmers...for miniature rotary switches–for any of these in standards or specials, look to Spectrol first.

Send for your copy of the new Spectrol Short Form Catalog.

Spectrol

SPECTROL ELECTRONICS GROUP

UNITED STATES **Spectrol Electronics Corporation** P.O. Box 1220, City of Industry, Calif. 91745, U.S.A. • (213) 964-6565 • TWX (910) 584-1314
UNITED KINGDOM **Spectrol Reliance Ltd.** Drakes Way, Swindon, Wiltshire, England • Swindon 21351 • TELEX: 44692
ITALY **SP Elettronica SpA** Via Carlo Piscane 7, 20016 Pero (Milan) Italy • 35 30 241 • TELEX: 36091

Circle 83 on reader service card

The no-one-else-comes-close line

Oak Rotary Switches



No one else comes close
in broad selection
—from tap switches to 60 position binary, BCD or hexadecimal coded switches, from 1/2" to 2 5/16" diameter multiple section switches—and Oak will build them into almost any PC board or component assembly that you specify.

No one else comes close
in innovativeness
—with creative new concepts like CMS333 that replaces solid silver clips and blades to provide equivalent performance at lower costs—or the Unidex® and Monodex® indexing mechanisms—or the Moduline® assembly system.

No one else comes close
in availability
—you can get most popular types from stock, through Oak distributors, nationwide...who can also construct over 2 million other variations, with the unique Moduline system, or you can use the Oak "Minuteman" service for fast factory delivery on short runs.

Consult our EEM pages or contact any Oak sales office or distributor for product line information.

IN TOUCH WITH TOMORROW

OAK Industries Inc.
SWITCH DIVISION

Crystal Lake, Illinois 60014
Telephone: 815/459-5000
TWX: 910•634•3353•TELEX 72•2447

Manufacturing facilities:
Crystal Lake, Illinois
Emmen, Holland (Oak Holland B.V.) and
Norwich, England. (Diamond H. Controls Ltd.)

For technical data—circle the reader service number.

200—1/2", 6-12 pos.
201—1", 3-16 pos.
202—1-5/16", 2-12 pos.
203—1-7/8", 12-20 pos.
204—1-17/32", 4-14 pos.
205—2-5/16", 9-24 pos.
206—2-1/2", 8-36 pos.
207—Programmable types
208—PCB types
209—Distributor types
210—For a salesman's call

Medical electronics

Microwaves help detect tumors

Researchers find that mass screening in 1.3-to-3.3-GHz range may be viable alternative to potentially hazardous X-ray exams

by Harvey J. Hindin, Communications & Microwave Editor

The very thought of breast cancer is terrifying because of its potential for physical and psychological mutilation. Mass screening to detect it in its early, most curable stages is a most welcome public health measure, and mammograms—breast X rays—were thought for 20 years to be the best way to go about it.

But this may not be so. Many questions have been raised by the National Institutes of Health, and separately by the NIH's National Cancer Institute, and by the Congressional Office of Technology Assessment, among others, as to the efficacy and safety of routine mammograms. The likelihood that breast X rays will cause cancer is small but real. Worse yet, the data that indicates that the procedure catches tumors early and saves lives is not very solid. And the cost is relatively high. However, there appears to be a solid alternative technique: detection of the breast's natural microwave radiation.

This is usually combined with thermography—passive infrared scanning of the breast (see "Detecting human radiation"). Infrared scanning is harmless since it also relies on the breast's natural radiation for its information. It is based on the fact that tumors are warmer than the surrounding tissue and thus generate more infrared radiation; however, the temperature difference is only about a degree or two. Point-to-point variation in breast temperature may exceed this figure, so even with the best available detection equipment it is very difficult for the medical specialist to be sure he has not missed any small tumors.

On the other hand, microwave radiation—much maligned in recent years, and accused of causing everything from headaches to cancer—is being used in many research laboratories to detect tumors. In spite of all the talk about low-level microwave radiation's potential for bad effects, there is no question that microwaves can detect breast tumors. There is a chance microwaves can even help cure the malignancies.

Microwave detection at 1.3 and 3.3 gigahertz has been used in clinical tests by Philips C. Myers and Alan H. Barrett of the department of physics of the Massachusetts Institute of Technology in Cambridge, Mass., since 1974. Tests have been done at Faulkner Hospital in Boston, where radiologist Norman L. Sadowsky cooperates in interpreting the infrared and X-ray analyses that are taken for data correlation for all three methods.

While the cancer detection rate depends on microwave frequency,

Penetration. Depth of penetration, hence depth from which microwaves escape, depends on wavelength and tissue's dielectric properties. Tissue water content is large variable.



tumor depth, and tumor size, among other variables, some conclusions have already been drawn. Most importantly, the dual approach—microwaves and infrared—can detect as many cancers as can X rays alone and has the same true negative rate. (The true negative rate or specificity of a test is the fraction of normal cases that the criterion identifies correctly.) Detection can be accomplished with a significant reduction in the number of women exposed to X rays if X rays are used only when the combined techniques (infrared and microwave) indicate a cancer presence.

Similar. Both the 1.3-GHz and 3.3-GHz radiometers are similar in construction. They are comparison-type superheterodyne receivers with a 100-megahertz intermediate frequency bandwidth centered at 60 MHz. The input to the first-stage tunnel-diode amplifier is switched at an 8-hertz rate between the antenna that picks up the human body radiations and a matched load whose temperature is controlled by a thermoelectric refrigerator.

The radiometer compares the emissions from the human source with the thermal emission from the temperature standard. Its output signal is fed both to a strip chart recorder and a light-emitting-diode display that indicates the temperature numerically. When properly tuned up and calibrated, a root-mean-square temperature sensitivity of 0.1° is readily achieved.

The antenna itself is a piece of rectangular waveguide placed flush against the skin when data is taken. Its impedance is adjusted so that there are minimal reflections of energy at the skin-waveguide-air interface.

The MIT-Faulkner team still has a lot to do. Work is continuing at the breast cancer detection clinic so quantitative tests can be applied to the measured temperatures in order to produce still higher true positive and true negative detection rates. And, to explore the effect of changing operating frequency, they have started work with a microprocessor-controlled 6-GHz radiometer.

Medical studies of this type tend to be long-range projects and conservative approaches are taken whenever human health is at stake. For example, James E. Thompson of the electrical and computer engineering department of the University of South Carolina in Columbia "does not plan to use human subjects in the near future" in his work. But he does have hopes that his technique will ultimately facilitate thermographic mass screening for tumors, because he has found that the inherent low sensitivity of thermography can be improved with the use of active low-level microwave radiation. Simply put, Thompson and his associates, Ted L. Simpson and Michael N. Huhn of the college of engineering and James B. Caulfield of the school of medicine at South Carolina, find that some tumorous tissue exposed to low-level microwaves heats up more intensely than the surrounding tissue. They then show up better on an infrared scanner.

NIH-sponsored research has started to answer some of the questions that naturally arise. Do all types of tumors react the same way? What if they are below the skin? Are the microwaves dangerous? Since ultrasonic energy also increases tumor temperature, that kind of radiation also will be examined. Because of the way research must be conducted, it will be a long time before these questions and others are answered, and years before the tests can be used on humans.

Yet Caulfield, for one, finds the prospect of improving the potential for spotting breast cancers and reducing the need for mammography an exciting project. While none of the researchers sees his work as the ultimate detection scheme, each would be a useful adjunct to the diagnostician's art if shown to be statistically significant.

Tryout. NIH-funded tests of the properties of millimeter microwave thermography (11 and 30 GHz) are being carried out by Jochen Edrich of the Denver Research Institute's Electronics division. He uses a noncontacting antenna to pick up the emitted energy and his system produces a gray-scale image similar to infrared thermography but different from the more discrete data obtained by Myers. Edrich's group is doing clinical trials of his millimeter systems combined with conventional infrared and mammograms at Denver's Swedish Hospital.

Still other work is in progress in Europe, where a group from Phillips GmbH in Hamburg, West Germany, is doing 2-GHz examinations at a breast cancer detection clinic in Strassburg, France. Their system features real-time compensation for variable antenna-skin interface energy reflections. □

Detecting human radiation

All human tissue—normal or otherwise—emits thermal radiation that ranges in wavelength over a wide span of the electromagnetic spectrum. At microwave frequencies, the radiation intensity is proportional to the temperature of the tissue.

By itself this is of little interest in medicine. But a cancerous mass is usually accompanied by an increase in local temperature of a few degrees. This radiation can travel through human tissue for distances up to several centimeters. It can also escape from the body if its source is close enough to the surface.

Once out, the radiation is readily detected by present-day microwave radiometric receivers. So, scanning of a patient's natural microwave emissions can be used to locate possible cancerous hot spots.

At normal body temperatures the maximum intensity of the naturally emitted thermal radiation occurs at a wavelength of about a 10 micrometers—the infrared range. This has led to the use of infrared receiving equipment for scanning. At a wavelength of 10 centimeters (typical microwave frequency), the radiated intensity is reduced by a factor of 10^8. But microwave radiometers—originally developed for radio astronomy—are more than sensitive enough anyway.

Both the microwave and infrared procedures are passive. No radiation is sent into the body and the patient is completely safe.



Has your power supply vendor left you up in the air?

Just when you need him most, your power supply vendor can't deliver. Maybe he's unable to meet your interface requirements. Or your performance needs. Or you found claims for his product to be somewhat "inflated".

Whatever the problem, you're in a fix. What to do? Call Powercube.®

Our Cirkitblock® power supply modules are readily available from stock. And you can use these miniature modules to design systems that fit (or retrofit) almost anywhere you want them. You can also count on them to do what you want done. Used for over a decade in major Military and Space programs, these proven 1″ × 1″ × 2″ modules meet the toughest specs for size, weight, performance and environment.

If you have a power supply problem — or want to avoid one — check your requirements with Powercube. Just call us at (617) 667-9500 or circle the reader response card.

It beats finding yourself in a box!



POWERCUBE

A SUBSIDIARY OF UNITRODE CORPORATION

POWERCUBE CORPORATION
EIGHT SUBURBAN PARK DRIVE
BILLERICA, MASSACHUSETTS 01821
(617) 667-9500

Consumer electronics

Auto stereo is a hot market

New emphasis on high-end sets approaching home-equipment quality has doubled expenditures in last three years

by Robert Brownstein, San Francisco regional bureau

In less than five years, automobile stereo systems have turned into big-ticket items. They are moving from the tacky cardboard displays in discount auto parts and department stores and are now shown in elaborate listening rooms like those used in quality home stereo retail stores. To be sure, these new environments are not designed to display those old "$59 specials" but instead sport systems that sell in many cases for $300 to $400. This high end is where most of the recent activity is taking place, helping to double the auto stereo market in the last three years to $1.3 billion.

This is only part of the story. "Of the 115 million passenger cars on America's roads, 29.9 million or 26% are equipped with stereo systems," says John J. Houlahan, president of the market analysis company J. J. Houlahan Co., Los Angeles. His outlook for the next two years is bullish; he sees a doubling in market size by an influx of 29 million more purchases.

The new high-end receiver-cassette tape combinations abound with features like those of quality living room stereos. Because they must build them small to fit within the auto dashboard, auto stereo manufacturers need integrated circuits more than makers of the bigger household systems. In addition to a-m/fm intermediate-frequency and multiplex decoder chips, auto stereo makers use ICs for phase-locked-loop varactor tuning, digital display drivers, voltage regulation, and a growing list of other functions. Most of the systems are imported from Japan and use mostly Japanese ICs. But RCA Corp.'s Solid State division and Motorola Inc.'s Semiconductor Group, in addition to supplying domestic auto radio manufacturers with chips, are turning out their own lines of high-end auto stereos.

Top-of-the-line systems often have tape-bias equalization switching and Dolby noise-reduction circuitry. However, unlike the home stereo situation where consumers are lukewarm to convenience features but demand performance touches, auto stereo buyers like such things as automatic tuners, which at the touch of a button scan the band in search of the next signal. Another product that is unique to the auto stereo market is the booster amplifier, a device with both low-impedance input and low-impedance output that boosts the typical system's 8-ohm output of 5 watts or less to 15 to 60 W. Most automobile speaker systems are unable to handle that much power, so speaker manufacturers like Jensen Sound Laboratories, Schiller Park, Ill., are now offering speakers that can.

One executive, however, feels that too much emphasis is being placed on the high end. Martin Roth, president of Comm Industries, Boston, says there's still a lot of growth potential in the mid-range auto stereo market. "Aside from L. A., Chicago, New York, and other high-end areas, the country is made up of mid-range buyers," he says. Roth believes most of them would balk at high-end prices.

Others, though, seem to agree with the president of Pioneer Electronics of America, Jack Doyle, who declares, "The mandate is clear;

Higher power, performance, prices

A sampling of Pioneer of America's 19 new products tells a typical car stereo story. Consumers will have more choice in performance and convenience features with this year's crop of new systems, but will pay more to get them. Here are some new models:

The KE-5000 is a top-of-the-line a-m/fm stereo with cassette player. It sells for $399.95 and has Dolby noise reduction, selectable tape-bias equalization, scan-and-seek station-finding, and front-to-back fader controls. In addition, the system features a varactor-tuned oscillator that is controlled by a phase-locked loop for electronic tuning and digital display of frequency. It also has a built-in clock.

The CD-7 graphic equalizer offers users the ability to tailor their music with adjustable active-filter circuitry covering the audio spectrum in seven segments. Selling for $179.95, the CD-7 also has an IC delay line to emulate concert hall acoustics.

The GM-120 power amplifier will produce 30 watts per channel at 0.8% total harmonic distortion into a 4-ohm load. It can put out up to 60 W per channel, but with higher distortion. Its price is also $179.95.

The TS-696 high-power-rated speakers were designed because an amplifier like the GM-120 would destroy the voice coils in conventional auto speakers. Pioneer offers this pair of 6-by-9-inch oval speakers rated to handle 40 W each at $119.95 per set.



Not a movie prop. This is the auto stereo dealer's answer to the sound rooms found in stores selling quality home stereo sets. The marketing methods of the two are growing similar.

consumers want better sound quality in their cars and are willing to pay for it." Pioneer is casting its line for a larger share of the $1.5 billion Doyle predicts for sales in 1980. To do so, it plans 19 new products almost exclusively geared to high-end setups.

Scruples. A problem that used to plague scrupulous home stereo manufacturers—specifications—is a current problem for auto stereo manufacturers. Whereas all quality home stereo products are power-rated with a root-mean-square value at a given distortion level and frequency (typically 1,000 hertz) into an 8- or 4-ohm load, power specifications for auto stereos are seldom so qualified. Then, too, there is the problem that the systems offered by auto makers are usually not rated at all, except to describe function and the number of speakers. Don Coleman, vice president of marketing for Clarion Corp. of America, Lawndale, Calif., says Clarion and several others have informally agreed to a standard for advertising specs.

Presently, analyst Houlahan says, 11% of auto stereo systems are installed by auto makers and the remainder by aftermarket companies. More than half of the aftermarket pie is gobbled up by manufacturers and retailers who sell to consumers who want to replace original-equipment radios with stereo units. Pioneer, Sanyo Electric of Japan, and Clarion belong to this group. Another group, with members like Altus Corp. of Melrose, Mass., and Audiovox Corp. of Hauppauge, N. Y., have made $500 million a year selling their wares to new car dealers as an alternative to the equipment installed by the automobile manufacturer.

This second group is fearful of a Detroit strategy that would make more new car models have radios as standard equipment. The Custom Automobile Sound Association has been formed to combat what it sees as an auto maker squeeze play.

The effect of the dollar's downslide with respect to the yen is causing some prices to rise to avoid whittling away profit margins on these largely imported products. However, some retailers indicate that the Japanese manufacturers have been good at throwing in some extra features along with the price increase, thus defusing consumer resistance. Some analysts believe that if the trend in price increases continues unabated it may provide an opening for domestic makers RCA and Motorola to develop a larger market share. And there is talk of Japanese manufacturers moving more production offshore. □



Hybrid Circosis*

Is it your problem? You'll find it most often in a new product or system as it emerges from the development stage. We've treated and cured many a case of it in the electronic, communications and aerospace industries—a nine pole bandpass active filter for the B-52 Tail Warning Radar; a driver-receiver used on the Lamps program; 20,000 V power supply regulator hybrid used in a computer terminal; C-MOS multi-layer hybrid for a PBX in a unique low-cost, hermetically sealed package—just to name a few cases.

Our service includes everything from designing and manufacturing in high volume to engineering and delivering exotic, hermetically sealed, military circuits. We've been doing it for years at our West and East Coast facilities.

Whether it's a matter of original circuit design, production to your schematic, special thick film printing and assembly, or a combination of all three, call us. We'll work out the answer for you, complete with exacting QC in the size and style of package you need.

Why suffer with Hybrid Circosis... let your hybrid circuit problem become ours... *now.*

*Hy'-brid Cir-co'-sis — n.— Difficult and time-consuming development of a functioning hybrid circuit, often complicated by excessive costs and late delivery.

The Hybrid Problem Solvers

integrated microsystems

Division of Aeroflex Laboratories Inc.
Eastern Operations:
35 South Service Rd., Plainview, NY 11803 516-694-6710
Western Operations:
1215 Terra Bella Ave., Mountain View, CA 94043 415-965-3900

Circle 89 on reader service card

Solid state

Semiconductor makers at crossroads

Hogan says they must become systems houses to survive, whereas Petritz foresees growing market for chips

by Arthur Erikson, Managing Editor, International

No one yet has come up with an equation for predicting the pervasiveness of the electronic technologies. And perhaps one really is not needed. For despite this shortcoming, forecasters almost to a man say that the electronics industries seem set for another decade of fast-paced growth as their traditional markets, like mainframe computers and telecommunications gear, continue to expand and completely new markets sprout as did calculators and microcomputers during the 1970s.

But the bullish forecast for electronics business during the 1980s does not necessarily portend easy days for semiconductor suppliers, whose chips make all these marvelous possibilities possible. For semiconductor technology, with the advent of very large-scale integration (VLSI), has reached a watershed—a perilous one for the people who run semiconductor houses. Those who cannot divine the right stream to follow simply risk seeing their business dry up.

Two opinions. The trouble is, no one knows for sure where the mainstream will flow, and so there is considerable argument over the best way to find it. For C. Lester Hogan, who has just announced his retirement as vice chairman of Fairchild Camera and Instrument Corp., the only way for a large semiconductor company to cross the divide successfully is to integrate vertically and become a systems house as well. Richard Petritz, not surprisingly, holds a different view. As managing director of Inmos Ltd., the new semiconductor firm backed by $100 million from the British government, he is convinced that the big market expansion in sight will leave plenty of room for merchant semiconductor houses.

Both Hogan and Petritz spelled out their reasoning in London last month at the "Tomorrow in World Electronics" conference held by Britain's daily business newspaper, the Financial Times. Both agreed that a new era is at hand as VLSI brings the promise—or the threat—of chips bearing a million components. But Hogan asks, "How many customers are there in the world who will buy thousands upon thousands of such large and complex pieces of electronic equipment?"

Not many, Hogan believes. And Gordon Moore, chairman of Intel Corp., agrees. He told the International Solid State Circuits Conference at Philadelphia in mid-February that if million-transistor technology were available today, he really wouldn't know what to do with it.

For Hogan, this means the end of

Confident. Richard Petritz, who heads Inmos, the new semiconductor firm, sees chip makers secure as markets expand.

Changes. C. Lester Hogan, about to retire as vice chairman of Fairchild, says large semiconductor makers must turn to systems.

Why you should buy a digital multimeter from the leader in digital multimeters.

If you're shopping for your first multimeter, or moving up to digital from analog, there are a few things you should know.

First, look at more than price. You'll find, for instance, that the new Fluke 8020A DMM offers features you won't find on other DMMs at *any* price. And it's only $169.

Second, quality pays. Fluke is recognized as the leading maker of multimeters (among other things) with a 30-year heritage of quality, excellence and value that pays off for you in the 8020A.

Third, don't under-buy. You may think that a precision 3½-digit digital multimeter is too much instrument for you right now. But considering our rapidly changing technology, you're going to need digital *yesterday*.

If you're just beginning, go digital.



Why not analog? Because the 8020A has 0.25% dc accuracy, and that's *ten times better* than most analog meters.

Also, the 8020A's digital performance means things like 26 ranges and seven functions. And the tougher your home projects get, the more you need the 8020A's full-range versatility and accuracy. The 8020A has it; analog meters don't.

If you're a pro.

You already know Fluke. And you probably own a benchtop-model multimeter.

Now consider the 8020A: smaller in size, but just as big in capability. Like 2000-count resolution and high-low power ohms. Autozero and autopolarity. And the 8020A has 3-way protection against overvoltage, overcurrent and transients to 6000V!



Beginner or pro, you'll find the meter you now have can't measure nanosiemens. So what? With the 8020A *conductance* function, you can measure the equivalent of 10,000 megohms in nanosiemens. Like capacitor, circuit board and insulation leakage. And, you can check transistor gain with a simple, homemade adapter. Only with the 8020A, a 13-oz. heavyweight that goes where you go, with confidence.

What price to pay.

$169.

Of course, you can pay more. Or less. In fact, you could pay almost as much for equally compact but more simplistic meters, and get far less versatility. And, the 8020A gives you the 'plus' of custom CMOS LSI chip design, and a minimum number of parts (47 in all). All parts and service available at more than 100 Fluke service centers, worldwide. Guaranteed, for a full year.

Rugged. Reliable. Inexpensive to own and to operate; a simple 9V battery assures continuous use for up to 200 hours.

Where to buy.

Call (800) 426-0361*, toll free, and we'll tell you the location of the closest Fluke office or distributor. Get a personal hands-on feel for the best DMM value going.

Price U.S. only.

*Alaska, Hawaii, Washington residents — please call (206) 774-2481.

Command Performance: Demand the Fluke 8020A.

FLUKE®

2525-8020

Circle #91 for literature only

AC voltage

HIGH?

LOW ?

LOGITEK AC Voltage monitors will detect high or low voltage conditions and shed loads or activate an alarm if preset limits are exceeded.

SPECIFICATIONS:

ACCURACY: ±0.1%, 1%, 5%
TEMPERATURE: −55°C to +125°C
−30° to +70°C
INPUT VOLTAGE: 115/220/440 VAC
50/60/400 Hz
DELTA/WYE.
CONTACTS: 2 Amps, 10 Amps.

LOGITEK MANUFACTURERS

MONITORS
FOR POWER LINE CHARACTERISTICS INCLUDING
VOLTAGE • FREQUENCY
PHASE • CURRENT

Also
TIME DELAY RELAYS, FLASHERS, ENERGY MANAGEMENT SYSTEMS

WRITE OR PHONE FOR LITERATURE

516-694-3080

LOGITEK INC.
42 CENTRAL AVENUE
FARMINGDALE, N Y. 11735

92 Circle 92 on reader service card

Probing the news

the time when electronics markets were driven mainly by advances in technology. In the integrated-circuit era, chip densities doubled every year, going from about 30 components on a chip in 1965 to approximately 30,000 in 1975. All along, semiconductor suppliers turned out what was technically feasible and found thousands of equipment makers who wanted to buy it.

But this state of affairs, which semiconductor houses found fairly comfortable, cannot continue. With the 64-K random-access memory, the count has reached about 135,000. Although the curve shows signs of flattening—to a doubling every two years—Hogan maintains that within five years the largest possible chips will be overkill for any reasonable system requirement.

"We can then no longer just build the most complex chip we can dream up," he says. "Precious few customers will find such a chip economical to use."

The changed market, Hogan insists, will go to the companies that take a complete systems approach. In a few rare cases the total system cost might be best with million-transistor chips, but most often the cost-effective volume-selling chips will have much lower component counts—100,000 or even 10,000.

The trend has already started. For example, Hogan puts the world market for 4-bit microprocessors this year at $15 million and projects a spurt to $207 million by 1982. "The 4-bit microprocessor has far outsold its much ballyhooed big brothers, and if we look to 1982, we expect the gap to get larger, not smaller," he comments.

The exception. The one main segment Hogan expects will carry on as before, with bigger and bigger chips driving system costs down and thus winning thousands of customers, is memories. And this exception, for Inmos's Petritz, proves a different rule. He maintains the chip of the future will be a big one, with "lots of memory controlled by on-chip logic." The new families of standard circuits that semiconductor houses will market, he agrees, will be sold by system costs rather than by sheer technology.

Hogan concluded his talk at the Financial Times's conference like this: "Personally, I believe that 10 years from today there will be no large pure semiconductor companies surviving. The same is true for large systems and equipment companies. Since the advent of the integrated circuit, systems companies have resented the loss of design flexibility, which they have surrendered to the semiconductor industry in the name of economy. Now, also in the name of economy, the two functions must again merge."

For the moment, Petritz has no mergers in mind. Except that it takes a lot more money now, he thinks the conditions for entrepreneurs in the semiconductor business are as good now as they were in the days when companies like Intel Corp. and Mostek Corp. started up (Petritz, remember, was one of the founders of Mostek). With the $100 million Inmos has from the UK government, Petritz has the wherewithal for a strong start. And Inmos will be getting into the business, he points out, when VLSI is forcing a shift to 2-micrometer technology. So newcomer Inmos will be working down the same learning curve as the established producers, which today mostly have 3- to 5-μm technology.

What is more, Petritz sees a big chance for innovation in the more powerful VLSI microprocessors and memories that are in the offing. And he is sure that fully integrated systems houses will not be the only ones able to tap the strong growth ahead for electronics markets new and old. IBM, the stellar integrated heavyweight in the computer business, he notes, recently placed whopping orders with Intel for memories and with Texas Instruments Inc. for logic circuits.

Above all, Petritz insists that success in the semiconductor business has always been highly dependent upon a few skilled circuit designers and process people. In the new semiconductor game that will be played over the next decade, a lot of players inevitably will wind up on the sidelines; but Petritz thinks that at Inmos he has put together a winning team. □

AEG-TELEFUNKEN

Wherever functional safety
is a minimum requirement

Decisively improved:

the new "Mini" case for photoreceivers and transmitters

Plastic case	Red	Orange-red	Green	Yellow	IR-Emitter	Detectors
ø 1,9	CQY 41 N	CQX 43 N	CQY 73 N	CQY 75 N	CQY 36 N CQY 37 N	BPW 16 N BPW 17 N
ø 3	CQX 25 N CQY 85 N	CQX 42 N CQX 41 N	CQX 26 N CQY 86 N	CQX 27 N CQY 87 N	CQX 46	BPW 42

We have eliminated the disadvantages of the previously used Miniplast and 3 mm LED cases.

Our new case has advantages such as:
Handling suitable for automatic machines. Clear identification of the polarity, good reproducibility of the optical parameters.

At the same time, we have designed the components in the new cases such that it is easy to construct LED rows!
And this together with good optical insulation, which means low optical cross talk.
We can supply the optoelectronic components you need; tested, in proven quality, future oriented, and TELEREL tested. Regardless of whether you need LEDs in various colors, different 7-segment displays, displays, infrared radiation sources or coupling elements, or, or...
If you would like to know more about our product range, ask for our newest brochures at:

AEG-TELEFUNKEN
Corporation
Route 22 –Orr Drive
Sommerville
New Jersey 08876
Tel.: 7 22 98 00
AEG-TELEFUNKEN
components

Optoelectronic Devices from AEG-TELEFUNKEN

S 8/V7-HN 0279

Circle 93 on reader service card

Electronics abroad

East, West meet at German TV maker

A year after Yugoslav company's takeover of financially troubled West German manufacturer, recovery plan is working

by John Gosch, Frankfurt bureau manager

Some people still can't get over it: a company in Socialist Yugoslavia coming to the rescue of a financially troubled electronics firm in capitalist West Germany. It all happened last summer when, for about $12.5 million, Yugoslavia's Gorenje concern bought control of a family-owned German television and hi-fi equipment firm, Körting Radio Werke GmbH, in Grassau, Bavaria, and set up Gorenje Körting Electronic GmbH & Co.

As expected, there were skeptics predicting that Gorenje would not get Körting back on its feet. But now that early results are in, the doubters have quieted down. "Not only have we reached our initial goals, we have passed them," says Yugoslavia-born Oskar Pistor, Körting's president since last Sept. 1, when the Gorenje/Körting deal took effect.

Pistor points to several accomplishments. His plans, he says, called for raising the number of employees by mid-1979 back to 1,200, the number Körting had before the change in ownership. But several months before the target date, the company already had a work force of 1,300. As for sales, "the $120 million level we have envisioned for this year will be reached," Pistor asserts. For 1980, he predicts, sales will increase to about $135 million, a jump of better than 12%. Such confidence is particularly remarkable as West Germany's entertainment electronics industry is now in the doldrums, with most companies expecting only minimal gains.

Körting's 1979 sales target translates into 170,000 color TV receivers and 35,000 high-fidelity systems plus some equipment for speech and language laboratories in schools. Since last September the company has invested about $2.2 million in research and development, and test and production facilities. More money will be earmarked for those purposes for 1980, Pistor declares.

A difference. To reach its sales targets, Körting has adopted a marketing strategy quite different from its former concept. Instead of selling its wares almost exclusively to a mail-order house, the company is now pushing sales to radio and TV dealers, says Bernd Zumkeller, general manager responsible for marketing. At the same time, the firm is emphasizing exports. What's more, "we are finding new market niches and filling them with products representing the latest in TV and hi-fi design," Zumkeller notes.

It was that mail-order business that was mainly responsible for the firm's financial troubles. When the mail-order firm was bought by one of Germany's biggest department store chains—one that had its own entertainment electronics suppliers—Körting found itself without its prime outlet. The firm also was unable to adapt to the changing monetary conditions triggered, for example, by devalued currencies in some foreign markets.

What is the company behind Körting's revival and what are its motives in gaining control of the German firm? The Gorenje concern, with annual sales exceeding $800 million, rates among Yugoslavia's top 20 industrial organizations. Known as a maker of household



Meeting place. Located at the foot of the Bavarian Alps, Gorenje Körting Electronic GmbH expects to make 170,000 color TV sets and 35,000 hi-fis this year.

Waveform versatility is only the beginning of TM 500 Function Generator performance...

from Tektronix.

Our function generators go beyond the basics to give you the kind of performance your applications demand. We designed the **40 MHz FG 504** to prove it. And it does, with features like these: internal log and linear sweep, phase lock, AM and FM modulation and external trigger and gate. From the rest of our function generator family, you can generate waveforms to fit almost any application—at any budget.

And, there's a lot more to TM 500 than high performance specs. Flexibility is insured with the TM 500 mix and match modular design. Match your function generator with a counter, multimeter and scope and you've put together a compact test set that goes where you go. Choose from over 40 compatible instruments and six mainframes including bench, standard rack and travel lab.

So when you're ready to talk about more than waveforms, talk to us. Tektronix is founded on a commitment to quality so each of our instruments is built to represent the most up-to-date technical and performance standards. Then we back up those instruments with a worldwide network of sales and service organizations to support them—wherever they go.

We would like to help you learn more about TM 500 high performance function generators. Call the Tektronix Field Office nearest you for details about TM 500 Function Generators. To request a copy of the TM 500 catalog call our toll-free, automatic answering service: 1-800-547-1512. In Oregon, call collect: 644-9051. In Europe: Tektronix Limited, P.O. Box 36, St. Peter Port, Guernsey, Channel Islands.

TM 500
Designed for
Configurability

Tektronix®
COMMITTED TO EXCELLENCE

For Technical Data circle 94 on Reader Service Card
For Demonstration circle 95 on Reader Service Card
For immediate action, dial our toll free automatic answering service 1-800-547-1512



No short-cuts!

Grayhill Solid State Relays

are made to keep switching reliably



Micro Cube package



Standard package



Commercial package

If you are concerned with product performance, nothing less than Grayhill Solid State Relays will satisfy your quality needs, because they are manufactured without the short-cuts that can adversely affect performance. Designed to switch inductive loads, Grayhill Solid State Relays have built-in snubber networks with high DV/DT characteristics and a high blocking voltage rating. This means continuing reliable performance, and lower total product cost. Grayhill Solid State Relays are available in optically isolated, transformer isolated and reed relay (Hybrid) versions (most with zero voltage turn-on), in six package styles. Ask for your free copy of our Engineering Bulletins on Grayhill Solid State Relays.

Grayhill INC

561 Hillgrove Avenue • LaGrange, Illinois 60525
(312) 354-1040

Chief. President of the Yugoslav-German firm is Oskar Pistor, a native of Yugoslavia. He is optimistic about the future.

appliances, electric machinery, and semifinished goods, Gorenje exports a hefty 30% of its output. The company's most lucrative foreign markets are in Western Europe.

Like virtually all Yugoslav firms, Gorenje is run by a workers' council that makes all decisions pertaining to investments, profit sharing, exports, vacations, and other social and business aspects. In this regard, Yugoslav firms are different from those in other Socialist countries where industrial enterprises are state-run.

Headquartered in the Slovenian town of Velenje, in northwest Yugoslavia, Gorenje developed from a small metal shop in 1953 into an industrial combine now employing some 20,000 people in 13 plants. Pistor, a 21-year Gorenje veteran, is one of the company founders. Before becoming president of Körting, he headed his firm's Munich-based sales operations in West Germany.

If appliances are Gorenje's forte, the company is no weakling in electronics equipment. Its product lineup encompasses color and black-and-white TV receivers, antennas, and various types of components and accessories. Electronic and electrical goods account for about 30% of Gorenje's total sales. Production of color and black-and-white sets last year came to about 100,000 and 70,000 units, respectively. The TV receiver output is mainly for Yugoslavia's own consumption.

Why the buy? There are several reasons for Gorenje buying into Körting, Pistor explains. One is to get around the high import duties imposed both by Yugoslavia and the Common Market. On TV display tubes and other electronic parts that Yugoslav firms buy in the West, the Belgrade government puts a duty of up to 35% of the product's value.

The Common Market, on the other hand, imposes a duty of 15% on TV sets that Yugoslavia exports to member countries. Faced with such high import and export tariffs, a Yugoslav company obviously has a hard time competing with Common Market–based firms. And with the Belgrade government unwilling to subsidize exports, Gorenje's financial involvement in Körting enables it to buy components and sell finished products under the same conditions that apply to other Common Market firms.

Another reason is to have a manufacturing base in West Germany from which to export entertainment electronics gear to other countries in the West. At present, exports account for a spectacular 58% of Körting's color-TV production, general manager Zumkeller points out.

Better access. Still another reason is to have access to Western TV designs and production know-how. To be sure, the two firms have had know-how exchange and parts-supply agreements since the early 1970s. But now, with the German firm under its control, Gorenje can draw directly on the expertise Körting has acquired since it was established more than half a century ago.

Although part of the Gorenje concern, Körting is autonomous in making decisions and setting its sales policies, Pistor points out. The Yugoslavs define the overall goals, however, and expect Körting to be profitable. A self-sufficient company within the Gorenje group, Körting has its own by-laws conforming to the standards of West German business and social legislation. And the Bavarian state government has pledged $2.7 million to help the company—and job rolls—grow. □

Let us make something perfectly clear.

When it comes to making assembly instructions easier to understand, one color picture can be worth a lot of words.

Which is why so many manufacturers are turning to the Xerox 6500 Color Copier.

Just place a 35mm color slide of the component you want assembled in the 6500's slide adapter.

Push a button.

In seconds you have inexpensive color copies which would have taken hours to render by hand. Call-out overlays are also easily prepared.

You can even place actual circuit boards directly on the glass platen and create transparent color overlays for use by quality-control inspectors.

And when you're not making color assembly aids with the 6500, you can use it to make color-coded copies of PCB stuffing, rework instructions, parts lists and wiring-harness diagrams.

Once you see the time and money the Xerox 6500 Color Copier can save you, something else will become perfectly clear.

Why you should have one.



This print made on a 6500.

XEROX

XEROX® and 6500 are trademarks of XEROX CORPORATION.

Parallel testing keeps your memory traffic moving.

Your production line is probably spewing out a virtual river of memory devices: RAMs, ROMs, EPROMs up to 65K x 8 bits. Your test system can't be a bottleneck. It must pace the flow, not choke it.

Fairchild developed the Xincom 5581 Parallel Operation Memory Tester specifically to speed throughput and help reduce the cost of testing.

The 5581 is a high performance, functional and parametric memory tester. It can parallel test up to four 65K x 4 bit multiplexed address RAMs. And it's done with only two heads, each with two sockets or connectors for wafer probers or device handlers. Thus, the 5581 combines the throughput of a 4-head tester with the mechanical simplicity of a 2-head system.

In its maximum configuration the 5581 will handle:

- ☐ 65K x 4 bit RAMs with multiplexed addresses, four at a time with two at each test head:
- ☐ 65K x 8 bit RAMs and 4K x 8 bit ROMs two at a time, one in each test head:
- ☐ 65K x 8 bit RAMs or 4K x 8 bit ROMs time sequential with a different device at each head.

On-the-fly timing edge control provides test accuracy and reproducibility for production testing of dynamic MOS and bipolar memories.

The 5581 can be used as a stand-alone tester or as a satellite to the Xincom III distributed test



system. As part of the Xincom III test system, it can store, analyze and process vast amounts of test data or prepare schmoo plots, wafer maps, or trend graphs. You also get compiling and test program editing capabilities.

To really appreciate the accuracy and throughput speed of the 5581 you should see one in action. Since there are numerous systems already installed there's probably one close to you. We'll try to set up an appointment for you to see one. Just give us a call.

Fairchild Test Systems Group, Xincom Division, Fairchild Camera and Instrument Corp., 1725 Technology Drive, San Jose, Ca 95110 (408) 998-0123

FAIRCHILD

Circle 99 on reader service card

Nicolet's Explorer...



...begins a new oscilloscope era.

This is an oscilloscope that's *many* times more accurate than traditional oscilloscopes, and it has an order of magnitude better resolution. It is a great storage oscilloscope, too, storing literally hundreds of times more information, without adjustments, at the touch of a button, and it doesn't "forget" until you want it to. It can show live waveforms, or stored waveforms, or live waveforms superimposed on stored waveforms. It has x64 display scale expansion which allows you to see fine details. You can see signal changes as small as a hundredth of a percent, while observing superimposed signal waveforms.

EXPLORER has "retroactive sweep trigger" which means you can observe signals that precede your sweep trigger just as easily as you can observe those that follow. Therefore, you can see the causes of an event as easily as the consequences. This is truly a *general purpose oscilloscope,* for signals in the frequency range of millihertz to a few megahertz, and of course, dc. It provides the same functions as general purpose analog oscilloscopes. The improvement is simply that it performs these functions superbly, with less hassle, and under a greater range of conditions.

An optional internal magnetic disk memory, with removable disks, allows you to store waveforms permanently and recall them in seconds for comparison or inspection. It records at the touch of a button, or automatically in sequence if a series of signals is to be stored. Another option is digital I/O, in case you want to analyze the signals by calculator or computer. RS-232 and IEEE 488 busses are available.

EXPLORER has plug-in unit construction so that you can choose one or two channel operation. You can choose fast plug-ins, or plug-ins designed for measurements of very low frequency and high sensitivity.

Nicolet? Who's Nicolet?

If digital oscilloscopes mark the beginning of a new era in oscilloscopes, you might wonder why little, unknown, Nicolet was the one who pioneered them, rather than one of the traditional manufacturers of 'scopes. Well, we're not so little, and are well known in other instrumentation fields. We manufacture high technology instrumentation including Fourier transform infrared spectrometers, superconducting magnet NMR spectrometers, research and clinical medical instrument computers, real-time FFT spectrum analyzers, and signal averagers. In every one of these product areas we are leaders, or right near the top.

Nicolet has what was needed to conceive and produce general purpose digital oscilloscopes: A fresh viewpoint, imagination, a good knowledge of what an oscilloscope should be and exceptional expertise in the design of digital instrumentation.

There's much more you should know about the EXPLORER, and how it can help you. For complete details or a demonstration, send the reader service card or call Jim Bartosch at 608/271-3333.

NICOLET INSTRUMENT CORPORATION
OSCILLOSCOPE DIVISION
5225 Verona Road, Madison, Wisconsin 53711
Telephone: 608/271-3333

ELECTRO Show Booths 1428-1430.

SALES AND SERVICE OFFICES WORLDWIDE

CANADA: Nicolet Instrument Canada, Ltd.
23-1616 Matheson Boulevard
Mississauga, Ontario L4W 1R9
(416) 625-3901

ENGLAND: Nicolet Instrument Ltd.
80A Emscote Road
Warwick, Warwickshire
(0926) 44451-52

EUROPE: Nicolet Instrument GmbH
Frankfurter Strasse 121
6050 Offenbach am Main
West Germany. 0611-812075

JAPAN: Nicolet Japan Corporation
Daisho Building, Room 1001
8-7, 6 Chome
Nishinakajima, Yodogawa-ku
Osaka 532. 06-305-2150.

Circle 100 on reader service card

Now supports F8, 3870, 3872.

A chip builder's business is building chips. Yours is designing with them. So is ours.

That's why we build a microprocessor lab like you'd design for yourself.

Both the Tektronix 8001 and 8002 microprocessor development labs now fully emulate the 3870, 3872 and F8. You can select the chip that best fits the job without repurchasing or relearning equipment.



INSTRUMENTATION BUILT OUR REPUTATION

The chip builders have their own specialties. But ours is similar to your own: as one of the world's foremost instrumentation designers, Tektronix deals with your kinds of design problems and your kinds of deadlines. We've learned through experience how to maximize equipment versatility and reliability.

That's why our lab supports chips from a variety of builders. Including the 3870, 3872 and F8. The 8085A and 8080A. The Z80A. The 6800. The TMS 9900.

Based on years of experience with microprocessor designs, our labs include many other capabilities like you'd engineer for yourself.

REAL TIME ANALYSIS OPTION

Dynamic monitoring with dual 49-bit breakpoint registers enables quick isolation of timing and logic problems.

ENHANCED BASIC

This enhanced compiler version of BASIC supports the instruction set of the 8080A and can run on the 8080A, 8085A and Z-80A. The compiler produces optimized code. Extensions include facilities for modular programming, interrupt handling, memory I/O, bit operations, and access to I/O ports.

COMPREHENSIVE WORKSHOPS

Microprocessor design workshops are held for our customers monthly, in several locations throughout the country. Programs include a 5-day design workshop and a 3-day course concentrated on the labs themselves.

From engineering to education, you get the painstaking quality you expect from Tektronix. Including expert service and consultation from nearby Tektronix field offices. Ask your Tektronix Sales Engineer for the full story, or contact Tektronix, Inc., P.O. Box 500, Beaverton, OR. 97077. In Europe, Tektronix Ltd., P.O. Box 36, St. Peter Port, Guernsey, Channel Islands.

For immediate action, dial our toll-free automatic answering service, 1-800-547-1512. In Oregon, call collect 644-9051.

Tektronix®
COMMITTED TO EXCELLENCE

Tektronix microprocessor development labs.

Designed by people on your side of the bench.

For 3870 information circle #127
For literature circle #128
For demonstration circle #129

Lab or field, production or process, OEM or general purpose...

The Omnigraphic® Series 100 lets you select the model that's right for your application

The Series 100 is a complete family of X-Y recorders with a model available to meet your specific recording need. Each model is built around a basic mainframe. The completely self-contained mainframe stands alone but can act as the basic building block for your particular application. The Series 100 meets both general purpose as well as special purpose system applications.

Houston Instrument's patented non-contacting capacitance feedback transducer replaces the slidewire and potentiometers, neatly eliminating the most troublesome components of X-Y servo systems.

For complete information contact Jim Bell, Houston Instrument, One Houston Square, Austin, Texas 78753 (512) 837-2820. Outside Texas call toll free 1-800-531-5205. In Europe contact Houston Instrument, Rochesterlaan 6 8240 Gistel Belgium. Phone 059/277445.

No more slidewire cleaner,
no more slidewire lubricant,
no more slidewire

Prices begin at $970*
Quantity discounts available

houston instrument | DIVISION OF BAUSCH & LOMB

"the graphics - recorder company"

* U.S. Domestic Price Only

® Registered Trademark of Houston Instrument

Circle 130 on reader service card

Lithography chases the incredible shrinking line

With better optical, electron-beam, and X-ray systems on the way, mass production of chips with submicrometer line widths will soon be here

by Jerry Lyman, *Packaging & Production Editor*

☐ In laboratories and design centers in Silicon Valley, Japan Inc., and Europe, integrated-circuit designers are busy shrinking line widths and lengths on current LSI designs while creating incredibly finely detailed, dense semiconductor structures for the coming generation of very large-scale integrated circuits. The aim is to produce chips containing over 100,000 gates each—a shrinking of IC patterns that is already bringing increasing switching speeds and reducing chip power consumption. Already a few ICs that need the VLSI definition have appeared—mainly 64-K random-access memories made with metal-oxide-semiconductor technology—and more are in the development stage.

But if VLSI is ever to go into full-scale production, a whole group of major breakthroughs in materials, lithography, processing, and circuit design and testing must occur. This report will concentrate on the lithography aspect of VLSI manufacturing, since VLSI is not possible without the ability to make clean and accurate exposures on resist-covered silicon wafers of circuit patterns with minimum line widths of 2 micrometers or less.

A wide choice

Today the IC processing engineer has a wide range of lithographic methods to choose from. They include contact, proximity, 1:1 projection, step-and-repeat reduction projection, X-ray, and electron-beam systems. Table 1, which purposely omits proximity lithography, summarizes each technique's parameters.

At the present time, contact and proximity printing are still in heavy use, but they will undoubtedly be gradually phased out because of their poor yield. Projection printing, mainly 1:1, is currently the most popular. Scanning electron-beam lithography is at present used mainly to make wafer masks and reticles—in effect, chip masks—for projection printers; in the future it will be used for writing circuit patterns directly onto resist-covered wafers. X-ray lithography has potential as a high-resolution, high-throughput process but still has a number of many practical problems to be ironed out.

Contact and proximity printing are the oldest types of lithographic systems available. In contact printing, a glass mask bearing an emulsion or chromium-film pattern is first aligned with reference points on a resist-coated wafer, then pressed directly onto the wafer and exposed to ultraviolet light with a wavelength of 3,600 to 4,600 angstroms. In proximity, or soft contact, printing, a gap of several micrometers divides mask from wafer.

The resolution of contact printing is limited only by the wavelength of the light used, so that 1-μm-wide lines can easily be printed with this technique, making it suitable for LSI and VLSI chips. Proximity printing has a slightly poorer resolution that varies with the gap size. However, the defect density of chips made with both these techniques is extremely high due to the mask damage and wafer contamination caused by contact between wafer and mask.

In spite of these deficiencies, contact aligners are still



1. One-on-one. Most production projection lithography is done on Perkin-Elmer Micralign machines capable of resolving 3-μm-wide lines. With a deep-UV source, it is theoretically possible to achieve 1.5-μm resolution with this type of machine.

2. In line. A strong competitor to the Micralign is Cobilt's CA 3000, shown interfaced with an automatic in-line wafer-processing system. The CA 3000 features automatic mask-to-wafer alignment and can accommodate up to 92% of a 5-inch wafer.

in heavy demand, for their good resolution and low price ($50,000 to $100,000) make them suitable for custom LSI or research and development applications. For instance, Computervision Corp.'s Cobilt division in Santa Clara, Calif., has supplied many of its $42,000 CA 2020 contact aligners to companies engaged in magnetic-bubble work. Only one mask is normally required for this type of device, and its 1-μm details are exposed by the CA 2020 with an alignment accuracy of ± 0.125 μm. The only other way of achieving this degree of accuracy would be by writing the bubble pattern directly on the chip with a scanning electron-beam machine or direct-step-on wafer projection system.

Canon Inc. in Japan has extended contact printing into the submicrometer range with a new deep-ultraviolet aligner, the PLA 520A. A combined contact and proximity aligner, it uses light in the 2,000-to-2,600-Å range, which has far less of a problem with diffraction effects than longer UV wavelengths. The PLA 520A can expose lines 0.5 μm wide in the contact mode or 2 μm wide in the proximity mode, with a gap of 20 μm between mask and wafer. This year's entire production of the $160,000 machine is already sold out.

So far as LSI and VLSI are concerned, however, contact/proximity lithography can never be a viable production method because of its high defect density—a problem neatly circumvented by projection systems.

Projecting an image

A sharp dividing line runs through the world of optical projection lithography. On one side of it are the well-established 1:1 reflective optical systems having resolutions in the 2- to 3-μm range, alignment accuracies of 0.5 to 1 μm, and throughputs of about 60 wafers per hour. On the other side are the reduction projection systems, or wafer steppers, with 1×, 5×, and 10× lenses. These machines have a better basic resolution (about 1.5 μm) and tighter alignment but lower throughput.

Perkin-Elmer Corp., Norwalk, Conn., delivered its first 1:1 optical projection printer, the Micralign, in 1973. Hundreds of these systems are now in use at almost every major IC manufacturer because they have much higher yields than contact aligners.

The Micralign has a complex reflective lens system that uses a mask to project an image the same size as the mask onto a wafer. Because it does not touch the wafer and therefore cannot damage it, the mask can be made of a hard material like chrome and thus achieve an extremely low defect density, thereby eliminating the chief drawback of the contact aligners. As for other specifications, the Perkin-Elmer machine exposes lines and spaces 2 μm wide with an alignment error of no more than ± 1 μm—more than adequate for the 2- to 6-μm features of today's LSI.

A new 1:1 projector

The latest Perkin-Elmer aligner, the model 140 (Fig. 1), can expose 90% of the area of a wafer 100 millimeters, or 4 inches, in diameter. With an automatic wafer feeder, it can process about 60 wafers an hour—about half the throughput of a contact aligner.

Perkin-Elmer's main competition in this field is Cobilt's CA 3000 (Fig. 2), which first appeared in 1978. This system has a 3-μm average resolution and a ± 0.5-μm alignment error, and it can expose 100% of a 4-inch wafer and 92% of a 5-inch wafer. Alignment of wafer with mask may be manual or automatic, and if automatic, will allow a throughput of up to 100 wafers per hour, says Ed Segal, Cobilt's marketing vice president.

Both the CA 3000 and the model 140 have a resolution of basically 3 μm. Perkin-Elmer's next goal is 2-μm resolution with an alignment error of ± 0.25-μm, and a machine with these specifications will probably appear before the end of this year.

A deep-UV option—say a 2,400- to 3,000-Å source—could reduce the average resolution of this machine to 1.33 μm. However, before this UV dream machine is constructed, some major problems remain to be solved.

TABLE 1: SCANNING THE LITHOGRAPHY FIELD

Method	Resolution (μm)	Alignment (μm)	Typical throughput (wafers/hr)	Approximate price
Scanning, 1:1 optical projection	2 (low volume) 2.5–3 (production)	± 1	60	$150,000–200,000
Scanning, 1:1 optical projection, deep ultraviolet	1–1.5 (not commercially available)	± 0.25	60	"about" $300,000
Direct-step-on-wafer, optical	1–2	± 0.25–0.5	10–60	$450,000–500,000
X-ray, contact/proximity	0.5–2	± 0.1–0.25	10–60	$150,000–200,000
Scanning electron beam, direct-write-on-wafer	0.2–1	± 0.05–0.1	1–2* (commercial machines) up to 22–30* (in-house types)	$1,000,000–2,000,000

*A function of resist, line width, wafer size, machine, etc.

Source: General Instrument Corp.

The lenses for deep UV will need new coatings and better optical tolerances. Available photoresists are not sensitive enough at these short wavelengths and require excessive exposure times. A light source has yet to be optimized for producing light at 2,400 Å. Finally, deep UV requires masks made not of glass but of fused silica, which is both fragile and expensive. These problems have deterred Cobilt from working on a deep-UV option for its projection aligner, though the company is developing a contact aligner with a deep-UV source.

The DSW alternative

For all their popularity, the 1:1 projection machines do have a serious limitation: if a wafer is distorted in processing, it will throw layer-to-layer registration of successive masks on the wafer out of specification, reducing the IC yield. In an effort to reduce this danger, a whole new class of projection aligners has sprung up in the world-wide centers of IC activity. They deal in smaller areas, aligning chip with mask, and aim at better than 3-μm resolution. Variously called reduction projection or direct-step-on-wafer (DSW) machines or wafer steppers, they all operate on the principle shown in Fig. 3—reduction of the size of the mask patterns.

A UV source is shone through the blown-up portion of an IC wafer pattern, commonly known as a reticle. The reticle's pattern is projected down through a reduction lens onto the surface of a resist-covered wafer. (The resist is a standard positive or negative UV type.) After exposure, the table is mechanically stepped to a new site for another exposure. This procedure is repeated until the reticle image is projected across the entire wafer surface. A high-resolution example of what is being done with a wafer stepper is shown in Fig. 4. This, of course, is the same step-and-repeat method that has been used in optical mask making for years.

The wafer stepper's main competition is the 1:1 projection machine, so a comparison of the two types is in order. The stepper boasts better resolution (1.5 μm versus 3 μm) and greater registration accuracy (it makes many alignment checks per wafer, not just one). It can handle much larger wafers, and reticles are much simpler to make than a 1:1 mask. The straight projection aligner, on the other hand, costs much less ($150,000 versus $500,000), has an inherently higher throughput (it makes one exposure instead of many), and is smaller.

Proponents of wafer stepping dispute the merits of high throughput. To quote Bill Tobey, marketing director of GCA/Burlington, Mass., division of GCA Corp.: "What is important is not wafer throughput per hour but good dice per month." Unfortunately, it is too soon to compare the two rivals on this score, although wafer stepper people expect a higher yield due to their system's potentially better layer-to-layer registration.

But no one disputes that the 1:1 systems are smaller. Most of the new reduction projection machines are quite large and a few approach an electron-beam lithography system in size and complexity. In any case, the potential advantages and sizable market for wafer steppers has brought forth many entries into this field.

The high steppers

A great many firms are convinced that the wafer stepper is the way to go for low micrometer resolution. In the U. S., GCA Corp. dominates with its 10× stepper, and Electromask and Optimetrix have entered similar $500,000 machines. All three offer minimum line widths of 1.5 μm and alignment accuracies of ±0.25 μm. Optimetrix and Ultratech also have 1× steppers with slightly higher resolution but lower prices. GCA Corp.'s Burlington, Mass., division already has orders for at least 50 of its $454,000 Mann 4800 DSW machines. At least 13 have been delivered. Prototype devices such as a bubble-memory with 1-μm details have already been exposed on a GCA stepper.

GCA's stepper has a 10× reduction lens (an optional 5× lens is also available) that can resolve usable line widths to 1.25 μm. Throughputs of 30 to 60 wafers per hour are possible with the 10× lens, and wafer sizes up to 5 inches in diameter can be accommodated.

The present system provides for one-time alignment of a wafer on the stage referenced to the system's optical axes. Mask-to-wafer alignment is through a television monitor with a push-button and joystick control. X-Y motion of the state is governed by a laser interferometer that controls the drive servos, the arrangement used in



3. Stepdown. The step-and-repeat reduction projection system, shown in a simplified form, can expose 1-μm geometries. A reduced image of a 10×-2× mask is stepped across a resist-covered wafer. With this method it is possible to align at each exposure.



4. Chip shrink. This four-layer bipolar high-frequency transistor with 1-μm details is an example of the lithography possible with a direct-step-on-the-wafer projection. The transistor's wafer was exposed on a Philips Silicon Repeater SIRE-3, a system with 5× optics.

most scanning electron-beam lithography units. Alignment is accurate to within ±0.25 μm for 2 sigma values.

This off-axis alignment, shown in Fig. 5, contrasts with the through-the-lens alignment of other wafer steppers. In the future, GCA will have an automatic aligner option based on its off-the-axis technique. However, it is also evaluating the through-the-lens alignment method.

In the U. S., GCA's main competitors are three California companies—Electromask Inc. of Woodland Hills, Optimetrix Corp. of Mountain View, and Ultratech Corp. of Santa Clara. Electromask is the strongest, having already received orders for several of its $450,000 systems. It expects to ship its first 700 SLR system this month. The Electromask wafer stepper has a 10× lens system and a wafer stage controlled by a laser interferometer. Resolution is 1 to 1.25 μm depending on field size. Throughput is 20 to 45 3-inch wafers per hour, and 4- and 5-inch wafers can be handled.

The 700 SLR achieves alignment accuracy to ±0.25 μm with a through-the-lens manual alignment method, which aligns the reticle directly with the wafer. In contrast the off-axis method aligns the reticle with fixed targets in the top block of a closed-circuit TV camera, and the wafer with a separate set of targets and optics at the lower end of the camera (Fig. 5).

Frank Chase, Electromask's vice president of marketing, points out that by aligning through the lens there is only one uncontrollable variable—the lens distortion—whereas in the off-axis system there are many variables, such as the lens orthogonality and lens reduction ratio. This is why Electromask can claim a machine-to-machine compatibility of 1 μm. In addition, through-the-lens alignment permits every chip to be aligned if necessary to compensate for wafer distortion.

In the future, according to Chase, Electromask will add an automatic alignment capability to its stepper. Another possibility is a redesign of the lens and source to be suitable for a 3,650-Å UV line. This could push the 700 SLR to 0.5-μm resolution.

A 10× model

Optimetrix, which is a Cutler-Hammer affiliate, also has a 10× stepper capable of 1-μm resolution with an automatically aligned through-the-lens system. Alignment and layer-to-layer overlap are specified at less than ±0.2 μm. Throughput is 30 to 60 4-inch wafers per hour and a laser interferometer controls an air-bearing wafer stage. The first of the $400,000 to $500,000 machines will be delivered in the spring. Aside from excellent optical specifications, the new machine measures only 46 by 38 by 70 inches, which is much smaller than either the GCA or Electromask machines. Also, it supposedly can work out on the production floor and not just in a temperature-controlled environment.

A second machine in development at this firm is a 1:1 stepper having a resolution of 1.5 μm on a 38-millimeter-square field. Alignment accuracy is to ±1.5 μm and throughput is 60 to 100 wafers per hour. Delivery on this $300,000 to $400,000 unit is in the summer. A 7× system with a larger field but the same accuracy as the 10× system is slated for the end of the year.

Last of GCA's U. S. competitors is Ultratech's model 900 projection stepper. It is a relatively low-cost ($185,000), automatically aligned 1:1 stepper.

Martin Lee, vice president of Ultratech, says: "We started out to make a 10:1 stepper but found we needed too much hardware and space to create this type of system with the performance we wanted. Instead we went to a system with simpler optics and less temperature control. A smaller overall unit resulted."

This stepper uses a 3-inch-square 1× mask with four 10-by-10-mm images on it. This allows a user either to choose an image with minimum defect density out of four identical images or conceivably to print four different ICs from four different images. Resolution of the system is 2.5 μm and alignment accuracy is to within 0.25 μm. The automatic alignment system aligns every chip to the reticle. Throughput is about 40 4-inch wafers per hour. Resolution could be extended further, down to 1.5 μm, with a lens design.

The system is controlled by a HP 9825 calculator rather than the minicomputer found in the other U. S. steppers. Size of the aligner is 36 in. deep by 46 in. wide by 60 in. high. Ultratech at present has a feasibility model running and expects to accept orders in mid-1979.

Japanese and European manufacturers are not sitting idly by but have developed optical steppers to compete with their American counterparts. In Japan, Canon has two high-throughput 1:1 steppers, while Nikon has a 10:1 model that competes directly with GCA's 4810 DSW. In the Netherlands, Philips has an improved model of its 5:1 stepper, while Liechtenstein's Censor Inc. is developing a 10:1 stepper due out in 1980. All of these machines resolve features in the 1-to-2-μm range.

Overseas steppers

The two Japanese companies that have developed optical steppers did so in cooperation with the VLSI Cooperative Laboratory [*Electronics,* June 9, 1977, p. 104]. Both machines can operate in the ultraviolet only at 4,360 and 4,050 Å because their makers believe that it is not feasible to design well-corrected lenses for operation at deeper UV wavelengths. Canon Inc. has started to sell its unit, the EP211A, but Nippon Kogaku Ltd. (Nikon) is not in production yet.

The Canon aligner has unity ratio optics and projects a 30-mm-square image. It can expose a 4-inch wafer in seven shots. Minimum line width is 2 μm, alignment error is ±0.3 μm. Alignment is done on each step, exposure control is automatic, and a throughput of 46 4-inch wafers per hour is claimed.

Canon has also announced the FPA 112A. This model exposes a 22-mm-square image on each shot. Resolution of the narrow field lens is higher, permitting exposure of 1.5-μm lines. Other stepper characteristics are the same. Either unit costs 50 million yen, or about $250,000.

The Nikon aligner features 10:1 reduction optics for a resolution of 1 μm. It also can handle 4-in. wafers. Automatic focusing at each step maintains resolution despite wafer distortion. Image size is 10 mm square. The system is designed for either automatic alignment at the initial position or automatic alignment at each step;



SOURCE: ELECTROMASK INC.

5. Alignment alternatives. Wafer steppers align wafer and reticle in one of two ways. Either the reticle is aligned with the wafer by eye directly through the lens (left) or alignment is referenced to off-axis targets. Most new steppers favor the first, easy-to-automate method.



6. Scanning by electron beam. In the scanning electron-beam system, a high-resolution pattern is written directly onto the surface of a resist-covered wafer by a computer-controlled electron beam. This technique eliminates the delay and defects of optical masks.

either way, the time per step is less than 10 seconds.

Philips' unit is called SIRE 3—short for third-generation Silicon Repeater. It projects a 5:1 reduced image of a pattern directly onto a wafer, stepping the wafer after each exposure. The machine's automatic wafer-reticle alignment system ensures an overlap precision of ± 0.25 μm. Minimum resolution attainable is 1.5 μm. Throughput is at least 50 4-inch-diameter wafers per hour. An unusual feature is the use of a helium-neon laser for the automatic alignment system; another is used for interferometric position sensing of the X and Y slider. Few steppers have a laser for autoalignment.

Delivery of the SIRE 3 is expected by the end of 1980. Estimated price is $500,000 to $600,000.

Censor's SRA-100 is a 10:1 reduction stepper featuring a resolution of 1 μm, autofocus, and autoalignment. Through-the-lens alignment at each step gives a registration accuracy of ± 0.2 μm at 2-sigma probability. Throughput is 60 4-inch wafers per hour and unit cost is $450,000. The first SRA-100 will be assembled at Censor's Reno, Nev., facility in time to be demonstrated at Semicon West in 1980.

Going public?

Despite the large array of machines here and abroad, step-and-repeat imaging directly on the wafer is still mostly in the research and development phase at IC fabrication facilities. Often purchase of these systems is veiled in secrecy to mask out company plans.

In the U. S., however, the Motorola Semiconductor Group in Phoenix, Ariz., admits to purchasing a GCA direct-step system. Bill Howard, director of strategic planning for Motorola Semiconductor's IC division, says, "We consider step-and-repeat a strong contender for the mainstay of the early 1980s." But he emphasizes that the promise of direct-step equipment "precludes nothing else" and Motorola has an open mind. Direct-step registration down to 0.25 μm is possible, he says, but he expects other types of equipment to come along to go with direct steppers that will be more economical.

National Semiconductor Corp., Santa Clara, Calif., has been heavily into conventional projection printing with Perkin-Elmer Micralign systems. Now, however, this IC giant is evaluating two GCA steppers. It is also fairly certain that Fairchild Semiconductor, Mountain View, Calif., is evaluating direct stepping. Finally, at IBM Corp.'s Thomas J. Watson Research Center, Yorktown Heights, N. Y., scientists have built an experimental 5:1 direct stepper that has exposed 0.8-to-1.0-μm images on resist-covered wafers.

In Holland, Philips has built five versions of its SIRE 2 for in-house use. In France, the EFCIS (Société pour l'Etude et la Fabrication de Circuits Intégrés Spéciaux) program shared jointly by Thomson-CSF and the Commissariat à l'Energie Atomique (CEA) is banking on direct stepping for ICs with 2-to-3-μm design rules. CEA's research facility in Grenoble is centered around a GCA DSW 4800 machine with a 10× reduction. Next year, the machine will be modified to accept a French-designed 5× lens that should permit 1-μm resolution.

No matter which kind of projection system—1:1 or stepper—comes out on top, all masks and reticles must be made by electron beam. And the same holds for any other high-resolution system that requires a mask. Only when IC design rules move to 1 μm and below is the era of direct writing on the wafer with an electron beam likely to begin. In any case, scanning electron-beam lithography is vital to VLSI.



7. Home-brewed. Hughes Research Laboratories has built five of these vector-scanning electron-beam lithography machines. They are mainly used for writing circuit patterns in the submicrometer range directly on the wafer, for either discrete microwave devices or ICs.

Scanning electron-beam lithography is now a fact of life in major IC facilities worldwide. In this approach a computer-controlled electron beam scans an IC pattern with extremely high resolution and accuracy across a resist-covered silicon wafer or a resist-covered mask substrate (Fig. 6).

Electrons to the fore

Today, a wide range of commercial electron-beam machines exist, all in the $1 million to $2 million range, and more are in the works. Most machines sold are committed to making masks—sometimes around the clock—for use in projection and X-ray lithography, and already several IC firms in the U. S. are ordering their second unit for this purpose. The direct scanning of patterns on wafers, on the other hand, has been mainly confined, at least in the U. S., to firms that have developed their own electron-beam systems. Some of the leaders in this field include IBM, Texas Instruments, Bell Labs, and Hughes Research Labs, Malibu, Calif.

Finally, a different type of electron-beam lithography, one with both great potential and great technical problems, has surfaced at Philips' Redhill facility in England and Electron Beam Microfabrication Corp., San Diego, Calif. (see "The electron-beam projector," p. 112).

The three greatest advantages of the scanning electron-beam system, in ascending order of importance, are its 0.2-to-1-μm resolution, its ability to align a pattern to within 0.05 μm, and its ability to correct for wafer distortion. Its greatest drawback is its throughput, which is invariably low. A complex function of the beam's characteristics, wafer and chip size, feature resolution, and resist, it ranges from 1 to 2 wafers per hour in commercial machines up to as high as 22 in IBM's EL-1 used in a production mode. Vector scanning, in which the beam scans selected areas of the chip, has a higher throughput than raster scanning, in which the beam moves across the entire surface, being switched on and off as the chip pattern requires.

Resolution is another problem. In electron-beam–fabricated structures, it is limited not by the electron optics, but by electron scattering in the resist. This is what sets the bottom limit of resolution to about 0.15 μm.

Finally, the initial cost of a scanning electron-beam machine is extremely high and there is a standing argument in the industry as to whether it can be cut. Undoubtedly, the improved scanners of the future will cost more than today's slower units.

Units for sale

Despite these disadvantages, electron-beam machines are selling at a rapid rate. Most sales in the U. S. have been made by three firms: ETEC Corp., Hayward, Calif., the Extrion division of Varian, Gloucester, Mass., and Cambridge Scientific Instruments Ltd., Melbourn, England, although GCA/Burlington and California's Electron Beam Microfabrication Corp. are developing high-throughput systems of the vector-scanning type to be available early 1980. The two commercial American machines are being used almost exclusively as mask makers. The British unit is a development tool capable of extremely fine submicrometer resolution when writing directly on the wafer, but the company has also sold electron-beam columns and scanning electron microscopes that have ended up or been converted into in-house electron-beam lithography systems.

The ETEC and Extrion machines are uprated licensed versions of Bell Laboratories' EBES [*Electronics*, May 12,

The electron-beam projector

One of the major obstacles preventing the scanning electron-beam-lithography direct-writing system from taking its place on IC fabrication lines is low throughput. A high-throughput alternative is the electron-beam projection system [*Electronics*, Nov. 23, 1978, p. 73], which two companies are in the process of developing. They are the Solid State Electronics division of Philips' Research Laboratories in Redhill, England, and Electron Beam Microfabrication Corp., San Diego, Calif.

This system is analogous to a 1:1 projection system, except that an electron-beam flood lamp replaces the ultraviolet-light source. To use it, a chrome-on-quartz mask is coated with photo-emissive caesium iodide and loaded into a vacuum chamber. Illumination from an intense ultraviolet lamp causes the unmetalized mask areas to emit electrons. These electrons are accelerated onto the wafer by an electric field of high intensity and focused there by a uniform magnetic field with unity magnification.

The method was first proposed by researchers at Westinghouse in the late 1960s. But it was put aside in favor of the scanning system because of problems with the mask and mask-to-wafer alignment and layer-to-layer registration. Now Philips has solved these problems and has a prototype electron image projection in operation at Redhill. Other systems are being constructed. Philips aims to have some pilot products made with its image projectors available within three years.

The wafers processed by the Philips system have special metallic guides on them that emit X rays. These are used by an automatic aligner to align mask to wafer and layer to layer to an accuracy of ±0.1 micrometer. Devices that actually have been fabricated in this way include logic circuits with 2-μm details and bubble memories with 0.6-μm geometries. Minimum resolution of the Philips' electron-beam projector is 0.3 μm. Complete exposure of a wafer take as little as 30 seconds (120 wafers/hr).

Electron Beam Microfabrication is working on a system for the Naval Ocean Systems Center. Its objectives for its system are a throughput of 60 4-in. wafers per hour with 0.5-μm resolution and ±0.2-μm alignment accuracy. Delivery is slated for 1980.

P. J. Daniel of Philips' Research Laboratories is bullish on the chances of the image projector against direct electron-beam writing systems. These, he claims, will retain a specialized niche in the low-volume custom VLSI market, but the larger markets will be served by either X-ray lithography or electron-beam imaging systems, since high-volume production will justify the cost of the specialized masks either technique needs.

1977, p. 95]. This is a raster-scanning unit with a continuously moving table, full wafer alignment, and a laser interferometer to feed the table position back to the electron beam's computer.

ETEC's MEBES is the electron-beam system most heavily sold in the U. S. Twenty-four of the systems have been ordered, about 12 of which have already been shipped to firms like Fairchild, Motorola, National Semiconductor, General Instrument, and RCA.

ETEC's system, aimed specifically at mask making, has a 1-μm resolution and an overlay accuracy with ±0.25 μm. Exposure time for a 4-inch mask is 40 minutes. The present unit can take up to nine 5-inch wafers and developmental work is in progress for even larger wafer sizes. A 10-cassette airlock substrate feeder is now available. System price is $1.6 million.

Wafer confrontation

ETEC also has a program for an advanced system that could write directly on the wafer. Objectives of the program are a throughput of 10 to 20 3- or 4-inch wafers per hour with improvements in line resolution and alignment. The new unit will be built around vector rather than raster scanning [*Electronics*, May 12, 1977, p. 94].

Extrion has recently improved the data rate and software of its version of the Bell EBES. The 20-megahertz data rate of its older EBMG-20 has been uprated to 40 MHz in the newer EeBES-40, enabling it to process a 3-inch wafer in 20 minutes. Otherwise, the two machines are identical. The EeBES-40 still has 1-μm resolution and ±0.125-μm alignment error, and it can accommodate up to a 6-inch wafer. A vacuum loading system for 10 cassettes is standard.

Varian has delivered one of these $1.5 million machines to Ultratech Corp., a maker of masks rather than chips, and recently sold another to Fairchild.

John Dougherty, Extrion's manager of electron-beam lithography, says that making reticles for direct-step-on-wafer machines is becoming just as important as 1:1 mask fabrication. Because of this Extrion has developed special software to go from the optical pattern-generator format to one acceptable to the EeBES-40. For extremely large, dense reticles, the electron beam is faster than optical pattern generation. For instance, a reticle for a large LSI chip that took 1 million flashes to expose at 25,000 flashes per hour would require about 40 hours to produce with an optical pattern generator. The same reticle could be turned out in less than an hour on the new Extrion system. Dougherty also points out that the uprated machine turns out reticles four to five times faster than its earlier version.

Cambridge Scientific Instruments is producing two vector-scanning electron-beam systems, EBMF-1 and -2. The EBMF-1 is a low-cost system having a 75-mm stage and with full computer control and full precision pattern writing. The EBMF-2 is Cambridge's main system with a laser-controlled 105-mm stage and temperature-controlled chamber and airlock; a fully operational system costs about $700,000.

As mentioned before, the EBMF system is a laboratory tool for directly writing high-resolution features onto resist-covered silicon (although it certainly can also be used to make a mask). Minimum line width is about 0.25 μm and alignment accuracy is specified at ±0.15 μm (2-sigma value). The EBMF-2 can handle 4-inch wafers or 5-inch mask plates. Since it is intended for use in research and development, throughput is less important than resolution and layer-to-layer registration.



8. Fine lines. These are samples of submicrometer geometries exposed on a Hughes electron-beam system. The two views show the interdigitated fingers of the pattern of surface acoustic-wave delay lines. Even finer lines have been successfully exposed.

Cambridge Scientific Instruments has been delivering electron-beam systems and components for more than a decade. Its U. S. customers include Xerox, Rockwell International, Hughes Research, Motorola, Cornell University, and General Motors. A European competitor is Philips Gloeilampenfabrieken in the Netherlands, which makes the electron-beam pattern generator EBPG-3 [*Electronics*, Nov. 9, 1978, p. 68].

Versatile

The EBPG-3 is a vector-scanning machine for either making masks or generating patterns directly on the wafer. The typical minimum line width it produces is 0.4 μm. It takes 20 minutes to cover a 3-inch wafer with a pattern using lines less than 2 μm wide and exposing 30% of the chip area to the beam; for a line width of 0.8 μm it takes 65 minutes.

Philips has orders for six machines both from outside customers and from in-house users that make components, such as its Dutch Elcoma division and affiliates outside of Holland like Signetics in California. The $2 million price of the EBPG-3 includes installation, training of personnel, and operational support.

In Japan under the guidance of the VLSI Cooperative Laboratory [*Electronics*, June 9, 1977, p. 104], two commercial electron-beam systems have been developed. One is a raster-scanning system developed at the research and development center of Toshiba Corp. but now being manufactured by an affiliate, Toshiba Machine Co. The Toshiba system was followed by one developed by Jeol Ltd., which vector-scans rectangular areas of variable size.

A prototype of the Toshiba system and the first commercial unit are both in operation at Toshiba. The system is designed for beam diameters of 0.25, 0.5, and 1 μm, with minimum line widths of four times these values to prevent rounding of the corners. The two finer resolutions are designed for direct exposure of masks; the coarsest resolution is designed for making 10× reticles for direct stepping on the wafer. A lanthanum-boride emitter provides density almost an order of magnitude higher than tungsten emitters of other systems.

Toshiba engineers claim their system can write patterns easily for several different devices on a mask without loss of time—an especially helpful feature during development. Typical exposure times for a 100-mm-square mask are 208 minutes for a minimum line width of 1 μm, 58 minutes for 2 μm, and for a 100-mm-square reticle, 34 minutes for a 4-μm minimum line width. Price of this system is 400,000 yen.

The Jeol Ltd. variable-rectangle vector-scanning system differs from the Toshiba unit in that the exposure time is proportional to the complexity of the pattern. The sides of the rectangles can vary between 2 and 12.5 μm in increments of 0.1 μm, with a maximum area per shot of 100 μm^2. The normal exposure rate inside the 2-mm-square area within which the beam can be deflected is 50,000 shots per second.

Movement of the stage makes it possible to expose masks up to 5 inches square. Benchmark performance for a 4-inch hard chrome mask with a resist sensitivity of 10^{-6} coulomb per square centimeter and a pattern with about 200,000 rectangles/cm^2 is about 25 minutes.

The system can also be operated to generate lines as fine as 1 μm wide. Three of these units have already been delivered to Japanese customers for a price of 420 million yen each.

The company introduced its earlier vector-scanning



unit, JBX-5A, in 1975 and has sold more than 20 copies of it. The maximum wafer diameter the JBX-5A can handle is 3 inches, and the exposure time for sensitive resist is about 20 hours. The system is capable of submicrometer patterns. Some customers have used the system for direct wafer exposure, in particular for microwave transistors, which are small and expensive.

In-house electron-beam units

Some of the most sophisticated and highest-resolution chips are being exposed on sophisticated machines designed in house at firms like Hughes. IBM, TI, and Bell Labs. In fact, IBM is one of the few companies in the world to write directly on production wafers.

Hughes Aircraft Co.'s Research Laboratories has been writing circuit patterns directly on wafers for about 12 years. It specializes in building high-performance submicrometer devices like gallium-arsenide field-effect transistors and charge-coupled devices. GaAsFETs with 0.5-μm details have been routinely produced, samples of the same circuits with 0.3-μm details have been made, and a program for 0.25-μm devices is under way.

At its Malibu facility Hughes has built five vector-scanning electron-beam systems based on its modification of scanning electron microscopes from Cambridge Scientific Instruments (Fig. 7). These systems can resolve 0.1-μm details, as shown in the views in Fig. 8, and have an alignment accuracy of ± 0.01 μm. Exposure time for a 4-inch wafer is about 57 minutes.

Being an R&D facility, Hughes has been less concerned with throughput than submicrometer ability. But now, with more demands from other Hughes facilities, it is becoming more production-oriented and is considering building or buying a system that could scan four wafers per hour at submicrometer levels.

IBM is one of the pioneers in electron-beam research, and its twofold effort backs both vector and raster scanning. Its Thomas J. Watson Research Center has developed the VSI system, a laser-interferometer–controlled machine that takes about 5 minutes to vector-scan a 3-inch wafer with 2½-μm details. For lines 1 μm wide, overlay accuracy is ± 0.1 μm. The system is exclusively an R&D tool and has exposed 0.5-to-0.6-μm line widths routinely, 0.016-μm and 0.025-μm details with the aid of a special technique.

IBM's other track

At IBM's facility in East Fishkill, N. Y., the EL-1 raster-scanning system is producing 22 2¼-inch wafers per hour in a direct writing mode. Minimum line width is 2½ μm. The system is at present being used to expose patterns for customized IC layers on logic chips for IBM's System/38 [*Electronics*, March 15, 1979, p. 108].

Texas Instruments has developed its own series of vector-scanning, laser-interferometer–controlled machines, mainly for production photomask making but



9. X-ray lithography. Bell Laboratories uses this experimental X-ray tool for exposures of 1-μm features on experimental integrated circuits. A palladium target provides 4.3-Å radiation for exposure of an organic, X-ray–sensitive resist through a gold-patterned mask.

also for writing directly on the wafer for evaluation purposes. TI's goal is a machine that can scan 10 4-inch wafers with 2-μm details per hour.

William Holton, manager of research development and engineering for TI's Semiconductor Group in Dallas, predicts that by next year electron-beam systems will be making masks for 1:1 projection systems and reticles for wafer steppers as well as writing on chip directly in a few areas. By 1985 he sees them becoming TI's primary tool, with X-ray lithography a "maybe."

Bell Laboratories in Holmdel, N. J., is the originator of the EBES raster-scanning electron-beam lithography system on which both the ETEC and Extrion commercial systems are based. Bell uses the EBES mainly for mask making, but has set one machine aside to see if its parameters can be extended. At the present time this machine has been converted to vector scanning, and extensive software redesign is also in progress.

X marks the spot

Bell Labs and the other firms that use electron-beam systems all recognize that they are too expensive and too slow. This is why there is renewed interest in X-ray lithography. Such systems promise to combine electron-beam resolution with higher throughput for the price of a projection aligner. As Jerry Molitor, manager of the physical electronics laboratory at Hughes Research Laboratories, says, "Eventually we are going to need a batch replicator like X-ray lithography or possibly electron-beam projection to get the throughputs needed."

The first commercial X-ray lithography machine has been produced in Japan, and a U. S. commercial machine is in the works. Meanwhile home-built machines at Bell, Hughes Research, General Instrument, and elsewhere are successfully turning out 1-μm, multimask ICs with good yield and reliability.

X-ray lithography [*Electronics*, Nov. 9, 1979, p. 99] is simply a form of contact printing in which an X-ray source replaces the UV source. It appears suitable for lines 0.5 to 2 μm wide and, with appropriate power sources, resists, and masks, should be capable of throughputs of 10 to 60 wafers per hour.

Resists designed specifically for X-ray exposure are now becoming available. But the masks, which must be opaque to X rays, have been a special problem; made of gold deposited on a layer of silicon, Mylar, or polyimide only 2 to 10 μm thick, they are very fragile. Fortunately, despite their fragility, they can be aligned easily with wafers by modified commercial optical contact aligners. Other problems with X rays are distortion caused by ripple in a processed wafer and a lack of standardization of mask designs.

Bell's X-ray approach

Bell Labs, one of the leaders in X-ray lithography, is now using a second-generation machine (Fig. 9) that has a stationary 4-kilowatt palladium source and uses a gold-plated Kapton mask on a Pyrex support. It can expose a 3-inch wafer in 4 minutes and has achieved registration accuracies of less than 0.5 μm on fast metal-oxide-semiconductor devices with 1-μm details.

Bell opted for a stationary power source to avoid vibration that could blur details in the exposed wafer. Don Herriot, head of lithography systems development in advanced LSI at Bell Labs in Holmdel, N. J., says that line widths so far are limited by the resist, the optical aligner, and the electron-beam–fabricated mask. However, he feels 1-μm devices are possible. Figure 10 shows some samples of present Bell devices.

In an effort to evaluate the reliability of devices exposed to X-ray beams, Bell took similar optically exposed devices and irradiated them with X-ray doses equivalent to those experienced during X-ray lithography. Their performance was not degraded.

Hughes Research has already made 1-μm devices in a similar program in X-ray lithography. The Hughes system employs a rotating 10-kW aluminum source, a Kapton mask, and a Cobilt contact aligner. Hughes can expose a 2-inch wafer coated with copolymer resist in 8 minutes. Tests comparing X-ray and optical lithography complementary-MOS-on-sapphire shift registers produced similar results to those of Bell Labs.

Synchrotron radiation has often been discussed as a source of high-power radiation for X-ray lithography. In France, a half dozen firms are testing this concept on



10. X-ray exposure. Shown above is a resist pattern of 1-μm-wide lines and spaces created by exposing a 2.6-μm-thick resist to X rays on a Bell Laboratories X-ray system. The steps shown are 1 μm high. Note the perpendicularity of the stepped features.

an electron storage ring at the Laboratoire d'Utilization du Rayonnement Electromagnétique at the University of Paris [*Electronics*, March 29, 1979, p. 74].

The firms share 18 hours a week on one of the six light lines out of the storage ring. Experiments being run include the effects of X-ray radiation on mask materials and silicon wafers. So far the damage to these materials is less than was expected.

Commercial rays

The single commercial X-ray aligner available to date was developed jointly by the Electrical Communication Laboratory of the Nippon Telephone and Telegraph Public Corp. and Nippon Kogaku (Nikon). Nikon has a prototype scheduled for completion in April and then will seek orders for delivery for 10 months or so later.

The system uses a rotating water-cooled silicon target with power inputs of 20 kW at voltages of 20 to 25 kilovolts. The system is relatively compact with a distance of only 350 mm between X-ray source and wafer. Mask-to-wafer spacing is 5 to 10 μm ±1 μm.

The minimum incremental step of the work stage is 20 μm with a resolution of better than 0.1 μm. Pattern position detection is also better than 0.1 μm. Alignment accuracy is within 0.2 μm—more than sufficient for Nikon's stated goal of 1-μm-wide lines.

Several types of masks have been used with this machine. The most promising is a sandwich of silicon dioxide between two layers of silicon nitride on a silicon wafer, because its optical transparency of 80% facilitates optical alignment and the three layers minimize stress that could otherwise warp the thin substrate. Silicon is etched away only in the region corresponding to the actual active chip areas, being left untouched elsewhere for added strength. Thus the mask resembles a multipane window, having a gold pattern formed by electron beam lithography on its planar lower surface.

In-house X-ray systems at General Instrument, Hughes Research, and Bell Labs all use Cobilt contact aligners to align delicate X-ray masks to wafers. In view of this, it is no surprise that Cobilt is developing its own X-ray lithography system complete with source and aligner and due out in about two years.

What users can expect

Most of this report has been about the makers of lithography equipment makers and the electronic giants who generate and use their own in-house lithographic equipment. But the IC industry, especially in the U. S., is composed mostly of firms that go outside for their equipment. In general, at independents like Motorola, RCA, Fairchild, National Semiconductor, and General Instrument, most small- and medium-scale ICs are still being made with contact aligners. Large- and very large-scale ICs (down to 2-μm geometries) are produced on Perkin-Elmer's 1:1 projection systems with masks made on electron-beam machines. Step-and-repeat projection systems at these firms are still being evaluated.

Each of these firms has a scanning electron-beam system committed to full-time mask making, and a few have already ordered a second such unit.

Only General Instrument is actively pursuing an X-ray program. This firm has constructed its own machine [*Electronics*, Nov. 9, 1979, p. 106], as well as masks and aligner, and arrived at a satisfactory resist. It has successfully fabricated MOS LSI chips with 1- to 2-μm line widths.

Most other independents are either not considering X-ray lithography or are wary of it. For instance, Jim Dey, manager of the Image Technology Center of National Semiconductor Corp., Santa Clara. Calif., says: "X-ray potentially is the highest-resolution lithographic process currently under development. But there are many problems to be solved before it can become a production technique. It will probably come into prominence at about the 1-μm level. But it could be as long as 8 to 10 years before it becomes economical to use in high volume." Dey thinks that the gap between 1 μm and 2.5 μm will be filled by wafer-stepping techniques and the use of electron-beam wafer writing to design products and write on selected layers in volume production.

For the 1980s, Bill Howard of Motorola can see getting down to 1-μm size with a million components per die by incremental improvements of present technology. "For now, it's electron-beam below 1 μm," says Howard. "But after 1982–3, all bets are off."

Bob Fink, director of industrial engineering of General Instrument Corp. in Hicksville, N. Y., has an entirely different projection of the future from the last two IC people. By 1980 he sees 1:1 projection lithography sharing VLSI with the wafer stepper. And he sees X-ray lithography taking hold as a production tool in 1982.

That is the foreseeable future, for, of course, everyone could be wrong. There is always the chance that some completely new form of IC lithography—perhaps based on ion beams, step-and-repeat X-ray, or laser scanning—could appear and upset all predictions. □

With the new improved bandstacking feature in our Model 2002A sweeper, you can now cover the entire 1 to 2500 MHz range in one fell swoop. You can also start and stop anywhere in between. Anywhere.

Try to find another stand-alone sweep-signal generator that has this capability. Or one with a front-panel meter on which you can easily set and read the output over its +13 to −77 dBm range.

Flatness is ±0.5 dB at the 20-milliwatt output; display linearity is ±1%. For compensation of frequency-dependent variations in test set-ups, a ±2 dB slope adjustment is right there on the front panel. There's also a provision for external leveling.

Besides all this standard equipment, the 2002A has options. Like a deluxe harmonic marker system that provides 1, 10, 50 and 100 MHz markers over the entire frequency range. Or you can order specific single-frequency markers when you buy your 2002A, or whenever a specific application comes along.

But the important thing to remember is that the Model 2002A gets you from 1 to 2500 MHz in a single sweep. And you can't get this anywhere for just $3,400. Not anywhere. Wavetek Indiana, P.O. Box 190, Beech Grove, Indiana 46107. (317) 783-3221. TWX 810-341-3226.

WAVETEK®

Circle 131 on reader service card



The A stands for anywhere.

SYNERTEK

6545 CRT Controller. The designer's choice.

DESIGN FLEXIBILITY.

That's what the SY6545 CRT Controller delivers, giving you an unlimited range of system design configurations—all programmable with the SY6545. You can design all your terminals with the same controller. It's easy. And it's all the result of the programmability and flexibility of the SY6545.

ROW AND COLUMN ADDRESSING.

In addition to the conventional binary sequential memory addressing modes, the SY6545 gives you the option of addressing the refresh memory by row and column. There's no need to perform special algorithms for address conversions. Because we've made the memory location one-to-one correspondent to the screen location.



TRANSPARENT RAM ADDRESSING.

Transparent RAM addressing allows the CRTC to address the refresh memory "transparent" to the MPU—the refresh memory can be configured to be a slave to the CRTC instead of being shared with the MPU. The SY6545 does all the work of generating memory addresses for display refresh and memory updates. The memory can be updated either during horizontal and vertical blanking periods or interleaved with screen refresh during the display period.

HIGH PERFORMANCE AT LOW COST.

The SY6545 allows maximum hardware/software design trade-offs. With its multiple mode operation, minimum component systems can be achieved without sacrificing performance. With fewer components, you get higher reliability. And lower systems cost. Add to this the fact that a second source is readily available for the proprietary SY6545 CRTC and you've got an unbeatable combination.

Our 6545 CRT Controller offers these standard features:

- Alphanumeric and semi-graphic capabilities
- Fully programmable display formats
- Interlaced or non-interlaced scan
- Fully programmable cursor
- External light pen capability
- Up to 16K RAM addressability
- Binary and row/column memory addressing
- Refresh memory can be slaved to CRTC
- Transparent RAM addressing allowing memory updates during horizontal/vertical blanking periods; interleaved during display period; and other modes
- Scrolling capability
- Internal status register to simplify system designs

UPWARD COMPATIBLE TO MC6845.

The SY6545 is plug-in replaceable with Motorola's MC6845, working in all systems designed for the MC6845—without the need for system modifications of any kind. That's compatibility. And more, too. Because the SY6545 does even more than the MC6845, operating in more modes and possessing additional features above and beyond the MC6845. That's upward compatibility.



PERFORMS

ACIA and Baud Rate Generator. A choice like no other.

WE'VE MADE IT SIMPLE.

Our 6551 Asynchronous Communications Interface Adapter is the world's most comprehensive ACIA. We made it that way by designing-in simplicity. It interfaces directly with 6500/6800 microprocessor families. And we've kept it small by eliminating unneeded synchronous protocols and conventions.

BENEFITS, PLUS SOME.

It all adds up to higher reliability, lower manufacturing cost and lower system cost. Among the 6551's features are:

- Single +5V power supply
- Requires only a standard 1.8432 MHz external crystal
- Non-standard user-provided baud rates at 16X external clock frequency (up to 125 kilobaud)
- Stop bits: 1, 1.5 (5-bit word) or 2
- Independently selectable transmit and receive baud rates
- Parity (odd, even, none, mark parity, space parity)
- Double-buffered transmitter and receiver
- Half or full-duplex operation
- Serial echo mode
- Interrupt feature and status register

ON-BOARD BAUD RATE GENERATOR.

The 6551's on-chip programmable baud rate generator eliminates the need for external components and features 15 programmable rates up to 19.2 kilobaud. For non-standard baud rates (up to 125 kilobaud) the 6551 allows the use of an external 16X clock. This wide-ranging programmability allows accommodation of a variety of applications—from point-of-sale, financial and intelligent terminals to front end processors, remote data concentrators, computer-to-computer links and more. Whatever your communications application, the 6551's built-in versatility delivers.

The 6545 CRT Controller and the 6551 ACIA can do the job for you in terminal applications. Put them to work with Synertek's high performance 6500 series microprocessors and memory products, and a high performance intelligent terminal for your needs is only a designer's inspiration away.

Find out how we can help you meet your needs. For information on the 6545 CRT Controller and/or the SY6551 ACIA, fill out the coupon or contact Clement Lee, Microprocessor Group, Synertek, Inc., 3001 Stender Way, Santa Clara, CA 95051. (408) 988-5614. TWX: 910-338-0135.

We've made it in production. We're making it in high technology.



SYNERTEK, INC.

Microprocessor Group
3001 Stender Way, Santa Clara, CA 95051

Gentlemen:
I have immediate needs for technical information on the following: ☐ SY6545 (CRTC) ☐ SY6551 (ACIA)

NAME _____ TITLE _____

COMPANY _____ DIVISION _____

STREET _____ TELEPHONE _____

CITY _____ STATE _____ ZIP _____

Circle 133 on reader service card

Analog ICs divide accurately to conquer computation problems

Housed in dual in-line packages, the hybrids can multiply, divide, or take the square root

by Yu Jen Wong, *Burr-Brown Research Corp., Tucson, Ariz.*

☐ Although analog dividers are basic building blocks in a wide variety of applications, until recently they remained bulky, very limited in operating range, and prohibitively expensive. Within the past two years, though, they have profited from the kinds of technological and design advances that have characterized the progress of integrated circuits in other areas.

Now, dedicated analog dividers are available in dual in-line packages, and their low price—typically less than $20—has gone hand in hand with performance that has improved by orders of magnitude. Burr-Brown Research Corp., for instance, makes a hybrid precision divider, the 4291, with a guaranteed maximum error of less than 0.25% over a 100/1 denominator voltage. With optional external trims, the error may be held to 0.10% over a 1,000/1 range.

What is an analog divider?

Analog dividers are widely used in such applications as ratiometric measurements, percentage computations, transducer and bridge linearization, automatic level- and gain-control systems, voltage-controlled amplifiers, and analog simulations. They may be thought of as black boxes having two inputs and one output and the transfer function given by the equation:

$$E_o = K(N/D)$$

where:

E_o = output voltage
K = a constant
N = numerator input
D = denominator input

For most commercial packaged dividers, K is internally set at 10. Since the divisor can never pass through zero, D is always unipolar. Because N can be bipolar, the divider will operate in two of the four quadrants, as shown in Fig. 1; it is therefore called a two-quadrant divider. Dividers that are designed for operation with N of one polarity are called one-quadrant dividers. At this point, no commercial four-quadrant divider exists, because it is impractical, though not impossible, to design one that would accept bipolar denominator voltages with a dead zone around zero.

There are two limiting conditions for every divider. First, the absolute value of N must be smaller than that of D to prevent the output from saturating beyond 10 volts. Second, a lower limit, D_{min}, is always specified for the denominator below which the divider will exhibit unacceptably large errors. These two conditions define the operating region of a divider (the shaded area in Fig. 1). For one-quadrant dividers, the operating region is either the top or the bottom half of the operating region of a two-quadrant divider.



1. Operating region. The shaded area represents the operating region of a two-quadrant divider. A one-quadrant divider will perform in either the top or bottom half of the shaded area. Below D_{min}, the denominator exhibits unacceptably large errors.

Performing division with multipliers

The oldest and perhaps still the most common method of performing analog division is to connect a multiplier in a feedback loop of an operational amplifier (Fig. 2a). An extra op amp is not needed with commercial packaged multipliers, since their output op amps can be employed through external pin connections.

Figure 2b shows a 4214 transconductance multiplier connected as a differential divider. One limitation of the multiplier–inverted divider (MID) is its limited divisor range. The divider error that limits the ranges can be estimated by:

$$\epsilon_d \doteq 10(\epsilon_m/D)$$

where ϵ_m is the multiplier error specified by the manufac-



2. Economizing space. An analog divider can be constructed by connecting an analog multiplier in the feedback loop of an op amp (a). Packaged multipliers (b) do not require that extra op amp to be pin-programmed for performing division.



3. More accurate. The multiplier–inverted divider exhibits improved accuracy when connected in the manner shown. The error equation is given approximately by $\epsilon_d = 10\epsilon_m/(KD)$, where K is the ratio of R_2 to R_1 and can be used to optimize the divisor's range.

turer and D is the denominator voltage. With a 0.5% transconductance multiplier, the divider error will go as high as 5% when D goes down from 10 to 1 v. Hence, for practical purposes, these dividers are accurate only over a 10/1 denominator range.

The divider error can be reduced by shifting the level of and preamplifying the divisor input and then shifting back at the output stage. In Fig. 3, with K defined by the ratio R_2/R_1, the divider error given by $\epsilon_d \doteq 10\epsilon_m/D$ will be reduced by a factor of K. However, the divisor input is thus limited to $-20/K$ volts. When $K = 2$, the divisor will swing within the same range of 0 to -10 v. In other



4. Converted converter. The multifunction converter may be used as a precision one-quadrant divider with a maximum error of 0.25% over a 100/1 denominator range. The maximum error can be reduced to 0.1% over a 1,000/1 range by using potentiometers R_2 and R_3.



5. Divider IC. The four op amps and the four logging transistors shown in the functional diagram (a) are rearranged and the voltage reference is replaced by a current reference to form a log-antilog divider that maintains a constant-level bandwidth with decreasing divisor voltages (b).





6. Taking the square root. Implementing either the multiplier–inverted divider (a) or the log-antilog divider (b) for finding the square root is a matter of the degree of accuracy wanted. Typical error curves for the two types are shown in the graph (c).

words, the divider error can be cut in half without sacrificing the divisor's dynamic range. With K greater than 2, say, K = 10, the divisor is limited to the range of 0 to −2 v.

One-quadrant divider

The well-known multifunction converter (MFC), through different external connections, can be used as a precision divider whose accuracy and dynamic range greatly exceed that of a multiplier–inverted divider. It is, however, good for one-quadrant operation only, whereas the MID is a two-quadrant divider.

The functional diagram of this converter is shown in Fig. 4. Its transfer function is given by:

$$E_o = X(Y/Z)^m$$

where m is determined by two external resistors and can range from 0.2 to 5. The circuit can be analyzed by applying to each of the four transistors used to achieve the logarithmic relationship, Q_1–Q_4, the Ebers-Moll equation:

$$V_{be} = (KT/q)\ln(I_c/I_s)$$

where:

V_{be} = base-to-emitter voltage
K = Boltzmann's constant (8.62×10^{-5} electron-volt/K)
T = absolute temperature
q = charge of an electron (1 eV)
I_c = collector current
I_s = emitter saturation current

Solving the equation for each of the four transistors simultaneously yields the converter's simple transfer function. This procedure assumes that the four transistors are matched, so that I_s and T are the same for all four equations.

The multifunction converter is capable of operating over a 100/1 denominator range with an error of less than 0.25%. At low input-signal levels, the offset voltages and bias currents of the Y and Z op amps contribute most of the errors. By trimming them out with potentiometers R_2 and R_3, the maximum error can be reduced to 0.1% over a 1,000/1 dynamic range. R_1 is used to trim out gain errors.

The 4291 analog divider has been optimized as a log-antilog divider. It is specified to be the most accurate two-quadrant, self-contained divider available in IC form. It operates in principle very similarly to a multifunction converter, but has several additional features. For one, it contains an internal level-shifting circuit for two-quadrant operation. For another, it is laser-trimmed to hold total error to less than 0.25% over a 100/1 dynamic range. In addition, both linearity compensation and an on-board temperature-compensated reference are provided.

Precise for two quadrants

The divider's functional circuit diagram is given in Fig. 5a. Q_1–Q_4 are the four logging transistors, which are always laid out on a monolithic chip along a thermal equilibrium line. Their geometries are specially designed for maximum conformity to a logarithmic output. In fact, log-conformity error is less than 0.05% over four decades of collector current from 100 microamperes to 10 nanoamperes. Thus, the divider can maintain its accuracy over many decades of denominator voltages.

The error sources at low input levels are mainly due to the offset voltages and bias currents of the numerator and denominator input op amps, and not to the logging transistors. Optional trims are usually provided by manufacturers in order to eliminate the offsets and bias

currents that are inherent in all op amps.

As with the multifunction converter and the multiplier–inverted divider, the bandwidth of the log-antilog divider decreases almost linearly with divisor voltage level; for example, a 400-kilohertz divider at a 10-V divisor voltage will become a 4-kHz divider at a 100-microvolt divisor voltage. By rearranging the four logging transistors and the four op amps and replacing the voltage reference by a current reference, a log-antilog divider whose bandwidth remains constant at high level even with decreasing divisor voltages can be realized (Fig. 5b).

Notice that the current through the output stage (Q_3, Q_4, and A_4) is determined by the reference current, I, and remains constant. If I is set high, the divider's bandwidth will stay fairly flat from a 10-V divisor voltage down to 100 mV and then start to drop gradually, at a much slower rate than the circuit in Fig. 5a. Using 741-type op amps and setting I equal to 200 μA, typical component values are:

R_1 = 50 kilohms R_4 = 10 kΩ
R_2 = 10 kΩ R_5 = 100 kΩ
R_3 = 33 kΩ C = 33 picofarads

As mentioned before, the offset voltages and bias currents of the op amps should be nulled out for low-signal operations. Unfortunately, with a reference current in place of a reference voltage, this divider circuit cannot be readily used as a three-input multiplier-divider to perform $E_o = XY/Z$.



7. Another approach. The multifunction converter (here, the 4302) may also be used as a square-rooter. To implement the transfer function, $E_o = X(YZ)^m$, m can be set equal to ½ (a) or to 1 (b), with the other connections appropriately made.



8. Linearizing bridges. The Wheatstone bridge has a nonlinear output dependent on the input variable (a). It may be linearized by using an op amp in a feedback loop (b), a multiplier–inverted divider (c), or an MID with an instrumentation amplifier (d).

One application of a precision divider is computing the square root of an input signal, often required in process-control systems. If the divisor's input is connected to its output terminal, the divider's transfer function, that is, $E_o = 10N/D$, becomes:

$$E_o = 10(N/E_o) = (10N)^{1/2}$$

The output is now proportional to the square root of the input, N.

Square-rooters

Square-rooters employing a multiplier–inverted divider and a log-antilog divider are shown in Fig. 6a and 6b, respectively. Since E_o is always unipolar, adding a diode at the output of the divider will help prevent the square-rooter from saturating to the opposite supply voltage, which is occasionally caused by power-supply transients. In Fig. 6b, a 1-megohm output load may be necessary to turn on the diode, because the input impedances of the divider are so high (about 10 MΩ) that, without the load, practically no current will flow through the diode.

The square-rooter's accuracy is strictly dependent upon the accuracy of the divider employed. With a multiplier–inverted divider, the accuracy is poor at low input voltages. The error-versus-signal voltage can be estimated from:



(c)



(d)

$$E_o = (10E_{in} + 10\epsilon_m)^{1/2}$$

where E_o and E_{in} are the square-rooter's output and input voltages, respectively, and ϵ_m is the multiplier error specified by the manufacturer. For example, for a 0.5% multiplier, ϵ_m = 50 mV maximum, and therefore the square-rooter's error would be 25 mV maximum at E_{in} = 10 V, but would be 109 mV maximum at E_{in} = 500 mV.

Figure 6c compares the typical error curves of square-rooters built with a multiplier–inverted divider and those made with a log-antilog divider. Typical errors would normally be much lower than in the graph. As can be seen, if small-signal accuracy is critical, a precision divider like the log-antilog type should be used.

With an external voltage reference, a multifunction converter may also be used to build a square-rooter. There are two ways to implement this function. The straightforward method is to set m = ½ with two matched resistors and connect X and Z to a 10-V reference (Fig. 7a). Then the output voltage becomes:

$$E_o = 10(Y/10)^{1/2} = (10Y)^{1/2}$$

Alternatively, m can be set to 1 as in Fig. 7b and the X input connected to a +10-V reference. By shorting Z to the output, E_o, the transfer function becomes:

$$E_o = 10(Y/E_o) = (10Y)^{1/2}$$

The accuracy of this square-rooter is about equal to that of a log-antilog divider.

The familiar Wheatstone bridge is widely used in measuring the resistance of sensors like strain gauges, pressure transducers, thermistors, and servo motors. Unfortunately, the output of the bridge is a nonlinear function of the input variable, the change in the resistance being measured. As illustrated in Fig. 8a, the output voltage, V_o, is related to the input variable, δ, by:

$$V_o = E\delta/(1 \pm \delta)$$

where 2E is the bridge supply voltage.

Linearizing the bridge

Because direct measurement and manipulation of nonlinear data is often undesirable, a circuit is needed to first linearize the bridge function. The simplest method of linearization uses an op amp. Connecting the variable-resistance arm in the feedback loop (Fig. 8b) causes the output of the op amp, V_o, to vary linearly with the variable, δ. Thus, $V_o = -E\delta$. However, some inexpensive bridges are packaged in four-terminal boxes and therefore will not work with this method, which requires five terminals.

A low-cost multiplier–inverted divider with differential Z inputs can, however, implement the inverse of the bridge function and linearize it. In Fig. 8c, the output voltage of the bridge, V_b, is given by:

$$V_b = 10\delta/(1 + \delta)$$

and the multiplier–inverted divider provides the transfer function, $V_o = 10V_b/(10 - V_b)$. The series connection of these two nonlinear circuits results in a linear function,



9. Controlling gain. The bandwidth of a 40-dB automatic-gain-control circuit using the 4291 (a), will be increased by n times, or its tracking range by n times, by cascading n dividers in the feedback loop shown in (b). The 400-kHz bandwidth, however, cannot be exceeded.

that is, $V_o = 10\delta$.

If the bridge supply voltage is single-ended, rather than floating as in Fig. 8c, an instrumentation amplifier is needed to convert the two output terminals of the bridge to a single output. The amplifier can be used effectively to compensate for bridge voltage variations. By inverting the signal such that $V_o = -E\,\delta/(1+\delta)$ and using four resistors to sum the bridge voltage with, and divide it by, V_o (Fig. 8d), the divider's denominator and numerator voltage become:

$$D = \frac{2R_{iD}}{3R_{iD}+2R_1}(E+V_o)$$

$$N = \frac{2R_{iN}}{3R_{iN}+2R_1}V_o$$

respectively, where R_{iD} is the input impedance of the divider's denominator input and R_{iN} is that of the numerator input.

The cleverness of this circuit becomes clear when D and N are substituted into the divider's simple transfer function, $E_o = 10N/D$. The bridge voltage, 2E, and the input impedance, R_i ($= R_{iN} = R_{iD}$), cancel out, resulting in $E_o = -10\delta$. Therefore, the output is independent of the bridge supply voltage. When R_1 is much smaller than R_i, the circuit is insensitive to the value of R_i.

Controlling the gain automatically

To compensate for amplitude fluctuations of any given signal, nothing less than a well-designed automatic-gain-control circuit will do. A good AGC circuit is one that can keep the output constant over a wide dynamic range of



10. A natural application. Direct readouts in percentage of such parameters as efficiency, distortion, gain/loss, and error are easily obtained by connecting a 4214 in a configuration that provides an output of 1 V = 1% with deviations measured up to ± 10%.

input signal levels (tracking range). Analog dividers are excellent candidates for such appplications.

The tracking range of an AGC is directly related to the denominator's operating range of the divider employed. For example, if a divider has a divisor operating range from 10 V down to 100 mV, the AGC circuit associated with it will track ac signals over a 40-decibel range.

Figure 9a shows an AGC circuit using a two-quadrant log-antilog divider. The divider serves as a voltage-controlled amplifier whose output increases with a decrease in divisor voltage. Diode D_1 rectifies the output voltage, e_o. Low-pass filter R_1–C_1 produces a negative voltage, V_n, proportional to the negative peak of e_o. The integrator, comparing V_n with a positive reference voltage, V_r, determines the divisor voltage of the divider.

Automatic gain control is achieved thus: as the input signal, e_{in}, increases, e_o tends to increase, pushing V_n further negative. This increases the integrator's output voltage, which is connected to supply the divisor's input. As the divisor voltage goes up, it will pull e_o back down until it reaches an equilibrium.

Typical values for audio applications are:

$R_1 = R_2/10 = R_3/10 = 1\ k\Omega$

$C_1 = 10C_2 = 10\ \mu F$

$V_r = 0.3$ V

These values will provide a 2-V peak-to-peak output amplitude, which can be reset by adjusting either R_3 or V_r. For subaudio frequencies, an increase in the values of both C_1 and C_2 is necessary.

The upper frequency limit is determined by the bandwidth of the divider, and the bandwidth of most dividers decreases with decreases in divisor voltage. This means that the bandwidth of the AGC will decrease with input signal voltages.

As an example, with a divider's 3-dB bandwidth specified for 400 kHz at a 10-V divisor voltage, the bandwidth will be, as a rule of thumb, 40 kHz at a 1-V divisor voltage and 4 kHz at a 100-mV divisor voltage. With these specifications, a 40-dB AGC circuit will operate over a 40-dB signal range only up to 4 kHz and over a 20-dB range up to 40 kHz. Although it can function up to 400 kHz, the circuit will have no practical tracking range at those frequencies.

The bandwidth of the AGC circuit can be expanded by cascading two or more dividers in the feedback loop (Fig. 9b). For the 40-dB example, each of the dividers operates actually over 40/n dB, where n is the number of dividers cascaded. The bandwidth of the AGC circuit will thus be increased by n times, but will, of course, never exceed the divider's maximum bandwidth of 40 kHz. The cascading technique will also increase the tracking range of the AGC circuit by n times; that is, two 40-dB dividers will yield an 80-dB AGC circuit. Ac coupling at the output of each divider is recommended to eliminate unwanted divider offset voltages.

Taking ratios

For ratiometric applications, a divider naturally comes to mind. Percentage measurement:

$$E_o = 100(E_2 - E_1)/E_1$$

is just another version of ratiometric measurement, but it requires a divider with differential numerator inputs and adjustable gain (from the nominal 10 to 100). With low-cost IC dividers, it is practical to provide direct readout in percentages of such parameters as efficiency, distortion, gain/loss, error, and so on.

Figure 10 shows a percentage measurement circuit employing a differential multiplier–inverted divider. The circuit, which provides 1 V = 1%, is capable of measuring ± 10% deviations. Wider deviations can be measured by decreasing the ratio of R_2/R_1, and narrower variations by increasing the ratio. If the dynamic range of E_1 is too wide for a multiplier–inverted divider to handle, a log-antilog divider may be employed, but an extra operational amplifier will be needed to take the difference $E_2 - E_1$.

The percentage circuit can also be used to sort components by first converting the component's parameter into a voltage and comparing it with a reference. A comparator at the output of the percentage circuit may then be set to separate units beyond a specified limit. □

References

1. Y. J. Wong and W. E. Ott, "Function Circuits: Design and Applications," McGraw-Hill, New York, 1976.
2. J. G. Graeme, "Designing with Operation Amplifiers: Applications Alternatives," McGraw-Hill, New York, 1977.



GET ALL THE INFORMATION YOU NEED ABOUT COMPUTERS AT ONE STOP.

No other stop makes as much sense. You've got a choice of a whole family of reliable computers from $100 computers-on-a-chip to $1,000,000 multi-programming networks. The knowledge that there are 60,000 Data General computers installed in 33 countries. And our promise to keep a steady flow of quality, low-cost products coming. Mail the coupon for more information.



Mail to: Data General, Westboro, Mass. 01581 412

Your ad stopped me. Send the brochures I've circled.

Brochure numbers: 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19

Name _____ Title _____

Company _____

Address _____ Tel. _____

City _____ State _____ Zip _____

Data General

We make computers that make sense.

Data General Corporation, Westboro, MA 01581, (617) 366-8911. Data General (Canada) Ltd., Ontario. Data General Europe, 61 rue de Courcelles, Paris, France, 766.51.78. Data General Australia, (03) 89-0633. Data General Ltda., Sao Paulo, Brazil, 543-0138. Data General Middle East, Athens, Greece, 952-0557. © Data General Corporation, 1979.

Micropower regulator has low dropout voltage

by Kelvin Shih
General Motors Proving Ground, Milford, Mich.

Designed specifically to regulate the output of lithium batteries, which have a low terminal voltage at low temperatures, this circuit provides a stable 5.0 volts at 10 milliamperes for an input voltage as low as 5.2 V.

The low dropout voltage of the regulator (5.2 − 5.0 = 0.2 V) is attained in part by operating the circuit's output transistor in the common-emitter mode. As a result, its collector-to-emitter voltage drop is much lower than the base-to-emitter drop of transistors operated as emitter followers in standard regulators. And, because it uses a low-power operational amplifier operating from a single supply, and a low-current, low-voltage zener diode for the voltage reference, the regulator's idle current is only 250 microamperes.

Three lithium batteries drive the regulator shown in the figure. Their terminal voltage is usually 3 V per cell at room temperature, but it will drop to 2 V at −40°C.

Z_1 provides a low-voltage reference (1.22 V) to the noninverting input of the LM224 op amp, A_1. The Intersil ICL 8069CMQ zener has been selected because it requires only 50 μA of bias current and has a temperature coefficient of better than 50 parts per million/°C.

The 1.22-V reference is compared to the output voltage from a divider network (R_1,R_2, P_1), which is used to trim the output voltage to the desired value. Any voltage difference appearing at the output of A_1 drives transistor Q_1, and thus determines the drive current to Q_2. As a result, Q_2 conducts more heavily if the output voltage is low, or limits the application of battery voltage to the load if the output voltage is high.

There will be no observable change of output voltage for an input voltage variation between 5.2 and 10 V, over the temperature range of −40°C to +70°C. □

Dropout minimum. Voltage regulator for lithium batteries maintains 5-volt output for a minimum input voltage of 5.2 V. Output voltage is constant over the temperature range −40°C to +70°C. Using a low-power op amp operating from a single-ended supply, and a low-current zener, the circuit holds the idle current to 250 μA, well below the 2 to 10 mA required by standard regulators.



Missing-pulse detector handles variable frequencies

by Joe Lyle and Jerry Titsworth
Bendix Corp., Aircraft Brake and Strut Division, South Bend, Ind.

Virtually all missing-pulse detectors require an input signal of fixed frequency in order to operate satisfactorily. They malfunction when the input frequency varies because their circuits employ detection networks that have a fixed time constant. Through the implementation of inexpensive voltage-to-frequency and frequency-to-voltage converters to derive an average, or reference, frequency that tracks the input signal, this circuit can pinpoint missing pulses without being affected by input frequency variations.

As shown in the figure, A_1 and A_2 establish the reference frequency, f_{ref}, using input frequency f_{in}. Missing pulses do not change the reference because of the integrating capacitors within the converters. Meanwhile, the three NAND gates comprising the one-shot produce pulses of 10 microseconds in duration, with a frequency determined by the input signal.

The chip labeled A_4 is clocked by f_{ref} and A_3 through a NAND gate. As long as the input train is continuous, the Q output of A_4 is low. If a missing pulse is detected, however, the one-shot will not generate a pulse to the reset pin of A_3, and the Q output of A_3 (which is also clocked by f_{ref}) will go high to clock A_4. A_4 and f_{ref} will then switch A_5's Q output to high.

This turns on transistor Q_1 and the pilot lamp glows. Switch S_1 is used to reset the circuit after a missing pulse has been detected. Note that circuit operation remains independent of the input frequency, since the arrival of f_{ref} and the 10-μs pulse at A_3 is synchronized to f_{in}.

The circuit should be calibrated by setting A_1 for an output voltage of 10 when a 10-kilohertz input signal is applied. Similarly, A_2 should be set to generate a 10-kHz signal for a 10-V input. □

Synchronous. The circuit detects the missing pulse independently of the pulse train frequency. Voltage-to-frequency and frequency-to-voltage converters derive a reference frequency whose average remains the same for small anomalies occurring in the pulse train: converters' integrating capacitors hold f_{ref} steady despite missing pulses. The reference in this way serves as a synchronous clock.





Our new Model 642 electrometer detects 10^{-17}A.

It delivers 0.005% resolution, is as easy to operate as a DMM and has made the vibrating reed electrometer obsolete. To build an instrument like the 642 takes tenacity, discipline and just a touch of idealism. It takes Keithley.

Voltage reading capability is 10 μV to 10V with $10^{16}\Omega$ input resistance. Charge is measurable from 4×10^{-16}C to 10^{-10}C; input current is only 5×10^{-17}A. Zero to 99% response time is 100 ms on 10^{-10}A ranges, and 400 ms on 10^{-11}A ranges.

Only a hard-nosed bunch of dreamers could've built it.

Inherent accuracy ranges from 0.05% on voltage to 1.5% on 10^{-12}A. Tedious hi-accuracy calibration has been eliminated. Zero check charge error is only a few femtocoulombs.

642 design reduces the impact of ambient temperature and humidity variations. Digital format means no calculations. Just simple, direct reading. Pushbutton control of all functions eliminates time-consuming referencing of instruction manuals. A full complement of accessories is available.

In short the 642 is the most significant development in low current measurement instrumentation since the introduction of the original vibrating reed electrometer in 1947.

If you know Keithley, the 642 comes as no surprise. Maybe any qualified company could have built it, but once again, only one company did.

For a 642 demonstration, literature or information on any Keithley instrument, call (800) 321-0560/Telex: 98-5469. In Ohio, call (216) 248-0400.

KEITHLEY

Keithley Instruments, Inc.
28775 Aurora Road
Cleveland, Ohio 44139
(216) 248-0400 Telex: 98-5469

Keithley Instruments GmbH
Heiglhofstrasse 5
D-8000 München 70
(089) 714-40-65 Telex: 521 21 60

Keithley Instruments, Ltd.
1, Boulton Road
GB-Reading, Berkshire RG2 ONL
(0734) 86 12 87

Keithley Instruments SARL
44, Rue Anatole France
F-91121 Palaiseau Cedex
01-014-22-06 Telex: (842) 204188

Circle 132 on reader service card

Charge pump cuts compandor's attack time

by Devlin M. Gualtieri
Allied Chemical Corp., Morristown, N. J.

Integrated-circuit compandors such as the Signetics NE570 could be more effective in high-fidelity noise-reduction schemes if it were not for one built-in shortcoming: their slow attack time permits large input signals to overdrive the device's compressor and thereby create distortion. But by adding a quad operational amplifier, a diode, and a few resistors, the compandor's attack-to-decay ratio (which is internally set at 1:5) can be dynamically controlled. Specifically, the attack time can be decreased for a given decay period. This concept can be extended to any charge-storage circuit, such as a sample-and-hold module, to speed voltage-level acquisition for a given set of circuit parameters.

The NE570 contains a full-wave rectifier, a variable-gain stage, and other peripheral circuits. The rectifier converts an audio-input signal into a pulsating direct current, which is averaged by an external filter capacitor, C, connected to the compandor's C_{RECT} terminal. The average value of the signal determines the gain of the variable-gain stage.

The compandor's attack and decay times are inversely proportional to the value of the filter capacitor. Thus attack time could be reduced simply by substituting a smaller capacitor for C. But the circuit's purpose is to reduce attack time without using a smaller C, because the third-order harmonic distortion generated when the compandor processes low- and medium-amplitude signals increases as the value of C decreases. The effective capacitance of C during charging is reduced by using this circuit as a pump to charge C more quickly for large input signals, thereby shortening attack time without appreciably reducing the average capacitance of C.

The averaging capacitor is connected to the compandor's rectifier through a 150-ohm resistor, R. At low signal levels, the LM324 quad op amp is not active, so that R contributes only 0.2% additional distortion to what would normally be expected with C alone.

When the rectifier processes a large signal, the relatively large voltage drop across R activates the circuit. Differential amplifier A_1–A_3 generates a large voltage at the input to A_4. This causes A_4 to charge C through D_1 at its short-circuit value of 40 milliamperes. C is effectively charged at 40 volts per millisecond, which corresponds to an attack time of less than 0.1 ms.

The threshold of the enhanced attack rate, which is set by the quiescent 1.3-v drop across C and the 0.7-v drop across D_1, is approximately 0.1 v root mean square (−20 dBm) with respect to the rectifier input. □

Designer's casebook is a regular feature in *Electronics*. We invite readers to submit original and unpublished circuit ideas and solutions to design problems. Explain briefly but thoroughly the circuit's operating principle and purpose. We'll pay $50 for each item published.



Dynamic. Circuit for decreasing NE570's attack time for large signals uses a quad operational amplifier for quick charging of compandor's averaging capacitor, C, in this way reducing its effective value. The fundamental waveform distortion from the compandor output is substantially reduced as a result, but third-harmonic distortion for low- and medium-amplitude signals is not substantially increased.

PROM controller makes fast work of serial jobs

Programmable memory outdoes microprocessor as replacement for flip-flops or logic array in sequential digital controllers

by John J. Petrale
Loral Corp., Electronic Systems Division, Yonkers, N. Y.

☐ Certain types of digital controllers can be far more effectively upgraded with programmable read-only memories than with microprocessors. Sequential controllers, which jump from one state to another, are a good example. Used for process control and various other serially organized tasks, they often cannot afford the time required by a microprocessor to fetch instructions and store them. PROM microcontrollers, on the other hand, make short work of cycling through a number of states one at a time.

However complex this serial algorithm, only three integrated circuits are needed to perform it—two PROMs and a storage register. This set of chips costs less than a microprocessor, yet can also be programmed for a variety of different applications, simplifying production.

No competition

The dedicated hardware traditionally used to build sequential controllers can seldom compete with this combination of simplicity and versatility. The flip-flop controller has to add more and more flip-flops and logic gates, the more complex the algorithm, and the result is often an entanglement of wires. The programmable logic array has the opposite defect: it often has too few elements (like AND and OR gates) for the number of logical operations involved.

Structurally, the PROM microcontroller is a typical digital sequence controller. Figure 1 shows its block diagram. The controller section is the brain of the system; its logic elements execute commands in accordance with the algorithm designed to process the data. The input/output blocks format the data going into and out of the system, and the registers store the data as it is being processed. The data operands modify or change the data, and the recorders indicate the number of events or loops that occur for a given operation.

The system idles, waiting for input. When received,



1. Sequencer. The control block, the heart of any digital sequence controller, responds to control variables from the system's other functional elements by generating micro commands to carry out the algorithm. A PROM version is both capable and easy to use.



2. States. This state diagram illustrates an algorithm that sequences through eight states. The five control variables (B, C, D, E, and F) instruct the controller where and when to branch. The numbers in the circles indicate the number of micro commands generated in each state.



3. PMC. With a PROM microcontroller, any complex algorithm can be realized with two programmable read-only memories and a storage register. The register in the PMC is built from D-type flip-flops. The flip-flop controller uses the J-K variety, which is more subject to noise.

the data is formatted for processing by the I/O block, which then sends a control variable (CV) to the controller. The controller then sequences to its next state, issuing a micro command (MC) to carry out the operation dictated by the last state plus the control variable.

In control

The micro commands control all system functions. The actual processing of the data is done by the data operands; operations here include shifting, adding, and transferring data. Control variables from the recorders, operands, and I/O flag the controller to indicate the end of a specific operation, at which time the data is transferred to the system's output.

A state diagram is used to define the operation of the system. The one shown in Fig. 2 diagrams an algorithm involving eight states. The control variables B, C, D, E, and F tell the sequence controller when and where to branch. In any given state, one, two or three micro commands are generated to perform such tasks as: add one to a counter, or transmit a register's contents to an I/O port.

In a flip-flop controller the logic elements used for the control algorithm are logic gates and J-K–type flip-flops. The flip-flops form storage registers that keep the system in the same state long enough to perform any operation. The output logic gates decode the flip-flops, generating micro commands, and also feed back the state to the input logic gates, for AND-ing with the control variable to elicit the next state.

A complex system can contain hundreds of J-K flip-flops and gates connected in a highly organized way. In

TABLE 1: WORD ALLOCATION FOR CONTROL PROM	
States	PROM addresses
S_0	0 to 31
S_1	32 to 63
S_2	64 to 95
S_3	96 to 127
S_4	128 to 159
S_5	160 to 191
S_6	192 to 223
S_7	224 to 255

translating its state diagram, the engineer must connect a myriad of wires between all these logic elements, knowing that he does so with a high probability of error.

The PROM microcontroller (PMC) reduces design time and hardware cost. Figure 3 shows a typical PMC. The input and output logic gates have been replaced by PROMs and the storage elements are the newer, faster, and less noisy D-type flip-flops. To synchronize all the logic functions, a clock is connected to all the registers, counters, and other such system elements. Otherwise, short high-frequency pulses may occur when the decode PROM switches from one location to another. (The situation is similar to what happens with a two-input logic gate when one input is falling while the other is rising—the overlap of the two signals causes a spike of noise.)

The control PROM at the input contains the truth table for the algorithm—the combinations of control variables and state-address lines that point to specific addresses in that PROM indicating the system's next state. At each clock pulse, the PROM outputs are transferred to the storage register, which in turn drives the decode PROM. For example, when the system is in state 1 (Fig. 2), the input address bits to the decode PROM will be 001, pointing to location 1. Location 1 will have 2 of its 8 bits programmed, so that either of two micro commands may be generated.

The size of the algorithm that the PMC can handle is a function of the number of control PROM outputs. For example, if a PROM has four outputs, it can handle 16 states. Control PROMs can, however, be connected in parallel to accommodate larger algorithms.

The control PROM

The 256-by-4-bit control PROM in Fig. 3 was selected to match the number of control variables and states. The algorithm in Fig. 2 has eight states, so that at least three output lines are required. The number of words, 256 or 2^8, corresponds to the five control variables and the three address lines encoding the states. For each additional control variable, the PROM doubles in size. If there were six control variables and three state lines, it would need to be a 512-word PROM.

Each of the 256 locations must contain a binary value corresponding to one of the eight states in the algorithm. Since the three address lines representing the machine's state are fed back to the high-order address lines of the PROM (Fig. 3), each state uses 32 PROM locations—more than enough for a system in which at most three CVs are required to occur concurrently. And in a given state, it is possible that the PROM will be switched through all 32 locations. The memory map in Table 1 shows the way the words are allocated.

The algorithm dictates how the locations in the control PROM will have to be programmed. For example, when the system is in state 5 (S_5), it will have to sequence to S_6

TABLE 2: PARTIAL PROM MAP FOR STATE 1											
State	Input function: Control variables					PROM address	PROM contents				Notes
	F	E	D	C	B						
S_1	X	X	0	0	0	32	0	0	0	1	Stays in S_1
S_1	X	X	0	0	1	33	0	0	1	1	$S_1 \rightarrow S_3$, B=1
S_1	X	X	0	1	0	34	0	0	0	1	Stays in S_1
S_1	X	X	0	1	1	35	0	0	1	1	$S_1 \rightarrow S_3$, B=1
S_1	X	X	1	0	0	36	0	0	0	1	Stays in S_1
S_1	X	X	1	0	1	37	0	0	1	1	$S_1 \rightarrow S_3$, B=1
S_1	X	X	1	1	0	38	0	0	1	0	$S_1 \rightarrow S_2$, B=0, C=1, D=1
S_1	X	X	1	1	1	39	0	0	1	1	$S_1 \rightarrow S_3$, B=1
S_1	X	1	0	0	0	40	0	0	0	1	Stays in S_1
S_1	X	1	0	0	1	41	0	0	1	1	$S_1 \rightarrow S_3$, B=1
S_1	X	1	0	1	0	42	0	0	0	1	Stays in S_1
S_1	X	1	0	1	1	43	0	0	1	1	$S_1 \rightarrow S_3$, B=1
.	.	.	.	.	.	.	.	.	.	.	. . .
.	.	.	.	.	.	.	.	.	.	.	. . .
.	.	.	.	.	.	.	.	.	.	.	. . .
S_1	1	1	1	1	1	63	0	0	1	1	$S_1 \rightarrow S_3$, B=1

X = "Don't care"

when the control variable E becomes 1 (Fig. 2).

Referring to the table, S_5 encompasses PROM locations 160 to 191. Each one of these 32 locations must therefore have a binary 5 or 6 programmed in to it. In those locations where E is a 1, 110 (S_6) must be programmed for a state change; where E is a 0, 101 (S_5) is burned in to keep the system in S_5. The status of all the other control variables is inconsequential.

Table 2 is a more comprehensive map for PROM locations 32 to 63 only. This area is reserved for state S_1, so that state-address lines from the storage register to the control PROM's high-order address lines are all 001.

PROM addresses 32 and 40 in the table indicate that when B, C, and D are all zero, the system stays in S_1. Therefore, both those locations must contain a binary value of 1. Two conditions must be met to sequence from S_1. When the control variable B is a 1, the system sequences to S_3. All the odd (not even) locations in Table 2—33, 35, 37, and so on—therefore contain 011 (S_3). Also, when B, C, and D are 0, 1, and 1 respectively, the PROM will point to locations 38, 46, 54, and 62 (S_2).

The decode PROM

A 32-by-8-bit PROM is used to convert the states into micro commands (Fig. 3). The number of outputs is determined by the number of micro commands in the algorithm, which in turn is determined by the number of logic functions under the control of the sequencer. For the problem being presented, there are seven micro commands which drive the various registers, operands, and counters in the system. As there are only eight states, an 8-word-by-7-bit decode PROM is sufficient. Since this size of PROM is not commercially available, a 32-by-8-bit PROM is used instead.

Truth tables are helpful in programming the control and decode PROMs. Table 3 shows a form the designer can use to map the control PROM. The present-state column defines the states in which the machine resides. This is followed by two columns for address locations. The grouping of the control variables and the present-state address lines represents the range of addresses in the PROM. Each location in that range must be programmed with the binary value of the next state.

The column for present-state address lines defines the bit configuration for the present state, while the control variable column defines all the control variables for the algorithm in Fig. 2. The X denotes the "don't care" conditions of the control variables for the state.

The next-state column gives the next state of the system when the appropriate CVs are activated. For example, if the machine is in S_5 and the control variable E is a 1, the PROM will point to a new location containing the binary value 110. All other locations within the range of addresses of S_5 will contain the binary value 101 (decimal value 5—the same state). Finally, the function

TABLE 4: DECODE PROM MAP

Input				Output of decode PROM micro commands (states)						
2^2	2^1	2^0	State	7	6	5	4	3	2	1
0	0	0	S_0	0	0	0	0	0	1	0
0	0	1	S_1	0	0	0	1	1	0	0
0	1	0	S_2	0	0	1	0	0	0	0
0	1	1	S_3	0	1	0	0	0	1	1
1	0	0	S_4	0	0	0	0	1	0	0
1	0	1	S_5	0	0	0	1	0	0	0
1	1	0	S_6	1	0	0	0	0	0	0
1	1	1	S_7	0	1	0	0	0	0	0
Addresses 8 to 31 are unused										

TABLE 3: SUMMARY SHEET FOR MAPPING CONTROL PROM

Present state	Address locations in PROM								Contents of PROM			Function
	Present state-address lines			Control variables					Next state			
				F	E	D	C	B				
S_0	0	0	0	X	X	X	X	X	0	0	1	$S_0 \rightarrow S_1$
S_1	0	0	1	X	X	1	1	0	0	1	0	$S_1 \rightarrow S_2$
S_1	0	0	1	X	X	X	X	1	0	1	1	$S_1 \rightarrow S_3$
S_2	0	1	0	X	X	X	X	X	0	1	1	$S_2 \rightarrow S_3$
S_3	0	1	1	X	X	X	X	X	1	0	0	$S_3 \rightarrow S_4$
S_4	1	0	0	X	X	1	X	X	1	0	1	$S_4 \rightarrow S_5$
S_4	1	0	0	X	X	0	X	X	1	1	1	$S_4 \rightarrow S_7$
S_5	1	0	1	X	1	X	X	X	1	1	0	$S_5 \rightarrow S_6$
S_6	1	1	0	1	X	X	X	X	0	0	0	$S_6 \rightarrow S_0$
S_7	1	1	1	1	X	X	X	X	0	0	0	$S_7 \rightarrow S_0$
Binary value	2^7	2^6	2^5	2^4	2^3	2^2	2^1	2^0	X = "Don't care"			



4. Multiplexed PMC. A multiplexer can be tacked onto the basic PROM microcontroller to accommodate more control variables than the control PROM could otherwise handle. This technique allows very complex algorithms to be implemented without large memories.

column summarizes what the controller will do when the appropriate CVs are activated for a specific state—for example, that it will sequence from S_5 to S_6 when E becomes a 1.

After the summary sheet is filled out, it is expanded to include all PROM locations. The map in Table 3 has "don't care" conditions for all the CVs when the system is in S_0. Therefore, every location from 0 to 31 must have a binary value of 001. Similarly, S_1, whose addresses span 32 to 63, must have the value 001 (S_1) assigned to 28 PROM locations. The remaining four (38, 46, 54 and 62) will have the value 010 (S_2). One of the four locations is activated when B, C, and D are in the combination 0, 1, and 1, regardless of the E and F values.

The control PROM just discussed is used to sequence the system through the algorithm. The decode PROM contains the sum of the product terms for each micro command; that is, the OR-ing of the various states that require the activation of the micro commands to drive the external logic circuits. The inputs to the decode PROM are the present state of the machine, as Fig. 3 should make clear.

Table 4 is a map of the decode PROM. Only those locations required for activation need to be programmed.



5. High speed. In applications where a very complex algorithm must be sequenced in very short time, pipelining can be used to eliminate the delay before the generation of the micro commands. However, the decode PROM must now be as large as the control PROM.

Each location represents a state, and since only eight states are used in this particular example, only eight locations are required. Each output of the PROM represents one micro command.

A multiplexed PMC

PROM microcontrollers can be built to accommodate input variables greater in number than the control PROM inputs. This allows very complex algorithms to be implemented with reasonably sized PROMs. Figure 4 shows how a multiplexer may be added to process the extra control variables. These variables are selected one at a time in accordance with the system's state; they therefore cannot include any that must occur simultaneously.

The control PROM's address is now composed of the S_0–S_7 address lines, the multiplexer, and the other CVs. Once again, the data at this location represents a state. The multiplexer-select bits, preprogrammed into the decode PROM, are used as for address of the multiplexer. These steer the selected CVs (B, C, D, E, or F) into the control PROM.

A high-speed version

In many applications a system must operate at very high speeds or a complex algorithm must be sequenced in a very short period of time. A technique called pipelining helps to satisfy this requirement by removing one level of delay between the state and the generation of the micro commands. It does so by moving the decode PROM to the control PROM position, as Fig. 5 illustrates.

Such a system no longer needs to wait until after the control PROM has entered the next state to decode the micro commands. They are now decoded in the previous state and are enabled at the same time the system goes into the next state. The only penalty is in the size of the decode PROM, which must now have as many locations as the control PROM.

The PROM micro controller is already an attractive alternative to a microprocessor, a programmable logic array, or J-K flip-flop controller. It will soon become still more attractive, with the availability of large-scale integrated circuits containing multiplexer, PROMs, and storage register on a single chip. □



WHEN HEWLETT-PACKARD WANTED TO PROTECT THEIR MEMORIES, THEY REMEMBERED US.

When a computer loses power, its volatile memory goes blank. Plain, simple, and costly.

It doesn't have to happen.

Because Gates Energy cells and batteries provide dependable standby power. They furnish the energy when the local power company can't.

That's why more and more major computer manufacturers are making Gates an integral part of their products.

Our energy cells have outstanding capability for float charging. So, they're always at peak power for emergency situations.

And, for portable instrumentation, Gates Energy cells offer safe, reliable sealed lead-acid construction and extended discharge service.

Learn more about Gates Energy. Send for our comprehensive information packet full of design data, spec sheets and application notes. Circle our Reader Service Number, or write us directly.

Gates Energy Products, Inc., 1050 South Broadway, Denver, CO 80217. Phone (303) 744-4806.

GATES ENERGY

EM4

Ready to rent, lease or buy test instruments? Let US help.

When you need test equipment you usually need it fast. That means that you can't waste a lot of time looking for the right equipment or sending back equipment that doesn't work the first time. USIR can help.

We can help you select the right way to acquire the instrument you need. Our exclusive Instrument Acquisition Analyzer pinpoints the relative costs of renting, leasing or buying an instrument.

We find the fastest way to put a working instrument on your bench. Whether it's air freight or one of our own delivery trucks, USIR finds the fastest possible way to put the gear you want on your bench. And you can be sure that it will work when it arrives because we check each piece of gear twice, once when it comes back from the field and then again just before we pack it for shipment to you.

We can tell you in sixty seconds what equipment is available and how soon you can have it. Using IDIOM, our computer system, we can find the instrument you need in one minute at any of our locations throughout the U.S. and Canada, tell you how much it costs and how soon you can have it on your bench. We can also suggest direct replacements if the instrument you need isn't immediately available.

Let US tell you more—Ask for this free Instrument Acquisition Analysis Kit. USIR has prepared a kit that will help you find the fastest, most efficient, least expensive way to acquire the instruments you need. The kit includes our Instrument Acquisition Analyzer, a current USIR catalog and our brochure, "Test Equipment—Think Of It As Money." This piece discusses the different ways of acquiring instruments from a manager's point of view considering all the costs of acquisition. Send for it today.





US INSTRUMENT RENTALS
A U.S. Leasing Company

2121 S. El Camino Real
San Mateo, CA 94403
(415) 574-6006

Circle 140 on reader service card

Fast electrical test monitors chip-package bond quality

Quantitative technique checks heat flow from chip to mounting surface—a crucial performance and reliability factor

by Bernard S. Siegel, *Sage Enterprises Inc., Mountain View, Calif.*

☐ The most critical heat-conductive link between a semiconductor chip and the outside world is the die attachment—the physical bond between the silicon and the package or header it is mounted on. Any gaps or voids between the chip and its mounting surface raise the junction temperatures in its active area and therefore degrade its parametric and functional performance. A mere 10°C rise in operating temperature can double a transistor's bias-current requirements and halve the life expectancy of a sensitive operational amplifier.

Clearly, any production quality control effort should include an accurate check of die attachment quality. A quantitative bond-quality specification would be very useful to potential users of a device in determining if it will meet performance and reliability requirements and in comparing different vendors' parts.

A number of bond quality evaluation techniques have been used in the past ("The hard way to judge bond quality," p. 142). But none of these has all the properties desirable for such a procedure: simplicity, speed, nonde-



1. Chip checker. With the help of an automatic device handler, a die-attachment evaluator can test and sort up to 12,000 devices like these TO-3 power transistors in one hour. Photo is courtesy of Fairchild Camera and Instrument Corp.

The hard way to judge bond quality

The oldest method of evaluating the quality of a bond between a chip and its package is simple but destructive: the chip is physically sheared from its header or package. Examination of the mounting surface reveals how well the chip was attached. This method has three strikes against it: it's destructive, time-consuming, and non-quantitative.

Two newer, nondestructive techniques are X-ray examination and thermal resistance testing. In the former, the cross-sectional area where the chip meets its mounting surface is X-rayed. A trained operator examines the picture for shaded areas representing voids between chip and mounting surface. The approximate percentage of total mounting area that appears shaded becomes the assembled device's effective void area number. That number and the void locations are considered in the judgment of bond integrity. Although this method is nondestructive, it is expensive, time-consuming, and qualitative; it is also unsuitable for certain types of metallic chip-package combinations.

Thermal resistance testing [*Electronics*, July 6, 1978, p. 121] is nondestructive and quantitative, but very time-consuming and relatively insensitive. The technique measures the total thermal resistance between the chip's active area and the environment under steady-state thermal conditions—which may take 10 minutes to establish under ambient-air conditions. Thermal resistance testing is a good indicator of heat-transfer efficiency between a packaged chip and, say, a heat sink, but it is too slow and insensitive to track the rapid flow of heat from an operating chip to its package. Moreover, it yields absolute values of bond quality, which may be useful to designers but are of little value during testing of hundreds of devices.



2. Thermal-equivalent circuit. The simplified electronic analog of the flow of heat from a semiconductor device to the outside world is a series of resistors and capacitors in parallel. For transient conditions, both are important.

structiveness, and the ability to yield a pass/fail judgment of bond integrity.

A new technique called electrically induced thermal transient testing finally brings all these properties to the job. The method is embodied in a stand-alone instrument, dubbed the die-attachment evaluator (Fig. 1), that can examine the bond between a semiconductor and its package in milliseconds. A proportional numeric display indicates bond quality.

Heat versus time

The principle of electrically induced thermal transient testing relies on the following two properties of packaged semiconductors:

- Every semiconductor device has at least one electrical parameter that varies linearly with junction temperature. If this temperature-sensitive parameter (TSP) is measured before and after the device is heated, its change in value indicates how well the chip dissipates heat from its active area through the package to the environment. The smaller the change in the TSP, the better the bond.
- The thermal time constants of the various components that comprise an assembled semiconductor device—chip, substrate, and package—typically differ from one another by at least an order of magnitude. Figure 2 is an electronic analog of the path of heat flow from a chip's active area to the outside world. Each section has a thermal time constant t_θ equal to the product of its thermal resistance θ and heat capacity C_θ, which respond to heat just as electrical resistors and capacitors respond to electrons.

In thermal resistance testing, the active area is heated electrically for a relatively long time—longer than the sum of $t_{\theta 1}$, $t_{\theta 2}$, $t_{\theta 3}$, and $t_{\theta 4}$—to establish thermal equilibrium. When thermal equilibrium is reached, the heat capacities no longer affect the flow of heat; the thermal resistance value obtained is the sum of the θs and indicates the integrity of the entire series of bonds between active area and environment.

The large differences in time constants between sections allow individual sections to be heated selectively by applying heat for controlled durations. Thermal tran-

TEMPERATURE-SENSITIVE PARAMETERS AND TYPICAL TEST CONDITIONS

Device type	Parameter voltage	Typical test condidtions
Bipolar transistors	base-emitter	$V_H = V_{CE}$ $I_M = I_E = 1$ mA for $I_H \leq 250$ mA $= 10$ mA for 250 mA $\leq I_H \leq 5$A
Gunn diodes	low-field	$I_M = 30-50$ mA for $I_H \leq 0.8$A $= 100$ mA for $I_H \geq 0.8$A
Impatt diodes	reverse	$I_M = 1$ mA
Schottky, pn, varactor and p-i-n diodes	forward	$I_M = 1-10$ mA for $I_H \leq 5$A $= 100$ mA for $I_H \geq 5$A
Integrated circuits	forward	$I_M = 1$ mA, on substrate-isolation diode
JFETs	gate-source (forward-biased)	$I_M = 0.1-1$ mA; $V_{DS} = 0$
MOSFETs	drain-body	$I_M = 1-10$ mA; $V_{GS} = 0$ or depletion voltage

I_H = heating current
I_M = measurement current
V_H = heating voltage
V_{GS} = gate-source voltage
V_{CE} = collector-emitter voltage





3. Temperature-sensitive. Powering a pn junction diode at I_M, then I_H, and then back to I_M changes the value of V_F from V_1 to V_2. The difference, ΔV, is proportional to the rise in junction temperature ΔT_J. This proportionality remains fairly constant for one device type.

sient testing, therefore, uses a chip's transient thermal behavior to measure the quality of individual bonds between sections. The behavior of the die attachment is of particular interest. If heat is applied just long enough for it to reach the die attachment—longer than $t_{\theta 1} + t_{\theta 2}$, but shorter than $t_{\theta 1} + t_{\theta 2} + t_{\theta 3}$—the measured change in the value of the TSP indicates how well the chip dissipates heat to that point.

Implementing the concept

A thermal transient test of a chip-to-package bond is a three-step procedure: initial measurement of the TSP voltage, application of heat of specific amplitude and duration, and a second measurement of the TSP. The difference between the TSP values, ΔV, is proportional to the change in junction temperature, ΔT_J, resulting from the applied heat. ΔV is therefore a measure of die attachment integrity. Table 1 lists TSPs for various semiconductor devices.

The table also lists typical measurement conditions for



4. Heating up. Semilog plot of ΔV against time from 1 millisecond to 1 second shows that the rate of heat flow between sections of a packaged semiconductor is not uniform. The optimum heating time should correspond to a slope maximum of the curve in region B.



5. The median is the message. These plots show the range of deviations in ΔV_{BE} from the average ΔV of 25 chips. The median device is chip 4. In the lower plot, data skews to the right since the ΔVs of well-bonded chips approach 0 (−60% deviation).

the parts. Most important is I_M, the measurement current. As shown in Fig. 3, I_M is applied for time t_1—just long enough to measure the TSP. The tabulated amplitudes of I_M reflect the rule of thumb that I_M should be roughly one fiftieth the heating current I_H to avoid heating the part during the first test step.

Figure 3 shows typical test waveforms for a pn junction diode, obtained as follows: first, I_M is applied for t_1. The TSP, in this case the diode's forward voltage drop V_F, is measured and called V_1. Then the current is raised to the heating value I_H for heating time t_H. During t_H the diode receives and dissipates heat, and the value of the TSP changes. At the end of the heating period, the TSP is measured again during t_2 and called V_2. V_1 minus V_2 equals ΔV, which is used to judge the integrity of die attachment.

The heating time t_H must be chosen carefully to maximize the test's sensitivity to voids in the die attachment. The simplest way to optimize t_H is to choose a typical part in the lot and test it at several different heating times, plotting the results against t_H, as in Fig. 4. Heat transfer between sections of the packaged device occurs at slope maxima of the curve, since the thermal capacities appear as short circuits when heat first reaches each section. For maximum sensitivity to voids between the chip and the substrate, the optimum value of t_H is at the slope maximum of the curve, which is usually midway through region B.

To demonstrate the effectiveness of the test, the mounting surfaces of 25 bipolar power transistor chips were selectively etched to produce voids ranging from 0% to 50% of the total mounting area. The die attachment evaluator, a D.A.E. 205 (built by Sage Enterprises Inc., Mountain View, Calif.), was connected to each device through a special Kelvin contact fixture.

Fixure 5 shows the results of testing the chips at three values of t_H. The plots are frequency distributions versus ΔV: the number of parts that yielded various values of ΔV at the three heating times. Each plot's horizontal axis represents deviations in ΔV from the average value for the 25 parts. From the middle plot, device number 4 was chosen as the median part and then tested over a range of t_H values to obtain a curve similar to Fig. 4. For this part, the optimum value of t_H is in the 30- to 80-millisecond range.

Once t_H is chosen, an entire lot can be compared to the median part. Those parts with ΔV values greater than that of the median part by more than the statistical standard deviation of a multi-part sample can be rejected. The ΔV deviation limit can be correlated to other test methods for greater accuracy.

This procedure would be relatively useless if the ΔV measurement for the median device could not be compared to those of other devices as a measure of the rise in junction temperature upon heating. Although the absolute values of V_1 and V_2 at given values of T_J vary for large numbers of devices of the same type, fortunately the relationship between ΔV and ΔT_J seldom does. Thus, devices from several production runs can be compared to a typical device using the same value of t_H. Should a change occur in the relationship between ΔV and ΔT_J, the ΔV limit may be scaled up or down. □

25MHz or 100MHz?

What Makes the Difference?

At Philips it's bandwidth and bandwidth alone. All of the most important standard features on our 100MHz scope are standard on our 25MHz. In fact we often talk 100MHz-customers into buying our 25MHz scope because they need our standard features, not our expanded bandwidth-which costs a mere $1,000 extra.

Aside from costing $1,000 less, the Philips PM3214 25MHz/2mV dual trace alternate time base scope gives you more for your money than any other 25MHz scope on the market.

Although its vertical bandwidth is 25MHz, it typically triggers to 40MHz or more. And it does so in the quick, convenient Auto mode.

When this Auto button is depressed the trigger level is automatically held within peak to peak amplitude of the signal. If there's no signal a zero line is displayed. Triggering is instant and unambiguous for a wide variety of measurement conditions. For phase measurements the level can still be adjusted between the extremes of the signal amplitude. TV trigger is also fully automatic.

Fully calibrated delayed sweep shows the PM3214's comprehensive time base facilities. There is independent triggering for each time base, separate source selection and DC coupling for both sweeps, plus an alternate time base mode. Good reasons the PM3214 can take the place of larger, more expensive scopes in the lab or field.



Priced at under $1500*, the Philips PM3214 gives you more for your money-and no more than you need.

For More Facts or a Convincing Hands-On Demonstration,
use our toll-free number, (800) 631-7172 in the continental U.S. In New Jersey, please call collect, (201) 529-3800. Or contact Philips Test & Measuring Instruments, Inc., 85 McKee Drive, Mahwah, New Jersey 07430.

*U.S. Domestic Price Only.

PHILIPS Test & Measuring Instruments

PHILIPS

Circle 144 for Literature

Circle 145 for Demonstration

TERADYNE HAS ALWAYS BUILT THE WORLD'S MOST PRODUCTIVE LINEAR TEST AND TRIM SYSTEMS.

Since we introduced the J273B Linear Test System, we have improved it almost continuously.

Over the past few years, we've introduced system elements for audio and am radio parts, chroma and VHF devices, as well as op amps, voltage regulators, and other devices. And we've developed standard packages for testing most devices in those families.

Teradyne is committed to linear testing. Committed to providing whatever new test capabilities the industry requires. Whether in industrial, consumer, automotive, or telecommunications markets.



As a result, the J273B continues to be the most flexible and economical system you can own.

In 1978 alone, we developed over a dozen new capabilities, all compatible with installed systems. And more are coming in 1979.

With almost two hundred systems in operation worldwide, the J273B is easily the best-selling linear tester. It is considered the industry standard by most people concerned with high-volume production testing and trimming.

Over 60 engineers working in analog test technology.

Teradyne supports the world's largest group of developmental engineers specializing in analog testing and trimming. As the facing page attests, they are a prolific lot.

Each engineering project begins with four objectives: 1) improve linear testing economics; 2) improve capability in all market areas simultaneously; 3) reduce applications work required; and 4) upgrade installed systems whenever possible.

Teradyne's commitment to linear testing goes far beyond engineering. From marketing, sales, and customer service to training and applications support, we are geared to serve the rapidly changing linear market.

Unusual benefits.

Our broad base of installed systems assures you uncommonly close correlation with your customers and vendors. Our unmatched experience provides many opportunities to save time and money for manufacturers and users alike.

In short, Teradyne is dedicated to providing both the best linear test systems and the best support.

We won our reputation in linear testing from the very beginning by offering what was needed. And the only way to keep that reputation is to keep surpassing ourselves.

Our new J273B Linear Test System brochure has all the facts. Just write: Teradyne, 183 Essex Street, Boston, MA 02111. Or call (617) 482-2700.

BUT THIS YEAR OUR ENGINEERS SURPASSED EVEN THEMSELVES.

Floating Point Math Package in the control software offers high-precision, on-line math routines including a full 36-bit mantissa, trig/log functions, high-resolution db calculations, etc.

IF Generator and Voltmeter covers the AC test range from 200 kHz-12 MHz.

Low Current Ammeter extends the J273B's total measurement capability to 10 pA-10A.

IEEE Bus Interface provides a standard means of controlling add-on test equipment required for special testing needs.

VHF Synthesizer covers the frequency generation and measurement range of 10 MHz-312 MHz.

Digital Drivers/Detectors offer 36 channels for testing linear devices with digital I/O, as well as purely digital parts.



Workstation Audio permits timeshared AC testing from 20 Hz-210 kHz.

Improved Laser Trimming capabilities enhance adjustment of monolithic devices. (Optional.)

RS232C Port extracts data from the system for output to RS232C-compatible peripheral receivers or higher-level computers.

M365M Computing Controller is a new, fast version of the Teradyne computer that can increase throughput by as much as 30% with a minimum engineering investment.

New Timesharing Techniques for J273B workstations improve total system throughput considerably.

DR070 Data Reduction Software is a powerful, easy-to-use, off-line capability for gathering data in the form of statistical summaries, ranked data, histograms, cumulative plotting, and correlation curves.

High-Voltage Power Supply extends the system capability to +300 volts at 200 mA.

TERADYNE

Circle 147 on reader service card

Discriminator computes frequency differential

by T. J. John
Meerut, Uttar Pradesh, India

This circuit computes the percent difference of two frequencies to 0.1% without needing an accurate, crystal-controlled timebase. It is useful in industrial applications that convert a process variable into a train of pulses in order to monitor that unknown quantity.

The circuit finds $\pm d = 100(p_x - p_r)/p_r$, where d is the percent difference, and p_x and p_r are the number of pulses counted from an unknown and a reference source, respectively, in a given time. By making p_r equal to a decade multiplier of 10^n for any general n, the first equation becomes $\pm d = (p_x - 10^n)(10^{2-n})$, where $p_x - 10^n$ is the difference between the number of pulses generated by the unknown source and the 10^n pulses generated by the reference, and 10^{2-n} indicates the position of the decimal point. Thus the equation is reduced to a form where it can be solved in hardware with off-the-shelf logic elements.

Note that for an accuracy of 0.1%, the value of n must be 3. Therefore, three cascaded decade counters must be used at each input for counting up to $10^3 = 1{,}000$, as shown in the figure.

A system clear initializes the counters to 0 and presets several circuit flip-flops. The carry output of the last 74192 in each chain then generates a negative-going pulse each time it counts to 1,000. Assuming a positive difference between unknown frequency B and reference frequency A, A_1 reaches 1,000 first and resets flip-flop A_2. A_2's $\overline{Q}$ output then fires one-shot A_3, whose on-time must be small compared to the period of the unknown



Comparison. The circuit for finding $\pm (A-B)/A$, in percent, needs no frequency standard and it can be built with standard logic elements. Results are directly displayed. Accuracy of measurement is 0.1%, obtained by using three cascaded decade counters at each input.

frequency measured. Flip-flops A_4 and A_5, the polarity-difference indicators, are then reset.

The preceding actions permit the 1,001st pulse counted by A_1 to be passed directly from the input to the display-counting circuit through enabled gates I and J. For each pulse appearing at the output of J, the counter is advanced by 1, starting from the least significant bit displayed. When the reference-frequency counter, A_6, reaches 1,000, A_7 is reset. A_8 in turn is reset through gate K and gate I is disabled. At that time, the display will directly indicate the magnitude of the difference between frequencies A and B, in percent. Because A_1 reaches 1,000 before A_2, A_5 is set and will indicate there exists a positive frequency difference between B and A.

In the event a negative percentage difference is measured, A_2 reaches 1,000 first. A sequence of events similar to those discussed previously then occurs, but with the upper portion of the circuit becoming active first, and with the end result that the negative-difference indicator, A_4, is set. □

8-channel scanner multiplexes data for strip-chart recorder

by James M. Palmer,
Optical Sciences Center, University of Arizona, Tucson

Using low-power analog multiplexers, this circuit converts a single-channel strip chart recorder into one that can handle up to eight lines of data. The dwell time between channels is selectable. Excluding the cost of the power supply, the circuit can be put together for an outlay of less than $25.

A_1 and A_2 are configured as an eight-channel differential multiplexer stepped by a dual binary counter, A_3,



Scanning. Circuit multiplexes eight data channels applied to A_1 onto single-channel strip chart recorder. Reference-voltage inputs at A_2 position trace at different levels on chart. A_3, A_4, and A_5 sample channels in sequence. R_1 to R_8 set dwell time between channels.

and an astable multivibrator, A_4. Each signal to be multiplexed by A_1 is positioned appropriately on the strip chart by the corresponding reference voltage applied to A_2. The circuit's supply voltage is 15 V, so input voltages to A_1 and A_2 may range from 0 to 12; if bipolar signals in the range of -5 to $+5$ V are to be multiplexed, the circuit will require supply voltages of ± 7.5 V.

Multiplexer A_5, which is also stepped, places resistors R_1 through R_8 in sequence in the timing network of A_4. As A_3 counts, A_1, A_2, and A_5 are advanced. Thus, the feedback loop formed by A_3, A_4, and A_5 automatically sets the monitoring time for each input channel, which is equal to $4.4R_iC$. Unwanted channels can be virtually skipped by using the minimum value required for R_i (10 kilohms), in which case the record time for that particular channel will be less than 0.1 second.

Several modifications can be implemented for increased circuit versatility. The circuit can be expanded to scan 16 channels by adding three additional multiplexers (two for channel selection, one for timing). If the multiplexing rate is slow, output voltages can also be measured with a digital voltmeter. Here, the output of A_4 is used to fire a second one-shot, thereby producing a trigger pulse for the voltmeter.

Finally, with the addition of a few resistors and switches, any channel can be randomly selected by jamming A_3's outputs. □

Reducing a PLL's even-order harmonics

by R. P. Leck
Bell Laboratories, Crawford Hill, Holmdel, N. J.

In contrast to the clean output they produce when operated in their fundamental mode, phase-locked loops generate even-order harmonics of the input frequency and excessive sideband noise when used in frequency-divider or frequency-multiplier circuits. The spurious responses may be reduced, however, by adding an extra break or corner frequency to the PLL's low-pass filter response, in order to reduce the modulation index at the input to the loop's voltage-controlled oscillator.

A block diagram of a typical PLL frequency multiplier is shown in (a). Detector A_1 compares the phase of the input signal, f_1, with the phase of the divided-down VCO signal. Thus A_1 generates a voltage proportional to the phase difference between its inputs. After passing through low-pass filter A_2, the signal is applied to the VCO, A_3, so altering its output frequency f_2 that the phase difference between f_2 and f_1 is minimized. The loop is in the so-called locked state when f_1 equals f_2 in frequency and phase.

As a result of placing divider N in the loop to make the PLL operate as a frequency multiplier, the output of the phase detector and thus the loop, which is picked off at A_3, also contains unwanted harmonics of f_1. The amount of sideband noise on each carrier signal, which is an indication of the modulation index (a relation too cumbersome to derive for most waveforms), is given by:

$$\theta_0(s) = NK_0F(s)V_d/s$$

where F(s) is the transfer function of the loop's low-pass filter, V_d is A_1's output voltage, and K_0 is the voltage-to-frequency control constant of A_3. So, by reducing the numerical value of F(s), $\theta(s)$ and the modulation index fall and harmonics are also reduced.

The transfer function of the active loop filter typically used in PLL circuits (b) is $F_2(s) = (s\tau_2 + 1)/s\tau_1$, where $\tau_1 = R_1C$ and $\tau_2 = R_2C$. By adding capacitor C′ across R_2 as shown in (c), the second-order filter previously shown is made a third-order network, whose transfer function is given by $F_3(s) = (s\tau + s\tau_3 + 1)/(s^2\tau_1\tau_3 + s\tau_1)$, where $\tau_3 = R_2C'$.

Note the corresponding curves of the filter's open-loop response. If the unwanted harmonics in question are all above the added pole frequency, $\frac{1}{2}\pi\tau_3$, they will be attenuated because the magnitude of $F_3(s)$ will be less than that of $F_2(s)$. At ω_{2f} in (b), there is no additional suppression beyond that which exists as a result of the integrating effects of the VCO and its low-pass filter. The attenuation is increased with the addition of C′ as shown in (c).

Adding C′ creates a network that, under some conditions, can be unstable. However, as long as the open-loop gain of the originally stable second-order loop is unchanged after C′ is added, and the slope at which the loop's log-magnitude plot crosses the unity-gain axis does not exceed -40 decibels per decade, there will be no problem. Both of these conditions are normally found in practice.

Adding the additional break point affects the network's damping factor, δ, and the system bandwidth, B, two of the most important parameters of interest in designing a loop filter. The effects of damping start to become noticeable when τ_3 starts to move down from infinity to $\tau_2/30$. It should be understood that with a reduction in harmonic output also comes a decrease in the range over which the PLL will operate.

As an example of how to design a filter network, consider the case where a PLL multiplier is to be scaled to generate a frequency f_{out} equal to $(108/109)f_{in}$, having a damping factor of 1.2 and a bandwidth of 100 hertz. Thus the VCO is made to multiply f_{in} by 108, and a divider is used to provide N = 109. Along with the initial considerations, an additional requirement is to suppress the sidebands at the divider output by 50 dB. This corresponds to a phase jitter of 0.4°.

A standard second-order filter design can meet the damping and bandwidth criteria, but a third-order filter is required to meet the sideband suppression and phase jitter requirements.

It will be realized that it is necessary to reduce the

Pick a partner for life

Pick a Zeiss Standard

Zeiss Standard Microscopes are precision engineered to last a lifetime—and be always up to date. Standards made more than 25 years ago accept all of today's new accessories, objectives, stages, and light sources. Try this with any other brand of microscope, and you'll appreciate Zeiss quality and durability.

Many to pick from

No matter what your field... INDUSTRIAL RESEARCH, PRODUCTION, QUALITY CONTROL; ELECTRONICS; GEOLOGY; PATHOLOGY; BIOMEDICINE ... you'll find a low-priced Zeiss Standard to fit your exact need and give you years of trouble-free, worry-free quality. You'll work happily ever after. **Nationwide service.**

The great name in optics

ZEISS

West Germany

Carl Zeiss, Inc., 444 5th Avenue, New York, N.Y. 10018 (212) 730-4400. Branches: Atlanta, Boston, Chicago, Houston, Los Angeles, San Francisco, Washington, D.C. In Canada: 45 Valleybrook Drive, Don Mills, Ontario, M3B 2S6. Or call (416) 449-4660.



first-order sidebands at least 10 dB, if the sidebands at the output of the divide-by-109 unit are to be at least 50 dB below the peak output voltage. By using the well-known two-pole RC filter equations (this discussion assumes familiarity with the design procedures of basic PLL filters), and setting δ to 2.2 and B to 100 Hz to get V_0 = 10 dB below V_d, it is found that $\tau_1 = 6.7(10^{-2})$ and $\tau_2 = 5.09(10^{-2})$. R_1, R_2, and C can then be appropriately selected.

From (d), an experimental curve generated for use in designing the three-pole filter, it is found that an *equivalent* second-order damping factor of 1.1 is obtained for such a loop when N = 21.2 and $\tau_3 = \tau_2/N = 2.5(10^{-3})$. Thus $C' = \tau_3/R_2 = 0.5$ microfarad if R_2 = 50 kilohms, a typical value of resistance. □

Engineer's notebook is a regular feature in *Electronics*. We invite readers to submit original design shortcuts, calculation aids, measurement and test techniques, and other ideas for saving engineering time or cost. We'll pay $50 for each item published.



Break point. Phase-locked loop (a) generates spurious energy when used in frequency-multiplying circuits. Low-pass filter (b) cannot provide sufficient input frequency harmonic suppression. Capacitor C′ (c) adds break or corner frequency to filter response, enables increased rejection of even-order harmonics. Effects of τ_3 on equivalent second-order damping are plotted (d) to aid in design example discussed in text.

Need 24 or 40-pin DIP's off the shelf? We're your source.



Want the speed, savings and reliability of mass termination with larger size D.I.P. connectors? Come to 3M. Our Scotchflex brand D.I.P. connectors in 24 and 40-contact sizes let you design quick, easy interboard jumpering with readily available parts. Their space-saving low-profile design makes them ideal for microprocessor applications. They also speed and simplify test jumpering or checkout of I.C. sockets.

Both connectors have .100″ x .600″ grid spacing and are available with either rectangular legs for use with standard I.C. sockets or round legs for use with high density packaging panels. They may be used with Scotchflex shielded, non-shielded or color-coded flat cable or with twisted pair or parallel lay woven cable.

Where frequent plugging and unplugging is necessary, strain relief bars and pull



tabs are available for all Scotchflex D.I.P. connectors including 14 and 16-pin sizes.

Need some more ways to simplify wiring and increase circuit density? 3M's Scotchflex line offers you the widest choice of mass terminating cable, connectors and system components to accommodate your design packages. Plus proven reliability. Off-the-shelf availability. And the unmatched experience of the people who pioneered the concept of electronic mass termination.

Scotchflex connectors are recognized under the component program of Underwriter's Laboratories, Inc.

"Scotchflex" is a registered trademark of 3M Co.

Scotchflex® systems from 3M. The source.

3M

Circle 153 on reader service card

Engineer's newsletter

Timer halves keys needed for repeat commands

When used as an oscillator, the 555 timer has an annoying characteristic—the first pulse generated after the reset (inhibit) port has been disabled has double the length of those that follow. Robert Dougherty of Dunedin, Fla., turns this drawback into an advantage in a one-chip circuit for the repeat key function on computer keyboards.

Generally, a keyboard's repeat key must be depressed at the same time as the key whose data is to be retransmitted at some specified rate. **Dougherty's circuit makes every key its own repeat key.** Simply wire the timer as an astable multivibrator, connect its output to the appropriate transmit line, and tie its reset terminal to the normally low keyboard bus (key valid line).

The timer's abnormally long first pulse gives the user enough time to react and terminate a call when he doesn't want the repeat function. When he does want it, he must make a very conscious effort to hold a key down long enough for the second pulse to occur. Even with a transmission rate of 8 hertz, there are 250 milliseconds in which to strike and release a key before multiple repeats are generated.

Phaseless measurements don't faze reflectometers

When it comes to performing complete parameter checks on elements operated in the microwave region, the new six-port reflectometers don't come close to network analyzers in capability. Still, it is possible for an interconnected pair of these recently developed instruments to gauge the element's scattering coefficients by using only the magnitudes of the input and output signals—**measuring phase is not required, provided the reflectometers are properly calibrated.** The National Bureau of Standards recommends a good procedure in "Calibrating Two Six-Port Reflectometers with Only One Impedance Standard," which is to connect the two reflectometers together and then to a calibration circuit consisting of a known and unknown impedance and a leveling loop. Find out more by requesting SD-003-003-01956-9 from the U. S. Printing Office, Superintendent of Documents, Washington, D. C. 20402. The price is $1.60 plus 25% for mailing abroad.

ICS expands its computer training programs

Integrated Computer Systems Inc. of Santa Monica, Calif., has come a long way since 1974, when it introduced a microcomputer home-training program geared to engineers. It will now offer at least ten workshop-type courses nationwide starting in April and running into early August. Most subjects, such as the fundamental-level course 160, "Microprocessor Hands-On Workshop," to course 444, "Spread-Spectrum Communications Systems," are discussed in intensive four-day sessions. Also offered are **courses in small computing systems, troubleshooting microprocessor systems, structured programming, data-base management, distributed processing and computer networks, and computer graphics,** as well as a one-day course in military and aerospace systems and a five-day course in digital signal processing. Each four-day session costs $695, the military and aerospace course is $195, and digital signal processing is $795. For complete schedules and other information, write or call ICS at 3304 Pico Blvd., P. O. Box 5339, Santa Monica 90405, (213) 450-2060, or 300 N. Washington St., Suite 103, Alexandria, Va. 22314, (703) 548-1333.

Vincent Biancomano

WHO'S WAY OUT IN FRONT IN HIGH SPEED DATA CONVERSION?

- ☐ ANALOG DEVICES
- ☐ COMPUTER LABS
- ☒ BOTH.

SEE US AT ELECTRO '79
Booths #2802-2804

Circle 155 on reader service card

COMPUTER LABS TEAMS UP

AN ADDED DIMENSION IN MULTI-MHZ A/D AND D/A CONVERTERS.



Computer Labs is the world leader in high speed A/D and D/A data converters. So it makes a lot of sense for Computer Labs to team up with the overall data converter leader, Analog Devices. And this means that all your data converter needs can now be served from a single source – everything from dc to multi-MHz in instruments, modules, hybrids, and monolithics.

Computer Labs puts Analog Devices on a fast track with its design and manufacturing expertise in high speed radar and video data converters and very fast hybrids, 150 products in all. Analog Devices brings its technological and customer support to Computer Labs in terms of sales and service, technical literature and documentation and application engineering. Which adds a new dimension to Computer Labs' wide range of high speed A/D and D/A converters, track and holds, deglitchers, and operational amplifiers in applications like computer interfacing, radar digitizing, digital communications, sonar systems and graphic display.

PRODUCTS LIKE THESE.



MOD-1005 HIGH SPEED VIDEO A/D CONVERTER

■ 10 bits @ 5-MHz word rate ■ Single PCB construction, only 27 sq. in. ■ Built-in track-and-hold with 25 psec. aperture ■ 20-MHz analog input bandwidth ■ Only 10-Watt power dissipation ■ Signal-to-noise ratio greater than 58 dB ■ Noise power ratio greater than 49 dB ■ Complete and self-contained with integral track-and-hold, encoder, timing circuitry, and output latches ■ Needs only power and encode command ■ 12-bit version available soon.



MATV-SERIES VIDEO A/D CONVERTERS

■ 8 bit accuracy, guaranteed monotonic ■ Ultra-high speed, dc to 20 MHz word rate ■ A family of the most economical video A/D's available featuring 11, 16 and 20 MHz word rates ■ All in 5.5" by 4.38" by 0.85" modules ■ Self-contained modules include input buffer, encoder, internal reference, timing circuits and buffered parallel output ■ Needs only power and encode command ■ Ideally suited for digitizing color television at three to four times NTSC or PAL subscriber frequencies as well as video time base corrector and frame synchronizer applications.

WITH ANALOG DEVICES.

HTS-0025 ULTRA-HIGH SPEED TRACK AND HOLD

Ultra-fast aperture of 20 psec. Exceptional 20 nsec. acquisition time Excellent 0.01% linearity Highly reliable hybrid construction Active laser trimming to null dc offset, hold pedestal, and switching transients Hi-Z FET input of 10^{10} ohms High output current can drive 50-ohm load.

HAS-1202 FAST HYBRID A/D CONVERTER

12-bit resolution Exceptional accuracy of 0.012% of F.S. Low power, 1.8 Watts 2.2 μsec. typical conversion time Available in a glass or metal 32-pin DIP Complete and self-contained for adjustment-free operation, no external pots required.

HDS-1250 HIGH SPEED CURRENT OUTPUT D/A CONVERTER

Fast 12-bit hybrid microcircuit Ultra-fast settling time, 50 nsec. to 0.025% of F.S. Guaranteed monotonic 0.85 Watt power dissipation Adjustment-free operation, no external pots required Full 10mA output current.



YOU'RE THE WINNER.

With this combined strength, Analog Devices and Computer Labs will continue to lead the industry in data conversion products through the use of innovative circuit designs and advanced processing technologies. Which will lead to industry breakthroughs like monolithic high-speed video A/D converters and a lot more.

Because Computer Labs and Analog Devices have teamed up, you get the broadest line of converters available from a single source. A complete family of dc to multi-MHz A/D and D/A converters encompassing bipolar, CMOS and I^2L technologies, from 8 to 18 bits available as instruments, modules, hybrids and monolithics.

For complete information on the products described here, call Ed Graves at (919) 292-6427. Or write Analog Devices, P.O. Box 280, Norwood, MA 02062.

ANALOG DEVICES

WAY OUT IN FRONT.

Analog Devices, Inc., Box 280, Norwood, MA 02062; East Coast: (617) 329-4700; Midwest: (312) 894-3300; West Coast: (213) 595-1783; Texas: (214) 231-5094; Belgium: 031 37 48 03; Denmark: (02) 845800; England: 01 94 10 46 6; France: 686-7760; Germany: 089 53 03 19; Japan: 03 26 36 82 6; Netherlands: 076/879 251; Switzerland: 022/319704; and representatives around the world.

Circle 157 on reader service card

Fluke Counters.

What's in a name?

A glance at our counter guide shows how broad a selection you have when you choose the Fluke name.

Pick resolution from six to nine digits, and top-end frequencies from 80-1250 MHz. Notice that all Fluke counters are multi-function, from the frequency/period/totalize capability of the 1900A to the six-function 1953A Universal Counter-Timer. All models have input signal conditioning for reliable readings in the presence of noise, distortion, and ringing, and most have attenuators for increased dynamic range. So for R&D, GENERAL BENCH or PRODUCTION LINE applications, buy exactly what you need over an affordable, performance-effective price range.

For FIELD MAINTENANCE AND SERVICE, most of the line is available with an optional rechargeable battery pack installed inside the compact, portable case. Let autoranging keep the display full at all times for "hands-off" convenience, and rely upon autoreset to eliminate erroneous partial-readings. In the Fluke tradition, they'll take a real field beating, too.

COMMUNICATIONS people find the 1911A through 1925A attractive for VHF/UHF measurements. They're so sensitive that a simple optional whip on the 50-Ohm fuse-protected input makes transmitter checks quick and easy. With automatic clean dropout, you'll always be right because the reading goes to zero with a fading signal. They're RFI-shielded, and TCXO timebases are available for the kind of high accuracy you might need over environmental extremes. And if you choose the 1920A, you can get a resolution multiplier for high-resolution audio measurements.

If you have an ADVANCED BENCH or SYSTEMS application, the 1953A was designed for you. With fully programmable ranges and functions (including trigger level), the 1953A is available with IEEE-488 or BCD parallel options, at a price more than $1,000 *less* than the competition's similarly-equipped models.

Fluke 1953A: a name and number to remember for perfection in programmable counter-timers.

CALL (800) 426-0361*, TOLL FREE and let us show you how the Fluke name is as meaningful in counters as it has been for other fine test and measurement instrumentation for the last 30 years. It's your assurance you've bought the best, backed by more than 32 service centers in 18 countries, worldwide.

Counter Selection Guide	**1900A**	**1910A**	**1911A**	**1912A**	**1920A**	**1925A**	**1952B**	**1953A**
Number of Digits	6	7	7	7	9	9	7/8	9
Frequency (MHz) *Basic Unit*	80	125	250	520	520	125	80	125
Options					1250	520		1250
Period	•	•	•	•		•	•	•
Totalize	•	•	•	•		•	•	•
Time Interval							•	•
Ratio		•*	•*	•*	•*	•*	•	•
A gtd by B							•	•
Sensitivity (mV)	25	15	15	15	15	15	50	30
Trigger Level Control		•	•	•		•	•	•
External Timebase Input		•	•	•	•	•	•	•
Battery Option	•	•	•	•	•			
TCXO Option		•	•	•	•	•	•	•
Ovenized Timebase Option						•		•
DOU Option	•	•	•	•	•	Std		•
Autoreset	•	•	•	•	•	•		
Autorange	•	•	•	•		•		
U.S. Price Basic Model (No Options)	$345	$395	$495	$620	$1095	$750	$995	$1195

*Using external timebase input

John Fluke Mfg. Co., Inc., P.O. Box 43210, Mountlake Terrace, WA 98043. In Europe, contact Fluke (Nederland) B.V., P.O. Box 5053, Tilburg, The Netherlands. Tel. (013) 673973. Telex: 52237.

*Alaska, Hawaii, Washington residents please call (206) 774-2481.

Command Performance: Demand Fluke Counters.

FLUKE®

7503-1900S

Circle #158 for literature

Circle #159 for demonstration



The complete sweeper. It's a Wiltron.



You don't build a complete sweeper after the fact. You build it from the ground up. You build it for automatic measurement. You build it with solid state plug-ins to cover the entire 100 KHz to 40 GHz range. You build it with the options to meet the needs of all users.

You build the Wiltron 610D!

Simply, the best sweeper for automatic testing.

Cover the 10 MHz to 18.5 GHz range in one continuous sweep. No need to stop and change plug-ins or external components. One test set-up using Wiltron's new 10 MHz to 18 GHz SWR Autotester is all you need.

It's clearly the superb system for broadband and high directivity (40 dB) SWR measurements.

Plug-ins for cost effectiveness.

There are 26 RF solid state plug-ins covering single, dual and multiple bands—the only complete line of sequentially swept units. Pick the exact unit you need. All units feature outstanding spectral purity, flatness, and the latest YIG tuned oscillators. The 6247D plug-in sweeps from 10 MHz to 18.5 GHz in one continuous sweep. Others go up to 40 GHz.

Advanced features all the way.

Field proven reliability is so good Wiltron gives you a two-year warranty on the oscillator. The 610D features a selectable Intensity, Video or RF marker. Phase lock to an external standard for crystal controlled accuracy. All plug-ins feature slope control to compensate for cables and connectors. Main frame weighs 18 lbs., plug-ins, 10 lbs. And it's compatible with our new 560 Scalar Network Analyzer as well as the other fellow's. Options include crystal controlled frequency markers, preset frequencies, additional markers and GPIB (IEEE 488-1975).

Excellent service, free field seminars.

No one provides faster service than Wiltron. If you're in a spot, we'll help you with a loaner. So you can get the most from your Wiltron 610D, we offer user seminars and technical notes.

Isn't it time for the complete sweeper?

For an early demo or literature, call us today. Phone Walt Baxter at (415) 969-6500, or write Wiltron, 825 East Middlefield Road, Mountain View, CA 94043.

WILTRON

Circle 161 on reader service card



America's sociologists and other behavior-watchers have been telling us that the cities of the Northeastern Snow Belt are making a comeback, so what better place than New York to look ahead and examine the direction of electronics in the next decade? That theme—electronics in the opening years of the 1980s and its expected impact on industry and individuals—will be the focus of Electro79 at the New York Coliseum and the Sheraton Centre (formerly Americana) Hotel from April 24 through 26.

Whatever the seers decide about the years to come, it is obvious that the last two or three have been good to the electronics industries. In fact, judging by the growth of Electro since 1976 when it began convening alternately in Boston and New York, the period has been exceedingly good. At the 1976 Boston show, some 265 exhibitors occupied 509 booths; in New York the following year about 300 exhibitors were housed in 511 booths. In 1978 the show's sponsor, the Institute of Electrical and Electronics Engineers, reported 350 exhibitors in 655 booths. Now, 1979 will see 400 groups and companies facing an expected attendance of 30,000 design engineers, managers, and technical executives from over 700 booths. Times have been good indeed; though a slowdown in various forms from dip to depression is forecast for this or next year, spirits in New York this month should nevertheless be high.

A clue to what could be the increasingly prevalent theme of the '80s may come on the first day and turn out to be one of Electro's highlights: a 1 p.m. special session devoted to an international electronics executives' forum that will tackle technical management.

Program: agenda for the 1980s. The most conspicuous feature of Electro seems to be what does not appear on its program of technical sessions. There is no single session devoted to semiconductors as such, perhaps an eyebrow-raising indication of what the show's organizers know about the coming years and the direction of electronics technology.

Most attention is being paid to computers in all sizes, functions, and ramifications. There are

scheduled discussions of microcomputer data-base systems, software manufacturing, nonvolatile storage, industrial control networks, and personal computers. In allied sectors, there is scheduled coverage of testing bubble memories, packaging, and signal processing, and a scattering of sessions on professional matters ranging from minorities in engineering to the engineer and public policy. Finally, one session will commemorate the centennial of Thomas A. Edison's invention of an electrical lighting system.

Software for microcomputers. S. B. Yao is excited about session 10, which he will chair. Yao, an associate professor visiting New York University from Purdue University in West Lafayette, Ind., calls his session "Data-Base Management Systems on Microcomputers"; his excitement stems from the fact that this is a new use for microprocessors. And as microcomputers and data-base management intertwine, mutual interaction of the system can be seen.

"Data-base systems will have a definite impact on microcomputer software," says Yao. "They will make programs easier to develop and they will actually be more independent of the type of data they can handle. But microcomputers will also affect traditional data-base systems, and specialized data-base microcomputer systems will be developed."

Of the three main types of data-base systems, Yao has invited speakers on two. The first, called the network model, will be covered by Rob Gerritsen and Richard Hackathorn of the University of Pennsylvania, who will discuss their commercially available system, Micro-SEED. A second scheme, the relational model, will be covered by Peter Ting and David Chai from Bell Laboratories, Holmdel, N. J., who will speak on a distributed system of LSI-11 microcomputers. The third, or hierarchical, variety of data base is not represented in the session.

"Reducing Risks in Microcomputer Development," session 16, is headed by Carol Anne Ogdin, a consulting editor for EDN magazine based in Alexandria, Va. "The risk I will address concerns the project-management issue," says

For designers of software, there will be a discussion of how microcomputers and data-base management intertwine to make programs easier to develop in a break with tradition

Ogdin about the paper she will present. "I will discuss how to sequence things to avoid problems like committing yourself to a hardware design you can't write software for."

Another speaker, Harlan Mills of IBM Corp. in Bethesda, Md., will tell how to write software correctly the first time. "Harlan is well known in the software engineering field for his ability to show people how to write error-free software," says Ogdin, "The major risk here is the reliability of software. He [Mills] takes a pragmatic approach to see why it works, and what you can do to make sure it will the next time."

The last of Ogdin's speakers, William Broderick from Tektronix Inc., Beaverton, Ore., has perhaps the most interesting topic. He will focus on how to avoid problems involving contemporary large-scale integrated input/output circuits and central processing unit parts. "The 6802 has a major bug in its data sheet, for example," maintains Ogdin. "The sheet says it's static, but the part is dynamic and that makes a big difference when you go to design with it. Also, the 8251 programmable communication interface chip has difficulty handling its control signals. There are lots of problems like this."

Session 26, organized by Emerson Pugh, manager of exploratory magnetics at IBM's Thomas B. Watson Research Laboratories in Yorktown Heights, N. Y., concerns nonvolatile storage for very small processors. "The thrust of the session," says Pugh, "is what you do if you need nonvolatile storage and the total system cost must be kept to a minimum." Four speakers will give the pros and cons of the various solutions.

Donald Craycraft from NCR Corp. in Miamisburg, Ohio, will discuss semiconductor storage devices such as electrically erasable programmable read-only memories and electrically programmable ROMs, as well as chips that exploit metal-nitride-oxide-semiconductor technology. J. Egil Juliussen from Texas Instruments in Dallas will be concerned with bubble devices vs semiconductors (like complementary MOS random-access memories) with battery backup. Floppy-disk storage will be covered by George Sollman of Shugart Associates, Sunnyvale, Calif., and digital cassettes by Bruce Minildi, Verbatim Corp., also in Sunnyvale.

Pugh calls each approach reasonable for a particular range of applications, but beyond that range the method becomes impractical. For example, for larger small systems, rotating magnetic storage appears most viable because it offers the lowest cost per bit. "But mechanical storage isn't always the lowest cost per box," says Pugh, meaning that when the system is small enough, bubbles and semiconductor storage become attractive. He finds bubbles more advantageous than silicon parts, though, possibly from vested interest. "MNOS, for example, has reliability problems and a long write time, and needs unusual voltages," he says adding that bubbles have some definite advantages. "Rockwell has already demonstrated a 1-megabit bubble memory using standard permalloy techniques."

Industry takes heed. Prices of microcomputer-based equipment continue to fall, so it is not surprising that industry is assembling more and more intelligent hardware into distributed data-acquisition and control networks. Session 27, "Microcomputer Industrial Control Networks," alerts management personnel and system designers to the communication problems posed by future, more complex architectures and deals with ways of solving them.

Robert Grant of Pro-Log Corp. in Monterey, Calif., will describe the key role played by modular hardware in the design of a multiprocessor control system on an STD bus. He will discuss the benefits of modularity—lower costs, greater flexibility, and simpler maintenance—and offer some caveats on second-sourcing, sizing, and selecting a microprocessor.

Waiting for a standard for industrial distributed-control networks? Daniel T. W. Sze of IBM in Boca Raton, Fla., will bring his audience up to date on the work being done by the IPW TC-5/ISA-72 committee. That group is outlining a standard for a process-control system's functional properties, communications capabilities, and architecture.

Communication within distributed-data-acquisition and control systems is the subject of a paper by Cleveland State University's James D. Schoeffler. He will quantify the delays in various network architectures, and explain how intrasystem messages must become longer to guarantee reliable communication.

Solutions to some of the above problems will

'Engineers are the ones coming up with the most creative applications for personal computers,' so there will be a session on how to sell such computers, as well as one on how to use them

be found in two applications papers. "Master-Master Party-Line Bus in a Microprocessor Network," by A. DiMond, W. Levy, R. Roth, A. Simon, M. Stickel, and W. Wong of RCA's David Sarnoff Research Center in Princeton, N. J., describes a passive party-line bus that can extend over 1,000 feet and handle more than 100 processors. A key to the system is the communications protocol, which houses six control lines to route calls and data between processors.

Applications of MC6801 and MC68588 microprocessors in distributed processing will be described by Donald Tietjen and Robert Thompson of Motorola's Integrated Circuits division in Austin, Texas. They will show how those two processors have been used to form a data-acquisition and control device compatible with the IEEE-488-1975 bus, and discuss hardware and software considerations.

Getting personal Significantly, this year there are separate Electro sessions on marketing and using personal computers. Frank Burge of Regis McKenna Inc., Palo Alto, Calif., organized both sessions and expects a heavy turnout because "engineers are the ones coming up with the most creative applications for personal computers, both in the office and at home." Burge adds that marketing techniques should interest engineers, too, since greater consumer acceptance of the product will help lower prices and motivate manufacturers to build more versatile machines.

Session 3, "Marketing Personal Computers," will focus on the most difficult aspect of personal computers—selling them. Ben Rosen, an analyst at the New York investment firm of Morgan Stanley Inc., will lead off with some optimistic projections for sales—from just 200,000 units sold last year to sales of $1.25 billion in 1980 and $5 billion by 1985. Rosen's crystal ball will also reveal that small businesses and educational institutions will form the nucleus of this expanding market.

Next, representatives of two manufacturers will relate company experiences in the marketplace. Lewis Kornfeld of Radio Shack Inc., Fort Worth, Texas, which has sold its TRS-80 for the past 20 months, links the success of personal computers to maintenance, often a low-priority item for conventional consumer products. Gene Carter of Apple Computer Inc., Cupertino, Calif., will then demonstrate how personal computers are logical evolutions from the Eniac in the 1940s, through the time-shared systems in the '50s and '60s, to today's personal models that give complete access upon demand.

Finally, Elliott Greene, owner of the Computerland store in Carle Place, N. Y., will present the retailer's point of view. Greene will explain how to cope with a weak link in the sales chain—contact with the consumer. What is needed beyond a quality product, he says, are competent salesmen who can attract potential buyers without mystifying them with esoteric computer jargon.

Session 9, "The Personal Computer: Hobby-Horse or Work-Horse?," will be a panel discussion of applications. Phil Roybal of Apple Computer will kick off the session with an overview of personal computers presently at work in industry, schools, and homes. One of his examples will be an Apple unit that for one year has been controlling, without failure, an oil-drilling rig in the Gulf of Mexico.

Among the other panelists who will describe uses for personal computers is Tom Carpenter, an engineer at Bell Laboratories in Allentown, Pa. He has gotten his entire family involved with the computer by putting it in the family room, right next to the television set. Food recipes can be filed and reviewed by category and scaled to the number of dinner guests. His 11-year-old daughter is the typist—she now recognizes syntax errors in Basic—and his 7-year-old son plays video games. Carpenter uses a Process Technologies VDM unit with a memory-mapped video monitor because its S-100 bus is compatible with his earlier programs.

Next will be Bob Berkovitz, director of research at Teledyne Acoustic Research in Norwood, Mass. Berkovitz has programmed an Apple computer in machine code to check the frequency response of his company's AT line of speakers on the production line—a task previously done by an expensive PDP-11/40 minicomputer. The company's present 8-bit unit does 256-point fast Fourier transforms in 3 seconds with 16-bit precision, and has been taken into the field to give color-graphics presentations helpful in teaching salesmen the audio basics.

Another panelist is Max Ule, a discount stockbroker at Rosenkrantz, Ehrenkrantz, Lyon, and

With robots leaving the drawing boards and making their way into assembly plants, there will be an examination of sensors, programs, and part-mating science as they pertain to the machines

Ross in New York. Ule will explain how he is presently using two TRS-80 personal computers to follow the stock ticker, figure commissions instantly, and send mailings to his clients. He started with one TRS-80 and subsequently added memory and peripherals such as printers, electric pencils, and lower-case conversions.

Finally, Peter Jennings of Personal Software Inc., in Boston, will tell how he developed a chess-playing program to run on several personal computers. One of his firm's most popular programs, Jennings expects it to appear soon in Europe in a dedicated board game.

Let the robot do it. Automation, a word first heard in the 1950s, is center-stage in session 33. Today, robots are off the drawing board, doing such jobs as attaching light bulbs to car dashboards, and more sophisticated machines are on the way. Co-organizer K. S. Fu of Purdue says that the session should be of interest both to those in automation research and development and to industrial firms wishing to automate assembly lines in their plants.

A robot is only as powerful as its eyes, and sensors are the topic of two papers. Antal K. Bejczy of the Jet Propulsion Laboratory in Pasadena, Calif., will discuss the design and controlling aspects of smart sensors—computer-based transducers of proximity, force-torque, and touch, for example. "Programming and Data Structures for Sensor-Controlled Robots," by Purdue's Richard Paul, demonstrates how to code a sensor's output in software.

G. C. S. Lee and session co-organizer G. N. Saridis of Purdue will also discuss matching programming language to a robot's task. Their paper will describe the development of a high-level, English-like language that serves as the robot's operating system and frees the user from programming each movement of its manipulator. The language is developed in two parts. The higher level interacts with the user via monitor and interprets and decodes input statements, translating them into basic control motions; the lower level controls the manipulator in real time and coordinates feedback signals. A preliminary version of the programming language has been implemented on a PDP-11/45 minicomputer that is attached to an electric arm, from the Massachusetts Institute of Technology, Cambridge.

J. L. Nevins and D. E. Whitney of the Charles Stark Draper Laboratory Inc. in Cambridge, Mass., will discuss the application of part-mating science—the interaction of parts during assembly—to automated assembly systems. They attribute growing interest in programmable systems to those machines' good repeatability and adaptability to different parts and to different market conditions.

Although their research has led to development of a machine that inserts rigid parts precisely using only springs, they will emphasize the need for continued research into the economics, software, engineering specifications, and scheduling of programmable robots.

Electronics and the environment. Everyone has a stake in a clean environment. But session 24, "Environmental Monitoring and Assessment," should be of particular interest to electronics engineers who use instrumentation to measure environmental quality. Session organizer and chairman Harlan J. Perlis of the New Jersey Institute of Technology in Newark, N. J., has limited its scope to airborne pollutants, which include noise, low-level radiation, particulate matter, and oxides of nitrogen and sulfur.

John Wesler of the Federal Aviation Agency in Washington, D. C., will begin with a paper entitled "The Monitoring and Analysis of Airport Noise." He will detail the year-old sound-measurement system at the capital's Dulles and National Airports. Microphones in 24 locations at both airports feed noise-level measurements over commercial-grade telephone lines to a PDP-11 minicomputer at Dulles. By mixing those measurements with air-traffic control data, the computer can identify the worst offenders.

Harold L. Beck of the Department of Energy's Environmental Measurement Laboratories in New York City will tell the audience what today's sensitive radiation monitors can do, and how to interpret their readings. His paper also describes DOE's past and present use of sensing equipment like ionization chambers, scintillation detectors, and germanium diodes.

Air-quality measurement is the subject of two papers. Richard Paur of the U. S. Environmental

Communications system designers can learn how to improve the signal-to-noise ratio of data links in overcrowded regions of the rf spectrum in a discussion of adaptive antennas

Protection Agency in Research Triangle Park, N. C., will describe a mobile laboratory that measures gaseous and aerosol concentrations in the field and tags them with precise geographic coordinates in a Hewlett-Packard System 45 computer. "Indoor-Outdoor Relationships of SO_2, NO_2, Fine Particulates and Sulfates," by John D. Spengler of the Environmental Health Department at the Harvard University School of Public Health in Cambridge, Mass., will report on techniques for measuring indoor pollution levels. The study aims, for example, to determine the effects of cooking and cigarette smoke on respiratory disease.



Logic analysis in larger systems. Since the early 1970s commercially available logic analyzer techniques and equipment have aided the digital designer greatly in the design, initial turn-on, analysis, and debugging of logic systems as well as in field repair and maintenance of those systems. Most of the users of this equipment, however, were designers working with microprocessor-based systems.

Session 14, "The Use of Logic Analyzers in the Development of Processor Systems," concentrates on applying logic-analyzer techniques to larger systems. Chairman Sam Lee of Hewlett-Packard Co.'s Colorado Springs (Colo.) division, observes that designers of larger systems, and minicomputer and mainframe computers, have been slower to make use of these new techniques for at least two reasons. Commercially available equipment is tedious to operate first because of difficulty in hook-up and interpretation of the data and second because of lack of measurement and indexing power. The larger systems often had reasonable debugging software available with their operating systems, and system designers wrote more. Consequently, logic analyzer techniques were slow to be put to use.

But the increasing complexity of bus architecture and the continuing difficulty in locating glitches due to coupling or race conditions have pushed designers to realize the value of logic analysis techniques. The session will describe some specific situations in which the speakers have used these techniques to solve specific design situations for their products and to meet customer requirements.

Julie Cates from HP Data Systems, Cupertino, Calif., will discuss her use of logic-timing analysis during development of the floating-point processor hardware for HP's 21MX minicomputer series. A discussion of equipment built by Digital Equipment Corp. for sorting real-time bus problems on the unibus will be presented by Erik Anderson of DEC's Maynard, Mass., facility.

Steve Sensabugh of Tesdata Systems Corp., McLean, Va., will provide some insights into how logic analyzer techniques in computer performance-evaluation equipment can provide real-time transparent measurements. These measurements allow designers and users to make intelligent decisions about operating-system design and parameters for greatly increased performance.

Spreading the work. Organizer Carmen J. Luvera believes that session 11, "Adaptive Antennas," will be interesting to communications engineers who must deal with improving the signal-to-noise ratio of data links in some overcrowded regions of the radio-frequency spectrum. Discussion will center around current methods of deriving control signals (special processing) from samples of the radiation field received by the antenna itself. When applied to appropriate software-based feedback systems, the signals electrically adjust the antenna pattern for nulls in a desired direction or form a main lobe (beam) in the direction of a desired signal. State-of-the-art system designs using analog, digital, and hybrid feedback system systems will also be presented, with some recent developments sharing the spotlight.

Opening the session will be Bernard Widrow and H. Mesiwala of Stanford University in Palo Alto, Calif., who will discuss "Compression of Eigenvalue Range by Using a Surplus of Adaptive Antenna Elements." Widrow and Mesiwala show how placing more elements than the minimum required in a system reduces the range of eigenvalues that may be assumed in its defining correlation matrix, which in turn speeds the response time of the system. Not content with that, they claim that a by-product of their method also yields better antenna directivity than would normally be attained.

W. K. Masenten of Hughes Aircraft Co. in Fullerton, Calif., will then present "Trends in Adaptive Antenna Circuit Design." He will discuss

One of the latest wrinkles in LSI is the circuit that combines analog and digital functions on a single substrate, and the three technologies used to make the chips will be discribed by their backers

some problems inherent in the design of adaptive-array subcircuits in systems incorporating "frequency hopping" to obtain a spread-spectrum waveform over a wide band. He then covers the implementation of analog and hybrid versions that accommodate a frequency-hopped spectrum. For either version, the implementation of the pattern-forming network and what is called the cross-covariance measuring functions are the critical design objectives, and Masenten discusses these subjects in detail.

Vidas Mikenas of the Harris Corp. in Melbourne, Fla., then shares his findings in comparing analog and digital control techniques for adaptive array systems. He defines the precise tradeoffs between the faster and more stable analog system to the flexible digital system, which Mikenas notes has been made more attractive in recent years by LSI technology. Peter Sielman, from Cutler Hammer Inc.'s AIL division, then takes over, discussing the degree to which a digital system can help enhance the depth of convergence rate and dynamic range and the precision of an adaptive array.

Finally, Larry Horowitz of MIT's Lincoln Laboratory discusses the first lab model implementation of the well-known sample-matrix-inversion algorithm for controlling the receiving pattern of an airborne adaptive array. Horowitz produces performance data for a lab-nulling system implementing the algorithm, whose main advantage is that it minimizes the rate of observations and computations required in the airborne environment. The results of the tests at Lincoln are compared with performance predictions based on measured component variations of the laboratory system.

Analog + digital + LSI = hot subject. One of the liveliest products coming out of wafer ovens is the integrated circuit combining analog and digital functions on one silicon substrate. But where n-channel MOS rules the roost in microprocessors, single-chip analog-with-digital ICs are emerging in a variety of technologies: n-MOS, complementary MOS, and even integrated injection logic. Session 2 will provide an overview of these product types under the title "Analog-to-Digital LSI."

Says session chairman Rob Walker of Intel Corp., Santa Clara, Calif., "Unlike watches and calculators, where the whole system is already integrated onto one chip and further advances don't really buy you anything, these new ICs allow system designers to pull more circuitry—like a-d converters, keyboard interface, and output drivers—onto the same chip." But since there is no general agreement on the best technology to use, Walker will have experts on the three major approaches speaking together.

Discussing C-MOS as seen in his company's model 7106/7107 3½-digit a-d converter will be William D. O'Neil of Intersil Inc., Cupertino, Calif. He will stress the low-power advantage of the approach and may talk about the still-to-be-announced 12-bit converter presently on Intersil's drawing boards.

Speed-power is the theme of Phil Marcoux's talk about Signetics Corp.'s use of I^2L for a-d chip design. He will use the Sunnyvale, Calif., company's codec as an example of what he calls "a true LSI circuit." Marcoux believes I^2L runs a close second to n-MOS in circuit density but has an advantage in accuracy because high-value resistors can be integrated with it. And though conceding that n-MOS runs away with the speed title, Marcoux believes that second-generation 1^2L, with its Schottky technology, will change that. Also, Marcoux says, C-MOS is in the running only in its low-power applications.

Not so, says Edmund K. Cheng, who designed Intel's 8022 a-d microprocessor. "The a-d portion of the 8022 takes up only one sixth of the chip and it's not a big chip," Cheng says. Compared to be I^2L a-d chip area, he says, n-MOS "beats them by a mile." He does concede, though, that n-MOS isn't the greatest technology for these types of circuits. Instead, he will attempt to show why its strength in other areas, such as cost and ease of interface to other relatively complex functions, are important tradeoffs that should be considered.

Doing it itself. The growing complexity of instrument designs, especially those based on microprocessors, continues to create testing and servicing challenges. Session 22, "Self-testing, Checking, and Calibration in Instrumentation," addresses the need for instruments with on-board diagnostics that can lower

Engineers working on large computers or telecommunications will have a session covering the problem of electromagnetic interference and how plastic packaging might solve it

servicing costs and earn more confidence from users, states session chairman Gordon Partridge of GenRad Inc., Concord, Mass. Although instruments with self-analyzing and calibrating features are more expensive, servicing and calibration costs, in addition to instrument downtime, are greatly reduced.

Partridge has lined up four speakers. Craig Johnston of Fluke Manufacturing Co., Mountlake Terrace, Wash., will stress the economy, and each of the remaining speakers will provide examples of instruments incorporating built-in diagnostic and calibration features. Michael Anthony of Keithley Instruments Inc., Cleveland, Ohio, deals with a parametric test system; the GenRad microprocessor-controlled impedance meter is Robert Sullivan's example. And James Griffin of Tektronix Inc., Beaverton, Ore., will demonstrate how self-testing added to a portable service instrument increases operator confidence in measurements at field locations.

Plastic packages as shields. More and larger systems are being packaged in plastic, particularly in the computer and peripherals fields. But along with the cost and shock-resistance advantages of plastic comes the problem of electromagnetic interference (emi). Session 6, "Plastic Packaging for Emi Shielding," is therefore of vital interest to engineers who are designers in large computer and telecommunications firms that are starting to package equipment in this type of material.

John J. Reilly of Electro-Kinetic Systems Inc. of Aston, Pa., points out that going to a plastic case or cabinet means losing all the shielding a comparable metal case would give, and John Jackman of NCR Corp., Wichita, Kan., discusses the use of economical metal-film coatings, flame-sprayed coatings, metal foil-tapes, and conductive molding compounds to protect data-processing systems packaged in plastic from electromagnetic or radio-frequency interference.

A paper by Dave Stutz of Battelle Memorial Institute in Columbus, Ohio, concludes that conductive plastic composites appear to be one of the better cost-effective ways to provide shielding. And Rick Stadterman of General Electric Co. in Pittsfield, Mass., discusses the cooperation necessary among the original-equipment manufacturers, packaging and component engineers, material suppliers, and shielding system vendors to identify and evaluate shielding systems early in the product-design phase of the operation.

Software in mass production. Computer manufacturers are spending an increasing proportion of their development budgets on software. It will therefore have to be manufactured in a standard manner, much like hardware, says Jacob Sternberg, chairman of session 4, "Software Manufacturing in the Distributed Environment—Theory and Practice."

Sternberg, who is with Conversational Systems Corp., a New York City–based systems house, notes that software "has traditionally been a customized, crafted product. The demand today is for a noncrafted, engineered product." Instead, he proposes, "software should be provided to users the way cars are. An automobile is assembled from basic subassemblies using standard tools. And after the car is sold, standard parts are available."

The question then is, who will create the software interfaces and modules? "Standards are coming up," Sternberg says. "Some will be dictated by industry giants like IBM and others by public utilities such as AT&T." The software modules themselves, he says, will be manufactured by a "new breed of company." To use the car analogy again, Sternberg makes the point that, "General Motors doesn't produce every part that goes into a car, and there will be no monopoly on software, either. Small software companies will supply small modules."

Among the various semiconductor technologies that have had an impact on computer design, the advent of dense random-access memories ranks as one of the most significant. And Sam Young, chairman of session 20, says the latest generation of 64-K RAMs will have an even greater impact.

"As memory has become denser and less expensive, computer designers use more memory. This has changed the thought patterns of software people," notes Young, of Mostek Corp., Carrollton, Texas. "Memories used to be precious, and the efficiency and compactness of a program was important. Now the philosophy

Caught between the FCC and Underwriters Labs, makers of switching power supplies will have a session that examines the question of emi limitations and their effect on the industry's future

has changed and less time is spent on software optimization." In addition, equipment such as microcomputers could not exist without the availability of low-cost RAMs, Young notes. This will be discussed by Wendel Sanders of Apple Computer, Cupertino, Calif.

Another area in which RAMs have made a significant impact is in minicomputer technology. "As the cost, power requirements, and size of RAMs have decreased, their performance and reliability have increased," says Michael Gutman of Digital Equipment Corp., Maynard, Mass., who will examine their effect on minicomputers. At the other extreme, Paul Higatshi, of NCR Corp.'s large systems facility in San Diego, Calif., will discuss the impact of the large dynamic RAMs on main frame computer design.

The road ahead for switchers. Session 34 on "The Future of Switching Power Supplies" should be provocative, for it explores the fate of the growing solid-state power supply industry. Chaired by Walter J. Hirschberg of ACDC Electronics, Oceanside, Calif., it will focus on a crucial aspect of power supply design—electromagnetic interference (emi). The industry currently is being confronted by both ends of the regulatory spectrum. On one hand, the Federal Communications Commission is considering sharply limiting emi radiation in the environment. On the other, Underwriters Laboratories is prescribing the amount of leakage current that can be reflected back into electric utility sockets.

Faced with these constraints, future switchers will have to be designed with tighter specifications on both subsystem assembly and component levels. To that end, three papers discuss novel circuit-design techniques and incorporation of basic supply circuits in integrated form to fine-tune the balance between high efficiency and compactness in switching power supplies.

Ken Check of Intel Corp.'s OEM Microcomputer Systems division in Hillsboro, Ore., will present a novel approach to silicon controlled rectifier-switched resonant inverters, where the regulating mode varies the frequency within an 18- to 36-kilohertz range. He will discuss a 400-watt switcher under design at Intel slated for the company's new line of supplies for computers and instruments in early 1980.

Barry Harvey of Siliconix Inc., also in Santa Clara, will deliver a get-acquainted paper on the power field-effect transistor, one of the most controversial parts to come out of the semiconductor industry for use in switching power supplies. The power FET is generally regarded as a mixed blessing by supply manufacturers, so Harvey will try to still the mistrust of potential users. Although much faster than bipolar transistors, FETs need a substantial amount of support circuitry to come close to the overall attributes of the bipolar devices. Interfacing either bipolar devices or FETs to the rest of supply circuitry is the subject of Stan Dendinger of Silicon General Inc. of Garden Grove, Calif.

Two papers concentrate exclusively on major hurdles—reliability problems and emi. Phil Koetsch of ACDC will look at reliability, specifically addressing the validity of the MIL-217B military standard in evaluating failure rates, since commercial switching supplies on the market now far exceed the rates stipulated by the standard.

The emi dilemma will be addressed by Joseph Banasiak of R&B Enterprises, Plymouth Meeting, Pa., who will investigate the impact of Government regulations concerning emission controls. With the proposed docket 20178 in front of the FCC, switcher manufacturers are faced with, among other requirements, a minimum noise suppression figure that will be difficult to meet.

Space spies. Organized and headed by chief scientist John Burgess of Rome Air Development Center, Rome, N. Y., session 5 provides an overview of RADC-sponsored work in satellite surveillance. Five contractors will discuss their work on space antennas, how to build them, and how to keep them powered.

"The programs to be described are all long-range," says Burgess, "with practical applications many years in the future." Typically theoretical are "The Space-Fed Lens—an Antenna for Space" by Jack Schultz of the Grumman Aerospace Corp. in Bethpage, N. Y., and "Space Antenna Far-Field Patterns" by Robert Hancock of Simulation Technology Inc. in Antioch, Tenn.

Schultz will describe his idea for an electronically steered, dual-frequency, dual-polarization antenna for a three-axis stabilized satellite. □

Kodak Precision Line film LEN7, is a pretty amazing act! Quality compares with the finest circuit negative films available at any cost...but LEN7 costs significantly less!

LEN7 delivers excellent line edge acutance, high maximum density and minimum pinholing...and the dimensional stability of a 7 mil Estar base.

LEN7. You've got to see it to believe it. It's an incredibly good film for circuit-making and other applications, at a remarkably low price.

For details, write for our information packet. Eastman Kodak Company, Dept. GA014, Rochester, N.Y. 14650.

Kodak

© Eastman Kodak Company, 1979

Ever Changing...Always Constant

The Measure of Excellence Goes On with Precision Instrumentation from

AILTECH

Ailtech's growing list of customers, spanning the globe, is representative of the ever changing needs of Industry in search of excellence...our skilled engineers' dedication and expertise in meeting these needs is always constant at Ailtech. Performance, Ease of Operation and Reliability have gained us recognition in the field of instrumentation...and we're confident that the measure of excellence which has become an Ailtech standard will be your first consideration whenever precision instrumentation is required.

For Instrumentation designed to meet the total needs of Industry today and in the future...Look to Ailtech.

- **A Microwave Spectrum Analyzers, 1-22 GHz**
- **B Synthesized Signal Generator, 10 KHz-2000 MHz**
- **C Noise Measuring Equipment, 1 MHz-40 GHz**
- **D Broadband Power Amplifiers, 1-512 MHz**
- **E EMI Instrumentation, 20 Hz-18 GHz**
- **F AC Instrumentation**
- **G Communication Service Monitors, 50 Kc-1.212 GHz**
- **H Broadband Sweep Oscillators, .01-18 GHz**
- **I High Power Signal Sources, 10 KHz-2500 MHz**

AILTECH
DIVISION CUTLER-HAMMER

CONTROL

Long Island Operation 2070 Fifth Avenue, Ronkonkoma, N.Y. 11779
Telephone: (516) 588-3600 • TWX: 510-228-6507
City of Industry Operation 19535 East Walnut Drive, City of Industry, Ca. 91748
Telephone: (213) 965-4911 • TWX: 910-584-1811
Los Angeles Operation 5340 Alla Road, Los Angeles, Ca. 90066
Telephone: 213-822-3061

International Offices:
France La Garenne-Columbes Tel: (01) 780-73 73 Telex: 620821 - Germany Munich - Telephone (089) 523 30 23 Telex: 529420
Nederland: Rotterdam, Telephone: (010) 81 4466 Telex: 28661 - United Kingdom Crowthorne, Telephone: Crowthorne 5777 Telex: 847238



MEMBER OF CUTLER-HAMMER INSTRUMENTS AND SYSTEMS GROUP

Circle 173 on reader service card


F
G
H
E



Quickie™: the total IDC System for design flexibility, fast assembly, reliable connections.

Meets a variety of interconnect needs.

- A wide choice of connectors: "Quickie" and "Quickie" low-profile females, female IC, edge card, male DIP, PCB, and quick-eject vertical and right-angle headers ... all in a broad range of sizes.
- Round conductor, flat cable on 0.050" centers.
- A selection of hand and air operated presses, cable shears, accessories and strain reliefs.

Efficient assembly saves time, material and money.

All connectors in the Quickie* system deliver reliable terminations in just a few seconds because:



- Cable slot designed to precisely position conductor for reliable termination, higher yields.
- Sight holes in cover permit visual inspection before and after assembly assuring proper cable alignment.

- The semi-automatic applicator completes terminations with a slide motion reducing assembly time. Or choose the manual applicator designed to minimize operator fatigue.



Over seven years proven performance. You can rely on "Quickie".

"Quickie" connectors are now specified by many of America's most quality conscious companies. Three high performance features demonstrate why:

1. Askewed tines firmly hold the wire for reliable termination.

2. Dual-beam contact assures redundant positive pin connection, even when subjected to vibration.

3. High-strength plastics withstand severe environments.

For a brochure giving details and complete specifications, write or call:

The Du Pont Company, Berg Electronics Division
New Cumberland, Pennsylvania 17070.
Telephone: (717) 938-6711.

DU PONT
REG. U.S. PAT. & TM. OFF.

BERG ELECTRONICS

Circle 175 on reader service card

VAX 32-bit software. It lets you write your programs in record time.





Compared with every other 32-bit OEM computer on the market, Digital's VAX-11/780 doesn't only run faster. It programs faster too.

And the reason is simple. The software.

The VAX-11/780 comes with the most comprehensive, most powerful set of 32-bit development tools ever offered to the OEM. Compilers. Linkers. An on-line HELP command. A symbolic de-bugger that can print out in familiar decimal notation, as well as binary. Editors that create new files while keeping prior versions available.

In addition, the VAX/VMS operating system is designed to do many of the things that would have to be written into the application program on other machines. It gives you features like a real-time scheduler. Automatic or user-controlled memory management. Built-in network protocols. And a file system that can access data any way you like. Since the operating system can do more, you do less—and deliver to your customer sooner.

With over 800 man-years of development behind it, VAX software is also incredibly reliable and fully mature.

The VAX-11/780.

It programs like it runs.

☐ Please send your new VAX OEM brochure.
☐ Please contact me.

Name _____

Title _____

Company _____

Address _____

City _____ State _____ Zip _____

Telephone _____

My OEM application is: _____

Send to: Digital Equipment Corporation, PK3/M-56, Maynard, MA 01754. Or call: (617) 493-9797. In Europe: 12 av. des Morgines, 1213 Petit-Lancy/Geneva. Tel. 93 33 11. In Canada: Digital Equipment of Canada, Ltd.

digital

Circle 177 on reader service card

Why should microprocessor users specify GE Triacs?

A little logic.



The Triac on the right is the new SC92, the smallest unit in industry's largest line of Triacs from General Electric. Available in a TO-92 JEDEC package, the SC92 is rated 0.8 amps rms up to 400 volts. Its 10mA gate sensitivity works directly from logic signals to provide the switching link between microprocessors and power output. This feature eliminates the need for an amplifier in many power control applications, solenoids, appliances, lamps and more.

Immunity from non-repetitive transient voltage damage is a feature unique to General Electric and patented glass passivated pellets add stable blocking life and reduced thermal fatigue. The SC92 offers low V_F for less heat, energy and power loss.

The SC92. The littlest Triac with a lot of little features that add up to big performance. The kind of performance you've come to expect from the world's leading manufacturer of Triacs and SCR's.

Call or write your nearest GE electronic component sales engineer or any authorized GE distributor for more information. For a free sample kit, write General Electric Co., Box 44A, West Genesee St., Auburn, NY 13021. In Europe, contact International General Electric of New York, County Louth, Dundalk, Ireland (042) 32371—Telex 33816. 222-13A

There's more to GE semiconductors than meets the eye

Stop by the GE booth 2536-38 at ELECTRO '79.

GENERAL ELECTRIC

Electro79

On April 24, when the New York Coliseum's doors open on the IEEE's annual show, instruments will be competing with microcomputers and data-acquisition systems for showgoers' attention

RCA unveils first five boards in its compact, low-power computer family

Entering the market for single-board computers with a flourish, RCA Corp. will use the Electro show as a launching pad for two central-processor-unit boards, three random-access-memory boards, and an interface board. They are the first members of the CDP18S600 series, with more boards to come.

The company intends to stress the compactness of the resulting systems. The boards are only 4½ in. wide by 7½ in. long, and the liberal use of the Cosmos complementary-metal-oxide-semiconductor process gives cool-running parts that permit tight stacking of the boards and need little power.

One of the RAM boards has room for five 1.5-v batteries, enough to power a small system. Thus RCA sees a good market among users that need an isolated system, as in medical applications; a system operating at a different potential level than surrounding equipment, as in a high-voltage environment; or a sealed system, as in a vacuum.

In general, the company has its sights on the industrial control market, says Michael Caterina, product-marketing manager for microprocessor systems. The boards' compactness also make them naturals for smart peripherals, he says.

The bus structure is RCA's own, using a 44-pin edge connector on the back of the boards and a 20-pin input/output connector on the front of the CPU boards.

The processor boards, the $549 CDBP18S601 and the $475 -603, both use the company's 8-bit 1802 C-MOS microprocessor and provide 20-mA current-loop or RS-232C serial interfaces. The 601 has 20 parallel programmable I/O lines and comes with 4 kilobytes of RAM and 24-pin sockets for 4 or 8 kilobytes of read-only memory or erasable programable ROM. The 603 has 20 parallel I/O lines, 1 kilobyte of RAM, and sockets for 2 or 4 kilobytes of ROM/EPROM.

The three C-MOS static RAM boards are CDP18S620, -621, and -622, costing $395, $1,195 and $795 respectively (quantity discounts are available on all five boards). The 4,096-bit-by-8-bit 620 uses the 5101 bulk-silicon RAM chip. The other two memory boards use RCA's C-MOS-on-sapphire MWS 5114 chip, with the 621 holding 16 kilobytes

and the 622 holding 8 kilobytes. The 622 comes with four penlite batteries for backup operation, easily converted into an internal power source by adding a fifth battery to give the necessary system total of 6 V.

Finally, there is the $175 CDP18S641 interface module, which is a universal asynchronous receiver/transmitter. Also being introduced at the show are two chassis, one holding five boards and the other holding 25. Both come with wired back buses, and Caterina says other chassis introductions are planned.

More I/O boards are in the works, as are more memory and CPU boards. Among the CPU cards will be some using the 1804, the forthcoming single-chip version of the 1802. The 1804 will include 2 kilobytes of RAM and ROM, a timer/event counter, and more instructions.

Another reason for using the RCA bus structure is that it offers hardware compatibility with the company's CDP18S005 Cosmac development system, Caterina says. Thus it is possible to develop software simply by plugging boards into the 005, later plugging the same types of boards right into the final system. Coming in about 60 days will be a prototyping system (shown) based on the five-card chassis.

RCA Solid State Division, Route 202, Somerville, N. J. 08876. Phone Michael Caterina at (201) 685-6599 [411]

System acquires 250,000 samples/s

Datel Systems Inc. has broken the link between high speed and high price in data-acquisition systems. The company claims that its PDAS-250 is the first off-the-shelf unit to combine an acquisition rate of 250,000 samples/second, 12-bit resolution, and the ability to pack up to 256 single-ended or 128 differential channels into a 3.5-in. rack-mountable package at a price that starts at $3,190.

"We achieved our high speed and low price with a technique we call overlapping conversion," explains Datel's product marketing manager, Larry Copeland. The analog-to-digital converter in the PDAS-250 is fast enough by itself, with a settling time of less than 2 μs. But after conversion, rather than wait for a "data dump" instruction from a host computer, it shunts its output into a temporary storage register, freeing itself for another conversion. According to Copeland, this makes the PDAS-250 ideal for applications like signal processing, vibration studies, aircraft flight testing, process control, real-time engine diagnostics—in short, any operation where a large number of fast-changing data channels must be monitored.



In addition to the successive-approximation a-d converter, the PDAS-250 contains a high-impedance input buffer, a high-speed multiplexer, a sample-and-hold network, data-output and status registers, random-access and sequential address logic, and mode controllers. Internal logic is complementary metal oxide semiconductor (C-MOS) to minimize thermal effects and power consumption, but interface levels are transistor-transistor logic (TTL) for data-bus compatibility.

The system operates with or without computer supervision. In its internally controlled mode, it can be much faster than its rated speed of 250,000 samples/s. Although Datel will not say how much faster, it does report achieving speeds of 300,000-400,000 samples/s during tests. Under computer control, speed is limited by the host computer. With better minicomputers having direct memory access, the PDAS-250 easily reaches its rated speed. The unit is plug-compatible with Nova, Eclipse, and PDP-11 minicomputers, and a VAX-11/80-compatible model is on the way.

For hookup to a mini, the unit requires a parallel digital input/output-port module, which is available from Datel. If they wish, users can develop their own software—a handler program to control and respond to command and status bits, to supply addresses and to accept data—but this can be time-consuming and costly. As a faster and less-expensive way of getting the PDAS-250 on line, Datel suggests using one of its series of Sinetrac, 256-channel,

Our tiny new 68c* quartz crystals just made your dream product possible . . .

. . . because now you can abandon the old price and design limitations on precision oscillators.



Magnified x 6

Actual Size

With our new CX series low-frequency quartz crystals, you can now design ultra-accurate timing circuits that are even cheaper — overall — than LC and RC oscillators. They will fit in the smallest spaces in the roughest, toughest environments. And will give your product the prestige and glamour that accompanies the phrase "Controlled by Quartz Crystal."

CX crystals are an order of magnitude cheaper, smaller and stronger than any low-frequency crystal currently available. They come in frequencies from 350 kHz *all the way down to 10 kHz* — in the same miniature package!

Statek crystals are totally different from conventional crystals. The design is patented and they are made in California by advanced semiconductor-type processing techniques. And they incorporate everything we've learned from producing 17 million quartz crystals since 1973.

To discuss your application, write or call Jeff Upton at Statek Corporation, 512 N. Main, Orange, California 92668. (714) 639-7810.

*Prices range from 68¢ to $1.17 in 100,000 quantity. See EEM and Gold Book for details.

STATEK *Innovators in Frequency Control*

EUROPEAN SALES REPRESENTATIVES: • FRANCE: Tekelec Airtronic, Cite des Bruyeres, Rue Carle Vernet, 92310 Sevres. Tel: (1) 027.75.35. • W. GERMANY: Alfred Neye-Enatechnik GmbH, 14 Schillerstr., 2085 Quickborn, Hamburg. Tel: 04108/6 12-1. • NETHERLANDS: Tekelec Airtronic B. V., Kruislaan 235, Amsterdam-Oost. Tel: 020-92 87 66. • SWITZERLAND: Dimos AG, Badenerstr. 701, CH-8048, Zurich. Tel: 01/626140. • UNITED KINGDOM: Interface Quartz Devices Ltd, 29 Market St, Crewkerne, Somerset. TA18 7JU. Tel: (046031) 2578.

Circle 181 on reader service card

digital interface controller boards. At about $1,500 to $3,000, these are available for PDP-11, Nova, and Eclipse minicomputers.

The PDAS-250 system expands in increments of 32 single-ended or 16 differential channels, to a housing maximum of 256 single-ended or 128 differential inputs. Two housings can be stacked to reach 512/256 channels; with expansion logic, users can go to 768 channels or more. Prices rise with the number of channels: a 32/16 channel system costs $3,190 to $3,470; one with 256/128 channels goes for $5,990 to $6,165; and 512/256-channel capability has a price tag of $9,890 to $10,160, including the required second housing. As factory options, Datel also offers digital-to-analog conversion circuitry for applications like real-time data logging, and simultaneous sample-and-hold circuits that are handy for signal processing.

Although it offers speed and flexibility, the PDAS-250 has uncompromised analog specifications. At 25°C, overall system error is less than ±0.04% of full-scale range, ±2 mV for single-ended inputs; in the differential mode, the figure is ±0.05% of full-scale range, ±2 mV. Nonlinearity is within ½ least significant bit. Gain drift with temperature is typically ±40 ppm/°C over a 0-to-70°C range.

Acceptable full-scale input ranges are 0 to 5 V, 0 to 10 V, −5 to +5 V, and −10 to +10 V. Input overvoltage is ±35 V maximum, for a steady-state, no-damage condition. Differential inputs have a common-mode range of ±10 V and common-mode rejection is 80 dB from dc to 60 Hz, assuming a 1-kΩ imbalance. Digital output is available in straight binary form, in bipolar offset binary, or in bipolar 2's complement. Delivery time is 10 to 12 weeks.

Datel Systems Inc., 11 Cabot Blvd., Mansfield, Mass. 02048. Phone Gilbert Parker at (617) 828-8000 [412]

Bandpass filter has sharp cutoff

"Brickwall" is the name Rockland Systems is giving its model 751A programmable elliptic bandpass filter to be introduced at Electro79. The reason: the unit features a roll-off rate of 115 dB per octave, giving a very sharp response curve. Stop-band attenuation is at least 80 dB.

The 751A permits independent programming of low- and high-frequency cutoffs, allowing the operator to set center frequency and bandwidth anywhere in the 1-Hz-to-100-kHz band it covers. Available as options are binary-coded-decimal and IEEE-488 bus interfaces for remote programming of cutoffs and prefilter and postfilter gains.

Employing a seventh-order elliptical filter, the unit has a 0.3-dB peak-to-peak passband ripple, and 85-dB stop-band attenuation above 1.7 times the low-pass cutoff and below 0.6 times the high-pass cutoff.



Rockland expects the Brickwall to find a wide range of applications "because it is the closest approach to the ideal 'brickwall' filter allowed by the present state of the art in component design," says marketing vice president David Kohn.

Availability of the 751A is 90 days, and the base unit price is $300. The 01 BCD option adds $375, or the 02 488 option may be specified for $650.

Rockland Systems Corp., Rockleigh Industrial Park, Rockleigh, N. J. 07647. Phone David Kohn at (201) 767-7900 [413]

Operational power works six ways

The first models in a second generation of bipolar operational power supplies will be launched at Electro 79, coming from the originator of the BOP concept, Kepco Inc. The new line will feature altogether six modes of operation, whereas the first generation featured only voltage stabilization.

"Bipolar operational power supplies are unique in their ability to control a voltage [or current] smoothly and linearly through zero from a positive to negative value without discontinuity and switching," says Paul Birman, Kepco's marketing manager.

Two models will make debuts: the BOP50-2M, which is a ±50-V, ±2-A unit, and the BOP100-1M, which is a ±100-V, ±1-A unit. The slew rate for the new units is a relatively speedy 3V/μs.

To the programmable constant-voltage mode, the new generation adds five others: constant current and positive and negative boundary limits for voltage and current. To keep operation within these limits, the power supply controls the conduction of series-pass transistors, also sending a signal to front-panel

Silent Partners.

Signetics' new dual op amps. Team them with your design for the industry's lowest noise.

Now the instrument OEM can specify op amps that deliver precision performance *and* low noise operation.

Our new duals combine the industry's lowest spectral voltage with a 600Ω output drive capability. The Signetics 5532 really shines at $6nV/\sqrt{Hz}$. And our 5533 brings it all home at $4.5nV/\sqrt{Hz}$.

Compare our monolithic pair to other "low-noise" op amps, and see what you've been missing. Like wide power bandwidths at exceptional slew rates.

Use them in your new design. Or specify them as superior replacements for not-so-low-noise op amps you may be using now.



Both devices give you a small-signal bandwidth of 10MHz, and high output drive capability.

By "high," we mean 10V rms into 600Ω at $V_s = \pm 18V$. Great for a wide range of applications. And either is the perfect choice for active filters or low-signal transducers.

Specs like these are going to let every instrument, telecom and wideband servo control systems designer upgrade his op amp requirements.

If you don't need two op amps on a single chip, check out our 5534. Same super features as our 5533. And this one's already become an industry standard. Whichever you choose, you're going to be dollars ahead and decibels lower. Join the silent revolution today with the op amps that let every OEM get the low noise performance that quality systems call for. Send us the coupon for full details. Or phone your nearest Signetics sales office or authorized distributor.

signetics

a subsidiary of U.S. Philips Corporation

Signetics Corporation
P.O. Box 9052
811 East Arques Avenue
Sunnyvale, California 94086
Telephone 408/739-7700

Signetics Dual Op Amps	
Part Number	**Key Specifications**
NE5532*	**Low Noise**: $6nV/\sqrt{Hz}$ (max.); internally compensated; 140kHz power BW @ 9V/μsec slew.
NE5533	**Low Noise**: $4.5nV/\sqrt{Hz}$ (max.); 200kHz power BW @ 13V/μsec slew.
NE/SE5530*	**High Slew**: 35V/μsec; internally compensated; 500kHz power BW; 3MHz small-signal BW.
NE/SE5535*	**High Slew**: 15V/μsec; internally compensated; 200kHz power BW; 1MHz small-signal BW.
NE/SE5538*	**High Slew**: 60V/μsec; compensated to gains of +5/−4; 700kHz power BW; 6MHz small-signal BW.

*industry standard pinouts

To: Signetics Information Services, 811 East Arques Avenue
P.O. Box 9052, MS27, Sunnyvale, CA 94086

☐ Rush details on Signetics NE5532/33 dual op amps.
☐ Tell me about Signetics industry standard NE5534 op amp.
☐ I want to get the noise out right now.
Please have an applications specialist phone me at:

E 412

( )_____ ext._____.

Name_____ Title_____

Company_____ Division_____

Address_____ MS_____

City_____ State_____ Zip_____

When you're searching for component solutions . . .

Centralab ceramic capacitors give you unparalleled selection and service...

- **Extensive product line of discs and monolithics**
- **Large-scale volume capability**
- **Over 200 U.S. distributors**
- **Multinational manufacturing sites**
- **Worldwide availability**

At Centralab you'll find a range of types, values, voltages, lead configurations, encapsulation and packaging that offers solutions to your ceramic capacitor needs. Our ceramic discs; monolithic chip, axial and radial leaded capacitors; CK/CKR and other hi-rel capacitors give you a wide selection, all from a single source.

And at Centralab, service is special too. We back our broad line with high volume manufacturing plants in five countries and a distribution system that's second to none. There are 75 worldwide Sales Representative offices and over 200 Industrial Distributors waiting to serve you. Our catalog will show you the unparalleled selection of ceramic capacitors and service available from Centralab. For a copy, call your Centralab Sales Representative or write us.

Products you need from people who care.

CENTRALAB
ELECTRONICS DIVISION
GLOBE-UNION INC.
4561 Colorado Boulevard
Los Angeles, California 90039

CERAMIC CAPACITORS • EMI/RFI FILTERS • POTENTIOMETERS • SWITCHES • THICK FILM CIRCUITS • TRIMMER RESISTORS

Circle 184 on reader service card.

... call your Centralab Sales Representative

ALABAMA
Huntsville
Cartwright & Bean, Inc.
(205) 533-3509

ARIZONA
Phoenix
Clemick-Neenan & Assoc.
(602) 279-7649

CALIFORNIA
Palo Alto
Brooks Technical Group
(415) 328-3232
Sherman Oaks
Clemick-Neenan & Assoc.
(213) 990-3150
Tustin
Clemick-Neenan & Assoc.
(714) 547-0966

COLORADO
Denver
Electro-Rep. Inc.
(303) 744-2821

CONNECTICUT
Meridian
Centralab
(203) 235-0766

FLORIDA
Ft. Lauderdale
Cartwright & Bean, Inc.
(305) 735-4900
Orlando
Cartwright & Bean, Inc.
(305) 422-4531

GEORGIA
Atlanta
Cartwright & Bean, Inc.
(404) 255-5262

HAWAII
Honolulu
Dougherty Enterprises
(808) 847-4144

ILLINOIS
Des Plaines
Centralab
(312) 694-4870

INDIANA
Indianapolis
Les M. DeVoe Co.
(317) 842-3245

IOWA
Cedar Rapids
Jerry Vrbik Co.
(319) 366-8733

KANSAS
Shawnee Mission
Lowell-Kangas & Assoc.
(913) 631-3515

LOUISIANA
Metairie
Cartwright & Bean, Inc.
(504) 834-2350

MARYLAND
Columbia
Bresson Assoc. Inc.
(215) 664-6460
Towson
Bresson Assoc. Inc.
(215) 664-6460

MASSACHUSETTS
Needham
Centralab
(617) 444-4781

MICHIGAN
Lathrup Village
Centralab
(313) 559-9095
St. Joseph
Centralab
(616) 983-0233

MINNESOTA
Minneapolis
Centralab
(612) 831-5212

MISSISSIPPI
Jackson
Cartwright & Bean, Inc.
(601) 981-1368

MISSOURI
St. Louis
Lowell-Kangas & Assoc.
(314) 821-4050

NEW JERSEY
Paramus
Centralab
(201) 262-6716

NEW YORK
Albany
Reagan/Compar Albany
(518) 489-7408
Endwell
Reagan/Compar Albany
(607) 723-8743
Fairport
Reagan/Compar Albany
(716) 271-2230
New Hartford
Reagan/Compar Albany
(315) 732-3775

NORTH CAROLINA
Charlotte
Cartwright & Bean, Inc.
(704) 377-5673
Raleigh
Cartwright & Bean, Inc.
(919) 781-6560

OHIO
Cleveland
Centralab
(216) 526-1205
Columbus
Centralab
(614) 888-2150

OREGON
Portland
Centralab
(503) 620-1611

PENNSYLVANIA
McMurray
Centralab
(412) 941-7440
Narberth
Bresson Assoc. Inc.
(215) 664-6460

TENNESSEE
Knoxville
Cartwright & Bean, Inc.
(615) 693-7450
Memphis
Cartwright & Bean, Inc.
(901) 276-4442

TEXAS
Austin
Centralab
(512) 454-9529
El Paso
Centralab
(915) 779-3961
Farmers Branch
Centralab
(214) 243-8791

VIRGINIA
Lynchburg
Bresson Assoc. Inc.
(215) 664-6460

WASHINGTON
Bellevue
Centralab
(206) 454-7754

WISCONSIN
Milwaukee
Centralab
(414) 228-2122

PUERTO RICO
Hato-Rey
M. Anderson Co., Inc.
(809) 751-2026

CANADA
BRITISH COLUMBIA
North Vancouver
Arwin Tech Sales Ltd.
(604) 980-4346

ONTARIO
Ajax
McHugh Electronics Ltd.
(416) 683-1540

QUEBEC
Ste. Dorothee Laval
Harnett Enterprises
(514) 689-4184

New products



indicators and to interface connectors whenever operation pushes to one of the four boundaries.

Moreover, the new models feature four-quadrant unrestricted source-sink operation and listener compatibility with the IEEE-488 bus. Where the first generation required external amplifiers for signal manipulation, the new models eliminate the need for this extra hardware with two internal preamplifiers.

In the constant-current mode, the compliance voltage for the BOP50-2M is 100 v and 200 v for the BOP100-1M. Output noise is 1 mv typically, 3 mv maximum root mean square, and ripple is 10 mv typically, 30 mv maximum peak to peak. Output line and load regulations are 0.0005% and 0.001%. The floating output can go 500 v above and below ground.

Single quantity price is $850, and availability is 90 days. Birman says the company expects the new models to follow in the steps of the first generation as power amplifiers, servo drivers, magnetic-beam steerers, and in such systems as automatic board testers, chip testers, and also avionics testers.

Kepco Inc., 131-38 Stanford Ave., Flushing, N. Y. 11352. Phone Paul Birman at (212) 461-7000, ext. 742 [414]

Acquisition unit resolves 16 bits

The number of applications for data-acquisition systems is on the rise as manufacturers broaden the dynamic ranges of their systems. Data Translation Inc. has taken the latest step forward with a new 16-bit analog-to-digital converter module for multiple analog signals. With 16-bit resolution and true 14-bit accuracy, the DT5716 accepts inputs between ±5 mv and between ±10 v.

"The DT5716 is especially good at measuring small deviations—like changes in temperature—from a central value," notes Stephen A. Connors, chief analog engineer. Fred Molinari, president of the firm, adds that "The DT5716 eliminates many of the front-end signal-conditioning costs associated with data-acquisition systems." He expects the module to be used in industrial and laboratory environments for distributed data collection, or as a signal conditioner and converter for a microprocessor or minicomputer. Other possible application areas he sees include temperature measurement systems, nuclear instrumentation, and gas chromatographs.



The DT5716 accepts data from 16 single-ended or 8 differential channels, expandable to 64 single-ended or 32 differential inputs. A resistor can be installed at each channel input to fix the gain of that channel, or the user can purchase a software-programmable variable-gain option. The user then can select a gain of 1, 2, 4, or 8 for high-level (±10-v) inputs, or a gain of 1, 10, 100 or 500 for low-level (±5-mv) signals. The module has byte-selectable, 16-bit three-state data outputs, in transistor-transistor or complementary-metal-oxide-semiconductor logic, for

If All Rental Companies Look Alike, How Do You Choose?



Need an oscilloscope or logic analyzer in a hurry? Do you have a short term need for a microprocessor development system? Chances are you've already discovered that renting the electronic equipment you need makes sense. But which rental company?

When you call Rental Electronics, you're tapping a multi-million dollar inventory of electronic equipment from Hewlett-Packard, Tektronix, Intel and every other major manufacturer. So we're sure to have what you need — even the newest equipment.

Our on-line real-time computer lets us give you immediate availability information while you're still on the phone. Even if what you need is at another of our ten stocking centers across North America.

Renting from Rental Electronics makes good economic sense, too. We're big enough to be as flexible as you need us to be, with competitive short term rates, lower rates for extended periods, even a selection of rental/purchase plans.

But there's an even better reason to make Rental Electronics your equipment rental company. It's called service. It starts when our rental experts answer your phone call. To us, service means going that extra step to meet your particular needs — for a special piece of equipment, a tight delivery schedule, a customized rental or rental/purchase arrangement, or just straight answers and a helpful attitude.

When it comes to service we're positively fanatical. And it pays off. During the past twelve months, for example, 92% of our first-time customers have come back for more.

Next time you consider renting, consider Rental Electronics. Give us a shot at your business. We're confident we'll turn you into a repeat customer.

Test and Measurement Instruments

Here is just a small sampling of the test and measurement equipment available today from Rental Electronics. For a complete list, use the coupon opposite.

Hewlett-Packard 1640A Serial Data Analyzer. Identifies and locates failures to the component level; RSC 232C; 2048 characters, monitor buffer, plus 1024 characters transmit message buffer; Sync or Async.

Biomation K 100 D Logic Analyzer. 16 channels; 1024 word memory; clock rates up to 100 MHz; signal timing resolution to 10ns; built-in display and keyboard control.

Honeywell 101 Recording System. 7 or 14 tracks depending on head assembly; ½ in. (7 tracks) or 1 in. (14 tracks) tape; 8 tape speeds from 0.937 ips to 120 ips; direct bandwidth to 2 MHz (wide band) and to 600 kHz (intermediate band); FM bandwidth to 80 kHz (wide band) and to 40 kHz (intermediate band); reel size 10½ to 15 in., coaxially mounted.

Tektronix 465 Oscilloscope. BW 100 MHz; display 8 x 10; 5 mV/div to 5 V/div sens.; sweep rate 50 ns/div to 0.5 s/div; x10 magnifier; dual trace; delayed sweep; x-y operation.

Hewlett-Packard 8565A/100 Spectrum Analyzer. 0.01 to 22 GHz with internal mixer; 14.5 to 40 GHz with 11517 external mixer; 100 Hz and 300 Hz resolution bandwidth; Absolute Amplitude Calibration: −110 dbm to +30 dbm.

Brush 260 Strip Chart Recorder. 1 mV to 500 V; chart speeds 125 mm/sec. to 1 mm/min., incl. four event markers; pressurized ink; response: DC to 100 Hz.

Rental Electronics, Inc.
An AMERICAL company

... a different breed.

direct connection to 16-bit buses.

The DT5716 acquires 16-bit channel data in 300 μs and converts it in 100 μs. System accuracy is within 0.0075% of full-scale range for gains between 1 and 10. Throughput rate is 2.5 kHz, with 1 μV rms of input noise. The operating temperature range is from 0° to 70°C.

The module contains a multiplexer, a precision instrumentation amplifier, a charge-compensated sample-and-hold amplifier, a high-resolution successive-approximation a-d converter, and control logic. The a-d converter has a temperature coefficient of linearity of ±2 ppm/°C, and a temperature coefficient of gain of ±15 ppm/°C. For the instrumentation amplifier, the gain tempco is ±10 ppm/°C.

Housed in a 3-by-4.6-by-0.375-in. package, the DT5716 sells for $1,195 in quantities of one to nine. A version with 14-bit resolution and accuracy, the DT5714, is available for $795 in the same quantities. The software-programmable option for high-level inputs costs $175; for low-level signals, the price is $100. Delivery is within five days after receipt of order.

Data Translation Inc., 23 Strathmore Rd., Natick, Mass. 01760. Phone Fred Molinari at (617) 655-5300 [415]

Low-cost units test Z80s, 8085s

The hunger for more efficient ways to debug bus-architectured systems can hardly be satisfied, even by the number and variety of logic analyzers coming onto the market daily. Sophisticated, expensive units catering to the programming gourmet not only monitor what is happening on the address and data lines but take control of the processor, too. But Pro-Log has taken a McDonald's approach to analysis and developed a pair of low-cost, portable analyzers that sample address and data information passively.



Designers of "take-out" instrumentation have to grapple with the problem of how much capability they can pack into a box before they compromise the ease of use, compact size, and light weight needed in the field. "Despite their light weight and low cost, these two products allow users to analyze the address and data lines of either the Z80 (model M 824) or the 8085 (model M 825) incrementally or at full system speed and they offer much help in hardware and software debugging," says Shay Adams, director of international marketing for Pro-Log. The 824 and 825 are priced at $1,250 each, about the same price as the personality modules required by more complex analyzers.

Each analyzer clamps onto its particular microprocessor with a DIP clip that terminates an interconnecting cable. The user traps data by setting the desired address on a rotary switch and putting the analyzer in the data-latching mode. When that address appears on the address bus, the byte on the data bus is latched and displayed both in hexadecimal and 8-bit binary formats.

Users can step through a processor's program either by instruction or by machine cycles and can add 0 to 100 cycles of delay to an address before the desired data is latched. Addresses are displayed on a four-digit hexadecimal readout. Incremental control of the processor is obtained by operating on its WAIT line, according to Adams.

An oscilloscope-synchronizing output allows users to examine address and data lines for noise and glitches on an external scope. "When a user has isolated the problem down

Choose:

Rental Electronics rents all kinds of Amplifiers, Analyzers, Calibrators, Counters, Couplers, Generators, Meters, Microcomputer Development Systems, Modulators, Oscillators, Oscilloscopes, Power Supplies, Printers, Probes, Recorders, Synthesizers, Terminals, Test Sets... and much more.

Rental Electronics rents equipment from ADDS, Ailtech, Associated Research, Beehive, Biomation, Boonton, Brush, Dana, Data I/O, Digitec, Doric, Dranetz, Elgar, Esterline-Angus, Fluke, GenRad, Halcyon, Hewlett-Packard, Honeywell, Hughes, Intel, Keithly, Krohn-Hite, Lambda, Lear Siegler, Marconi, Monsanto, Narda, Nicolet, Northeast, Power Design, Programmed Power, Singer, Sorenson, Tally, Techni-Rite, Tektronix, Tenney, Texas Instruments, Wavetek...and many more.

Rental Electronics, Inc. Rental Centers **In the U.S.:** Anaheim, CA (714) 879-0561 • Mountain View, CA (415) 968-8845 • Northridge, CA (213) 993-7368 • Ft. Lauderdale, FL (305) 771-3500 • Orlando, FL (305) 351-3015 • Des Plaines, IL (312) 827-6670 • Burlington, MA (617) 273-2770 or (800) 225-1008 • Gaithersburg, MD (301) 948-0620 • Greensboro, NC (800) 638-4040 • Oakland, NJ (201) 337-3788 or (800) 452-9763 • Rochester, NY (800) 631-8920 • Cleveland, OH (800) 323-8964 • Dallas, TX (214) 661-8082 • Houston, TX (800) 492-9021 • Seattle, WA (206) 641-6444 • **In Canada:** Vancouver, BC (604) 278-8458 • Rexdale, Ontario (416) 675-7513 • Montreal, Quebec (514) 681-9246.

Call one of our rental centers today for immediate action. Or return this coupon to Rental Electronics, Inc., 19347 Londelius St., Northridge, CA 91324.

☐ Send me your Rental Catalog.

☐ Send me your Equipment Sales Catalog—I may be interested in buying some of your "previously owned" equipment.

☐ I have an immediate need for the following rental equipment:

_____

_____

Please have someone from your nearest Inventory Center phone me at _____.

Name _____

Title _____

Company _____

Address _____

Mail Stop _____

City _____

State/Zip _____

Phone _____

Rental Electronics, Inc.

EL4/79

GSA # GS-04S-21963 Neg. © 1979 Rental Electronics, Inc.

When the Mini-Mizer® protects against power surge... Plenco helps take the charge.

According to the manufacturer, Brown Electronics, Barbourville, Ky., Mini-Mizer Surge Protectors guard against power surges caused by lightning, static charges, switching, etc., helping prevent damage, fire hazards, expensive repair costs. Handles current surges up to 10,000 amps.

Housed in cases molded of a heat-resistant Plenco compound, Mini-Mizers are offered in the two models shown: large, for major electronic equipment; small, for computers, office machines, TV sets, two-way radios, household appliances. The Molder: Recto Molded Products, Inc., Cincinnati, OH.

They report that our Plenco 485 black phenolic compound, "is easy to mold and we not only get required resistance to high temperatures, we get very fast cure, rigid set, low shrinkage and excellent surface finish."

Should you get the urge to surge ahead on your own particular molding application give Plenco a chance to help. Dial us at (414) 458-2121.

PLENCO
THERMOSET PLASTICS

PLASTICS ENGINEERING COMPANY
Sheboygan, WI 53081

Through Plenco research...a wide range of ready-made or custom-formulated phenolic, melamine-phenolic, alkyd and polyester thermoset molding compounds, and industrial resins.

to a few instructions," explains John P. McDonald, the design engineer whose approach this is, "he can dial up those addresses one at a time and, as each one of them comes up, it will trigger the scope." Both products will be available for delivery in June, Adams declares.

Pro-Log Corp., 2411 Garden Rd., Monterey, Calif. 93940. Phone (408) 372-4593 [416]

V-f units have small footprints

The days when fast voltage-to-frequency converters had to have large footprints on printed-circuit boards is past; Teledyne Philbrick is unveiling a high-reliability 1-MHz converter housed in a standard hybrid package.

Designated the 4735, the 24-pin unit is only 0.8 in. wide by 1.39 in. long and therefore requires only one quarter the area that a typical 2-in.-square module would.

The highest-frequency member of the family of converters introduced early last month [*Electronics*, March 1, p. 160], the 4735 resembles its relatives in its specifications. Like them, its operation is fully described over the temperature range from $-55°$ to $+125°C$. "It is the only 1-MHz hybrid V-f converter with such a wide temperature range on the market," claims Wah Fea Ng, the company's product specialist for linear and nonlinear voltage-to-frequency converters.

Changes in output at full scale due to temperature variation are guaranteed to be within ± 50 ppm/°C and

Whatever you need in an IC socket...

RN has 'em all!

—and with "side wipe" reliability

PRODUCTION SOCKETS

BURN-IN, TEST SOCKETS



NEW! ICL Series
26% lower profile—.150" Ideal for high density, high volume configurations, provides maximum vibration resistance. Solder type, single leaf "side-wipe" contacts. 8 to 40 contacts.



TS Series
very long contact life. Very low insertion force. Ideal for incoming inspection. With 14 to 40 contacts. Also strip sockets up to 21 positions.



RN HIGH RELIABILITY eliminates trouble. "Side-wipe" contacts make 100% greater surface contact with the wide, flat sides of your IC leads for positive electrical connection.



ICN Series high reliability general-purpose sockets. Low insertion force allows automatic IC insertion. In solder or wire-wrap. 6 to 64 contacts. Dual leaf "side-wipe" contacts.



IC Series
moderate cost, long life. Designed for general test and burn-in up to 350°C. With 14 to 40 contacts.



ICA Series
high reliability pin socket contacts. Low profile in solder or wire-wrap. 8 to 40 contacts.



ICN/S2 Series
lowest cost burn-in socket available. Designed to accept IC extraction tool. With 8 to 40 contacts, with strip sockets up to 25 positions.

WRITE TODAY for latest R-N "Short Form" Catalog...

... of R-N production DIP sockets. Contains full specs, dimensions and material data. Get yours now.

RN® ROBINSON NUGENT, INC.

ROBINSON-NUGENT, INC. • 800 East Eighth Street • New Albany, Indiana 47150 • Phone: (812) 945-0211

Circle 189 on reader service card

325 ways to keep ahead of the game.

You need 24 enclosures. You phone your local source. They'll make them. But, it's all going to take a while. You live with it because you've always done it that way.

There's a better way. Bud. We have 325 distributors. There's one near you. He stocks Bud standard enclosures. If he shouldn't have what you want, no problem. We'll ship immediately from our warehouses in Willoughby or Phoenix.

We're the industry's largest. Why? The people we deal with realize the value of service. The service they get from Bud. Get the name of your local Bud distributor and with it, some service for a change. Bud Industries, Inc., 4605 E. 355th St., Willoughby, Ohio 44094. Phone: 216/946-3200. Bud West, Inc., 3838 N. 36th Ave., Phoenix, Arizona 85019. Phone: 602/269-3151.



Our small enclosures come in 31 designs, 181 sizes, 19 colors. And they're in stock.

Service. BUD

Circle 190 on reader service card

Talk About Packing Density!



CEC'S 1-180 SERIES SIGNAL CONDITIONERS

pack 14 data channels into a 19″ RETMA rack!

Then — within this extremely flexible family of amplifiers — CEC can give you sensitivities to 1mV for full scale outputs of ±1 volt or ±10 volts, and galvanometer drive. Other available features include switchable filters, strain gage conditioning and high common mode voltage protection . . . plus much more.

Let us send you our signal conditioning "family album" with all the specifics. We think you'll find it a lot more interesting than the usual canned sales pitch.

CEC DIVISION
360 Sierra Madre Villa, Pasadena, California 91109

BELL & HOWELL

190 Circle 136 on reader service card

typically they are ±30 ppm/°C. Temperature has little effect on the offset voltage, too; it is stable to within a guaranteed ±50 μV/°C and typically to within ±15 μV/°C.

Accepting power supply voltages between ±9 V and ±18 V, the 4735 is guaranteed linear to within ±0.015% of full scale (typically, within 0.005% of full scale). The dynamic range of the converter is 100 dB guaranteed (126 typically) and the common-mode rejection ratio is a guaranteed 60 dB (70 dB typical) with the common-mode voltage at 10 V. Overrange is typically 100%, and 50% is guaranteed.

The 4735's output is compatible with transistor-transistor or complementary-metal-semiconductor logic levels. The output pulse width can vary from 0.1 to 0.3 μs, and the output impedance is 6.8 kΩ ±20% when the pulse goes high.

Some applications for the converter are high common-mode voltage isolation, two-wire digital transmission, analog-to-digital conversion of up to 20 bits, and optical data links. Wah Fea Ng suggests that "it can act as the voltage-to-frequency end of a data link. Teledyne Philbrick should have a 1-MHz frequency-to-voltage converter very soon."

The 4735 costs $145 each for one to nine units. It is fully screened to meet MIL-STD-883. Also available is the 4735-83 at $185 (for one to nine); screened to MIL-STD-883 as well, it has additional burn-in and temperature cycling. Delivery is in 6 to 10 weeks for both.

Teledyne Philbrick, Allied Drive at Rte. 128, Dedham, Mass. 02026. Phone Wah Fea Ng (pronounced Eng) at (617) 329-1600 [417]

THD analyzer is easy to use

For such important and widely used instruments, distortion analyzers have had very little human engineering expended on them. Typically they are difficult to operate and require technicians to spend a good

IMPROVED PERFORMANCE

The "INTELLIGENT" DVM's from Guildline



MODEL 9575—5½ digit (shown above)
MODEL 9576—6½ digit
Similar measurement functions
Different performance capabilities

Guildline's two new voltmeters measure DC voltage, AC voltage and resistance PLUS they use their measured results as a data base for processing information on a real time basis.

MEASUREMENT

Conventional measurements can be displayed, processed and displayed, and recalled at the end of each run. Accuracy ± 0.0009% • Stability—7ppm/6 months • Resolution—1uV • Scale length—3½ digits to 6½ digits • Ranging—auto and manual • 400 high speed readings/second

PLUS

Microprocessor Controlled Features include automatic calibration balance, 9 built-in programs—21 individual calculations.
Full math capabilities: $Y = Ax + B$ or $Y = A(x + B)$

PLUS

Special Processing Power
DATA REDUCTION—scaling, offset, ratio, logarithmic, squaring, and thermocouple linearization
STATISTICAL—% deviation, rolling average, updated variance, updated standard deviation, RMS, min., max., peak to peak
CONTROL—high-low limits, real time programmable clock, full internal time control: start, stop, interval between measurements and run time

PLUS

Data Systems Options
IEEE—488/1975, RS-232, Binary, BCD
Independent connectors offer time sharing between GP-IB and RS-232. 10 nanavolt resolution with any interface option to 6½ digits



To get a wealth of information at your fingertips, call or write

Guildline Instruments, Inc.
2 Westchester Plaza, Elmsford, NY 10523 (914) 592-9101 • TELEX—GUILDLINEEMFD145487

Electro/79 Booths 1627 & 1629

Circle 191 on reader service card

98 ways to save some embarrassment.

You need enclosures for a new system. You explain everything to your local source. Their prototypes miss the mark. You explain again. Hope it works. If not, embarrassment will be the least of your worries.

There's a better way. Bud. To the point, our 98 sales representatives. They will give you experienced guidance on what standard Bud enclosure will house your system. Advise you on new products, for example, see-thru plexiglass doors for upright racks. Counsel you on how Bud accessories help make systems even more effective.

Get the name of your Bud sales representative and get some correct advice for a change. Bud Industries, Inc., 4605 E. 355th St., Willoughby, Ohio 44094. Phone: 216/946-3200. Bud West, Inc., 3838 N. 36th Ave., Phoenix, Arizona 85019. Phone: 602/269-3151.



Write for clear-cut facts on the new Bud plexiglass doors.

Dependability. BUD

Circle 192 on reader service card

Sprague-Goodman. The first and last name for trimmer capacitors.



PISTONCAP®/CERAMIC/FILMTRIM™/MICA

At Sprague-Goodman we specialize in trimmer capacitors. They're our only business. So we offer prompt service and off-the-shelf delivery of our full line of catalog parts. From multi-turn tubular Pistoncaps® in glass or quartz, thru ceramic single turn and Filmtrim™ plastic single turn, to our new Mica compression line.

Our comprehensive line of trimmer capacitors deliver reliability at competitive prices, and our staff is always available for custom designing to your needs.

So the next time trimmer capacitors are called for, call us or your distributor and ask for them by name...Sprague-Goodman.

SPRAGUE GOODMAN **Sprague-Goodman Electronics, Inc.**
(An Affiliate of the Sprague Electric Company)
134 FULTON AVE., GARDEN CITY PARK, N.Y. 11040 • 516-746-1385 • TLX: 14-4533

New products



deal of time on learning how they run. Now, for all those firms making audio-band equipment, from operational amplifiers to active filters and consumer sound gear, there's Krohn-Hite Corp.'s model 6800 automatic distortion analyzer. The instrument measures percent total harmonic distortion (THD) quickly and accurately and does not require the skills of a piano player to operate.

Further, the price is right at what, for this market, is a very low $1,500.

The 6800's front panel is simple compared with those of competing units. There is a 3½-digit planar plasma display and, nearby, a mode switch with one position for ac-voltage measurements and a second for distortion analysis. The only other important control is a set of push buttons for frequency-band selection.

Unlike most competing units, the 6800 is fully automated. Some analyzers require that parameters like amplitude, frequency, and phase be set manually; others automate one or two of these functions. The 6800 manages everything.

Its "autonull" circuitry homes in on the frequency of the test signal and matches it in phase by using a twin-T circuit built with photosensitive resistors, switched capacitors, and—to complete the loop—light-emitting diodes to control the resistors. Amplitude, also, is a hands-off parameter. The 6800 accepts inputs from as low as 100 mV to as high as 130 V. Using a combination of dropping resistors and variable-gain amplifiers, the 6800 amplifies or attenuates the input until it reaches the unit's 2.7-V internal working level.

Thus about all that the user need do is select the gross band of interest from among the following: 1–10 Hz, 10–100 Hz, 100–1,000 Hz, 1 kHz–

It's no coincidence that Murata-Georgia is the fastest growing ceramic capacitor manufacturer in the U.S.A.



In 1973, we made a decision: Murata-Georgia would create an unsurpassed ceramic capacitor capability and we'd do it fast. We're well on our way. Since 1974, our Rockmart, Georgia plant, already one of the most automated ceramic disc facilities in the world, has been expanded four times. We're presently building a completely automated plant to meet the unprecedented demand for monolithic glass, epoxy and chip capacitors in Douglasville, Georgia. Our corporate headquarters in Marietta, Georgia ties it all together with one of the most sophisticated data processing systems in the industry for inventory control and customer service.

Combine Murata-Georgia's rapidly expanding production capability with a line of ceramic discs, monolithics and high voltage units based on over 30 years of ceramic capacitor experience, and it's easy to understand why Murata-Georgia is the fastest growing manufacturer in the field.

Coincidence? Not on your life. We've planned it that way.

muRata-Georgia

MURATA CORPORATION OF AMERICA
1148 Franklin Road, S.E.
Marietta, Georgia 30067
Phone: 404-952-9777

ceramic capacitors, subminiature potentiometers, piezoelectric ceramic filters, resonators and transducers, resistor networks. Posistor® PTC thermistors

56 ways to break an old habit.

You need enclosures. You go to a fabricator across town. They'll make some metal "boxes". You may have to guide them. You may get sporadic delivery and maybe their "boxes" are sometimes off the mark in size, color, quality. But you live with it because you've always done it that way.
There's a better way. Bud. Bud standard enclosures: small, medium, large; 56 styles, 326 sizes. The broadest line of standard enclosures in the industry. Available from any one of 325 stocking distributors.

We're the industry's largest. Why? The people we deal with realize the value of a dollar. The value they get from Bud. Get our catalog and with it, a choice for a change. Bud Industries, Inc., 4605 E. 355th St., Willoughby, Ohio 44094. Phone: 216/946-3200. Bud West, Inc., 3838 N. 36th Ave., Phoenix, Arizona 85019. Phone: 602/269-3151.



Our racks come in eight designs, 81 sizes, 19 colors. Shipped fully assembled. And they're in stock.

Value. BUD

Circle 190 on reader service card

Amazing AIRBRASIVE® "Wonder Tool"

It can cut or etch. Or strip and clean. Or drill and deflash. Amazing!

Try it. You'll wonder why you waited so long. You'll see why the versatile S.S. White Airbrasive tool is *the* low cost production tool for precision work on small electronic parts and components. It works on metals or glass, quartz or ceramics, the most delicate-to-handle semiconductor and crystalline materials. Airbrasive's stream of micro-abrasive particles gives you cool, shockless jet machining to the most critical tolerances. And at real savings in production time *and* labor costs.
Wonder how much Airbrasive costs? Just $1015 for Model K — ideal for lab work, pilot runs, and similar light-duty, limited production. Model H, at $2050, can deliver jet-machined production parts in high-volume to meet your most demanding production schedule.
Write for our illustrated brochure today. Or arrange for a demo and try the Airbrasive Wonder Tool on your parts. Write or call Jim McDonald, S.S. White Industrial Products, Pennwalt Corp., 151 Old New Brunswick Road, Piscataway, NJ 08854 (201) 752-8300.

®Trademark of Pennwalt Corporation

S.S.WHITE INDUSTRIAL PRODUCTS
PENNWALT
EQUIPMENT ■ CHEMICALS
HEALTH PRODUCTS

Precise and shockless enough to cut intricate patterns in an eggshell.

New products

10 kHz, or 10 kHz–110 kHz. If an input is outside the preset range, the digital display will flash until the operator presses the correct range button.

The display reads THD directly in percentage with resolution to 0.001%. Actual distortion measurement capability is close to this figure, but K-H spokesmen are sticking with an admittedly conservative specification: 0.005% residual distortion.

Because the effects of noise, hum, and electromognetic interference are very great when measuring such small amounts of distortion, K-H has included a pair of filters. A high-pass filter rolls off low-frequency artifacts like hum and noise at 12 dB per octave below 1,000 Hz and is typical of the instrument breed. Atypical is the 6800's low-pass filter that tracks the input fundamental frequency and rolls off information above its fifth harmonic at 6 dB per octave; this is an automated feature once switched in.

The 6800 also functions as an ac voltmeter with a frequency range that extends from 110 kHz all the way down to 1 Hz. As in the analyzer mode, the voltmeter works with voltages from 100 mV to 130 V rms. Measurement uncertainty is ±(2% of reading + 1 count) for voltages between 1 V and 130 V, regardless of frequency. For voltages of 100 mV to 1 V, measurement uncertainty above 40 kHz increases to ±(2% of reading + 3 counts). Below 40 kHz, the accuracy is the same as for the higher voltages.

The input impedance of the 6800 is fixed, regardless of mode: 110 kΩ shunted by less than 100 pF.

The 6800's $1,500 price cannot include everything. One of the things it excludes is a multifrequency oscillator. The oscillator in the Krohn-Hite instrument is a fixed-frequency unit that runs at 1 kHz with no more than 0.001% distortion. It is supplied mainly for system test and calibration. However, because so many audio measurements are referred to 1 kHz, it turns out that the built-in oscillator is all that many users will need. For those who really need

Aromat Amber Relays

solve PC board cleaning problems.

Aromat's leak-free Amber Relays are N_2 gas-filled and sealed in plastic so they're simple to clean with most degreasers and detergent cleaners, without affecting the maximum contact reliability of the relays.

In addition, Aromat's vacuum annealing production process completely outgasses all plastic parts, thereby completely eliminating any possible contact contamination.

Aromat can help you substantially reduce your labor costs! Just use Aromat Amber Relays on your PC board in conjunction with automatic wave soldering.

The total savings are even greater when you use Aromat Amber Relays. Aromat Amber Relay prices are right in line with standard non-seal types.

Aromat Amber Relays. When you want maximum reliability and maximum savings. And only Aromat makes them.

Series	Contact Form	Rating	Style	Size
RS	1 Form C	1 Amp	Half size	(.787Lx.394Wx.394H)
NF2E	2 Form C	2 Amp	Flat pack	(1.165Lx.772Wx.425H)
NF4E	4 Form C	2 Amp	Flat pack	(1.165Lx.953Wx.425H)
K2E	2 Form C	2 Amp	Cradle type	(.929Lx.748Wx1.181H)
K4E	4 Form C	2 Amp	Cradle type	(1.157Lx.748Wx1.181H)
K6E	6 Form C	2 Amp	Cradle type	(1.370Lx.748Wx1.181H)
HC1E	1 Form C	5 Amp	General purpose	(1.097Lx.827Wx1.280H)
HC2E	2 Form C	3 Amp	General purpose	(1.097Lx.827Wx1.280H)
HC4E	4 Form C	2 Amp	General purpose	(1.097Lx.827Wx1.280H)

Relays for Advanced Technology

68

Contact Your Aromat Representative or Distributor Today.

Aromat Corporation:
250 Sheffield Street
Mountainside, NJ 07092
(201) 232-4260

Mid-Western Office:
311 Lively Blvd.
Suite 1
Elk Grove Village, IL 60007
(312) 593-8535

Western Office:
10400 North Tantau Avenue
Cupertino, CA 95014
(408) 446-5000

Aromat
Member of Matsushita Group

Circle 195 on reader service card

ELORG FERRITE DEVICES WILL NEVER LET YOU DOWN UNDER WIDE AMBIENT TEMPERATURE VARIATIONS HIGH HUMIDITY VIBRATION SINGLE OR REPEATED IMPACTS

Ring magnets of "3.1 BA" Grade ferrite for moving-coil speakers:

- minimum residual induction 0.38 T (3,800 Gs)
- minimum induction coercive force 167 kA/m (2,100 Oe)
- minimum magnetizing coercive force 171 kA/m (2,100 Oe)
- maximum specific magnetic energy 12.3 kJ/m³ (3.1 MGs²Oe)

Magnet standard size	Dimensions with tolerance, mm Outside dia.	Internal dia.	Axial length
K45 x 22 x 10.5	45±1	22±0.6	10.5±0.1
K51 x 24 x 9	51±1.2	24±0.6	9±0.1
K56 x 24 x 12	56±1.2	24±0.6	12±0.1
K56 x 24 x 8	56±1.2	24±0.6	8±0.1
K61 x 24 x 8	61±1.5	24±0.6	8±0.1
K61 x 24 x 13	61±1.5	24±0.6	13±0.1
K72 x 32 x 10	72±1.5	32±0.7	10±0.1
K72 x 32 x 15	72±1.5	32±0.7	15±0.1
K86 x 32 x 10.8	86±1.5	32±0.8	10.8±0.1

Antenna cores
E-shaped, U-shaped, ring and pot cores
Yoke cores for deflection systems

Sole exporter –

ELORG

32/34 Smolenskaya-Sennaya
121200 Moscow
USSR
Telephone 251-39-46, Telex 7586

multifrequency operation, the company recommends its 4000 series broadband oscillators.

Small in price, the 6800 is also light in weight—only 10 lb, or a tenth the weight of some competitive units. It is also light on power consumption, requiring a mere 15 W.

Delivery time is 30 days.

Krohn-Hite Corp., Avon Industrial Park, Bodwell Street, Avon, Mass. 02322. [418]

Handheld meter race gets tighter

It's beginning to look like a track meet in the 3½-digit handheld multimeter market. Fluke's $169 8020A was challenged recently by Data Precision's look-alike model 935 [*Electronics*, Feb. 1, 1979, p. 150], which is priced at $149 and by Beckman Instruments' $130 model 3010 and $170 model 3020 [*Electronics*, March 15, 1979, p. 168]. Now, Fluke plans to use Electro79 to vault back into contention with its $129 model 8022A.

With this new meter, Fluke is trying to catch the competition between its improved 8020A and the new instrument. "We're using higher-precision references and input dividers in the 8020A now," says Charles B. Newcombe, product marketing manager, "and it now matches the 0.1% accuracy spec of the 935 and the 3020." Other added



NEW DEVELOPMENT

Semikron introduces the rectifier assembly

the maximum in cost-efficiency, reliability and flexibility

Semikron, the industry leader in innovative design of semiconductors for the past 28 years, introduces another first — the first rectifier assembly with unlimited flexibility. The adaptation of our SEMIPACK® power module to this concept achieves a dual objective — cost-effectiveness and genuine reliability.



The inherent design of the SEMIPACK® provides complete electrical isolation of the components within its configuration and permits . . . simple assembly of modules on a common housing . . . muliple housing assemblies on a common heat sink and . . . simplified electrical connections.

Basic features of the rectifier assembly:

- Highly cost-effective — saves assembly time.
- Compact configuration — saves space.
- Permits larger power handling (from 4 to 150Kw, from 20 to 320A).
- Provides for greater heat dissipation — eliminates cooling problems.
- Chances for error in circuit interconnection are minimal.
- Eliminates drilling and tapping.

Technical information available on request. Call or write today, Tel: 603 883-8102.

Semikron's basic products include thyristors and diodes from 1 to 1000A to frequencies of 10KHz; SEMIPACK electrically isolated power modules; small and medium power bridges, half controlled bridges, avalanche bridges and doublers.

SEMIKRON INTERNATIONAL INC.

11 Executive Dr. / P.O. Box 83, Hudson, N.H. 03051

'See us in Booth 2608, Electro '79'

Circle 197 on reader service card

Delevan Power Chokes

...strike the perfect balance

Our Series 3443 molded power inductors offer the optimum design balance in switching regulator systems. They combine low unit cost with the high reliability of a molded configuration.

Rugged construction with heavy 18 gauge molded-in solder-coated radial terminals . . . ideal for printed circuit board applications.

A broad spectrum of standard inductance values ranges from 1.0 to 15,000 μH. Current ratings up to 10 Amp.

Delevan molded power chokes reduce ripple transients . . . reduce incremental current effects at a lower cost than conventional toroid design. Inductance values will not change more than 10% with up to 70% of rated current.

TYPICAL APPLICATIONS
- Switching regulator power supplies
- DC to DC converters
- Suppression and decoupling chokes

Get the details for your application. Ask for Data Sheet 3443.

Delevan Division — AMERICAN PRECISION INDUSTRIES INC.

270 QUAKER RD., EAST AURORA, N.Y. 14052
TELEPHONE 716/652/3600 TELEX 91-293

OTHER DIVISIONS & SUBSIDIARIES INCLUDE:
APITRON, BASCO, DUSTEX, AMERICAN PRECISION INDUSTRIES (U.K.) LTD., DUSTEX OF CANADA, INC.

features include an extra year's warranty (two years now) and the carrying case (formerly a $10 option).

The 8022A does not have the unusual conductance mode of the 8020A, nor does it match the improved meter's accuracy. It does have five functions: ac and dc voltage to 2,000 V, ac and dc current to 2 A, and resistance to 20 MΩ. Its basic dc-voltage–measurement uncertainty is ±(0.25% of reading + 1 count) and its ac bandwidth is 450 Hz (compared to 5 kHz for the 8020A model).

Low-power operation in the 8022A is provided by both its custom complementary-metal-oxide-semiconductor circuit and its liquid-crystal display. Because these components consume little power, the meter can operate for up to 150 hours on an ordinary 9-V battery or 200 hours using an alkaline battery. (The Beckman units, however, get 2,000 hours from the same size and type power sources.)

Reliability is enhanced by the meter's small number of parts (only 47) and its built-in overload protection. The instrument can safely withstand overloads of 1,000 V in its voltage modes, 500 V in its resistance mode, and 2 A in its current modes.

Both the 8022A and the new version of the 8020A will be available with 30-day delivery times.

John Fluke Manufacturing Co., P. O. Box 43210, Mountlake Terrace, Wash. 98043 [419]

Single-step board speeds debugging

Debugging systems built with Mostek's Micro Design series (MD) series of inexpensive microcomputer boards will be faster with the latest addition to the Z80-based line.

Designed for use with the line's MDX-CPU1 and MDX-DEBUG boards, the new MDX-SST will allow users to step through programs one instruction at a time and display the

WHY NOT USE A 30 MHz FUNCTION GENERATOR FOR YOUR AM/FM REQUIREMENTS?





1. **30 MHz Top Frequency** for standard sine, square, triangle, and pulse waveforms.



2. **Variable Phase Control** permits varying the start/stop point 180° in trigger, gate, pulse, and burst modes.



3. **Amplitude Modulation** from 0% through 100% to double-sideband suppressed-carrier using AM Level and Carrier Level.



4. **Multi-waveform AUX** generator provides square, triangle, and sine AM/FM modulating frequencies variable up to 1 MHz.



5. **Variable Symmetry** Control allows symmetry ratio adjustment from 19:1 to 1:19. Great for linear sweeping.

more reasons why the Exact Model 739 is the most AM/FM function generator ever sold.

TWO GENERATORS IN ONE. The Model 739 is two complete and separate generators in one box. Both generate sine, square, and triangle waveforms. The Main generator frequency range is 0.0001 Hz to 30 MHz. The AUX generator frequency range is 0.01 Hz to 1 MHz.

WIDE BANDWIDTH. The carrier can be frequency modulated by the AUX generator over a 3 decade frequency band. It can also be swept over a 1000:1 range manually, or with an external or internal ramp.

INTERNAL AM/FM SOURCE. The AUX generator can frequency modulate, sweep, gate, trigger, or amplitude modulate the Main generator. It can also amplitude modulate an external carrier. The AM modulation is adjustable from 0% through 100% to double-sideband suppressed-carrier.

TRIGGER/GATE (Internal and External). The Main generator can be triggered (single cycle) or gated (multiple cycles) either manually or by an external signal when GATE or TRIG modes are selected. The AUX generator is internally connected to gate or trigger the Main generator when BURST or PULSE modes are selected.

VARIABLE SYMMETRY. Variable symmetry controls for each generator allow the symmetry of the selected waveform to be varied from 19:1 to 1:19. When the AUX generator is internally connected to the Main generator, this provides linear frequency sweeping at a rate 19 times the retrace time.

SIMULTANEOUS AM/FM. The Model 739 provides increased flexibility by allowing simultaneous amplitude and frequency modulation. Examples are: AM/frequency shift keying using squarewave modulation, linear AM/FM using triangle or ramp modulation, and sinusoidal AM/FM using sinewave modulation.

SEPARATE AM, FM, AND CARRIER LEVELS. The Model 739 has separate level controls for FM width, AM carrier, and AM modulation. The 30 V P-P open circuit (15V P-P into 50Ω) output can be attenuated up to 80 dB. 60 dB is in fixed 10 dB steps and a variable amplitude control provides 20 dB. The modulation percentage is not affected by the attenuator settings. Approximately 40 dB additional attenuation is available by using the carrier level control when in the AM mode.

RUGGED ALL-METAL CASE. Die castings, extrusions and sheet aluminum combine to make a rugged instrument 43 cm wide, 13 cm high, and 35 cm deep. With the optional rack mounts it uses only 5¼" of vertical space in a standard 19 inch RETMA rack.

PRICED RIGHT. Compare all of these Model 739 features with those of any other combination AM/FM function generator available today. Then compare the price of the Model 739 at *$1295.00 FOB Tillamook, Oregon. There is no contest!

*Domestic U.S.A. price only

BOX 347 TILLAMOOK, OR
97141 Tel. (503) 842-8441
TWX 510-590-0918
EXACT electronics, inc.

Circle 199 on reader service card 199

HOT
OFF THE PRESS

GE Quick-rental instruments catalog

AND READY FOR YOUR USE

Now! Our all-new Rental Catalog is your handy-indexed ready reference to more than 15,000 test instruments.

- Recorders—scopes—meters—hi-pots plus many unique and hard-to-find instruments.
- Top makes & models from all the leading manufacturers—Gould Brush, Biddle, Esterline Angus, Fluke, GenRad, Hewlett-Packard, Honeywell, Tektronix, etc.
- Order your FREE copy today!

General Electric Company
Instrumentation and Communication
Equipment Service
Manager—Rental Services
1 River Road, Building 6, Room 328
Schenectady, N.Y. 12345

GENERAL ELECTRIC

contents of all the CPU1's registers after each instruction. Under keyboard control, the SST employs the CPU1's nonmaskable interrupt and DEBUG-resident firmware to supply users with enhanced debugging capabilities.

With the SST, users may specify a number of instructions to be stepped and the starting location in the program. All 18 of the CPU1's 8-bit registers and its four 16-bit registers can be displayed or printed out after each instruction cycle.

Like other cards in the low-priced series, the SST measures 4.5 by 6.5 in. and slips into the STD-Z80 bus designed jointly by Mostek and Pro-Log. Mostek expects that it will be used most frequently with the MDX-



PROTO, a prototyping package that includes the CPU1, DEBUG, DRAM8 (an 8-K-by-8-bit dynamic-memory board), and card cage.

With a $1,095, single-quantity price, the PROTO package is offered primarily as a low-cost tool for hardware and software evaluation, says Harold Webb, microcomputer systems manager. Development work is possible with the PROTO kit alone; the DEBUG board contains a 10-kilobyte software package in read-only memory with assembler, text editor, loader, and debugger. So as Webb explains, "We saw fit to

Circle 143 on reader service card

Why fool around?

Our Snap-Lock makes your tough little connector decisions easy. It's the rugged, make-sure miniature circular connector to call for when you just don't want to fool around.

It has the right quality features: metal housing, high contact density, moisture-proof, can be pressure resistant and/or hermetically sealed.

And you can choose from enough sizes and options to make designing-in Snap-Lock as easy as it is dependable: 2 to 19 contacts, reversible, and crimp removable or soldered — plus a variety of mounting styles, back shells and potting boots.

Positive, vibration-proof locking. You can hear it snap into place. It won't shake loose. But release is easy with a squeeze of the metal ring.

Need a quick, pull-the-cable disconnect? We have it: Pull-Lock. Friction holds the connector together, but a firm yank on the cable pulls it apart.

For all the details... They're in our new Snap-Lock catalog. It's just off the press, with all the latest specs. Send for your free copy.

O.K. Send me your latest Viking Snap-Lock miniature circular connector catalog.

MY APPLICATION: _____

NAME: _____

TITLE: _____

COMPANY: _____

ADDRESS: _____

CITY: _____ STATE: _____ ZIP: _____

Viking CONNECTORS

21001 Nordhoff Street, Chatsworth, CA, U.S.A./(213) 341-4330

This is DigiTec's NEW, low cost, alphanumeric, desk top printer.



(6410 Printer actual size: 7½" W x 5⅜" D x 2⅞" H, Weight: 3½ Lb.)

We've opened a whole new world of printer applications to both the OEM and end user.
A built-in, one chip microprocessor provides the simplest possible interfacing. Just plug into the standard EIA connector.
You read first line-up . . . just like a book, its electric writing is quiet enough to use in a library, and it's designer-styled to look good in any environment.

It's the **Lowest Priced** Printer at **$295.** (in OEM quantities)

DigiTec. UNITED SYSTEMS CORPORATION

DIGITEC: Precision measurements to count on.

918 Woodley Road, Dayton, Ohio 45403
(513) 254-6251, TWX (810) 459-1728

Information Only Circle #149

Demonstration Only Circle #160

enhance the PROTO by introducing the SST to take advantage of existing firmware."

For really extensive development projects, Webb recommends the dual-disk AID-80F program development system. But for smaller tasks he foresees the PROTO-SST combination as providing a fast solution.

The MDX-SST is available now at a price of $150 in single quantities and $100 in lots of 100 or more.

Mostek Corp., 1215 Crosby Rd., Carrollton, Texas 75006. Phone (214) 242-0444 [420]

Cinch gets into flat-cable market

The crowded market for flat-cable connector systems gains a new competitor this month with the introduction of TRW Cinch Connectors' new three-part system. Grid socket connectors, pin headers, and dual in-line package (DIP) plugs from TRW "basically look just like the others," concedes a TRW official, but the company is counting on its worldwide distribution chain to become an off-the-shelf supplier of the connectors. Prices will range from 60 cents to $2 depending on the exact size of the connector.

Seven sizes of grid socket connectors are available, and strain relief is an option. Up to 50 terminations are possible, with two contact points per position. With locking latches in the cover, the socket connectors can be compact in design: connector spacing is 0.250 in.

Six-pin headers for interconnecting printed-circuit boards with flat-cable sockets are available in straight and right-angle configurations, with two solder tail lengths (0.092 or 0.155 in.) and a 0.610-in wire-wrap tail. Four DIP plugs can be either permanently soldered to a printed-circuit board or inserted into standard integrated-circuit sockets. Delivery time for the products is six to eight weeks.

TRW Cinch Connectors/Electronic Components Division of TRW Inc., 1501 Morse Ave., Elk Grove Village, Il. 60007 [339]

"For the Price of This Handler, You Can't Afford to Test ICs Manually!"



Model 2608M
8,500 DPH
Expanded Input
DIP Handler



Model 2608
10,000 DPH
DIP Handler



Model 2608E
7,000 DPH
Elevated Temperature DIP Handler

. . . It's MCT's Model 2604

Why test ICs manually when we make efficient, reliable automatic DIP handling available at such a reasonable price?

Our MCT* Model 2604 is the DIP handler designed and priced for users cycling a moderate volume of devices. Its 5000 DPH speed and four-track output assure efficient throughput for normal operation as well as peak load conditions. Its low price generates a fast return on investment even if your work load only requires that you run your handler part time.

The Model 2604 offers the ruggedness of more expensive handlers at a reasonable price. Its quality components, wear-resistant materials, long contact life, and 'leads up' handling of devices reduce downtime and insure trouble-free operation. The Model 2604's proven reliability means that it will be earning its keep long after other handlers are down for repair.

The Model 2604 is just one of our many fine IC handlers. It is fully supported with installation, service and operator training programs. Find out for yourself why we're the leader in IC handling equipment.

For more information on the Model 2604, contact Micro Component Technology, Inc., P.O. Box 43013, St. Paul, MN 55164 or call (612) 482-5170.

MCT™

*MCT is a trademark of Micro Component Technology, Inc.

Circle 150 on reader service card 203

If you go one place for automatic test equipment and someplace else for applications software, where do you go for support?



What happens if the company you pick for your manufacturing test hardware can't back you up when you need programming help?

What happens is that you have to turn to *another* supplier. Which means you lose time—and end up with the problem of figuring out exactly who's responsible for what.

With GenRad, no such problem.

We've built the world's leading automatic test equipment company on the idea that you should be able to get hardware, software, and support from a single source.

Us.

So besides giving you the most advanced technology in both electronic and mechanical test products, we give you the industry's strongest back-up. Including our one-of-a-kind Custom Programming Group—a team of full-time applications specialists ready to offload your programmers whenever you get into a jam.

And if we pay this much attention to a service you'll rarely need, imagine what we put into the type of support you'll use more often: systems consultants, field applications engineers, training experts, a software support group, and a worldwide network of service and repair personnel. Nobody else has that depth of commitment. In fact, nobody even comes close.

GenRad.

One reason we sell more automatic board test and mechanical test systems than anyone else is that we put more behind them.

For our free booklet, "The Automatic Solution to Manufacturing Test," call toll-free 800-225-7335 (in Mass. 617-779-2825), or write GenRad, Concord, MA 01742.

GenRad 2230 Component Test System allows rapid testing of components and hybrid circuits.

GenRad

Put our leadership to the test.

Circle 152 on reader service card

With Multiwire, startups come fast.



®Multiwire is a U.S. registered tradename of Kollmorgen Corporation

Product life cycles are shrinking dramatically. Every design phase must be shortened drastically.

Under such pressures, Multiwire® is a far better high-density system for interconnection than multilayer to have on your side. As we will note, it has advantages over wirewrapping, also.

With Multiwire, startups come much faster. Multiwire board design requires power and ground artwork only. It eliminates all the steps in creating multilayer board artwork.

Development of Multiwire wiring paths is fully computerized. Beginning with your point-to-point interconnection list, Multiwire software programs do all the wire routing. You get fast, early documentation of the design from actual-size graphic printouts showing all wiring paths and connections.

The same software package generates the magnetic disk that controls our Multiwire machines. As a result, the manufacturing cycle is fully defined the moment you approve your graphic printout.

Multiwire machines lay down extremely dense patterns of insulated wire with precise line spacing between lines and between cross-overs. Your chance for malfunction of boards because of unpredictable manufacturing problems is virtually nil.

With multilayer, you've got to wait.



What about design changes? Most wires are accessible in the typical Multiwire board, so circuit paths can be interrupted and new paths patched in by hand in minutes. Opportunities for doing this with success are far less in multilayer.

Making new boards with changes is extremely fast with Multiwire. There's no wiring artwork to correct or start from scratch. We simply input your changes into the computerized net list. Computers do the rest.

Compared with wirewrapping, Multiwire boards are, of course, much thinner. Wirewrapping is typically used for prototyping before multilayer production, leading to switchover problems, Multiwire is both a prototype and production system.

Multiwire also has significant advantages over larger complex two-sided printed boards. Too often, the routing paths on these printed boards can't match the component loading. Not so with Multiwire. Its inherent ability to crossover solves the routing problem.

Multiwire is proven as the way to meet the time pressures of today. And you will get a pleasant bonus. Because your time frame to start up can be condensed by Multiwire, your development costs will be lowered.

To provide you with even faster service, Multiwire manufacturing centers are now on each coast.

Our new Multiwire guide will show you how easy it is to use Multiwire. For more information and location nearest you contact Multiwire, 31 Sea Cliff Ave., Glen Cove, NY 11542, (516) 448-1307

MULTIWIRE

Circle 154 on reader service card

It has come to our attention that some designers are still using discrete EMI/RFI filters



And that's a shame.

Because Cannon® connectors with integral filter contacts save as much as 75% on space and weight. Increase system reliability. And can cut your total installed costs by 40% and more.

Filter connectors from ITT Cannon Electric are available in rectangular and circular, miniature and subminiature configurations. To meet commercial, ARINC and MIL specifications. For computers and communications systems, medical and test instrumentation, aerospace and automotive applications.



Computer I/O filters

Filtering is available on all or any contacts within the connector. A ferrite tube surrounding the contact forms a series inductor within a concentric, selectively-coated ceramic tube which forms the capacitors of a pi-filter.



Completed connectors, like the computer I/O configuration shown, aren't much larger than the standard connector, yet provide typical attenuation of 70 dB. They eliminate the components, wires and "dog box" that you've had to deal with, and all the engineering, assembly and testing that go with them.

And Cannon filter connectors can reduce your total installed costs by 40% or more. Now that you know, there's no excuse not to use them, so contact your nearest ITT Cannon field office today.

ITT Cannon Electric, International Telephone and Telegraph Corporation, 2801 Air Lane, Phoenix, AZ 85036, telephone (602) 275-4792.



CANNON ITT

Six decades on the leading edge of interconnect technology.

Array of hope for slow computers

38-bit array processor can perform up to 8 million operations per second in floating-point format, is aimed at original-equipment manufacturers

by Robert Brownstein, San Francisco regional bureau

By taking advantage of technologies developed since the advent of its first machines, Floating Point's designers have fashioned a system that is half the size, uses half the power, but has roughly the same computational performance as a low-end 333-ns memory version AP-120B. It is only to be marketed in original-equipment manufacture quantities, and as such does not replace the AP-120B, which is available in singles and small quantities.

The FPS-100 is aimed at those who put together systems for such applications as radar signal analysis or flight simulation, says James Strelcham, product marketing manager for the company. By employing low-power Schottky medium-scale integrated devices, its designers cut the power to about 1 kW, half that of the AP-120B. By using large-scale integrated memory chips and four state-of-the-art very large-scale integrated multiplier chips, the size was cut (to half that of an AP-120B) and the price set at $18,000 for quantities of 50 of the basic configuration system.

Like its first two machines, Floating Point's new box derives its number-crunching clout from a network of 38-bit-wide data paths linking a separate floating-point multiplier with a floating-point adder so that they can perform their functions simultaneously. An independent 16-bit integer-control arithmetic and logic unit deals with address calculations and program indexing, freeing the floating-point hardware to handle its programmed computations.

Conventional 32-bit minicomputer word length is only capable of resolving six decimal digits and has a dynamic range of only $10^{\pm 38}$. On the other hand, the FPS-100's 38-bit data words allow it to resolve eight decimal digits with a dynamic range of $10^{\pm 153}$.

Its 64-bit instruction word is broken down into 10 control fields so that as many as 10 operations can occur during an instruction cycle. With its 4-MHz clock, the FPS-100 fires off its synchronous machine cycles at 250-ns intervals for a throughput potential of 8 million floating-point operations per second.

Whereas lower power dissipation is gained by extensive use of low-power Schottky MSI devices, a significant reduction in parts count was achieved in the floating-point hardware by using TRW's VLSI 16 × 16 multiplier chip, the MPY-16. "It allowed us to reduce to 4 chips what would ordinarily have required 96 chips to implement," says Paul Wiley, product specialist.

Metal-oxide-semiconductor random-access memories are used for the main data memory, which can be expanded from 8-K to 16-K, 32-K or 64-K 38-bit words. For sizes up to 32-K words, a 16-kilobit RAM is practical, but at 64-K it becomes unwieldy. The designers solved the problem by using Mostek's 4332, a 16-kilobit-sized package that contains two 16-kilobit dice for a total of 32 kilobits each. Thus memory of any size up to 64-K 38-bit words can be fit on one plug-in printed-circuit board.

There are three approaches to using an FPS-100. Computational subroutines can be called up in Fortran IV by the host—a simple



You get a much better performance when the maestro is a SHARP SM-4.



Low power consuming 4-bit one chip C-MOS microcomputer for direct interface with Liquid Crystal Displays (accurate time control with crystal oscillator)

Our little SM-4 delivers a perfectly-orchestrated performance from all kinds of instruments—from calculators to vending machines. And it's not only versatile, it consumes very little energy. Since it contains high RAM/ROM capacities, static shift register, 15-stage divider and other peripheral circuits on one chip, it can be mass produced at a substantial reduction in cost. So at Sharp, we've already put our little semiconductor to work directing the operation of such products as our electronic tape processor and clock-calculators. So look over the numbers behind the SM-4 performance. We think you'll like this little maestro so much you'll end up asking for encores.



ROM capacity	2268 bytes x 8 bits
RAM capacity	96 words x 4 bits
Instructions	54
Subroutine level	1 level
Input port	6 bits
Output port	41 bits
Input/output port	4 bits
Divider	15-stage divider with reset
Drive circuit	LCD internal drive circuit (external RAM drive)
Others	Internal crystal oscillation circuit, internal low voltage detection circuit, single power supply (—3V Typ.), 60-pin quad package



System Construction.

Applications
- Clock-calculators
- Programmable remote controls
- Programmable digital timers
- Programmable timing systems
- Multi-function telephone sets
- Cameras, etc.

For further information, write to:
Mr. Nobukazu Yagi, Sales Representative
SHARP ELECTRONICS CORPORATION
10 Keystone Place
Paramus, New Jersey 07652

SHARP

210 Circle 165 on reader service card

New products

procedure, but the least efficient because of the need for repeated communication between array processor and host. The user can purchase the optional Fortran compiler and write his own high-level programs which are then converted to assembly language—a more efficient scheme. Those users who must have the maximum throughput may work in assembly language and squeeze more of those simultaneous operations into the 64-bit words.

A Fortran software package, Apsim, allows a user to simulate the action of the FPS-100 on his host so new programs can be developed and tested without tying up the actual array processor.

In situations where input/output operations are better handled directly by the array processor than through the host, optional I/O processors can be fitted to the FPS-100. One is used for interfacing to fixed-protocol peripherals such as display terminals. The other, which is programmable, has dual processors, one for I/O control and another for format control. The latter processor features a 32-word writable control store. It converts fixed formats into floating point or one format of floating point into another; it can also be used to pack or unpack data. There are 70 formatting routines in Floating Point's routine library.

In addition, there are over 250 computational routines available from its math library. Housed in its 18-inch-wide, 10.5-inch-high and 24.4-inch-deep chassis, the FPS-100 can accommodate up to 15 plug-in boards, enough for its floating-point arithmetic unit, integer controller, all memories, plus one optional I/O processor. Extra I/O processors are housed in an expansion chassis, but the power supply in the main box can supply both, Strelchun says. Host computer interface hardware, which also fits in the main chassis, is available to link the FPS-100 with Digital Equipment Corp.'s PDP-11 systems and Data General's Nova series. First delivery of the FPS-100 is slated for last quarter of 1979.

Floating Point Systems Inc., 11000 SW 11th St., Portland, Ore. [340]

R-ohm has a better way to say RC07

R-25

Some of the world's most respected OEM's are specifying R-Ohm's R-25 Carbon Film Resistors instead of RC07 carbon composition types. Why aren't you? R-25's give you greater stability and reliability at less cost. Dimensions are the same. Every value is available and our distributors keep plenty in stock. Break out of the RC07 tradition today. Ask for R-Ohm R-25's instead. Carbon film is a better way to go.

TYPE	R-25
Equivalent MIL Style	(Meets MIL-R-11F RC07)
Wattage Rating at 70° C (158° F)	0.25W
Maximum Working Voltage	250V
Maximum Overload Voltage	500V
Resistance Tolerance	±5%(J) ±2%(G)
Resistance Range	0.5Ω to 5.6MΩ (for ±2% 10Ω to 3.3MΩ)
Temperature Range	−55° C to +155° C

Rohm
QUALITY · RELIABILITY

16931 Milliken Avenue, P.O. Box 19515, Irvine, California 92713
Telephone: (714) 546-7750. Eastern offices: (312) 843-0404.

DISTRIBUTORS

AZ Phoenix: Kachina (602) 269-6201; **CA Gardena:** Bell (714) 521-4914 (213) 321-5802; **Glendale:** Weatherford (213) 849-3451; **Irvine:** Ratel (714) 549-8611; **Los Angeles:** Western Electromotive Shepherd (213) 820-3777; **San Diego:** Shelley-Neumann (714) 453-7133; **Santa Clara:** Western Electromotive Shepherd (408) 985-0908; **Santa Monica:** Frank Shelley Electronics (714) 554-7930 (213) 871-0930; **Sunnyvale:** Bell (408) 734-8570; **CO Denver:** Integrated Electronics: (303) 534-6121; Ratel (303) 934-5813; **IL Chicago:** Bell (312) 982-9210; **Elmhurst:** Genesis (312) 530-2272; **Westmount:** RM Bodelle: (312) 323-9670; **IN Indianapolis:** RA-DIS-CO (317) 637-5571; **South Bend:** Radio Distributing (219) 287-2911; **IA Cedar Rapids:** DEECO (319) 365-7551; Iowa Tech. Supply (319) 377-5795; **KS Wichita:** Radio Supply (316) 267-5213; **MA Burlington:** RC Components (617) 273-1860; **MD Baltimore:** RESCO (301) 823-0070; **MI Wyoming:** RM Electronics (616) 531-9300; **Farmington:** Startronix (313) 477-7700; **MN Minneapolis:** Cassidy (612) 835-7746; **MO St. Louis:** Olive (314) 426-4500; **NJ Camden:** Gen. Radio Supply (609) 964-8560; **NM Albuq.:** Bell (505) 292-2700; **NY Buffalo:** Summit (716) 884-3450; **Farmingdale:** Harrison (516) 293-7990; **Rome:** Rome (315) 337-5400; **NC Raleigh:** RESCO (919) 781-5700; **OH Cincinnati:** Sheridan (513) 761-5432; **OK Tulsa:** Cybernetics (918) 627-4159; **OR Beaverton:** Parrott (503) 641-3355; **TX Dallas:** Weatherford (214) 243-1571; **WA Bellevue:** Bell (206) 747-1515; **Blaine:** MEMCO (604) 943-3552; **CANADA Vancouver:** Bowtek (604) 736-1141

A CONSTANT FORCE IN A CHANGING WORLD

Circle 211 on reader service card

ANNOUNCING THE LOW-COST 16-BIT MICROCOMPUTER, MP/100.



THIS IS HOW FAR YOUR MONEY CAN GO.

Function and economy. Those are the two reasons we packed more features in our new 16-bit microNOVA® MP/100 than anyone would have thought possible. And at a price lower than anyone would have thought possible.

Available at chip, board or box level, the MP/100 is based on the new Data General designed and manufactured 16-bit mN602 NMOS microprocessor. This is where the true functionality begins. Our single, 40-pin package includes the full NOVA® 16-bit architecture and multifunction instruction set, hardware stack and frame pointer, 16-bit multiply and divide, realtime clock, multiple addressing modes, standard and high-speed data channels (2M byte/sec), 16-level priority interrupt and dynamic RAM refresh. It's capable of supporting up to 64KB of RAM/PROM/EPROM memory in standard applications and up to 128KB in special application requiring additional memory.

The MP/100 gives you the mN602 microprocessor, an asynchronous interface with full modem control, automatic program load, power/monitor/auto restart and soft control panel all on a single 7½" x 9½" board.

All microNOVA computers are available in a compact, modular 5¼" eight-slot chassis featuring a single board power supply for increased reliability and maintainability. Plus a low cost four-slot card cage for product OEMs.

Our new 16-bit microNOVA MP/100. It can take you a long way on a small amount of money. Most important, the MP/100 is not only compatible with other members of the microNOVA family but also within the entire Data General family of NOVA and ECLIPSE computers. It's a smart way to grow.

ANNOUNCING THE HIGH PERFORMANCE 16-BIT MICROCOMPUTER, MP/200.

THIS IS HOW FAST YOU CAN GO.

Speed and performance. These are the two features that give you the power of a mini in a 16-bit microcomputer. Our new microNOVA® MP/200 is the highest performance microcomputer in the marketplace.

Offering the flexibility of product line integration at multiple levels – board, box or fully packaged system – the MP/200 features fast instruction execution times with an 0.84 microsecond ADD and a full 16-bit hardware multiply in 4.9 microseconds. Standard and high-speed data channel (DMA) provides input/output data rates of up to 3.7M bytes/second. An enhanced NOVA® instruction set featuring byte operations as well as signed and unsigned integer Multiply/Divide add to the MP/200's power.

The MP/200 is completely compatible with the MP/100 which means that all peripherals and interfaces are interchangeable. And the MP/100 and MP/200 feature the industry's broadest range of compatible field-proven software for program development and execution. Including disc and real-time operating systems and high level languages such as Business BASIC, Extended BASIC and FORTRAN IV.

Function and economy. Or, high performance. Whichever your need, you'll find the best, cost-effective answer in the MP/100 or MP/200 16-bit microNOVAs from Data General. The right fit for today with the growth for tomorrow. Send the coupon for complete information. And fast. Or call 800-225-7282 or contact your nearest Schweber or Hall-Mark distributor.

MAIL TO: microNOVA PRODUCT INFORMATION
DATA GENERAL CORPORATION
WESTBORO, MA 01581

Name_____

Title_____

Company_____ Tel No._____

Address_____

City_____ State_____ Zip_____

Data General Corporation, Westboro, MA 01581, (617) 366-8911. Data General (Canada) Ltd., Ontario, Canada. Data General Europe, 61 rue de Courcelles, Paris, France, 766.51.78. Data General Australia, (03) 89-0633. Data General Ltda., Costa Rica, Latin America, 22-79-42. Data General Middle East, Athens, Greece, 952-0557.

© Data General Corporation, 1979.

E412

Data General

We make computers that make sense.

Why Verbatim® re-invented the wheel.

Our patented "Belt Driven Floating Roller" is the key engineering design element in the TC-150. The Verbatim TC-150 offers at least ten improvements over the other design.

TC-150 mini data cartridge, shown actual size.



1. Our **unitized construction,** consisting of symmetrical shell halves, provides structural stability and the strength of advanced polymer. Construction is simpler and less expensive, yet the entire shell has thermal consistency. No differing rates of expansion to stress critical tape paths.

2. Our simplified Floating Roller design, employing fewer moving parts, **reduces variability** caused by environmental changes, age and use.

3. Our TC-150 mini data cartridge uses Verbatim's unique **gamma ferric oxide digital** tape. This special formulation has been extensively field proven to have long life and low head abrasion.

4. Each cartridge is **completely certified** after final assembly to be 100% error free before packaging.

5. Our Floating Roller design, which eliminates the unstable function characteristics of corner rollers, **improves recording quality** by producing repeatable tape tension across the read/write head.

6. Our metal-free advanced polymer shell design **resists static buildup.** A metal baseplate can cause damage from static electricity as the cartridge is inserted into the system. Synthetic carpets can build up big charges.

7. The Verbatim TC-150 mini data cartridge has a **broad operating temperature range.**

8. The tape hub material was formulated to produce a rate of thermal expansion that exactly matches the tape's. This **prevents "pack shift"** and uneven tape wear.

9. **Less power is consumed** when driving our Floating Roller cartridge because the elimination of corner rollers dramatically lessens friction.

10. Since we have **eliminated the corner rollers,** we don't need the metal baseplate which is subject to warping, dents and burrs.

Any resemblance between the Verbatim TC-150 mini data cartridge and the old fashioned 3M DC-100A and HP 9162-0061 cartridges it replaces, ends with the form factor. We completely re-engineered this useful byte-oriented data cartridge, for the good reasons noted above. You'll want to test our improvements, which happily result in a lower cost. Call any of the Verbatim distributors listed on the facing page.

Special Limited Offer: Buy a sample order of at least five Verbatim TC-150's and our distributor will give you, on delivery of your order, a coupon redeemable for one of our mini data cartridges **free.** This offer is only available through participating Verbatim distributors and is void where prohibited by law. Limit one coupon to each customer.



"Nothing on a computer isn't important."

Our distributor will also be delighted to supply you with quality Verbatim diskettes and cassettes.

Verbatim Corporation.
323 Soquel Way, Sunnyvale, CA 94086.
(408) 245-4400.
TWX: 910-339-9381.

PEOPLE WHO PLAY THE COMPUTER

Specify Verbatim®

Circle 214 on reader service card

Components

Triac driver is driven by logic

Optically coupled unit with zero-crossing detector has isolation rating of 7.5 kV

To be able to switch 115-v ac loads using a logic-level signal, with no adverse effects on nearby circuitry, has been a difficult goal to realize. Motorola's MOC3030 triac driver achieves that goal and provides a few extra features at the same time.

The device consists of an infrared-light-emitting diode optically coupled with a bilateral detector. The detector, which includes a zero-crossing sensing circuit, is a monolithic unit. Both components—the IRED and the detector—are housed in a six-pin dual in-line package.

The use of optical coupling gives the MOC3030 an input/output isolation-voltage rating of at least 7,500 v ac. A breakdown-voltage rating of at least 250 v for the output switch provides a comfortable safety margin for switching the 115-v root mean square line. At the same time, to drive most triacs, the driver circuit can deliver a gate current of 100 mA.

The zero-crossing feature prevents optical excitation from triggering the device when the instantaneous line voltage differs from zero by more than ±20 v. This not only greatly reduces electromagnetic interference, but also extends the lifetimes of certain load devices, such as incandescent lamps, by preventing sudden inrush currents.

Motorola implements its zero-crossing detector with a pair of phototransistors, each shunted by a field-effect transistor whose gate is connected to the phototransistor's collector. As a result, when the voltage on the collector exceeds the threshold voltage of the FET, the base current is shunted to ground, greatly decreasing the output signal. Consequently, the triac driver can only be triggered when the voltage across its output terminals is less than the threshold voltage of the FET—about 20 v.

The FET also acts as an active dv/dt suppression network, since it clamps much faster than most transients can rise. The MOC3030 can therefore be used in circuits with inductive loads with no need for an



Where to order Verbatim's re-invented wheel:

ARIZONA
LeBus Datacenters
(602) 277-3395
CALIFORNIA
American Word Processing
(213) 705-2245
Computer Media Products
(714) 565-7802
Devoke
(415) 494-7511
E. D. Poe & Associates
(213) 879-5881
FSI
(213) 705-4202
FSI
(714) 292-5136
FSI
(415) 321-9492
Golden State
(408) 295-9922
IDEA
(408) 732-5030
Quiet Designs
(209) 957-8631
COLORADO
Computer Ribbons
(303) 573-6284
CONNECTICUT
Associated Computer Products
(203) 261-6504
Hartford Office Supplies
(203) 525-8641
FLORIDA
American Computer Supply
(305) 442-1300
Tech-Data Corp.
(813) 577-2794
GEORGIA
Data Supplies, Inc.
(404) 449-6300
Forms & Supply Inc.
(404) 452-0620
ILLINOIS
Maggs, Ltd.
(312) 282-6966
Visible Computer Supply
(312) 377-0990
KANSAS
American Business Supplies, Inc.
(913) 492-4010
Inland Assoc.
(913) 362-2366
KENTUCKY
Appalachian Computer Supply
(606) 254-9317
LOUISIANA
Memory Products of Lafayette
(318) 235-4057
MASSACHUSETTS
A. W. Mayer Co.
(617) 965-1111
G. A. Blanco & Sons, Inc.
(413) 274-3838
(800) 628-5086
Newmar Computer Supplies
(617) 245-7960
(800) 225-4435
R. H. Sturdy Co.
(617) 235-3330
Serene & Foley
(617) 426-7087
MICHIGAN
Harold Ray Lucas
(313) 884-7602
Robert Fairbanks Associates
(313) 355-3372
MISSISSIPPI
Kuykendall Computer Supply
(601) 969-5937
NEW HAMPSHIRE
Morley Co.
(603) 436-5430
(800) 258-7113
NEW JERSEY/NEW YORK METRO AREA
CTC
(212) 594-6991
MISCO
(201) 946-3500
Technical Electronic Distributors
(201) 384-8000
Tricor Industries, Inc.
(212) 947-2221
Ventura Corp.
(516) 643-6513
NEW YORK STATE
Computer Resources Co.
(607) 748-8959
MAD Data Products
(716) 694-0044
OHIO
DAK Supply Corp.
(216) 771-2771
OKLAHOMA
Indel Davis Inc.
(918) 587-2151
Tel-Tex
(405) 840-2748
OREGON
Century Business Systems
(503) 227-3815
PENNSYLVANIA
Computer Resources Co.
(215) 439-1717
Keysto.ie Forms & Supply
(412) 341-2001
RHODE ISLAND
New England Resources
(401) 434-5650
SOUTH CAROLINA
Computer Supplies of Carolina
(803) 271-8680
TENNESSEE
Creative Software Development, Inc.
(615) 584-5105
TEXAS
CompuQuip
(713) 937-9193
Tel-Tex
(713) 526-8326
Tel-Tex
(214) 231-8077
VIRGINIA/WASHINGTON, D.C. METRO AREA
D. Owens & Associates
(703) 525-6307
Mag Systems
(703) 361-3121
Paragram Sales Co., Inc.
(703) 356-0808
Scientific Trading Inc.
(703) 560-6012
Word Processing Services, Inc.
(703) 522-9673
Word Systems
(703) 893-5777
WASHINGTON
Data Card
(206) 633-4346
Data Northwest
(206) 284-9094
CANADA
Montreal
Dyna Media Computer Products, Ltd.
(514) 739-3183
North Vancouver, B.C.
Data Marketing
(604) 986-1554
Ottawa
Dyna Media Computer Products, Ltd.
(613) 224-1687
St. John N.B.
Dyna Media Computer Products, Ltd.
(506) 693-1570
Toronto
DASCO Data Products, Ltd.
(416) 498-6990
Toronto
Dyna Media Computer Products, Ltd.
(416) 441-1595



"Buy a sample order get one free. Call your local distributor on this Liszt."

You know Hamlin reed switches Now get to know Hamlin reed relays.

Hamlin has long been Number One in reed switches. Now make Hamlin your Number One choice for PCB and dual in-line packaged reed relays.

Hamlin reed relays are hermetically sealed in epoxy with a choice of Form A, B or C contacts; diode or electrostatic shielding optional. These are available as dry reed or mercury-wetted, no-bounce operation. One mercury model permits operation in any position — a Hamlin first!

All Hamlin reed relays can be driven directly with TTL and CMOS logic and provide total isolation between input and output circuits. The epoxy encapsulation provides high vibration and shock immunity and gives total protection to the coil and contacts in hazardous environments.

For More information, write or call:
Hamlin, Inc.,
Lake & Grove Streets,
Lake Mills, WI 53551
Phone: 414/648-2361
TWX 910/260-3740



HAMLIN
INCORPORATED

1448

Circle 216 on reader service card

The magazine you're reading now, could be your own.

Drop off the routing list. Get your own fresh, unclipped copy mailed to your home or office. Turn to the subscription card in the back of the magazine. If somebody has beat you to it, write: Electronics, P.O. Box 430, Hightstown, N.J. 08520.

external snubber network.

Power dissipation for the driver is 330 mW. It comes in two versions: the 3030 requires 30 mA of IRED drive for the output to latch up; the more sensitive 3031 needs only 15 mA. Each has a holding current of 100 μA for both polarities.

In lots of 100 or more pieces, the 3030 sells for $1.80, whereas the 3031 is priced at $2.37. Samples are available now with production quantities coming in the third quarter.

Motorola Semiconductor Products Inc., P. O. Box 20912, Phoenix, Ariz. 85036. Phone (602) 244-3965 [341]

Detector and amplifier share the same can

Housed in an eight-pin TO-5 can, the UDT-455 consists of a silicon photodiode that can be connected for either photovoltaic or photoconductive operation and a monolithic operational amplifier with junction-field-effect-transistor input.

The amplifier's typical offset and input bias currents are low (3 and 30 pA, respectively), as are its offset temperature coefficient and typical offset voltage (0.5 μV/°C and 1 mV, respectively). Slew rate is a minimum of 40 V/μs.

In single quantities, the hybrid 455 costs $57 and delivery time is 30 days.

United Detector Technology Inc., 2644 30th St., Santa Monica, Calif. 90405. Phone (213) 450-8585 [345]

Avalanche rectifier ensures safe trip for microprocessors

The MR2525 is a 25-A avalanche rectifier diode designed to protect sensitive electronic circuitry such as microprocessors and memories from high-voltage surges. The device serves particularly well in automotive applications, for example, where 200-to-500-ms transients with peaks of 80 to 120 V can occur when a battery being charged by an alternator is disconnected—a situation

What is a Stackpole?



"Most important is how well your component fits in with our overall design. Can you help?"

We can. Because at Stackpole we understand the concerns of electronic design engineers. And we can help by supplying a variety of standard as well as custom components that are flexible and adaptable, for more specialized jobs.

More than just an electronics company

A half-century of component manufacturing experience has made us the world's largest producer of slide switches for commercial applications. And we produce millions of rotary, rocker and key switches annually.

Stackpole soft ferrite cores have helped electronic design engineers upgrade the quality and performance of TV sets, radios and a wide range of power supplies.

Our carbon-comp, carbon-film, industrial and special-purpose resistors, as well as our resistor networks, are integral parts of the electrical and electronic products we all use every day.

Ceramic magnetizable powders and permanent magnet materials, used in a wide variety of automotive, appliance and industrial applications, are produced by our Magnet Division.

More than just another source.

As a result of our manufacturing expertise and electronics know-how, we're capable of meeting your specific design needs. Whether your concern is switching, resistance or ferromagnetics, Stackpole has both the products and a special willingness to help solve your component and materials problems.

To learn more, call or write: Mr. Dauer Stackpole, Corporate Marketing Manager, Stackpole Carbon Company, St. Marys, Pa. 15857. Phone: (814) 781-1234.

STACKPOLE
Get to know us. We can help.

This is a Stackpole.

Circle Reader's Service Card No. 90.

LSI-11 interface . . . from MDB

GP Logic Modules ▪ Peripheral Controllers
Communications Interfaces ▪ Systems Modules
Chassis Assemblies ▪ Microprocessor Modules
Memory ▪ Power Supplies

When it comes to LSI-11 interface, MDB has it:

- ☐ General Purpose Interfaces
  - Parallel for programmed I/O **and** DMA
  - Bus foundation modules
  - Dual and quad wire wrap for any DIP design
- ☐ Device Controllers for most major manufacturer's
  - Printers
  - Card equipment
  - Paper tape equipment
  - Plotters
- ☐ Communications/Terminal Modules
  - Asynchronous
  - Asynchronous with modem/data set control
  - Synchronous
- ☐ (P)ROM Memory Modules
  - Read-only modules (without memory)
    - For 2704, 2708 and 1702 UV PROMS
    - For 5623, 5624 and 3625 PROMS and ROMS
- ☐ Chassis Assemblies
  - Backplane/Card Guide (8 quad slots)
  - Chassis Enclosure
  - Roll-Around Cabinet
- ☐ Power Supplies
  - Single, dual and triple output configurations available
- ☐ I/O Cable Assemblies

MDB interface products always equal or exceed the host manufacturer's specifications and performance for a similar interface. MDB interfaces are completely software transparent to the host computer. MDB products are competitively priced, delivery is 14 days ARO or sooner.

MDB places an unconditional one year warranty on its controllers and tested products. Replacement boards are shipped by air within twenty-four hours of notification. Our service policy is exchange and return.

MDB also supplies interface modules for PDP*-11, Data General, Interdata and IBM Series/1 computers. Product literature kits are complete with pricing.

MDB SYSTEMS INC.
1995 N. Batavia Street
Orange, California 92665
714-998-6900
TWX: 910-593-1339

* TM Digital Equipment Corp.

Circle 167 for LSI-11; 168 for PDP-11; 169 for DG; 170 for Interdata; 172 for IBM.

New products

known as a load dump.

To provide protection, the unit uses a chip of more than 38,000 square mils; previous avalanche rectifiers had chip sizes of less than 120 square mils. The greatly increased size allows the 2525 to withstand nonrepetitive forward-surge currents of up to 600 A and repetitive reverse-surge currents of 62 A. Breakdown voltage for a reverse current of 40 A (with a pulse width of 10 ms and a duty cycle of 2%) is a maximum of 40 V.

The unit is available in a stud-mounted case with standard polarity (cathode to case) or reverse polarity for $2.50 in lots of 100 or more. It also comes in an axial-lead mount priced at $2.44 in like quantities. Delivery is from stock.

Motorola Semiconductor Products Inc., P. O. Box 20912, Phoenix, Ariz. 85036. Phone (602) 244-6900 [343]

Bucket-brigade device keeps the buzz out of echos

Intended for audio and other analog signal-delay applications, the BBD3010 is a bucket-brigade device in a 14-pin dual-in-line package that introduces a noise level of only 210 μV. The unit contains two segments of 512 stages that can be combined in series to provide a delay of up to 51.2 ms or else used separately to retard signals by as little as 0.52 ms.

The unit works with clock frequencies of from 10 to 200 kHz, responds to frequencies in a wide range approximated by 0.3 times the



Unlike fabricated metal, GE Engineering Structural Foam can show a beautifully simple side plus an incredibly complex side together, in one piece.

Take the outside. In GE Engineering Structural Foam resin, the total effect is a clean, integrated, contemporary look. And it stays that way with excellent impact, heat or chemical resistance. Yet, while the outside looks like a work of art, the other side works. And works hard.

That's because GE Engineering Structural Foam is so rigid, strong and stable, it supports internal components and assemblies all by itself. Costly secondary parts, materials and operations are eliminated. What's more, GE Engineering Structural Foam is double-insulated and can meet UL 94 V-O*. Best of all, its simple one-step molding process eliminates metal's numerous, costly production steps, and its lighter weight reduces shipping costs.

For more information, write Structural Foam Resins Section 300, Plastics Division, General Electric Company, One Plastics Ave., Pittsfield, MA 01201.

Or talk to NCR, TRW and Datapoint.

GE ENGINEERING STRUCTURAL FOAM RESINS BEATS METAL WHERE IT COUNTS:

STYLING FREEDOM OUTSIDE



COST REDUCTION INSIDE.

*This rating is not intended to reflect hazards presented by this or any other material under actual fire conditions.

WHAT THE WORLD IS COMING TO: GE ENGINEERING STRUCTURAL FOAM
LEXAN® NORYL® VALOX®

GENERAL ELECTRIC

Circle 219 on reader service card

INTERNATIONAL

OE CRYSTAL OSCILLATOR ELEMENTS

International's OE series of Crystal Oscillator Elements provide a complete crystal controlled signal source. The OE units cover the range 2000 KHz to 160 MHz. The standard OE unit is designed to mount direct on a printed circuit board. Also available is printed circuit board plug-in type.

The various OE units are divided into groups by frequency and by temperature stability. Models OE-20 and OE-30 are temperature compensated units. The listed "Overall Accuracy" includes room temperature or 25° C tolerance and may be considered a maximum value rather than nominal.

All OE units are designed for 9.5 to 15 volts dc operation. The OE-20 and OE-30 require a regulated source to maintain the listed tolerance with input supply less than 12 vdc.

Prices listed include oscillator and crystal. For the plug-in type add the suffix "P" after the OE number; eg OE-1P.

OE-1, 5 and 10 can be supplied to operate at 5 vdc with reduced rf output. Specify 5 vdc when ordering.

Output — 10 dbm min. All oscillators over 66 MHz do not have frequency adjust trimmers.

Catalog	Oscillator Element Type	2000 KHz to 66 MHz	67 MHz to 139 MHz	140 MHz to 160 MHz	Overall Accuracy	25°C Tolerance
035213 035214 035215	OE-1 OE-1 OE-1	$14.24	$16.35	$20.57	±.01% −30° to +60°C	±.005%
035216 035217 035218	OE-5 OE-5 OE-5	$17.67	$20.83	$27.43	±.002% −10° to +60°C	±.0005% 2 −66MHz ±.001% 67 to 139 MHz ±.0025% 140 to 160 MHz

Catalog Number	Oscillator Element Type	4000 KHz to 20000 KHz	Overall Accuracy	25°C Tolerance
035219	OE-10	$20.83	±.0005% −10° to +60°C	Zero trimmer
035220	OE-20	$30.59	±.0005% −30° to +60°C	Zero trimmer
035221	OE-30	$63.30	±.0002% −30° to +60°C	Zero trimmer

INTERNATIONAL CRYSTAL MFG. CO., INC.
10 North Lee, Oklahoma City, Oklahoma 73102
405/236-3741

New products

clock frequency, has a signal-to-noise ratio of about 85 dB, and typically distorts signals by only 0.4%. Also typical is its 0-dB insertion loss.

The BBD3010 is the tenth in a series, extending the choice of devices to create reverberation, vibrato, chorus, double-voicing, and similar effects in electronic musical instruments, and to produce time compression and delay in voice-communication systems. In 1,000-piece lots, the units are priced at $8.95 apiece.

Panasonic Inc., One Panasonic Way, Secaucus, N. J. 07094. Phone Bill Bottari at (201) 348-7276 [346]

Op amp plus transistors equals 20-W output

By adding power transistors to a 741C operational amplifier, designers of the PA-011 have come up with a bidirectional class-B linear-power amplifier providing a peak power of 20 W for 10 seconds working from a ±24-V supply. The amplifier can deliver 1 A, peak power, and 5 W continuously.

The PA-011 has a maximum absolute differential voltage of ±30 V dc and a maximum common-mode voltage of ±12 V dc. Its common-mode rejection is 90 dB, its input-offset temperature coefficient is 6 μV/°C, and its input bias current is 0.5 μA. Differential and common-mode impedances for the PA-011 are 300 kΩ and 2 MΩ, respectively. Full-power response for the unit reaches to 5 kHz.

The unit is designed for operation in environments whose temperatures range from 0° to 65°C. Its molded housing measures 1.2 by 2 by 0.6 in. and its pins are designed for spring-loaded contacts. Among its recommended uses are relay driver, sound amplifier, servo valve, solenoid, and motor applications.

The PA-011 costs $52 in single quantities and delivery takes two weeks.

Torque Systems Inc., P. O. Box 588, 225 Crescent St., Waltham, Mass. 02154. Phone (617) 891-0230 [344]

NOW...

obsolete decoupling capacitors

with Q/PAC™



New, high capacitance Q/PAC* power distribution elements are the exciting, revolutionary way to eliminate decoupling capacitors from printed circuit boards. Rugged Q/PAC elements are easy to install and increase system reliability through reduced part count.

Q/PAC elements are available in capacitance values up to 0.05μf per inch in lengths up to 16 inches. Configurations allow for either vertical mounting or horizontal installation under DIP packages.

Q/PAC elements eliminate the need for on board power traces and extra board layers. They maximize packaging density and minimize signal interconnection problems.

Q/PAC elements feature a low dissipation factor, low inductance and low impedance.

Pack more on static and dynamic MOS memory boards, more on critical random logic boards.

**Patent Applied For*

Contact the Q/PAC Product Specialist at (602) 963-4584.

ROGERS

Rogers Corporation
Chandler, Arizona 85224

EUROPE: Mektron NV, Gent, Belgium JAPAN: Nippon Mektron, Tokyo

For immediate need circle #176

For information only circle #221

Why IERC's new heat dissipation system for .300" DIPs is more efficient, simpler and costs less than alternate technologies.



The IERC system provides significant thermal transfer for better thermal balance as well as an efficient thermal interface from DIPs to card holder.

The Problem

The thermal management of large numbers of dual-inline packages on a single PC board can be a problem, particularly in telecommunications and logic networks. Single DIPs rarely dissipate as much as one watt, but a board full of them can add up to 15-25 watts. IERC's system of conduction bars and side rails provides a simple, inexpensive, off-the-shelf solution to the problem.

Some Expensive Solutions

Ladder networks will do the job. Of course there is the cost of fabrication, and the difficulty of epoxying the networks to the boards, which makes assembly and repairs a nightmare.

Another approach is to plate heat-dissipation strips directly onto the board. A good idea for some applications, except the cross-sectional dimensions of plated strips (and hence their dissipating efficiency) is limited by the plating process. Also, plated strips require valuable board space and often introduce capacitance and induction problems into your design.

Boards with heat-dissipating metal cores require extremely careful engineering, and are costly and very difficult to make.

IERC's Better Solution

IERC's heat dissipation system consists of conduction bars and side rails, both of which are made from high-thermal-conductivity copper (solder plated) and are available in practically any length. The conduction bars can be wave-soldered into place along with other board components. The IERC system permits quick fabrication of a custom heat-dissipating network for .300" DIP systems, with no restrictions on the distance between DIPs or rows of DIPs. Call or write today for more information.



Standoffs raise conduction bar .020" above circuit board to accommodate metal traces between the standoffs, and to permit removal of solder residue.

IERC's conduction bar system lowers substrate temperatures 30% — 40%.





A — Device only, natural convection, horizontal board;
B — Device only, natural convection, vertical board;
C — Device with conduction bar, natural convection, horizontal board;
D — Device with conduction bar, natural convection, vertical board;
E — Device with conduction bar, side rails attached to infinite heat sink.

IERC

International Electronic Research Corporation, 135 West Magnolia Boulevard, Burbank, California 91502 (213) 849-2481

FLEXIBILITY



One instrument. Multiple measurements.

Tektronix Plug-In oscilloscopes combine a number of diverse measurement functions in the same instrument. And in combinations you require. One instrument takes the place of many. You get maximum measuring power with a minimum of instruments.

How? By choosing from the continually evolving 5000 and 7000 families of Plug-Ins. Already there are 14 mainframes and 21 plug-ins in the 5000-Series; 19 mainframes and 35 plug-ins in the 7000-Series. (With them, you can also use compatible logic and spectrum analyzers plus other special purpose plug-ins.) Choose from a family providing up to 8 input display channels. Analog and digital delayed sweeps. Sampling displays. Digital interconnections. And differential inputs. Just to name a few.

No matter what your test and measurement situation, we offer a Plug-In oscilloscope that fits. From circuit design to plasma physics research. From balancing rotating machinery to measuring the accuracy of D to A converters. With every scope representing the same superior research and engineering you expect from Tektronix.

What about your own particular situation? Are your measurement capabilities confined by monolithics? Contact the Tektronix Field Office near you and get your hands on the kind of flexibility that only a Plug-In scope can deliver.

Tektronix®
COMMITTED TO EXCELLENCE

For literature, call (800) 547-1512 toll free.

For Technical Data circle 179 on Reader Service Card
For Demonstration circle 223 on Reader Service Card

PTK lights CRTs

COMMERCIAL
2 to 30kV, 3 to 30 watts. High voltage power supplies. Custom flyback transformers.

MILITARY
Mil grade units for ground, ship and aircraft.

L.V. / H. V. COMBO'S
High voltage power supplies combined with a multiple output low voltage switcher.

SPECIALS
Miniature and sub-miniature high voltage power supplies to 20kV. Ultra stable or ultra low ripple designs.

Send for Data Package on standard product lines, or call Factory for technical assistance.

PTK Corporation
1173 Los Olivos Avenue
Los Osos, CA 93402
(805) 528-5858

HIGH VOLTAGE
FOR VIRTUALLY ALL CRT APPLICATIONS

C-100 Series

MAJOR FEATURES:

- Low Cost • 2 to 22kV at 10W.
- Excellent Transient Performance
- Focus and G1 Bias Voltages to ±1kV.
- Standard Input +26V ±10%
- Demonstrated MTBF > 100,000 hours
- UL Recognized for Medical Applications
- Input, Output, Mounting and Connector Options Available.
- 3 YEAR WARRANTY



Circle 224 on reader service card

When nobody's got just what you need in Magnetic Materials

PERMAG'S Got It!

In stock. Off-the-shelf. 24-hour delivery. Grinding to your prints. Engineering assistance. Fabricating facilities. In addition, PERMAG has exotic, exclusive hard-to-get items. Complete facilities for measuring, testing, and producing special materials. 8 modern plants stocked, staffed, and equipped to meet your every requirement.

Write for new catalog.

IN THE MAGNETIC FIELD PERMAG IS NO. 1.

YOUR NO. 1 SOURCE FOR ALL MAGNETIC MATERIALS

PERMAG

ALL ACROSS THE COUNTRY

Consult your Yellow Pages for address and telephone number of Permag near you

Circle 270 on reader service card **Electro '79-Booth 3515**

The magazine you're reading now, could be your own.

Drop off the routing list. Get your own fresh, unclipped copy mailed to your home or office. Turn to the subscription card in the back of the magazine. If somebody has beat you to it, write: Electronics, P.O. Box 430, Hightstown, N.J. 08520.

THE ONLY 32K BYTE COMPUTER FOR UNDER $1000. (QTY=1)



Our NAKED MINI 4/10 is a genuine price/performance breakthrough. For OEM quantity discounts that'll improve your bottom line even more, call one of the following sales offices: Santa Ana, CA, (714) 546-9550; Santa Clara, CA, (408) 985-6800; Denver, CO, (303) 399-1383; Orlando, FL, (305) 896-1440; Atlanta, GA, (404) 455-1649; Elk Grove Village, IL, (312) 860-1810; Waltham, MA, (617) 890-7190; Livonia, MI, (313) 261-5170; Bloomington, MN, (612) 854-2305; Bloomfield, NJ, (201) 338-8300; Greensboro, NC, (919) 294-5367; Cincinnati, OH, (513) 771-7530; N. Olmsted, OH, (216) 777-8700; King of Prussia, PA, (215) 265-5770; Nashville, TN, (615) 383-3315; Dallas, TX (214) 350-5681; Houston, TX, (713) 981-8859; Bethesda, MD, (301) 656-1217; Bellevue, WA, (206) 455-9650; or write us at 18651 Von Karman, Irvine, CA 92713.

ComputerAutomation
Naked Mini® Division

WHERE OEM'S COME FIRST.

Circle 225 on reader service card

The Personal Computing Book



Take the computer revolution into your own hands!

More than 50 articles are presented from leading publications in the field to give you this up-to-date guide that answers all your questions on personal computing precisely and reliably.

Hardware • Software • Theory • Applications • Helpful Hints

Order today, and don't forget the other valuable Electronics Magazine Books listed in the coupon below.

Electronics Magazine Books
P.O. Box 669, Hightstown, NJ 08520

Send me...

_____ copies of *Microprocessors* @ $8.95
_____ copies of *Applying Microprocessors* @ $9.95
_____ copies of *Large Scale Integration* @ $9.95
_____ copies of *Basics of Data Communications* @ $12.95
_____ copies of *Circuits for Electronics Engineers* @ $15.95
_____ copies of *Design Techniques for Electronics Engineers* @ $15.95
_____ copies of *Memory Design: Microcomputers to Mainframes* @ $12.95
_____ copies of *New Product Trends in Electronics, No. 1* @ $14.95
_____ copies of *Personal Computing: Hardware and Software Basics* @ $11.95

Discounts of 40% on orders of 10 or more copies of each book.

I must be fully satisfied or you will refund full payment if the book is returned after ten-day trial examination.

☐ Payment enclosed ☐ Bill firm ☐ Bill me

Charge to my credit card: ☐ American Express ☐ Diners Club ☐ Visa ☐ Master Charge

Acct. No. _____ Date Exp. _____

On Master Charge only, first numbers above name _____

Name _____ Title _____

Company _____

Street _____

City _____ State _____ Zip _____

Signature _____

Instruments

LCD thermometer computes, too

Unit measures and stores temperature in three scales and figures rate of change

In a marketplace already overcrowded with portable digital thermometers, why would a company introduce another one?

"Because people need one that is not only convenient and accurate," replies Tracy L. Varnum, general manager of Caspar Integrated Systems, "but is also able to do computations for them." Consequently, CIS is introducing a microprocessor-based handheld model that it claims offers significantly better performance than benchtop units costing several times more.

The DPT 600 measures temperature over a wide range—−192° to +407°C—and shows the result on its 4-digit, 0.5-in.-high liquid-crystal display. Celsius, Fahrenheit, or Kelvin scaling can be selected and platinum resistance temperature probes are offered for any of four types of measurement: immersion, surface, surface-piercing, or gaseous.

To ensure accuracy, the thermometer's 8048 microcomputer uses an algorithm, based on DIN RTD standards, that corrects inputs to within 0.05°C. The chip is also programmed to correct for circuit nonlinearities, so total system error does not exceed ±0.2°C from −150° to 407°C and ±0.3°C down to −192°C.

Busy chip. Taking full advantage of the 8-bit microcomputer, CIS incorporated additional switch-selectable functions: storage and recall of minimum and maximum temperatures, computation of rate of temperature change, and latch-in display of temperature extremes.

Minimum and maximum temperature readings are automatically captured and stored in memory locations no matter what functions the unit is performing. They are updated three times every two seconds and, at the press of a switch, can be recalled

...holes chemically machined as small as .002" to any shape!

Fotoform™ and Fotoceram® materials, Corning's unusual family of glass and glass ceramics, adds a new dimension to precision tolerances.

Rigid, strong, dimensionally stable and chemically inert, they resist temperatures up to 750 degrees C and mechanical stress to 3000 psi. Electrical stability is excellent. Natural homogeneity means zero moisture absorption and surface finishes to less than a micro inch.

How precise are Fotoform materials? Tolerances to within .001"; holes as small as .002"—and packed as close as .004" apart. (50,000 of them would fit in a postage stamp space, with room for more.)

They don't have to be round either. Do you want an ellipse? Or a rectangle? How about a triangle or even a star? Do you want the holes to go straight through—or at an angle?

If in fact we can photographically reproduce the configuration that you want, we can, with our proprietary process of chemical machining, physically produce it as well.

Fotoform and Fotoceram materials are being applied in many new high technology products such as wire guides in several new dot matrix impact printing systems, and magnetic recording heads used in computer disk memory units. This photograph shows an enlarged section of a cell sheet used in a gas discharge display.

Three different materials are available, Fotoform glass, Fotoform Opal glass-ceramic and Fotoceram glass-ceramic.

We've prepared a special technical package, "Materials for the Design Engineer," that will give you the specs on Fotoform and Fotoceram materials—and more. We're the Fotoform Products Group, part of the Materials Business. MS-123A, Corning Glass Works, Corning, New York 14830.

Yes, it's glass

CORNING

Circle 227 on reader service card

Fotoform and Fotoceram are trademarks of the Corning Glass Works.

Get the FACTS on DISPLAY DRIVERS from

SOLID STATE SCIENTIFIC

The MOSSOURCE.



Wow, Robota! With big beautiful eyes like yours, you must be using the new LCD DISPLAY DRIVERS From SOLID STATE SCIENTIFIC.

Right, Rob! Write SSS for ALL the facts on their MOS IC LCD DISPLAY DRIVERS.

ANOTHER of the MANY SIDES of SOLID STATE SCIENTIFIC

Copy or clip coupon below and attach to your letterhead. Mail to: **SOLID STATE SCIENTIFIC, Montgomeryville, Pa. USA 18936**
or Call: **215-855-8400**

E 4 9

Send me Facts about your MOS IC LCD DISPLAY DRIVERS.

Name _____
Position _____
Company _____
Street _____
City _____ State _____
Zip _____
Phone _____

SOLID STATE SCIENTIFIC

Also send information about THE MANY SIDES OF SOLID STATE SCIENTIFIC:

- ☐ μMOS 1800 Microprocessors
- ☐ DT/μMOS Systems
- ☐ μMOS Memories
- ☐ Custom MOS ICs
- ☐ Hi Rel MOS
- ☐ Data Communications
- ☐ Security ICs
- ☐ 4000 Series
- ☐ Timekeeping

Circle 228 on reader service card



HOPE

The project a ship launched.

First there was the hospital ship S.S. HOPE, now retired. Today HOPE is an established project which has carried its goal of improving health through education to 24 developing countries of the world and the United States.

Give to:

PROJECT HOPE Department A
Washington, D.C. 20007

New products

to the display. Thus, the 600 can serve as a simple data logger. For more complex recording, an interface provides peripherals with binary-coded data and permits external control of operating modes.

In the latch mode, the thermometer monitors significant change (±1°C) from an initial value and displays the direction and extreme of that change during the time the mode is selected. Selecting the rate-of-change mode causes the unit to calculate temperature variation per minute and display it every six seconds, also indicating the direction of change.

Varnum eyes a host of sensing applications for the 600 including surface temperature on wafer fabrication lines, oven temperature, and general process control. Plus, he says, it is the only handheld unit that can handle cryogenic research requirements with high accuracy.

The 600 is priced at $495 and delivery is from stock to 90 days. Probe prices vary from $110 to $175 depending on type.

Caspar Integrated Systems, 337 Redwood Ave., Fort Bragg, Calif. 95437 [351]

Digital storage eases signal processing in 22-GHz analyzer

New data-manipulation and display capabilities, plus digital outputs of the displayed information, are the benefits Ailtech derives from digitizing the video signal in its model 757 spectrum analyzer. The instrument, which will be unveiled at Electro79, features internal calibration of its



The low-risk microprocessor choice. TI's 16-bit 9900 family. Compatible from components to systems.

Choosing a microprocessor is getting harder. And riskier. As more people jump upon the 16-bit bandwagon. But considering all factors, the 9900 Family from Texas Instruments offers you the least risk. And the most viable foundation for the future.







Software preservation

Compatibility unites the 9900 Family. It is anchored on a memory-to-memory architecture so advanced that programming time is substantially cut. It employs a uniform instruction set. A common memory bus and peripheral interface. And the same development systems. The result: you are protected against software obsolescence.

You can begin at any level of integration—components, module or system—then move as you will within the family now and tomorrow. Your software remains valid and your investment is preserved.

Broad and flexible family

The 9900 Family spans the field of microprocessors, microcomputer modules, and minicomputers.

- **Cost-effective CPUs**—There are four 9900 Family microprocessors utilizing NMOS or I^2L technologies. Plus expandable building blocks for use where customization is needed. A choice that matches price and performance to design needs.
- **Economical peripherals**—A wide selection of support circuits completes your design. Including a full range of serial, parallel and special-purpose I/O, RAMs, ROMs and EPROMs.
- **Low-cost microcomputer modules**—Pre-assembled and pretested to save you the time and cost of developing your own hardware. Expansion modules are part of the series. There's an educational module with tutorial text.
- **Affordable minicomputer**—The 990 computer systems offer an OEM system configuration complete with peripherals, operating systems and high-level languages.

Hardware/Software support

The 16-bit 9900 Family is the best supported compatible family.

High-level languages—TI PASCAL, POWER BASIC* and FORTRAN—boost programmer efficiency, while reducing maintenance and documentation costs. TI PASCAL (TIP) is ideal for larger or higher-volume projects, providing simplified maintenance and self-documentation with minimum overhead. POWER BASIC, one of the fastest English-like languages, is available for development on single modules or turnkey minicomputers. Optimized for real-time control systems, it is ideal for rapid development of low-volume products.

For run-time support, new prefabrication software handles common executive functions: the TIP Microprocessor Executive (TIPMX) for use in minicomputer-based development, and TIMBER for ROM-based modular development.

AMPL*, TI's Advanced Microprocessor Prototyping Laboratory, allows powerful in-circuit emulation, while monitoring address and data buses simultaneously. Simple to use because of self-prompting procedures, it allows symbolic debug of hardware and software concurrently.

Proven and available

A pioneer in 16 bits, the 9900 Family is here and now—not on paper, not a promise. Proven in applications, readily available, second sourced.

Family on the grow

One final reason to choose the 9900 Family. It is growing and TI is committed to its continuation and expansion. As needs change, and as new technologies develop, expect other members to join the family.

Let us tell you more

For free brochures on the entire 9900 Family, call your local TI distributor, or write Texas Instruments Incorporated, P. O. Box 1443, M/S 6404, Houston, Texas 77001.

TEXAS INSTRUMENTS MOVING AHEAD IN MICROPROCESSORS

*Trademark Texas Instruments Incorporated

TEXAS INSTRUMENTS
INCORPORATED

© 1979 Texas Instruments Incorporated

85561

Circle 229 on reader service card

We want you to know how wrong you are.

Your error rate is an important parameter. And you can determine it *exactly* with an instrument from the world's broadest line of bit-error-rate test sets (BERTS). You can buy a laboratory or field instrument with a data format that matches your needs. In stand-alone or modular plug-in units. At data rates as high as a gigabit! And, for those highly customized applications with special data patterns and interface requirements, we'll even build a special unit for you.

Tau-Tron. When you need to know.



tau-tron inc
11 Esquire Road. North Billerica, Mass. 01862
Tel: (617) 667-3874

Circle 230 on reader service card

From Electronics Magazine Book Series. Zero-risk trial offer.

New Product Trends in Electronics, Number One
From "New Products," state-of-the-art materials and equipment, arranged according to function. $14.95

Name _____ Title _____
Company _____
Street _____
City _____ State _____ Zip _____
Signature _____

Electronics Book Series
P.O. Box 669, Hightstown, N.J. 08520

Send me _____ copies of "New Product Trends in Electronics, Number One" at $14.95 per copy

Discounts of 40% on orders of 10 or more copies.
I must be fully satisfied or you will refund full payment if the book is returned after ten-day trial examination.

☐ Payment enclosed ☐ Bill firm ☐ Bill me
Charge to my credit card:
☐ American Express ☐ Diners Club
☐ Visa ☐ Master Charge

Acc't No. _____ Date exp. _____
On Master Charge only, first numbers above name _____

five frequency bands, keeping them accurate to within 1 MHz over the instrument's tuning range of 1 MHz to 22 GHz.

With the aid of front-panel push buttons and a type 2147 4,096-bit read/write random-access memory, the operator can store signals and perform various other operations. An immediate benefit of digitally stored and refreshed signals is the complete absence of flicker, even at very low scan rates, notes Joseph P. Engeman, product line manager. Moreover, punching the HOLD button freezes the signal in the memory so that it may be closely studied for an unlimited length of time.

The normal display mode of the analyzer uses only 1,024 bits of the memory. By punching the SAVE button, the operator can store the signal in another 1-K segment, without disturbing the displayed signal. He may later recall that signal, or he may punch the SIGNAL-INPUT button, thereby feeding to the display the difference in amplitude between the stored signal and the real-time signal at the analyzer input. Yet another button allows the live signal and the stored signal to be displayed simultaneously for comparison, a handy feature when making production-line adjustments in filters and the like, Engeman says.

Digital output. The 757 also provides an on-screen readout of six important parameters: center frequency, reference level, vertical scale, scan width, scan time, and intermediate-frequency filter bandwidth. Moreover, these six parameters and the 1,024 horizontal points of the displayed waveform feed to rear-panel outlets for connection to a computer, printer, or storage device.

Another aid to semiautomatic testing is the 757's ability to step across the selected frequency band in response to a remote signal. This capability was optional on the preceding model 727, but is standard on the new instrument.

Like its predecessor, the 757 has a 100-dB dynamic range, a low-end sensitivity of −125 dBm, and a high-end sensitivity of −90 dBm. (The sensitivity figures apply with a 1-kHz

One day, the pencil factory started producing pencils with erasers at both ends,
because the machine that put the erasers on went haywire,
because the computer gave it the wrong message,
because one of its printed circuit boards malfunctioned,
because one of the I.C.s was in backwards,
because the DIP insertion machine made an error,
because there was no DIP verifier to catch the mistake,
because the DIP insertion machine wasn't a Dyna/Pert.

Announcing Dyna/Pert's new DIP verifier, DCV-A. Even with automatic DIP insertion, there's such a thing as human error. But the DCV-A guarantees that the correct DIP with the correct polarity goes into the correct PCB position, every time. It tests both digital and analog I.C.s without slowing down the insertion cycle one bit, and without requiring any extra labor investment. Tremendous cost savings and no human error: that's the whole point.

We help you do it right the first time.

DYNA/PERT®

Division of USM Corporation, Elliott Street, Beverly, Massachusetts 01915

An **EMHART** Unit

Mini and Submini Feedthrus

- Single, dual and quad assemblies **and submini octal assemblies.**
- for operating pressures $<10^{-10}$ torr
- Ceramic-metal
- Minis bakeable to 350° C, Subminis to 550° C
- Weld adapter or vacuum flange mounted
- Brazeable subminis
- Non-magnetic cryogenic

Request Bulletins



7708 (Mini) and 7709 (Submini)



SINGLE UNIT MOUNTING DIAMETERS
Mini—0.247"(6.27mm);Submini—0.154"(3.91mm)

Ceramaseal, Inc.
A SUBSIDIARY OF INTERPACE CORPORATION

NEW LEBANON CENTER, NEW YORK 12126 (518) 794-7800 • Telex 14-5442

Circle 232 on reader service card

If it has to do with heat dissipation, it has to do with us.

EG & G Wakefield Engineering is your source for heat sinks and thermal products. We have the largest inventory of off-the-shelf heat sinks including extrusions and stampings as well as proven custom-design capabilities. Our extensive distributor network, east and west coast manufacturing facilities, reliable service and competitive prices are second to none. That's why . . . if it has to do with heat dissipation . . . people throughout the electronics industry call EG & G Wakefield Engineering.

EG&G WAKEFIELD ENGINEERING
60 Audubon Rd., Wakefield, MA 01880 (617) 245-5900

Visit us at Electro '79 at Booths 2347 and 2446

Circle 180 on reader service card

New products

i-f bandwidth.) Moreover, the new unit's height has been cut from 12.5 to 8.75 in., and its weight has been pared about 25 lb to 65 lb.

Scheduled to be available by the end of the quarter, the 757 will sell for $19,975—about $2,200 more than the earlier model. However, besides the benefits of digital processing, it offers, as standard, three features that formerly were extra-cost options: the semiautomatic response to remote-signal tweaking, a preselector-filter bypass that can increase sensitivity by 10 dB when the filter is not needed to reduce noise, and a local-oscillator output.

Ailtech Division, Cutler-Hammer Inc., 2070 Fifth Ave., Ronkonkoma, N. Y. 11779. Phone Charles Sheetz at (516) 528-3600 [353]

Automatic meter measures audio distortion and noise

Tuning the fundamental rejection frequency across the frequency range of interest is one of the most time-consuming parts of making a manual distortion measurement. The model F242A performs the tuning automatically, both saving time and eliminating operator error.

With its frequency range of 20 Hz to 20 kHz, the meter is suitable for testing all sorts of audio gear, including amplifiers, oscillators, tape recorders, line equalizers, and filters. In addition to distortion, it can measure audio gain, frequency response, and signal-to-noise ratio.

Input circuit configurations include both unbalanced and balanced circuits either terminated in 600 Ω or bridged. When terminated in 600 Ω the F242A has a residual noise of less than −110 dBm. It sells for $2,425; delivery time is 60 days.

Marconi Instruments, 100 Stonehurst Court, Northvale, N. J. 07647. Phone (201) 767-7250 [355]



If you've never had a chance to do your best work, here's your chance.



At Storage Technology Corporation, we continually strive to make our already advanced technology even better. We've built a solid reputation for quality with reliable, well-engineered products.

STC is only ten years old and we are already the world's largest manufacturer of high density tape data storage products and the leading independent supplier of fixed media disks for the IBM compatible market. And we can be very proud of that accomplishment.

Our people have made us what we are today and they are working hard to make us even better tomorrow. We recognize them and appreciate the creative, aggressive contributions made by each of our employees. That's the STC philosophy. And that's one reason we've been able to establish such a rapid, stable growth pattern.

Living in the Denver-Boulder area is just the beginning of an exciting career at STC. We offer challenging projects where you can be in control, where doing your best work means greater opportunity for advancement.

We offer exceptional opportunities at every level and we have some exciting career alternatives that we think you'd like to know about.

Write or send your resume in complete confidence to the Professional Employment Department at the address listed below. Your correspondence will be answered promptly and courteously, and we'll tell you what it's like to be part of our company, and why we can say with pride at STC, people count and technology truly is our middle name.

An equal opportunity employer.

E412

STC

STORAGE TECHNOLOGY CORPORATION

2270 South 88th Street, MD-13, Louisville, Colorado 80027

R379

DEAR DEVELOPMENT SYSTEM:

You'll love letting Data I/O's System 19 do your programming while you do the important things.

Once you've developed a PROM program on your development system, simply download it into a Data I/O System 19. This frees your development system for the next person who needs it.

Later, if you discover that a statement has been left out, or you need to edit the program, you can use the System 19 to make all the necessary changes without once interrupting work being done with the development system. And your System 19 can program every kind of bipolar and MOS PROM—not just the few MOS PROMs that most development systems program.

The System 19 saves you time by eliminating the need for you to build software packages so your development system can transmit data to the programmer. System 19 offers all these development system object code formats in a single package:

RCA Cosmac, Motorola Exorcisor, Intel Intellec 8/MDS, Signetics Twin, MOS Technology, Fairchild F8 Formulator, Tektronix 8001, and Zilog MCZ-1.

Best of all, Data I/O System 19 is priced within just about everyone's budget.

You haven't shopped around until you've looked at Data I/O. Let us show you the difference. Circle the reader service number or contact Data I/O, P.O. Box 308, Issaquah, WA 98027. ***For answers fast, call toll free: 800-426-9016.***

Good idea! DATA I/O

Programming systems for tomorrow...today.


High flexibility
Pragmatic. Asthetic.
From hard use lab assignments to easy going office jobs — the flexibility of Cramer Hi-Model is unlimited.
Cramer offers the options on a complete line of Hi-Models. Choose footrings, posture backs, casters. All Hi-Models are available in a vast selection of decorator fabrics. Frames and legs in mirror, or brushed chrome. We offer Auto-Lift for immediate height changes — Posi-Lok for less frequent height adjustments.
Whatever the job type or individual need — Cramer is high in design and practicality.
CRAMER
CRAMER INDUSTRIES INC.
625 Adams Street, Kansas City, KS 66105
Phone: 913/621-6700
Toll Free: 800/255-4096
Showrooms in spaces 982 to 985 Chicago Merchandise Mart
Kansas City, Los Angeles
Circle 235 on reader service card

Micro power

The fastest 32K ROM available. That's Rockwell Micropower.

Rockwell is now producing industry standard, fully-static NMOS 32K, 24-pin ROMs. We've got capacity for more orders in 1979 if you're ready to order right away.

The fast R2332-3 features maximum access and cycle time of 300ns. Both the R2332-3 and the standard 450 ns R2332 use 400 mW power and one 5V power supply.

R2332 and R2332-3 inputs are TTL compatible with a 400 mV minimum noise immunity on both the HIGH and LOW inputs. All eight outputs are tri-state drivers capable of driving 100 pf and a TTL gate.

The R2332 operates totally asynchronously and requires no clock input, so it's compatible with both static and clocked-static versions. Two mask-programmable chip select inputs allow four 32K ROMs to be OR-tied without external decoding.

A fast ROM plus fast turnaround from us to you. That's Rockwell Micropower.

Phone (714) 632-3729 or telex 910-591-1654 for your local Rockwell Rep.

Or write: D-727-F5 Microelectronic Devices, Rockwell International; P.O. Box 3669, Anaheim, CA 92803.



Rockwell International

...where science gets down to business

SE 7000: Multiband performance – Multi-channel check-out

SE 7000 Series Instrumentation Recorders give you 8 speed recording up to 2MHz Direct, 500 kHz FM and up to 30 k bpi HDDR. The SE 7000 has in addition a unique range of features essential to lab quality recording,with a convenience, simplicity and reliability that no other recorder can offer.

Consider, for instance, the versatile built-in calibrator module with DVM for "set and forget" control, and the unique simultaneous all-channel FM electronics to electronics facility, without tape movement – the higher reliability of hard-wired, all speed active filters, equalisers and other tape speed sensitive components – the proven dependability of co-planer format resulting in more gentle tape handling and lower tape wear.

Don't accept second best. We would like to show you how the SE 7000 can match your requirements in instrumentation recording. Call us on 203-744-3500 or send reader card for details.

SE 7000M– the only wideband portable with built-in 14 channel electronics to electronics FM calibration and pre-record checkout.

EMI Technology

EMI Technology Inc.,
55 Kenosia Avenue, Danbury CT 06810.
Tel 203-744-3500 T W X 710-456-3068

A member of the EMI group. International leaders in music, electronics and leisure.

Circle 237 on reader service card

COMPUTER AIDED DRAFTING—ADVANCED STATE OF THE ART

Between $18,000 to $45,000
Simply input ideas with Joystick or Graphic tablet



Computer does work, you do the thinking

Instant Recall: Add or delete entire blocks of drawings with one command



Plotter gives camera ready art in minutes



Only at I Corporation
Order yours today!

- ★ PC Layout
- ★ Schematic
- ★ Mechanical
- ★ Hybrid

(415) 848-6600

I Corporation

835 Addison Street
Berkeley, CA 94710

New products

Microcomputers & systems

Micro-company uses big bubbles

Portable microcomputer with ¼-megabit memories weighs only 20 lb

While titans IBM and Bell Labs publicly discussed their newest bubble technologies at Indian Wells, Calif., last month, a tiny Los Angeles company had something to say about bubbles, too.

"We are now marketing the first microcomputer that uses ¼-megabit bubble devices," announced Michael Wurmbrand, vice president of nine-person Findex Inc.

Called the Findex 128, each typewriter-sized computer contains four of the first ¼-megabit production parts delivered by Rockwell Inc. In addition to the basic 128 kilobytes of mass storage that these devices provide, the 20-lb unit includes 48 kilobytes of dynamic random-access memory, 1 of static RAM, and 8 of read-only memory expandable to 32 kilobytes.

Storage and RAM can also be expanded, and users can pack 500 kilobytes of bubble memory and 128 kilobytes of RAM into the single housing or expand them to 2 megabytes each with an additional chassis. Presiding over all this is a Z80 processor that can ship out data over four serial or 46 parallel lines or on an S-100 bus. Where more I/O is needed, a further 64 parallel lines can be added.

To keep the unit's weight and volume down, Findex engineers chose a scrollable gas-discharge display rather than a bulky cathode-ray tube. Users can put up to six lines of 40 dot-matrix characters in upper and lower case while scanning the system's data base. For hard copy, there is an integral tape printer: an external printer can also do the job using the bus or I/O lines.

Getting their first product to market was not an overnight project, according to Wurmbrand. The company's four engineers began designing the computer some 3½ years ago, building their own driver circuitry based on Rockwell's original single-loop design. Then, when Rockwell changed to a multiple-loop structure last April, it was back to the design board. "It's the price you pay if you want to deal with new technology," Wurmbrand warns.

But fast-acting Findex was ready when Rockwell started delivering the parts last February. As they come in on a 45- to 60-day schedule, Findex is able to plug them in, test, and ship



Now you can add these Mallory QPL capacitors to your approved vendor list.

We want to update you on our line of capacitors qualified under MIL-C-39003 and MIL-C-39006.

In solid-electrolyte tantalums we now offer the following:

MIL Style	Mallory Type	Life Failure Rates
CSR 13	TER	M, P, R
CSR 23	TXE	M, P
CSR 33	TXR	M
CSR 91	TNR	M, P, R

In non-solid (wet) tantalums:

MIL Style	Mallory Type	Life Failure Rates
CLR 10	XTM-XTK	L, M, P
CLR 14	XTL-XTH	L, M, P
CLR 17	XTV	L, M, P
CLR 65	TLX	L, M, P, R
CLR 69	TXX	L, M, P

All of these capacitors are available through authorized Mallory distributors.

For complete specifications write for our new QPL bulletin. Or call:

Mallory Capacitor Company, a division of P. R. Mallory & Co., Inc., Indianapolis, Indiana 46206 (317) 856-3731.

MALLORY

Circle 239 on reader service card

for energy storage specify Custom MICA Capacitors



Energy Density .05 - .25 joules/in³ at high voltage
Capacitance to 40 uf
Voltage to 50 KV
Temperatures to 125° C. without derating
Custom's C Series mica capacitors will meet your requirements for a totally solid capacitor. Dielectric inspected before production for maximum reliability.

Available in three basic types: CMR ("wrap and fill"); CER (epoxy housed); CEM (epoxy molded). Quick quotation and delivery.
Also available: High Voltage K Series mica for maximum volumetric efficiency and Low Voltage T Series film for high temperature applications.
Write for FREE C, K, T Series TechniTips.

CUSTOM ELECTRONICS, INC.
12 Browne St., Oneonta, NY 13820
PH: 607-432-3880 TWX: 510-241-8292

Circle 240 on reader service card

Portable Miniscopes for Electronic Professionals on the Go!!!

The standout oscilloscope development of the decade!!!

Now—single & dual trace models. Compare the performance, then compare the price.

MS-15 $318 MS-215 $435

● 15-megahertz bandwidth. ● Accuracy—3% full scale. ● Internal, line or external trigger. ● Batteries and charger/transformer unit included. ● Graticule: 4 x 5 divisions, each division 0.25″. ● Weight: Less than 3 lbs with batteries. ● Size: 2.9″ H x 6.4″ W x 8.0″ D.

NLS products are available from Nationwide Electronic Distributors.
Send for our brochure today!

Non-Linear Systems, Inc.
Originator of the digital voltmeter.
Box N, Del Mar, California 92014 Telephone (714) 755-1134

240 Circle 182 on reader service card

out the product 90 days or less after receipt of order. The company can currently produce 20 to 30 units each month.

The 128 comes programmed in business Basic, but also supports Fortran and Cobol. With minimum memory, it can be purchased for $8,230 or leased for $250/month. Additional bubble increments of 128 kilobytes cost $3,000.

Findex Inc., 1625 W. Olympic Blvd., Los Angeles, Calif. 90015. Phone Claudine Muller at (213) 734-6339 [371]

Z80 emulator frees MDS by taking on test chores

Along with other tasks, trouble-shooting and production-line test chores are often assigned to microprocessor development systems. But rather than tie up an MDS—priced at $4,000 up—for those jobs, engineers working with Z80-based systems can turn to a less expensive device, the EZ-80.

Designed to emulate that popular processor, the $2,295 unit can be plugged into the Z80 socket of the system being evaluated, providing program control and system diagnosis without restricting memory addressing or programming technique. Data in memory, in microprocessor registers, and at input/output ports can be displayed in hexadecimal form on the EZ-80's front panel and altered as required. Front-panel keys let users step through a program one instruction at a time or run it at full processor speed. Moreover, a trace memory will capture 255 machine cycles for later display; hardware-implemented breakpoints can be



GET OFF THE PINS . . . and GET ON THE ZEBRA®!



Permanent Connection

- ZEBRA-STIK—LCD PROTOTYPE APPLICATIONS
- SELF-SUPPORTING ZEBRA UP TO 8" FOR LCD AND DOT MATRIX
- ZEBRA CONNECTOR ASSEMBLY—DUAL AND SINGLE INLINE
- CUSTOM ZEBRA CONNECTORS

ADVANTAGES



Easy Disassembly

No Soldering



Penny Per Contact



Shock and Vibration Absorption

Easy Disassembly

8" Long Zebra

Less Than 1" Assembly

Zebra-Stik

Send for Free Zebra-Stik Sample

TECKNIT® 129 DERMODY ST., CRANFORD, NJ 07016 • (201) 272-5500

Circle 241 on reader service card



AO STEREOSTAR® Microscope. It has everything from A to Zoom.

ALL ESSENTIAL FEATURES FOR AN OUTSTANDING INDUSTRIAL MICROSCOPE

Auxiliary Lenses: .5x, 2x

Body Rotation: 360°

Eyepieces: 10x, 15x, 25x

Field Size Range (inches): .13–2.25

Magnification: Standard 7–30x; Range 3.5–150x

UL listed Illuminator

Working Distance: Standard, 4.0 inches; Range, 1.4–5.7 inches

Zoom Range: .7–3x; Zoom Control: Dual Side Mounted; Zoom Ratio: 4.3–1

These are all features you want and need for efficient assembly or inspection of microcomponents. The AO STEREOSTAR ZOOM Microscope was specifically designed for production-line applications. It's easy to use, with plenty of working distance plus coupled zoom control conveniently located on both sides. And traditional AO quality optics give very high resolution for crisp, sharp images. Send for a detailed brochure. American Optical, Scientific Instrument Division, Buffalo, NY 14215.

AO® American Optical

used to stop the program at a specific address whenever it occurs or only when it occurs after another specified address.

Nine diagnostic routines, including scope loops, are built into the emulator. These routines repeatedly access a designated memory location or I/O port while disabling memory refreshing to simplify signal tracing by oscilloscope. In addition to built-in routines, system-defined diagnostics can be performed by plugging a programmable read-only memory containing user-generated tests into a front-panel socket.

Delivery of the EZ-80 is from stock to six weeks.

Applied Microsystems, 11064 118th Place N. E., Kirkland, Wash. 98033. Phone Robin Knoke at (206) 827-9111 [373]

Low-cost board breeds F3870 family familiarity

Engineers who would like to familiarize themselves with the F3870 family of microcomputers can now buy a prototyping, evaluation, and programming board, called PEP for short, for $450. The unit provides real-time in-circuit emulation of the various family members (F3870, F3872, F3876, and F3878) through a 40-pin umbilical cable.

In addition to an on-board keypad and six-digit hexadecimal display, the system includes 2 kilobytes of static read/write random-access memory, expandable to 4, which simulates the read-only memory and RAM of the various microcomputer models. A separate 128-byte RAM provides workspace in which to examine the contents of the comput-



One company can cut keyboard costs. Even when their keyboards cost more.

The most expensive mistake you'll ever make selecting a keyboard could be spending too little. In the long run, that adds up to cutting corners, not costs.

So to make sure you get the keyboard that really meets your needs, MICRO SWITCH uses Value Engineering.

Through Value Engineering, we look at your particular product needs to design a cost-effective solution to your problems. That means designing a keyboard that interfaces with your total system and meets your needs. Precisely.

It also means we can often lower your total system cost. For example, we might be able to incorporate into a keyboard several levels of codes that you had been paying for separately. And at a much higher cost.

Or maybe customize integrated circuits to provide you more logic for less money.

Besides giving you cost-efficiency, MICRO SWITCH keyboards out-feature practically every other in the industry.

You can choose LED or incandescent lighting. Tactile or linear feel. Sealed versions for military and industrial uses. Alternate or momentary action. Encoding techniques that'll meet any code requirement.

There are also wired-only assemblies or separate modules available. And you can pick from the industry's largest legend library.

Standard, solid state Hall-effect technology throughout the line delivers reliability no mechanical keyboard can offer. Plus, we back up every keyboard we make with a 1% Acceptable Quality Level and a two-year warranty.

It all adds up to quality you can put your fingers on every time.

For more information, call 815/235-6600.

With MICRO SWITCH, you'll be paying for keyboards instead of mistakes.



MICRO SWITCH

FREEPORT, ILLINOIS 61032

A DIVISION OF HONEYWELL

MICRO SWITCH products are available worldwide through Honeywell International.

Circle 243 for data

ASSOCIATED ENVIRONMENTAL SYSTEMS

Reliable Low Priced Chambers



Low cost liquid CO_2 cooled BK series chambers from ½ ft.³ to 27 ft.³ working volume. Temperature ranges from −100°F to +425°F with control stability ± ½°F. All with RFI free, solid-state controls, forced air circulation, adjustable high temp failsafe, stainless steel interiors, all as standard items. Automatic programmers, various size viewing windows, access ports, liquid Nitrogen (LN_2) cooling, and ambient air cooling are optional.

Mechanical Refrigeration Chambers

For those customers with longer test requirements, Associated offers the most complete line of self contained mechanical, cascade refrigeration chambers — the SK and FK Series. Ranges from −120°F to +350°F with control stability ± ½°F. Bench top units in 1, 2, 5, 8 ft.³ and floor models in 14, 33, and 64 ft.³. Associated also offers a complete line of temperature-humidity, salt spray test component chambers and walk-in rooms.

ASSOCIATED ENVIRONMENTAL SYSTEMS
Subsidiary of Walter Kidde & Company, Inc.
KIDDE
360 MERRIMACK ST., LAWRENCE, MA 01842
(617) 683-9501 • TWX 710-342-0765

er's registers. Also provided are sockets for programming 2716 erasable, programmable ROMs or the E-PROM of the F38E70, and space for up to 6 kilobytes of E-PROM.

PEP can be down-loaded from a development system with a cross-assembler. It communicates with an RS-232C or current-loop terminal at rates of 110, 300, or 1,200 bits/s and supports a high-speed paper-tape reader. Pre-production quantities are available now and production quantities will be rolling out next month.

MOS Products Division, Fairchild Camera and Instrument Corp., 464 Ellis St., Mountain View, Calif. 94042 [374]

Basic for the 6800 is faster for floating point

The latest attack in the battle of the 6800 Basics has been launched by Technical Systems Consultants with its TSC Basic, which the company claims is typically 2 to 10 times faster than other versions of the language in performing floating-point calculations.

Including all standard Basic instructions, the program resides in 9.5 kilobytes of memory and can run on 6800-based systems with as little as 12 kilobytes of memory available from location 0000, although 16 kilobytes is recommended for more serious applications. Floating-point arithmetic is performed to an accuracy of seven digits internally, with all answers printed to six digits.

TSC Basic provides an IF . . . THEN . . . ELSE construct for more structured programming and permits up to 127 characters in the input line buffer. Peek and Poke operations can be performed in hexadecimal, rather than decimal, and there can be as many nested loops, subroutine calls, and string variables in a program as memory permits. String length is limited only by memory, does not have to be specified before use, and may be changed at any time. Furthermore, variables can be labeled with two-letter names and both colon and slash symbols, used

Press-fit telephone connectors with wire-wrappable tails hard to get? Not from Elco!

We're ready to meet your I/O needs with Telewrap™ press-fit telephone connectors that provide a reliable, solderless, gas-tight connection. Unlike competing units, Elco Telewrap connectors have an integral tail, so there's no need for extra holes in the board. Offered in both plug and receptacle styles, in all existing grid systems.

Total Interconnect Systems

Elco offers a broad range of press-fit connectors, metal plate connectors and card-edge connectors, as well as heavy copper backpanels, sophisticated multilayer and aluminum backpanels, and backpanel systems. In fact, Elco can provide the total interconnect package, including wire wrapping and accessory hardware.

For a free copy of our comprehensive Backpanel Interconnect Systems catalog, call or write:

Elco Corporation
Interconnect Systems Division
2250 Park Place, El Segundo, CA 90245
(213) 675-3311/TWX 910-325-6602

GW **Elco Corporation**
a Gulf + Western manufacturing company

Circle 245 on reader service card

Save time. Save money. Eliminate loudspeakers and hand soldering with the new AT27 and AT32 Audio Transducers.

They mount directly to P.O. board; are wave solderable; low current drain; provide sound pressure levels of 75 or 90dBA at 1 foot at 2.0-2.9kHz. Frequency range of 1.6-4.0kHz. A 15Vpp signal will produce 80 to 95dBA.

For literature, write Projects Unlimited, Inc., 3680 Wyse Road, Dayton, Ohio 45414.
Phone: (513) 890-1918.
TWX: 810-450-2523.

projects® unlimited

NO SPEAKERS REQUIRED

Circle 246 on reader service card



NYLON GROMMETING

Make your own grommets to fit any size or shape opening with Weckesser Type 6/6 Nylon Grommeting. Extruded grommeting available in 25 and 50 foot lengths, five standard sizes to fit panel thicknesses from .052" to .250". Also available in molded flexible strips, 12-3/4" long. All available in black or natural.



Weckesser COMPANY, Inc.
4444 West Irving Park Road • Chicago, Illinois 60641 • 312/282-8626

New products

in multiple-line statements, are supported by the new language.

The program is available from stock on cassette with a user's manual for $39.95. A source listing is not available, but a disk version that runs under the Flex DOS will be available shortly.

Technical Systems Consultants Inc., Box 2574, West Lafayette, Ind. 47906. Phone (317) 463-2502 [377]

Boards for S-100 bus built around 16-bit 8086

Users of the S-100 bus systems have had to be content with 8-bit processors while the rest of the world heads rapidly toward 16 bits. No longer, however, need that be the case; a three-board system meeting the proposed IEEE 16-bit protocol for that bus based on the 8086 has been developed.

Appropriately named the 8086/S-100, the system is composed of a 4- or 5-MHz central processing unit, an appropriate-speed read/write random-access memory board with 16 kilobytes of RAM, and a card combining a programmable read-only memory monitor and serial and parallel input/output ports.

The serial output port works with RS-232 or current-loop devices and the 24 lines of parallel I/O can be programmed in groups of eight for either input or output. Memory is expandable in accordance with the proposed protocol up to 1 megabyte.

Most S-100-bus peripherals currently available can be joined to the S-100/8086 without degrading the system's performance and assembly language software from existing 8080 systems can run on it.

The CPU board is priced at $895 and the PROM-I/O card sells for $495 with monitor PROM or $350 without. The 16-kilobyte memory board, strappable for data widths of 16 or 8 bits, costs $495. Discounts are available for original equipment manufacturers.

Tecmar Inc., 23414 Greenlawn Ave., Cleveland, Ohio 44122. Phone (216) 382-7599 [375]

Your sure way out of the impedance jungle.

Untangle R-C-L component measurement with a cost effective ESI digital bridge.

μP SPEED ON THE PRODUCTION LINE
This dual frequency bridge is RCL production King of the Beasts. Fast. Versatile. Automatic. Measures R,C,L to 0.1%, at up to 16 tests/sec., plus G,D,Q. Multiband sorting, parts handling interfacing. Under $5000 USA.

LOW COST INCOMING RCL INSPECTION
Fend off wild components with this low cost meter. Measure R,C,L to 0.25%, plus get G & D. Autoranging, low frequency optional. Under $800 USA.

AUTOMATIC 1 MHz CAPACITANCE
Renegade components at RF levels are quickly and surely snared with this 1 MHz RCL bridge. Measure R,C,L to 0.1%, plus get G,D,Q,X,B—all with μP muscle and speed.

SUPER ACCURACY FOR ABSOLUTE OHMS
Cage any species resistance with this precision ohmmeter's 3 modes: switched DC, continuous DC or single pulse. 0.02% accuracy to 20 MΩ. 1 μΩ resolution available.

See us at Electro, Booth 2232.

The sure way to innovation.

esi® ELECTRO SCIENTIFIC

Electro Scientific Industries, Inc.
13900 N.W. Science Park Drive
Portland, Oregon USA 97229
503/641-4141; telex 36-0273



NEW.

Meet Super Grip II, the great new test clip from A P Products.



New narrow-nose design makes it easy to attach on high-density boards. And now you can test ICs with only .040" between opposing legs.

New "duck bill" contacts are flat, won't roll off IC leads.

Open-nose construction enables probe at IC leg.

Pin rows are offset for easy attachment of probes.

Contacts are gold-plated phosphor bronze. "Contact comb" construction separates contacts with precision. No shorts.

Heavy-duty, industrial-grade springs for firm contact pressure—and a good grip when pulling ICs. They'll keep their spring indefinitely. No intermittents.

Steel pivot pin. Engineering-grade thermoplastic body molded around contact pins. Made to last!



New button-head pins keep probes from sliding off. (Straight pin models for logical connections.)

The new A P Super Grip II is, without question, the best way there is to troubleshoot DIP ICs.

You get positive contacts. No intermittents. No shorts. Ever.

So it's endlessly useful to you—and it's built to stay useful indefinitely.

Try one. Your local A P distributor has 8, 14, 16, 16 LSI, 18, 20, 22, 24, 28, 36 and 40-pin models. (Be sure it's the A P distributor.)

Need the number? Phone (toll-free) 800-321-9668. And ask for our complete A P catalog, The Faster and Easier Book.

A P PRODUCTS INCORPORATED
Box 110 • 72 Corwin Drive
Painesville, Ohio 44077
Tel. 216/354-2101
TWX: 810-425-2250

Faster and Easier is what we're all about.

Introductory offer to new members of the COMPUTER PROFESSIONALS' BOOK CLUB

any *two* of these great professional books for only $2.95

values up to $69.95

Two special bonus books come to you for $2.95 with your first club selection

Books are selected from a wide range of publishers

784/612
MICROPROCESSOR ARCHITECTURE AND PROGRAMMING
by W. F. Leahy
Pub. price, $19.95
Club price, $14.95



353/670
MICROPROCESSORS & SMALL DIGITAL COMPUTER SYSTEMS FOR ENGINEERS & SCIENTISTS
by G. A. Korn
Pub. price, $27.50
Club price, $18.95

491/380
MICROCOMPUTER-BASED DESIGN
by J. Peatman
Pub. price, $24.50
Club price, $17.50



783/934
FUTURE DEVELOPMENTS IN TELE-COMMUNICATIONS
by J. Martin
Pub. price, $34.95
Club price, $24.50



785/201
MICROPROCESSOR SYSTEMS DESIGN
by E. E. Klingman
Pub. price, $19.50
Club price, $15.95



783/659
MICROPROCESSOR AND MICROCOMPUTER SYSTEMS
by G. V. Rao
Pub. price, $24.50
Club price, $19.50



785/988
COMPOSITE / STRUCTURED DESIGN
by G. J. Myers
Pub. price, $15.95
Club price, $12.50

435/278
MICROPROCESSOR APPLICATIONS MANUAL
by Motorola, Inc.
Pub. price, $35.00
Club price, $25.00



785/511
ADVANCES IN COMPUTER ARCHITECTURE
by G. J. Myers
Pub. price, $21.00
Club price, $16.50



783/845
THE 8080A BUGBOOK MICROCOMPUTER INTERFACING AND PROGRAMMING
by P. R. Rony, D. G. Larsen & J. A. Titus
Pub. price, $9.95
Club price, $8.45

786/119
IMS PROGRAM-MING TECHNIQUES
A Guide To Using DL/1
by D. Kapp & J.F. Leben
Pub. price, $17.95
Club price, $13.95

785/252
CHESS AND COMPUTERS
by D. Levy
Pub. price, $12.95
Club price, $10.50

786/372
REAL-TIME PROGRAMMING WITH MICROCOMPUTERS
by R. C. Turner
Pub. price, $16.95
Club price, $13.95

772/223
COMPUTER STORAGE SYSTEMS & TECHNOLOGY
by R. E. Matick
Pub. price, $29.95
Club price, $23.95

786/380
FUNDAMENTALS OF COMPUTER ALGORITHMS
by E. Horowitz & S. Sahni
Pub. price, $19.95
Club price, $15.95

785/058
MICRO-ANALYSIS OF COMPUTER SYSTEM PERFORMANCE
by B. Beizer
Pub. price, $22.50
Club price, $17.25



Be sure to consider these books as well—

save time and money
by joining McGraw-Hill's

COMPUTER PROFESSIONALS' BOOK CLUB

THIS professional club is designed to meet your day-to-day on-the-job needs by providing practical books in your field on a regular basis at *below publisher prices.* If you're missing out on important technical literature—if today's high cost of reading curbs the growth of your library—here's the solution to your problem.

The Computer Professionals' Book Club was organized for you, to provide an economical reading program that cannot fail to be of value. Administered by the McGraw-Hill Book Company, all books are chosen by qualified editors and consultants. Their understanding of the standards and values of the literature in your field guarantees the appropriateness of the selections.

How the Club operates: Thirteen times a year you receive free of charge *The Computer Professionals' Book Club Bulletin.* This announces and describes the Club's featured book of the month as well as alternate selections available at special members' prices. If you want to examine the Club's feature of the month, you do nothing. If you prefer one of the alternate selections—or if you want no book at all—you notify the Club by returning the card enclosed with each *Bulletin.*

As a Club Member, you agree only to the purchase of four books (including your first selection) over a two-year period. Considering the many books published annually, there will surely be at least four you would want to own anyway. By joining the club, you save both money and the trouble of searching for the best books.

MAIL THIS COUPON TODAY

COMPUTER PROFESSIONALS' Book Club
P.O. Box 582, Hightstown, New Jersey 08520

Please enroll me as a member and send me the three books indicated. I am to receive the two bonus books at the introductory price of $2.95 plus my first selection, plus tax, postage, and handling. If not completely satisfied, I may return the books within 10 days and request that my membership be cancelled. If I keep the books, I agree to take a minimum of three additional books during the next two years at special Club prices (guaranteed 15% discount, often more). I will receive the Club Bulletin 13 times a year. If I want to examine the featured selection, I need take no action. It will be shipped automatically. If, however, I want an alternate selection—or no book at all—I simply notify the Club by returning the convenient card always enclosed. I will always have a minimum of 10 days in which to return the card and you will credit my account fully, including postage, if this is not the case. Membership in the club is continuous but cancellable by me at any time after the four-book purchase requirement has been filled. *This order subject to acceptance by McGraw-Hill. Orders from outside the continental U.S. must be prepaid. Company, business, or institutional tax exemption status is not applicable to purchases made through individual Club memberships. All prices subject to change without notice. Offer good for new members only. A shipping and handling charge is added to all shipments. Members are billed when books arrive.*

Write Code # of 1st *bonus* book selection here	Write Code # of 2nd *bonus* book selection here	Write Code # of 1st book selection here

Name _____

Address _____

City _____ State _____ Zip _____

EXTRA SAVINGS: Remit in full with your order, plus any local and state tax, and McGraw-Hill will pay all regular postage and handling charges. **P39392**

Performance Makes Electrical/Electronics Plastics Profitable

NPE/79

Plastics for Profits

NPE/79 will be the largest and most comprehensive Plastics Exposition ever staged by the U.S. plastics industry. From June 18-22, 1979, more than 500 companies from all over the U.S., Canada, Mexico, Europe, the Far East and South America will be introducing their most up-to-date advances in plastics materials, processes, machinery, instrumentation in Chicago's McCormick Place. A concurrent Conference will feature authorities reporting plastics industry developments, new technology, new marketing opportunities. The combination package will show you how plastics' performance can mean profits for your company.

The diversified electrical/electronics industry consumed 1.6 billion pounds of plastics in 1977 and current demands point to 2.65 billion by 1980. Projections call for utilization of 6.8 billion pounds by the turn of the century! New developments in high performance plastics will help spur a 40% increase in the business machine sector by 1980. Data processing equipment manufacturers comprise a practically bottomless market segment. Plus new plastics wire/cable insulating materials for construction, mass transit, nuclear power uses ... illustrate numerous imaginative concepts being rendered practicable by plastics.

Come see it all at NPE/79—the latest material/process innovations—revolutionary design modes—newest production techniques.

Single Low Fee Covers All Events

A single economical registration fee entitles you to unlimited access to the 1979 National Plastics Exposition plus all 16 seminars of the National Plastics Conference. Both events are held in McCormick Place. Unlimited two-way free bus service between major Chicago hotels and McCormick Place is also included.

Plastics Conference—Electrical/Electronics Update

The concurrent 1979 National Plastics Conference will feature authorities from the electrical/electronics and plastics industries reporting the latest developments in technology as well as new marketing opportunities. Learn about emerging trends in major application areas, including computers and business machines, small and large appliances, home entertainment products, as well as the impact of new insulation standards. A special plastics course will be conducted daily.

Register in Advance

By registering in advance, you pay a discounted fee of $7.50 (vs. $10.00 on-site), and avoid the registration line when you arrive at the Exposition. Write now for complete registration materials to address given below.

See an Entire Industry Under One Roof

At NPE/79 you will see the exciting new developments that have been taking place in plastics since the last Show in 1976—all under one roof at one time. Every industry sector will be represented. Write to NPE/79, The Society of the Plastics Industry, Inc., 355 Lexington Avenue, New York, New York, 10017, for your pre-registration kit.

1979 National Plastics Exposition

June 18-22, 1979
McCormick Place
Chicago, Illinois

Sponsored by:
The Society of the Plastics Industry, Inc.

250 Circle 250 on reader service card

NEW!





WHY CUT?
WHY STRIP?
WHY SLIT?

WHY NOT...

JUST WRAP™

U.S.A. FOREIGN PATENTS PENDING

- AWG 30 Wire
- .025" Square Posts
- Daisy Chain or Point To Point
- No Stripping or Slitting Required
  ....JUST WRAP™....
- Built In Cut Off
- Easy Loading of Wire
- Available Wire Colors:
  Blue, White, Red & Yellow

***$14.95**

	JUST WRAP TOOL WITH ONE 50 FT. ROLL OF WIRE	
COLOR	PART NO.	U.S. LIST PRICE
BLUE	JW-1-B	$14.95
WHITE	JW-1-W	14.95
YELLOW	JW-1-Y	14.95
RED	JW-1-R	14.95
	REPLACEMENT ROLL OF WIRE 50 FT.	
BLUE	R-JW-B	2.98
WHITE	R-JW-W	2.98
YELLOW	R-JW-Y	2.98
RED	R-JW-R	2.98



DAISY CHAIN POINT TO POINT

ok®

MACHINE & TOOL CORPORATION 3455 CONNER ST., BRONX, N.Y. 10475 (212) 994-6600/TELEX 125091

*MINIMUM BILLING $25.00 / AD SHIPPING CHARGE $2.00 / NEW YORK CITY / STATE RESIDENTS ADD APPLICABLE TAX.

Circle 251 on reader service card

Low profile Schadow Modular Switches

disc

the heart of the disc switch

- Low cost
- 3 point sealed contacts
- High reliability
- SPST, momentary, crisp tactile feel
- Cycle life: $5x10^6$ @ 50mA
- Broad range of switching power...from a few milliwatts to 30 watts
- Low bounce (less than 100 micro-seconds)
- Variety of actuators with or without L.E.D. illumination

digitast



SPDT momentary switch with crisp, tactile feel. Cycle life: $5x10^6$ @ 20mA. Black, white, red, blue, grey, green, orange, yellow buttons. L.E.D. illumination and graphics optional. Variety of cap styles.

REK



Flat compact design. Low cost. SPST or SPDT. Crisp, tactile feel. Cycle life: $1x10^5$ @ 10mA. Electrical rating: 20mA. Black, white, red, blue, green, orange, yellow buttons with or without graphics.

Fast service on free samples, specs and price quotations.

Ask for switches by our first name ...Schadow

ITT Schadow Inc.
8081 Wallace Road, Eden Prairie, MN 55344
612/944-1820 • TWX 910-576-2469

ITT Schadow

Data acquisition

Z80-based system offers flexibility

Real-time computing unit uses modular approach to serve differing needs

Flexibility should be the cornerstone of any product aimed at a broad market. That was the philosophy of engineers at Signal Laboratories when they designed CompuDAS, a real-time computing data-acquisition system intended for a wide variety of industrial measurement and control applications.

"CompuDAS fills the gap between limited-capability data loggers and costly minicomputer systems," explains Allen Roth, the company's vice-president of engineering. "Since this is such a wide gap, we made the instrument completely modular, allowing users to tailor systems to their particular applications." Such applications, according to Roth, include process control, testing in research and development laboratories, and data collection either with or without connection to a host computer.

The basic unit, built around a portable or rack-mountable chassis with an 18-slot card cage, contains: a Z80 microcomputer board; 16 kilobytes of random-access read/write memory; the programming language Dabil 1, an easy-to-learn subset of Dartmouth Basic, housed in read-only memory; one RS-232-peripheral port; and all necessary power supplies. A real-time clock is included in software; a more accurate battery-powered clock is optional.

The user can increase the processing power of the instrument by adding another 16 kilobytes of RAM and a high-speed arithmetic processing card that contains an array of commonly used arithmetic and trigonometric functions. To customize CompuDAS to the application, the user adds dedicated plug-in circuit cards, all with integral signal conditioning, from one or more of the following functional groups.

For electrical measurments, a digital input/output board provides software control over 64 discrete transistor-transistor-logic input or output lines. A low-level board containing a multiplexer, an analog-



← Circle 252 on reader service card

Everything you need to know about flat cable/ connector systems.

To save space. To increase circuit flexibility and reliability. To lower total installed cost. To profit from the state-of-the-art in mass termination.

T&B/Ansley offers you the industry's broadest line of flat cable/connector systems. That's because we've been flat cable specialists for decades, and we were pioneers in the development of cost effective mass-termination techniques for volume production and ease of assembly.

Now we're also offering an engineering specification bible that tells you everything you need to know about mass-termination cable/connector systems.

That includes connectors, headers, mounting hardware. It includes round and flat conductor flat cable, as well as jacketed and shielded jacketed cable. It includes our MICRO-PITCH line, which is ideal for mass termination in high density, controlled impedance applications. And our FLEXSTRIP® Jumpers, the most flexible, reliable components available for interconnecting one circuit board to another.

It includes a complete line of hand and bench tools for volume installations, small production runs, or field service applications.

And a great deal more. And it's free. So you'll never get a better offer. Call or write today.

T&B/Ansley

The mass termination company.

T&B/Ansley Corporation
Subsidiary of Thomas & Betts Corporation
3208 Humboldt St. • Los Angeles, CA 90031
Tel. (213) 223-2331 • TELEX 68-6109
TWX 910-321-3938

Stocked and Sold through Authorized Ansley Distributors.

Circle 253 on reader service card

Send for your free copy today!

International T&B/Ansley Offices: AUSTRALIA, Brookvale, (02) 938-1713 • **AUSTRIA,** Vienna, (222) 645206 • **CANADA,** Iberville, Quebec, (514) 347-1014 • **ENGLAND,** Luton, (0582) 597-271 • **FRANCE,** Rungis, 687-23-85 • **HOLLAND,** Zoetermeer, (79) 214688 • **ITALY,** Milano, 02-4986451 • **JAPAN,** Tokyo, 03-354-9661 • **SINGAPORE** (65) 2923711 • **SOUTH AFRICA,** Benrose 24-8134 • **SPAIN,** Barcelona, (93) 212-8607 • **SWEDEN,** Upplands Vasby, 0760-86140 • **SWITZER-**

to-digital converter, and an amplifier scans 30 channels of differential analog data at 1,500 channels per second, accepts it at five strap-selectable levels, amplifies it by one of seven programmable gains, and converts it with 12-bit precision. A multiplexer expander board increases the analog input capacity to 480 differential or 992 single-ended channels that accept voltages with amplitudes up to ±10 V, full scale.

A resistance interface board provides excitation, bridge completion, balance, and calibration for eight variable-resistance transducers like strain gages and resistance temperature detectors. A counter-timer board lets CompuDAS measure eight channels of time intervals, events per unit of time, and frequency. Further, an isothermal interconnect tray enables ambient-temperature compensation of thermocouples in 10-channel groups.

For control, a digital-to-analog output board with four 12-bit d-a converters permits control of proportional valves and outputs to strip-chart recorders and analog displays. The board can be strapped for five different output-voltage ranges, or for a 4-to-20-mA current loop. A relay output board gives the user 16 relays for controlling external loads up to 1 A each, with manual-override capability.

For communications, the user can purchase several front-panel options that allow CompuDAS to function as a stand-alone unit. These include a 20-column thermal printer, a microcassette recorder, an interactive 40-character alphanumeric dot-matrix display, and a 37-key keyboard with 15 dedicated-function keys and eight light-emitting diodes for indicating operating modes. To expand the unit's communications capability beyond the one RS-232 port provided, the user can add a four-channel serial input/output board that allows interface with four additional RS-232 peripherals like display terminals, printers, floppy-disk drives, and host computers.

Depending on the configuration, CompuDAS costs from $11,900 to $25,000. It measures 10.5 by 16.5 by 22.5 inches and weighs about 60 lb. Delivery takes 60 to 90 days from receipt of order.

Signal Laboratories Inc., 202 N. State College Blvd., Orange, Calif. 92668. Phone (714) 634-1533 [381]

BEGONE CURSED ALIAS

The new Precision 616 cuts clean with programmable ease. 80 dB/octave attenuation slopes and time domain filters superior to Bessel. Up to 16 filter channels, programmable for gain and cutoff frequency. Interfaces with mini, micro or GPIB. Typical phase match is ½°, with worst case of 2°. You get performance that used to require a custom instrument, without paying a custom price.



Call Don Chandler, 607-277-3550, or write for complete specs and a demonstration.

PRECISION FILTERS, INC.
303 W. Lincoln, Ithaca, N.Y. 14850



D-s converter drives three torque receivers

Board modules of the 14-bit digital-to-synchro converter series can drive up to three size-11 torque receivers in parallel, keeping accuracy within ±6 min. The converters accept transistor-transistor-logic–level binary input signals, transforming them into three-wire synchro or four-wire resolver outputs of 90 or 11.8 V rms line to line at frequencies of 60 or



400 Hz, depending on the model.

Outputs are short-circuit–protected and current-limited. Standard output power is 5 VA. The modules measure 4½ by 9¼ by 1 in. and come in industrial and commercial temperature versions. In reasonable production quantities, the converters cost less than $475 each and delivery time is four to six weeks.

Computer Conversions Corp., 6 Dunton Ct., East Northport, N. Y. Phone (516) 261-3300 [383]

12-bit analog input cards board STD bus at low fare

Original-equipment manufacturers designing low-cost 12-bit data-acquisition systems can now consider using Mostek's MD series or Pro-Log's 7000 series microcomputers, thanks to the introduction of four analog-input boards. The STD-bus–compatible DT2720 series consists of cards that range in price from $225 to $325 in lots of 100.

For systems requiring isolation of slowly varying signals in noisy environments, the model 2725 at $325 offers four differential channels that can withstand voltages of up to ±250 V. Absolute full-scale input ranges of 10 mV to 10 V and unipolar and bipolar input modes are resistor selectable.



The card uses a multiplexer and an integrating a-d converter that can provide throughput rates of 20 conversions/s for random channel addresses and 40 conversions/s for sequential. Conversions are accurate to within 0.03% of full-scale range at 10 V and 0.1% at 10 mV. Resolution is within ½ least significant bit. And each $325 model 2735 expands the number of isolated differential channels by eight; as many of these cards can be added as the processor allows.

For faster, nonisolated applications, the $275 model 2724 lets users choose 16 single-ended or eight differential channels. Input configurability and system accuracy are the same as for the 2725. The 2724's multiplexer, sample-and-hold ampli-

GOODBYE ALIAS, HELLO GAIN

The new Precision 416 combines filter and amplifier in 16 programmable channels. You save 35% by buying one instrument instead of two for conditioning analog data for digital conversion. Time delay filters superior to Bessel. Elliptics with 80 dB/octave attenuation. DC differential input stage with



100 db CMRR. Both pre-filter and post-filter gain are programmable for optimum signal quality. Both include overload indicators. Interfaces with mini, micro or GPIB. Phase match is less than 2°. **Call Don Chandler,** 607-277-3550, or write for demonstration and complete specs.

PRECISION FILTERS, INC.
303 W. Lincoln, Ithaca, N.Y. 14850



Circle 255 on reader service card

Speech Synthesizer

†Invented by Forrest Mozer



NEW, LOW-COST, FIXED VOCABULARY SPEECH SYNTHESIZERS FOR OEM USE

- Two 64-word vocabularies available
  - –Full spoken numerics plus a variety of measurement words
  - –ASCII characters: numerics, alphabet, punctuation
- Clear, highly intelligible male voice
- All MOS-LSI circuitry
- 6-bit parallel strobed input
- No external clocks required
- Inputs are TTL compatible
- Analog Speech output signal

$179.00*

*Boards with numbers & calculator functions... only ..... $95.00 **

**Plus state sales taxes where applicable*

Custom Vocabularies can be produced for your particular application.

TELESENSORY SYSTEMS, INC.
3408 Hillview Ave., P.O. Box 10099
Palo Alto, California 94304
Telephone (415) 493-2626

Circle 256 on reader service card

Tool kit or tool case, isn't it time you owned a Jensen?

A Jensen tool kit's combination of functional case, exclusive pallet design, and proven selection of professional-quality tools gets work done faster, more efficiently. Its executive appearance gives you pride in your work; gives customers confidence in your service. Assures you of front-door access to the equipment you are charged to maintain. Choose from more than 50 standard models or let us custom-design a kit to match your needs. Write or call for more information or a free catalog.

JENSEN TOOLS AND ALLOYS
1230 SOUTH PRIEST DRIVE TEMPE, ARIZONA 85281
(602) 968-6231

Circle 185 on reader service card

New products

fier, and successive-approximation d-a converter provide throughputs of 32 to 270 μs per channel depending on full-scale range. The $225 expander card for the 2724, the 2734, provides 24 additional single-ended or 12 differential channels.

All boards are available from stock to five days.

Data Translation Inc., 4 Strathmore Rd., Natick, Mass. 01760. Phone (617) 655-5300 [384]

S-d unit in a single module converts two-speed inputs

The model SDC-361 is a single module measuring about 2.6 by 3.1 by 0.8 in. It converts the input from a two-speed (1:36) synchro into digital outputs in Type II servo loop format. Working in the 47-to-1,000-Hz range, the unit consumes 2 W and can replace bulkier, dual-module systems.

The s-d converter accepts all standard synchro or resolver inputs and can track at rates of 1,000°/s for a 400-Hz carrier and 250°/s for a 60-Hz carrier. The 361 requires no field adjustments and features a control transformer algorithm that makes it inherently more accurate than other systems, according to the manufacturer.

The converter meets the specifications of MIL-STD-202E and is sold in versions that work from 0° to 70°C and −55° to +105°C. In single quantities it is priced at $695 and delivery is from stock to 90 days.

ILC Data Devices Corp., Airport International Plaza, Bohemia, N. Y. 11716. Phone (516) 567-5600 [385]

Fast 18-bit d-a converter sells for under $500

Will engineers want an 18-bit digital-to-analog converter that provides 16-bit accuracy? At Analog Devices—they believe the answer is definitely yes, so they are bringing their DAC1137 with them to display at this year's Electro at the Coli-

Tone Receivers, two ways from two sources.

Two tone receivers with versatile performance capabilities are available from two sources, ITT and Mitel.

Both offer the 88205 single package Hybrid DTMF Receiver System.

Or ITT's 3044 and 3045 DTMF group filters, along with additional limiter circuitry, can be used with Mitel's MT 8820 — or any other similar decoder chip — to design your own tone receiver.

You will find all of these components to be of high quality, and packaged with reliability to meet your most stringent demands. Specify them for your next central office, PABX, key system, mobile paging system or signaling application.

For more information, contact: ITT North Microsystems Division, 700 Hillsboro Plaza, Deerfield Beach, Florida 33441. Phone: (305) 421-8450, TELEX & TWX: 510-953-7523.

ITT North

Microsystems Division

Circle 257 on reader service card

We'll do it your way...



TOGGLES
Bat: 0.21", 0.29", 0.37", 0.413" lengths.
Ball: 0.29" length, 5/32" dia. plastic ball - black, red, blue or white.
Grooved: 0.39" length for that modern look.
Baton: 0.39" length, vinyl inlay - black, red or blue.

BUSHINGS
Plain: Bright nickel finish (.176" dia.)
Threaded: 10-48 with D-flat, or 1/4-40 with keyway.
Watertight: Available in 10-48 or 1/4-40 threaded models.

CASES
Single Pole, Double Pole, Four Pole.

TERMINALS
Wired, PC, Extended PC, Right Angle PC, Vertical Right Angle PC, Right Angle Wirewrap.

CONTACTS
Choice of Gold or Silver

Switches shown are typical of our new TT Toggle Switch Series and are actual size. Pushbuttons and slides, available also.

Our engineering and production groups can provide customized switch designs promptly and economically. Choose from a wide variety of standard TT Series actuator styles, terminal configurations and switching functions.

ALCOSWITCH®

ALCO ELECTRONIC PRODUCTS, INC. a subsidiary of Augat®
1551 Osgood St., No. Andover, MA. 01845 USA
Tel: (617) 685-4371 TWX: 710 342-0552

Circle 256 on reader service card
See us at Electro '79 booth no. 2732

LASERMARK MEANS



A PERMANENT MARK

Problems with smeared or faded marks?
Instead of inking the surface, lasermark produces the desired mark by removing or changing a microscopically thin layer of surface material. The image can be numbers, words, a trademark or any other desired pattern or code and is clear, permanent and unsmearable.

Why not let us lighten up your marking problems! To get the full story on these unique, inkless, non-contact coding and marking systems, contact:

LASER MARK
A DIVISION OF LUMONICS RESEARCH LIMITED
105 SCHNEIDER ROAD, KANATA, (OTTAWA), ONTARIO
CANADA K2K 1Y3
(613) 592-1460

Bringing marking and coding out of the Dark Ages

New products

seum in New York City.

A low-end version of the laboratory-quality DAC1138, the unit's current output settles to within ½ least significant bit in just 10 μs for a full-scale-input step. And its long-term offset and gain stability is within ±2 ppm over a 1,000-hr period. Furthermore, the high-quality converter sells for less than $500.

"People will use a product like this in a non-lab environment," Robert W. Glines, senior marketing specialist for modular converter products, proposes. "It gives them security; they are not going to need field service people to fiddle with it constantly."

The integral and differential nonlinearity temperature coefficients for the module are ±0.5 ppm/°C. The unit will operate over a temperature range of 0° to 70°C, and its gain tempco is ±8 ppm/°C.

The converter gives either current or voltage outputs (jumper connection of the internal amplifier to the current output will give the voltage output). Output ranges of 0 to 5 V, 0 to 10 V, ±5 V, or ±10 V are user-selectable by jumpers. The voltage settling time to ±½ LSB for a full-scale step is 250 μs.

Housed in a 2-by-4-by-0.4-in. package, the converter requires ±5 V dc and +15 V dc power. Acceptable inputs are transistor-transistor logic-level-signals.

Applications for the DAC1137 are abundant, according to Glines. He can rattle off a long list that includes data-distribution systems, high-resolution cathode-ray-tube displays, automatic semiconductor testing, typesetting, frequency synthesis, and nuclear reactor control. "There are two main sets of customers for this converter," Glines summarizes. "Those who need linear resolution for analytical instrumentation and servo systems will use the DAC1137; it will also be excellent for the 16-bit marketplace."

The DAC1137 sells for $460 in quantities of 1 to 9. Delivery is stock to four weeks.

Analog Devices Inc., Rte 1 Industrial Park, Norwood, Mass. 02062. Phone Bob Glines at (617) 329-4700 [382]





Chemicals for a bold new world.

Optical waveguides. Thin film memory. Liquid crystal displays. Wherever today's breakthroughs are shaping tomorrow's world, you'll find EM Laboratories as a source for fine chemicals.

We manufacture chemicals for vacuum deposition, liquid crystal displays, fiber optics, crystal growth... dopants for electronics ... that's just the start. And the R&D for tomorrow is bubbling in our labs.

Pure consistency in fine chemicals from EM Laboratories. Whatever you need to frame your future, we produce it. For a better world.

Pure Consistency...

EM Laboratories, Inc.
associate of
E. Merck, Darmstadt, Germany
500 Executive Boulevard
Elmsford, N.Y. 10523
(914) 592-4660

◆ Chemicals for electro optics ◆ Suprapur® ◆ Patinal®
◆ Aneron® ◆ Licristal® ◆ Selectipur®

Circle 259 on reader service card

Symbols of the World's Most Precious Elements



Pt, Au, Ag, Gs

The last symbol in our list stands for GUARANTEED SPECIFICATION. To us at TELEDYNE PHILBRICK, it's every bit as precious as platinum, gold, or silver. That's because our customers know that when we guarantee a performance parameter, the guarantee is as good as gold.

Another reason why....

No One Does It Better Than Philbrick

TELEDYNE PHILBRICK

DATA CONVERTERS, V/F/V CONVERTERS, LINEARS, NONLINEARS, POWER SUPPLIES

Allied Drive at Route 128, Dedham, Massachusetts 02026
Tel: (617) 329-1600 TWX: (710) 348-6726 Telex: 92-4439

Circle 703 on reader service card

Feed all your forms to our wide-open printer

The OEM impact printer wide open on 3 sides



With an edge guide sensor on one side and the other three sides open, our alphanumeric DMTP-8 impact form printer ends worries about forms that won't fit. You can easily insert from bank checks to out-size pages, single sets to multipart reports... any forms where you need to print up to 50 characters per 4" line.

Consider the advantages! Programmable character pitch, heavy-duty construction and an extra long-life dot matrix printing head means real durability. Its exceptionally long needle stroke turns out crisp multiple-copy printings on thicknesses from .003" to .015" —without adjustment.

Its easily replaceable ink rollers and self-reversing ribbon gives you a 10 million character life.

ALL THAT, YET STILL ECONOMICAL— ONLY $269 IN 100's.

PA **PRACTICAL AUTOMATION, INC.**

Trap Falls Road
Shelton, Conn. 06484
Tel: (203) 929-5381

Circle 260 on reader service card

What makes Northern Ireland work for the electronics industry?

More than 40 firms in the industry are at work in Northern Ireland today. Companies headquartered in the U.S., Europe, and Great Britain are engineering everything from appliances to sophisticated components.

The industry is long established. Support services are in place for research and development as well as for manufacturing. And there are special grants available to help you turn R&D into profitable products.

There is no shortage of skills in the work force of Northern Ireland. American companies who have come here find that people bring to work not only experience, but also a deep sense of company loyalty, a good labor relations record, and positive attitudes toward attendance and productivity.

New arrivals also find transportation links and first-class telecommunications that make it easy to do business in the Common Market or anywhere else. And nowhere in the EEC is there a better overall package of incentives to help a new venture succeed.

Find out how the people and the province can work for you. Get the facts from Reg Browne or George McLaren at the Northern Ireland Industrial Development Office in New York. They can quickly tailor an offer of assistance to suit your plans. Call (212) 593-2258. Or write: NIIDO, British Consulate-General, 150 E. 58th Street, New York, NY 10022.



Kieran Fitzpatrick works. An apprentice for the past year, he's building a career in electronics with Grundig.

Northern Ireland works.

Circle 261
on reader service card

When your chips are down your best bet is an AQ Interactive μP System Analyzer



It's fast and safe - In-circuit interactive testing allows direct probe connection to your microprocessor chip. The chip always remains in its socket. Can even be soldered in. The possibility of damage to chip or socket is eliminated. Test your whole system in its own configuration, including the microprocessor chip.

It's versatile - The AQ6800 Analyzer is compatible with all 6800 and 6802 systems. And the new AQ8080Z covers the 8080, 8085, and Z80. Ideal for development work, production testing, and field service.

It's interactive - Examine or modify memory locations, I/O ports and internal registers. Run or single step your program. Isolate hardware and software troubles fast with selective real time monitor and breakpoint.

Don't gamble - Call Steve Halpern today at (914) 962-4264 for all the facts. Or write for free brochures with all specifications.

AQ SYSTEMS, INC.

1736 FRONT STREET, YORKTOWN HEIGHTS, N.Y. 10598
(914) 962-4264

Circle 262 on reader service card

It's what you expect from Data Precision.
Our 3½ digit Model 935 full function DMM gives you 0.1% accuracy on DC volts, as good as many lab/bench instruments, and equally high accuracy on all of its 29 ranges. All this comes in a palm-sized, lightweight package that goes anywhere to solve your measurement problems.
It stays accurate too. Guaranteed for a full year between calibrations (by only one adjustment!). And even if you bang it around or subject it to large overloads — the 935 is designed to take it.
MODEL 935. Unmatched performance at an unmatched price: $149.00 (USA)
Available from stock at all Data Precision representatives.

ACCURACY Where you need it.

DATA PRECISION®
Performance in the field.

Data Precision Corporation, Electronics Avenue, Danvers, MA 01923. Telephone: (617) 246-1600, Telex 921819.

Circle 704 for demonstration
Circle 705 for further information

VISIT US AT ELECTRO, BOOTHS
1814-16-18

LOW BOUNCE!

Low level switching for dry circuits





For years, EAO Series 01 and 31 Lighted Pushbutton Switches have been supplied for applications in control panels, instrumentation, telecommunications, computers and medical electronics.

Now both the 01 and 31 Series are available with low level switching elements that can handle the dryest of dry circuits . . . from micro-volts and micro-amps up to a maximum of 100 mA at 60 volts. This is made possible by our unique contact design . . . 4 gold plated contact fingers of different length . . . contact bounce less than 100 micro-seconds.

This low level, low bounce switch is perfect for direct interface with today's requirements of electronic circuitry. With 5 million operations and a price no higher than our standard 01, 31 units.

Low level lighted pushbuttons come with round, square and rectangular bezels, momentary or maintained action with universal terminals for soldering, P.C. board mount, or quick connect termination.

The original and still the finest Series 01 and 31 from EAO SWITCH CORPORATION.

EAO Switch, you can feel the difference.

EAO SWITCH CORPORATION

255 Cherry Street/Milford, CT 06460/(203) 877-4577/TLX-EAO SWITCH MFRD 964347

ELECTRO/79 Booth 3604

Circle 263 on reader service card

GIMINI Cricket

The chip that chirps....

or cheeps, bleeps, hums, peeps, buzzes, dings, rings, roars, beeps, toots, blips, bongs, honks, hoots, hics, pings, booms, whistles, arts, or...

The point is, if you need a sound, GI's new "GIMINI Cricket" programmable sound generator, the AY-3-8910, can produce it. This gives a designer practically unlimited possibilities because, under full software control, the chip can generate complex sounds or combinations of sounds — music to soothe, rings and buzzes to alarm, and just about anything in between.

The AY-3-8910 is a natural for any products using microprocessors, interfacing easily to most 8- and 16-bit MPU's. In addition, it readily connects to most single-chip microcomputers — our PIC series, for example. The low-cost, AY-3-8910 has three independently programmed sound channels, an analog envelope generator, and two general purpose 8-bit I/O ports.

And all that's required for operation is a single 5V supply, a 2 MHz clock and a microprocessor controller.

With virtually all the hardware necessary to meet most audio needs, the AY-3-8910 has immediate application for a wide variety of systems and products providing audible signals, synthesized music and unique sound effects, to name but a few. The "GIMINI Cricket" chip is available in quantity and ready to chirp, cheep, beep — or whatever you decide to program into your product.

For more information on the AY-3-8910 and a free copy of our 1978 Product Guide, write to General Instrument Microelectronics, 600 West John Street, Hicksville, New York 11802, or call (516) 733-3379.

We help you compete.

GENERAL INSTRUMENT CORPORATION
MICROELECTRONICS

Industrial

Weighing system displays 5 digits

Load-cell digitizer with 40,000-count resolution sells for $295 in 100s

Load-cell digitizers are constantly breaking fresh ground in industrial weighing applications as companies seek the advantages of electronic over mechanical scale systems. Analogic Corp. is meeting this market need with a five-digit microprocessor-based digitizer able to drive four 350-Ω load cells.

The AN5315 digitizer offers tool-operated tare switch, center-of-zero indicator light, switch-selectable pound or kilogram display, and a light-emitting-diode readout up to 99,990 with polarity indication. The internal count resolution is 40,000, whereas the display's full-scale increment totals are selectable by internal switch as any multiple of 1,000 from 1,000 to 10,000. The center-of-zero requirement of a 4:1 minimum ratio of internal-to-display resolution accounts for the 10,000 display maximum. Display multipliers are also internally selectable.

The dead-load zero offset has a normal maximum of 30 mV (2 mV/V), which is adjusted in three stages. The coarse adjustment is by means of a DIP switch. The medium adjustment is made by an internal potentiometer, and the fine adjustment uses a front-panel potentiometer. This method allows the overall temperature coefficients to meet the U. S. and OIML regulations of 20 and 5 ppm/°C, respectively.

The display, which is updated every 400 ms, has a jumper-selectable decimal point for each digit. In case of overload (more than 102% of full scale) it goes blank.

An important error-reducing feature of the AN5315 is its push-to-acquire tare function. A tool-operated switch allows the unit to acquire the gross weight display as the tare value. This value is automatically converted into the appropriate pound or kilogram value depending upon the position of the lb/kg front-panel switch. Therefore, no error can be caused by changing



Choose a TELEQUIPMENT Oscilloscope for:

Reliability.

Like the reliability you'll get when you take the 15-MHz D34 with you on a service call. A dual-trace, battery-powered portable, the D34 is built to take the rigors of on-site service and bounce back for more. It's a top choice for servicing business machines and communications gear.

Reliability is no accident with the D34 or the 8 other instruments built by Telequipment, a division of Tektronix. A family of high value oscilloscopes priced from $495* to $1,995*, TELEQUIPMENT Oscilloscopes are engineered for reliability from the earliest stages of design. Circuits require minimum calibration and components are chosen for off-the-shelf availability, stability and long life.

And TELEQUIPMENT Instruments are now sold through stocking distributors offering local availability, service, warranty repairs and models previously not sold in the United States.

For facts on Telequipment reliability and the name of the Telequipment Distributor nearest you write: Telequipment U.S. Sales, (43/000), P.O. Box 500, Beaverton, OR 97077 or call: (503) 644-0143.

*Suggested U.S. list price

TELEQUIPMENT

A division of Tektronix U.K. Ltd., a subsidiary of Tektronix, Inc.



For Technical Data circle #706 on Reader Service Card
For Demonstration circle #265 on Reader Service Card

A vibrant beat from Switzerland: the Quartz DE-26.*

32 kHz leaf-type tuning-fork crystal. Only 2 x 6 mm. Low resistance, high Q. Excellent resistance to shock and vibrations.

Introducing the DE-26 Quartz from Switzerland. It's as conveniently miniaturized as any on the market. So is its price.
It's made the way the Swiss make everything: reliable. Using state-of-the-art processes backed by repeated, methodical inspections.

In technology and in price, the Quartz DE-26 is designed for a broad and growing range of applications where reliability is as important as tight costing.

DE-26: the rational solution from Switzerland. Write for specs today.

ETA SA

Fabriques d'ébauches / Division diversification
2540 Grenchen, Switzerland
telephone 065/51 11 21, telex 34 284 assa ch
A membre of the Ebauches Group.

Wide Band, Precision

CURRENT MONITOR

With a Pearson current monitor and an oscilloscope, you can measure pulse or ac currents from milliamperes to kiloamperes, in any conductor or beam of charged particles, at any voltage level up to a million volts, at frequencies up to 35 MHz or down to 1 Hz.

The monitor is physically isolated from the circuit. It is a current transformer capable of highly precise measurement of pulse amplitude and waveshape. The one shown above, for example, offers pulse-amplitude accuracy of +1%, −0% (typical of all Pearson current monitors), 10 nanosecond rise time, and droop of only 0.5% per millisecond. Three db bandwidth is 1 Hz to 35 MHz.

Whether you wish to measure current in a conductor, a klystron, or a particle accelerator, it's likely that one of our off-the-shelf models (ranging from ½" to 10¾" ID) will do the job. Contact us and we will send you engineering data.

PEARSON ELECTRONICS, INC.
4007 Transport St., Palo Alto, CA 94303, U.S.A.
Telephone (415) 494-6444



Circle 267 on reader service card

New products

from kg to lb, or vice versa, as can happen in weighing systems that employ a thumbwheel switch to enter the tare value.

The AN5315 comes in table-top and panel-mounting versions. Its water-sealed front panel uses pressure switches. The unit's specified operating temperature range is −10° to +50°C.

Available options include automatic zero tracking (to compensate for minor variations in climatic and other oprating conditions), binary-coded-decimal output, and a printer interface. The interface includes a motion detector to inhibit the printer if the output is not stable and also in case of overload or negative gross weight.

Paul F. Coughlin, marketing manager for the industrial digitizing systems product group, believes the AN5315 will find its greatest use in the retrofitting of mechanical scales, although platform scales and tank weighing will be close in market applicability. "We'll be able to automate mechanical systems and, we hope, make them more precise," he observes. "The advent of the microprocessor has allowed us to offer features not available before at a reasonable price."

The AN5315 sells for $295 in hundreds and has a delivery time of four weeks.

Analogic Corp., Audubon Road, Wakefield, Mass. 01880. Phone Paul Coughlin at (617) 246-0300 [401]

Process-control system performs hardwired logic tasks

The WP6000 is a microprocessor-based process control system that lets the instrumentation or original-equipment manufacturer establish the logic, time, and control requirements for a small process without reconfiguring any hardwired logic. By means of branching functions in its 79-step program, the WP6000 can perform the work of a hardwired logic system requiring several thousand steps.

Selling for under $400, the con-

Choose a TELEQUIPMENT Oscilloscope for:

Performance.

Like the performance you'll find in the 25-MHz D67A. A real bench-top work horse with dual trace, calibrated delayed sweep, 10 mV/div sensitivity, and a big 8 x 10 cm crt display. All for only $1,660.* Ideal for the researcher, engineer, educator, or service technician.

There are eight other TELEQUIPMENT Instruments combining the performance you'd expect from a division of Tektronix with the high value you demand in low-cost instrumentation. Storage models, battery powered portables, low-cost basic oscilloscopes, and even an inexpensive curve tracer. Priced from $495* to $1,995.*

And TELEQUIPMENT Instruments are now sold through stocking distributors offering local availability, service, warranty repairs and models previously not sold in the United States.

For proof of Telequipment's performance and the name of the Telequipment Distributor nearest you, write: Telequipment U.S. Sales, (43/000), P.O. Box 500, Beaverton, OR 97077 or call: (503) 644-0143.

*Suggested U.S. list price.

TELEQUIPMENT

A division of Tektronix U.K. Ltd a subsidiary of Tektronix Inc



For Technical Data circle 707 on Reader Service Card
For Demonstration circle 708 on Reader Service Card

troller has eight front-panel control functions, five programmable input signals (including a predetermining counter), and four control relay outputs. At present the WP6000 can accommodate four input/output channels, and expansion kits will be offered at a later date to handle greater I/O needs.

Once a system's requirements have been defined, users may purchase a chassis version of the WP6000 without programming switches that contains the controlling program in read-only memory. Based on volume and program complexity, the WP6000 will drop from under $400 for a single development unit to $100 each for some chassis packages. Delivery is from stock for both the programmable system and the chassis.

Minarik Electric Co., 232 E. Fourth St., Los Angeles, Calif. 90013. Phone Blair Randle at (213) 624-8876 [403]

LED photoelectric scanners come with complete package

Designed for a wide range of motion-control applications, each miniature photoelectric scanner in the Trim Scan series has as its active elements a light-emitting-diode source, a sensor, a power supply, an amplifier, and an output relay. These devices are enclosed in small housings that can be easily mounted for different configurations. The series consists of three retroreflectors operating over distances to 20 ft and one reflector with a 12-in. range.

Weighing only 5.5 oz the model MCS-164 has a control response time of 30 ms and a scanning rate of 1,000 per minute and does not need an external lens. In addition to the MCS-164, the −161-1, −162-1,





Here's why Raytheon relies on Titchener redesign.

This one-piece, welded steel wire and sheet metal monitor frame, used in the "intelligent terminal" of Raytheon Data Systems' information retrieval system, replaced a sheet metal unit that required six separate riveting operations. As a result, Raytheon reports a reduction in unit costs. What's more, our redesign reduced assembly time; provided easy accessibility for testing and maintenance; trimmed the assembled unit's shipping weight. And because it's a completely welded, one-piece design, Raytheon got a stronger chassis, too!

How do we do it? Many customers ask us that question. We analyze part cost and functions, eliminating unnecessary metal and simplifying machining and assembly operations wherever possible. And in every case you get a design that improves performance and/or reduces production costs.

We'd like to tell you more about our creative design and production concepts and how they can improve performance *and* save you money. Got an idea you'd like to talk over? Call us at (607) 772-1161. And write for your free "Design Idea File". You'll find it's full of more actual examples of the techniques we've used to reduce total costs *and* improve functional performance.

TITCHENER

E. H. Titchener & Co.
24 Titchener Place
Binghamton, N.Y. 13902 (607) 772-1161

Creative design and production in wire, sheet metal and tubing.

PCB Simplicity with Bendix Brush Connectors.



Bendix Brush Connectors can streamline your printed circuit board designs. They don't require the extra board support necessary with conventional, higher mating force connectors and they eliminate the need for secondary actuation systems or procedures used with zero-insertion force connectors. Here's how:

Bendix Brush Connectors increase circuit count per board.

- Reduce number of boards by allowing more circuits per board.
- Greater board effectiveness by providing exact circuit counts up to 400 contacts in only one connector!

Bendix Brush Connectors reduce mating force 70% to 90%.

- Less complex board supports.
- Secondary actuators eliminated.
- Extended mechanical life. Up to 20,000 mates/unmates.
- Fewer damaged boards.
- One connector instead of multiple, fixture-mounted connectors.

Bendix Brush Connectors—a broad product line.

- Mother Board, Daughter Board, Input/Output, PC receptacle body styles.
- 2, 3 and 4 row configurations.
- 90° and straight PC, solderless wrap, crimp removable terminations with multiple lengths and plating options.

Bendix Brush contacts improve electrical characteristics.

- Highly redundant contact sites with multiple electrical paths and wiping action.
- Gold plated wire bristles mesh together intimately with gas-tight junctions.
- Stable contact resistance even after extreme mechanical durability abuse to 20,000 matings.



For full information, call (607) 563-5302, or write The Bendix Corporation, Electrical Components Division, Sidney, New York 13838.

Bendix

We speak connectors.

Circle 269 on reader service card

Electronics Magazine Books Offers You:



1. Microprocessors What you must know about available microprocessor technology, devices, information, 4th printing. $8.95

2. Applying Microprocessors 2nd and 3rd generation technology. 26 detailed applications from data networks to video games. $9.95

3. Large Scale Integration Covers the basic technology, new LSI devices, LSI testing procedures, plus system design and applications. $9.95

4. Basics of Data Communications Includes 47 articles from Data Communications magazine covering more than 11 key areas. $12.95

5. Circuits for Electronics Engineers Contains 306 circuits arranged by 51 functions from Amplifiers to Voltage Regulating Circuits. Saves design drudgery. $15.95

6. Design Techniques for Electronics Engineers Nearly 300 articles drawn from "Engineer's Notebook." A storehouse of design problem solutions. $15.95

7. Memory Design: Microcomputers to Mainframes The technology, devices, and applications that link memory components and system design. $12.95

8. Personal Computing: Hardware and Software Basics More than 50 articles from leading publications, including specifications, helpful hints, subject index. $11.95

Electronics Magazine Books P.O. Box 669, Hightstown, NJ 08520
I must be fully satisfied or you will refund full payment if the book is returned after ten-day trial examination. Send me:

_____ copies of **1.** *Microprocessors* @ $8.95
_____ copies of **2.** *Applying Microprocessors* @ $9.95
_____ copies of **3.** *Large Scale Integration* @ $9.95
_____ copies of **4.** *Basics of Data Communications* @ $12.95
_____ copies of **5.** *Circuits for Electronics Engineers* @ $15.95
_____ copies of **6.** *Design Techniques for Electronics Engineers* @ $15.95
_____ copies of **7.** *Memory Design: Microcomputers to Mainframes* @ $12.95
_____ copies of **8.** *Personal Computing: Hardware and Software Basics* @ $11.95

Discounts of 40% on orders of 10 or more of each book.

☐ Payment enclosed ☐ Bill firm ☐ Bill me
Charge to my credit card:
☐ American Express ☐ Diners Club
☐ Visa ☐ Master Charge

Acct. No. _____ Date Exp. _____

On Master Charge only, first numbers above name _____

Name _____ Title _____
Company _____
Street _____
City _____ State _____ Zip _____
Signature _____

New products

and −163-1 all operate in the infrared region and have a life expectancy of 100,000 hours at −20° to +60°C. For these models, response time is 20 ms and scanning rate is 1,500/min. Delivery is from stock.

Warner Electric Brake & Clutch Co., 449 Gardner St., Beloit, Wis. 53511 [404]

IR thermometer measures 2,500°C target temperature

The 1600WR infrared thermometer can measure target temperatures from 0° to 2,500°C with an error of less than 1% of the indicated temperature. The instrument uses two IR sensing heads that each measure 2 in. by 2 in. by 7 in. and weigh less than 2 lb.

Using radiometric techniques, the 1600WR is zeroed continuously with respect to background temperature to ensure drift-free performance in environments up to 40°C (105°F). Optional water-cooled enclosures for the sensing heads permit measurement in surrounding environments up to 150°C (300°F).

The IR sensing heads can be fitted with various sighting accessories and also can be used as handheld thermal survey instruments. Minimum



resolution is 1.5 mm (0.06 in.). The emittance response can be adjusted by using a 10-turn potentiometer located on the front panel of the indicator-amplifier unit. Response time may be varied from 1 to 5 s. Two set-point alarm relay outputs are accessible on the amplifier's back panel. An optional rechargeable nickel-cadmium battery supply is available for portable operation.

Capintec Instruments Inc., 136 Summit Ave., Montvale, N. J. 07645. Phone (201) 391-3930 [407]

The Cook-able Computer

Introducing a ruggedized version of Intel's iSBC* 80/10A Single Board Computer

From Cryogenics to Hades

Our ruggedized SECS 80/10A likes it hot — or cold. It shrugs off shock, vibration, moisture. And thrives on dust, dirt and grime.

Meets MIL-E-5400, 16400, 4158 — and more. This makes our SECS 80/10A perfect for military systems and tough industrial applications — petroleum, steel, oceanography, communications.

In fact, anywhere a rugged microcomputer is needed.

Functional counterpart of Intel iSBC 80/10A

Exclusively licensed by Intel, our SECS (Severe Environment Computer System) is a functional counterpart of the standard iSBC 80/10A board. Even uses the same development system software.

*Trademark of Intel Corporation

The difference is in the packaging

Our SECS 80/10A, which uses rugged Intel 883B chips, is mounted on a 9″ by 6″ shock and vibration resistant, full ATR compatible board. Conduction cooled, it operates from −55°C to +85°C. Add our numerous support modules and you end up with a versatile severe environment microcomputer system at a fraction of the development cost.

Other SESCO products

We also have a complete line of MIL SPEC core and semiconductor memories. New products include D-DAS, a digital data acquisition system for the 1553 bus, and SETS, a compact digital tape recorder with 23 megabit capacity.

When you're faced with a tough environment, "buy SESCO... it works!"



SECS 80/10A

SESCO

Severe Environment Systems Company

A Subsidiary of Electronic Memories & Magnetics Corporation

20630 Plummer Street • P.O. Box 668 • Chatsworth California 91311
Telephone: (213) 998-9090 • Telex: 69-1404

FASTEST GROWING MANUFACTURER OF REED SWITCHES AND RELAYS.

STANDEX REED RELAYS

Series	Features	Part No.	Poles	Rated Coil Volts	Must Operate	Must Release	Coil Ohms
DG	• D.I.P. and S.I.P. (DG100 & DG109)	DG100-1-5	1	5	4.0	.5	500
	• Diode suppression	DG100-2-12	2	12	9.6	1.0	500
	• Materials UL rated	DG109-1-5	1	5	4.0	.5	500
		DG109-1-12	1	12	9.6	1.0	500
JG	• Dust covered, self leaded	JG100-1-5	1	5	4.0	.5	500
	• 1.00 X .100 and 1.00 X .150 pin spacing	JG100-2-12	2	12	9.6	1.0	440
	• Materials UL rated	JG102-3-6	3	6	4.0	.5	85
		JG102-4-12	4	12	9.6	1.0	250
LG	• Low cost	LG101-1-5	1	5	4.0	.5	500
	• Single and dual poles	LG101-1-12	1	12	9.6	1.0	500
	• 1.00 X .100 pin spacing	LG100-1-5	1	5	4.0	.5	500
		LG101-2-12	2	12	9.6	1.0	300
MG	• Molded construction, self leaded	MG100-1-5	1	5	4.0	.5	500
	• 1.00 X .100 and 1.00 X .150 pin spacing	MG100-2-12	2	12	9.6	1.0	440
	• Materials UL rated	MG102-1-6	1	6	4.0	.5	125
		MG102-3-24	3	24	19.0	2.0	1360

STANDEX REED SWITCHES S.P.N.O. (Form A)

Switch Type	Operate A.T.	Glass Dia. X Lgth. In.	Power Cap.	Current Switch	Voltage Switching	Contact Resis. Max.	Break Volts Min.	Insulation Resis. Min.
GS125 / GR125	30-62.5 / 17.5-62.5	.125 X .780	10VA	1 amp	150 VDC (250 VAC)	.150 ohm	350 VDC Min.	10^{12} ohm
GS100 / GR100	30-62.5 / 17.5-62.5	.095 X .780	10VA	1 amp	150 VDC (250 VAC)	.150 ohm	350 VDC Min.	10^{12} ohm
GT200	50-200	.210 X 2.20	50VA	3 amp	150 VDC (250 VAC)	.100 ohm	500 VDC Min.	10^{10} ohm
GT150	50-100	.150 X .850	25VA	1.5 amp	150 VDC (250 VAC)	.150 ohm	350 VDC Min.	10^{10} ohm
GS560 / GR560	30-42.5 / 12.5-42.5	.090 X .560	10VA	1 amp	100 VDC (250 VAC)	.150 ohm	250 VDC Min.	10^{10} ohm
VS200	100-250	.210 X 2.10	50VA	0.005 amp	7.5KV	.100 ohm	10KV	10^{10} ohm

CONTACT MATERIAL: GS-Standalloy ***(copper/gold)*** GR-Rhodium GT-Tungsten VS-Optional

Standex Electronics a Standex company

4538 Camberwell Road, Cincinnati, Ohio 45209 • (513) 871-3777

Morley Road, Tonbridge, Kent, England • (732) 358398

The Microcomputers you should take seriously.

The C3 Series is the microcomputer family with the hardware features, high level software and application programs that serious users in business and industry demand from a computer system, no matter what its size.

Since its introduction in August, 1977, the C3 has become one of the most successful mircocomputer systems in small business, educational and industrial development applications. Thousands of C3's have been delivered and today hundreds of demonstrator units are set up at systems dealers around the country.

Now the C3 systems offer features which make their performance comparable with today's most powerful mini-based systems. Some of these features are:

Three processors today, more tomorrow.

The C3 Series is the only computer system with the three most popular processors— the 6502A, 68B00 and Z-80. This allows you to take maximum advantage of the Ohio Scientific software library and the tremendous number of programs offered by independent suppliers and publishers. And all C3's have provisions for the next generation of 16 bit micros via their 16 bit data BUS, 20 address bits, and unused processor select codes. This means you'll be able to plug a CPU expander card with two or more 16 bit micros right in to your existing C3 computer.

Systems Software for three processors.

Five DOS options including development, end user, and virtual data file single user systems, real time, time share, and networkable multi-user systems.

The three most popular computer languages including three types of BASIC plus FORTRAN and COBOL with more languages on the way. And, of course, complete assembler, editor, debugger and run time packages for each of the system's microprocessors.

Applications Software for Small Business Users.

Ready made factory supported small business software including Accounts Receivable, Payables, Cash Receipts, Disbursements, General Ledger, Balance Sheet, P & L Statements, Payroll, Personnel files, Inventory and Order Entry as stand alone packages or integrated systems. A complete word processor system with full editing and output formatting including justification, proportional spacing and hyphenation that can compete directly with dedicated word processor systems.

There are specialized applications packages for specific businesses, plus the vast general library of standard BASIC, FORTRAN and COBOL software.

OS-DMS, the new software star.

Ohio Scientific has developed a remarkable new Information Management system which provides end user intelligence far beyond what you would expect from even the most powerful mini-systems. Basically, it allows end users to store any collection of information under a Data Base Manager and then instantly obtain information, lists, reports, statistical analysis and even answers to conventional "English" questions pertinent to information in the Data Base. OS-DMS allows many applications to be computerized without any programming!

The new "GT" option heralds the new era of sub-microsecond microcomputers.

Ohio Scientific now offers the 6502C microprocessor with 150 nanosecond main memory as the GT option on all C3 Series products. This system performs a memory to register ADD in 600 nanoseconds and a JUMP (65K byte range) in 900 nanoseconds. The system performs an average of 1.5 million instructions per second executing typical end user applications software (and that's a mix of 8, 16 and 24 bit instructions!).

Mini-system Expansion Ability.

C3 systems offer the greatest expansion capability in the microcomputer industry, including a full line of over 40 expansion accessories. The maximum configuration is 768K bytes RAM, four 80 million byte Winchester hard disks, 16 communications ports, real time clock, line printer, word processing printer and numerous control interfaces.

Prices you have to take seriously.

The C3 systems have phenomenal performance-to-cost ratios. The C3-S1 with 32K static RAM, dual 8" floppies, RS-232 port, BASIC and DOS has a suggested retail price of under $3600. 80 megabyte disk based systems start at under $12,000. Our OS-CP/M software package with BASIC, FORTRAN and COBOL is only $600. The OS-DMS nucleus package has a suggested retail price of only $300, and other options are comparably priced.

To get the full story on the C3 systems and what they can do for you, contact your local Ohio Scientific dealer or call the factory at (216) 562-3101.

The C3 Series from Ohio Scientific.

C3-B wins Award of Merit at WESCON '78 as the outstanding microcomputer application for Small Business.

C3-S1

C3-OEM

Circle 273 on reader service card

OHIO SCIENTIFIC

1333 S. Chillicothe Road • Aurora, Ohio 44202

Computers & peripherals

System grows to fit big picture

Modular graphic system puts 20,000 vectors on screen, uses adaptive timing

An increasingly competitive graphics market is forcing designers to put together quality systems with both performance and price matched to a particular application. Realizing this, Megatek is unveiling two modular vector-refreshing families dubbed Whizzard.

"This building block concept is especially important to the systems designer and original-equipment manufacturer," stresses Peter Shaw, director of marketing. "It gives them the opportunity to satisfy sophisticated application requirements at the lowest cost—they are not locked into one expensive configuration." This opportunity is provided by the Whizzard 5000 and 7000 series, whose members range from boards to stand-alone systems.

Units in the 7000 series are capable of drawing over 20,000 short vectors, from point to point, on 4,096-by-4,096-element screens refreshed at a rate of 30 Hz. The end points of two different vectors can come within 0.005 in., seeming to the unaided eye to touch neatly, and their intensity is uniform.

These effects are accomplished by a technique in which the electron gun is brought up to speed by being made to trace a loop starting at a vector's beginning coordinate before the beam turns on. To optimize drawing time, loop size and drawing speed are less for smaller vectors, and beam intensity is adjusted so that all vectors are equally intense—a process called adaptive timing.

Bits and prices. For $18,000, designers can purchase the basic 7000 processor unit, which includes the processor board with a 32-bit microprocessor tailored from 2901 bit-slice parts, a vector-generator board, a 62-kilobyte refreshing memory built from 4116-type RAMs dynamic and expandable to 128 kilobytes, a power supply, and a chassis. With monitor, it is priced at $24,000.

The system interfaces not only with popular hosts like the PDP-11, NOVA, and Eclipse, but also with the IBM Series/1, the VAC 11/780, and minicomputers from Varian, Hewlett-Packard, Interdata, and Prime, to name a few.

Graphics data within the system travels over a 32-bit bus while peripherals use a 16-bit bus. Rather than waste the host's processing time by letting it track a cursor, the system's joystick, data tablet or digitizer, and keyboard can be interfaced to an intelligent peripheral controller that records cursor locations; it supplies them to the host only on demand.

An additional $6,000 buys a hardware clip, rotating, scaling, and translating unit that animates two-dimensional pictures in real time and, for an extra $2,000, performs the same chore for three-dimensional graphics as well.

When hard copy is needed, a Rastorizer will pull data from the memory rather than the screen, format it, and plot it on a 4,000-point-line electrostatic printer in 8 to 15 seconds. The board shares the vector generator's microprocessor and is priced at $3,000.

Even cheaper. For really low-cost entry to the Whizzard group, users can buy a 5000 series graphics-processor and vector-generator set for only $6,400. Adding a monitor, keyboard, and hardwired character generator to the two 15½-by-15½-in. boards boosts the price to around $14,000. And as a complete stand-alone system, with dual floppy-disk drives and Data General minicomputer, it costs about $33,500.

By means of its Emutek software, the 5014 version emulates a Tektronix 4014, accepting software routines from it and letting programmers generate new, animated two-dimensional graphics.

Both families use Megatek graphics software based on Fortran and offering a wide variety of display formats. Delivery time is 60 to 90 days.

Megatek Corp., 3931 Sorrento Valley Blvd., San Diego, Calif. 92121. Phone Peter Shaw at (714) 455-5590 [361]

Auxiliary storage unit makes video terminals smarter

The 232 series of data stations can boost the abilities of intelligent cathode-ray-tube terminals or educate

DON'T GET BURNED. GET LEXAN® 940. RESIN

LEXAN 940 resin is one material that keeps you from getting burned on metal's costs and flame retardant plastics' processing problems.

That's because it has metal-like strength at the price of plastic, meets or exceeds most agency flammability standards and, unlike other flame retardant materials, has excellent process stability, flow, and mold release properties.

LEXAN 940 features all standard LEXAN resin properties: 12 ft-lbs/in notched Izod impact strength, optimum dimensional stability, high dielectric strength, exceptional clarity or molded-in color, high gloss and lower finished part cost than metals.

In addition, LEXAN 940 meets UL 94 Standard for V-O*, has an Oxygen Index of 35, is rated at 110°C for continuous use with impact, and produces significantly less smoke emission and toxic gas evolution upon ignition.

And with LEXAN 940 resin, the proof is in the products. For case histories and complete data, write: LEXAN Products Department 318, General Electric Company, One Plastics Avenue, Pittsfield, MA 01201.

*This rating is not intended to reflect hazards presented by this or any other material under actual fire conditions.

Circle 275 on reader service card

WHAT THE WORLD IS COMING TO: GE PLASTICS
LEXAN® NORYL® VALOX® GENAL®

GENERAL ELECTRIC

VISIT US AT BOOTHS 2702, 2704, 2706, 2603, 2605, 2607 AT ELECTRO '79.

The worldwide switch is at hand.

Manufacturers of computers and computer peripherals throughout the world use C&K switches. Producers and designers of test instrumentation, panel boards, word processing, and telecommunication equipment are switching our way too.

And here's why. Our line of mini, submini, and microminiature switches is literally hundreds of thousands of models long. Quality is incredibly high because we specialize exclusively in switches and have developed our own specialized engineering techniques. C&K switches are readily available, at highly competitive prices and with no minimum order requirements.

If you're not with us yet, start switching. Send for our complete new catalog and see for yourself. We give you more to switch about than anyone in the world.

C&K

The Primary Source Worldwide.

C&K Components, Inc.

15 Riverdale Avenue, Newton, MA 02158
Tel: (617) 964-6400, TELEX: 92-2546. TWX: 710-335-1163

ELECTRO/79 Booths 2725-2727

Circle 3 on reader service card

The Personal Computing Book



Take the computer revolution into your own hands!

More than 50 articles are presented from leading publications in the field to give you this up-to-date guide that answers all your questions on personal computing precisely and reliably.

Hardware • Software • Theory • Applications • Helpful Hints

Order today, and don't forget the other valuable Electronics Magazine Books listed in the coupon below.

Electronics Magazine Books
P.O. Box 669, Hightstown, NJ 08520
McGraw-Hill

Send me...

_____ copies of *Microprocessors* @ $8.95
_____ copies of *Applying Microprocessors* @ $9.95
_____ copies of *Large Scale Integration* @ $9.95
_____ copies of *Basics of Data Communications* @ $12.95
_____ copies of *Circuits for Electronics Engineers* @ $15.95
_____ copies of *Design Techniques for Electronics Engineers* @ $15.95
_____ copies of *Memory Design: Microcomputers to Mainframes* @ $12.95
_____ copies of *New Product Trends in Electronics, No. 1* @ $14.95
_____ copies of *Personal Computing: Hardware and Software Basics* @ $11.95

Discounts of 40% on orders of 10 or more copies of each book.

I must be fully satisfied or you will refund full payment if the book is returned after ten-day trial examination.

☐ Payment enclosed ☐ Bill firm ☐ Bill me
Charge to my credit card: ☐ American Express
☐ Diners Club ☐ Visa ☐ Master Charge
Acct. No. _____ Date Exp. _____
On Master Charge only, first numbers above name _____
Name Title
Company
Street
City State Zip
Signature

New products

dumb ones. The data stations are auxiliary storage/retrieval peripherals that are controlled by 16-bit microcomputers.

The peripherals come in versions with up to 16 kilobytes of read-only memory and 64 of random-access, as well as one or two tape transports that accept DC 100A tape cartridges. Each unit connects to a terminal's computer and to a peripheral, printer, or plotter through an RS-232 interface. Communication rates of 100 to 9,600 b/s can be selected by switch.

The stations read and write at 30 in./s and search at 60 in./s. Files may be packed toward the front of the cartridge to minimize search time, and they can be edited an unlimited number of times.

A single-cartridge data station with 3 kilobytes of ROM and 2 of RAM sells for $2,495; a dual-cartridge one for $2,995. Delivery time is under 60 days.

Digital Datacom Inc., 17951 Skypark Circle, Suite K, Irvine, Calif. 92714. Phone (714) 549-8943 [364]

Terminals dash off hard copy in both directions at 180 c/s

The TP2 series of Dasher terminals, consisting of two receive-only printers and two send-receive units with keyboards, prints 180 characters per second, three times faster than earlier versions. Combined with a 1,000-word random-access memory, this speed makes the bidirectional units efficient at continuous rates of up to 1,200 bits per second without any data loss.

Half- and full-duplex transmission

WE WENT TO MULTILAYER BOARDS TO ELIMINATE INTERCONNECT PROBLEMS. NOW QA SAYS WE NEED TO TEST THE BARE PC BOARDS. WHY?

Multilayer boards have solved some interconnect problems but as the complexity of boards increases new problems are created making the need for test at bare board level perhaps more important than ever.

In older methods of assembly the wiring was exposed and as errors were found in system test it was a simple matter to repair the wire connections. With multilayer construction the interconnects have become an integral part of the board assembly. Narrower land widths, closer spacing between land runs and other characteristics of current multilayer board construction offer greater chances for specks, nicks, dirty bath debris and photo errors to occur in board processing. It is not uncommon to experience a yield rate of only sixty to seventy per cent on complex multilayer boards with no "layer" level testing. At this point, identification of errors and subsequent repair is extremely expensive (if not impossible) bringing the average board production cost up dramatically.

As the complexity of multilayer boards increases, the need for test at bare board level becomes a necessity. Testing at inner layer level saves!

Rapid pay back periods can be expected on ATE for multilayer board manufacturing. Bottom line profit is important! Bare board testing makes its contribution and the right test equipment will show a good return on investment.

The Difference in Testing!

DIT-MCO INTERNATIONAL CORPORATION

Dit-Mco International Corporation
5612 Brighton Terrace
Kansas City, Misouri 64130
Telephone (816) 444-9700
Telex Number 42-6149

•

European Technical Representative
RADIX HOUSE
Central Trading Estate
Staines, Middlesex, TW18-4-XA, England
Telephone: (0784) 51444

Circle 10 on reader service card 277

matrox
microprocessor displays

GRAPHICS



256 X 256 to 512 X 512

ALPHA NUMERICS



8 X 16 TO 24 X 80

COMBINED

ALPHA NUMERICS/GRAPHICS

SINGLE CHIP CONTROL



ALPHA CHIP

COMPUTER TO TV MONITOR INTERFACE
AMERICAN & EUROPEAN

VIDEO RAM:	A complete family of alphanumeric CRT controllers with display formats from 8 X 16 to 24 X 80.
GRAPHICS:	Resolutions from 256 X 256 to 512 X 512. Easily combined with alphanumeric VRAMs.
COLOR:	Single board 256 X 256 X 4 bits pixel or multiboard to 512 X 512 X 8 bits pixel.
ALPHA CHIP:	Single chip LED alphanumeric/keyboard display.
ALPHA/GRAPHICS:	Single board aspect ratio combination board 24 X 80 alpha and 240 X 320 graphics.
CUSTOM:	Designed to fit specific needs.

Matrox offers a highly diversified selection of modules and PC boards allowing customers to solve display problems rapidly and cost effectively. These ready to use sub-systems are available off the shelf in self-contained modules, for any uP, or on PC boards, bus compatible with DEC LSI-11, PDP-11, Mostek/Prolog STD, Intel/NSC SBC Multibus, Motorola Exorciser, and S100.

matrox electronic systems

The Visible Solutions Company

5800 ANDOVER ROAD, MONTREAL, QUE. H4T 1H4
TEL.: (514) 481-6838
U.S. ONLY, TRIMEX BUILDING, MOORES, N.Y. 12958

Circle 212 on reader service card

New products

can also be handled at rates selectable up to 4,800 b/s. The terminals (at whose core is the time-tested 16-bit processor of the first microNova generation) use a nine-wire printing head to print upper- and lower-case letters in a seven-by-nine-dot matrix; a 96-character ASCII set is provided. The TP2s also can write user-designed characters and symbols, employing a software feature called down-line loading, and can plot graphic data.

Normal or double-width characters may also be chosen by switch or software, and densities of six or eight lines per inch can be set by switch. Models of the 132-column units are available that print condensed characters, too, at a pitch of 16.5 characters to the inch.

The receive-only printers, the 6075 and the condensed-print 6076, are priced at $3,550 and $3,700, respectively. The keyboard terminals, the 6077 and the condensed-print 6078, sell for $3,750 and $3,900, respectively. Delivery time for all units is 90 days.

Data General Corp., Route 9, Westboro, Mass. 01581. Phone (617) 366-8911 [363]

Unit lets Harris terminals generate printouts and plots

Owners of Harris 1600 remote batch and job entry terminals can now generate electrostatic plots and printouts on any of 18 Versatec printers, thanks to development of a remote plotting controller.

With Versaplot software on the host computer, input data is processed and compressed, then transmitted over data communications lines in encoded raster format to the Harris terminal and thence to the remote plotting controller. Independently, the controller decompresses the data and prints or plots it.

The controller accepts input over RS-232 lines at rates of up to 9,600 b/s and includes self diagnostics. It sells for $6,000; prices for Versatec plotters begin at $6,200.

Versatec, a Xerox company, 2805 Bowers Ave., Santa Clara, Calif. 95051 [365]

Pay as you grow.

When you start to work, it's easy to spend your whole paycheck.

And that's a good reason to join the Payroll Savings Plan and buy U.S. Savings Bonds.

Because Bonds grow with you. So while you're working hard doing your job, Savings Bonds can be working hard doing their job. And that job is making money for you.

Bonds can help cultivate your dreams. Whatever they are. A college education, down payment on a new house, or a long-awaited vacation. Even a retirement nest egg.

Put U.S. Savings Bonds to work for you, storing away the fruits of your labor.

Plant the seeds of your future today. You'll be surprised what they can grow into.

E Bonds pay 6% interest when held to maturity of 5 years (4½% the first year). Interest is not subject to state or local income taxes, and federal tax may be deferred until redemption.

Take stock in America.

Ad Council A public service of this publication and The Advertising Council.

THE 200 MILLISECOND C/V CURVE



MEANS THE HIGHEST THROUGHPUT AVAILABLE

The LOMAC LM25/LM80 Production Process Control and Electrical Wafer Test System gives you:

THROUGHPUT. Lomac production test systems are ten times faster than any other automated testers available, which means remarkable increases in productivity when the LM25/LM80 system replaces your manual curve tracers.

VERSATILITY. The LOMAC systems are *full DC function* testers that perform a wide variety of parametric tests for process control evaluation. In addition to C/V measurements, you can test voltage or current using any combination of up to 96 pins. Other capabilities include ultra-low current measurements, providing 0-100 pA full scale on the most sensitive range.

EASE OF USE. The LM25 and LM80 are easy to use. These Z80 microcomputer-based systems using an enhanced form of Basic, called LOMAC TEST LANGUAGE, allow turnkey operation for immediate testing and data acquisition under full software control.

FLEXIBILITY. The LM25 and LM80 fit the engineering environment as well as the production line. All measurements can be made routinely to an accuracy of 1 part in 4000 (full scale). Contact capacitance has been minimized with the full Kelvin and driven guard bus and matrix structure. Design engineers can quickly evaluate many design options and facilitate engineering characterization of all MOS and bipolar devices.

LM80 with host computer.

EXPANDABILITY. If your needs are modest, you can start with a single, low-cost LM25, which offers the same high throughput of the more sophisticated LM80. The LM25s continue to be an integral part of your system as you expand since each LM80 will coordinate up to four LM25 test systems.

COMPATIBILITY. The LOMAC system will continue to expand to meet your needs, with a wide range of peripheral equipment available for the system, including printers, floppy discs, hard discs, tape drives and smart probers. Available software programming allows up to eight LM25/LM80s to be controlled by a host computer enabling program and data transfer to or from the host in background mode. Supported host computers include those made by Digital Equipment Corporation, Hewlett-Packard Corporation, and Data General Corporation.

LOMAC has been the leader in design and production of systems for process control and electrical wafer test for over six years. Nationwide distribution and service, along with a full one year system warranty, has made LOMAC the leading supplier to all of the major semiconductor manufacturers in the United States.

For more information, write or call Ms. Rosanna McClure at (408) 984-5982.

LOMAC CORPORATION

2118 Walsh Avenue, Santa Clara, CA 95050

Circle 215 on reader service card

Have it your way



The only 40 column printer with NCR reliability now available almost any way you want it.

1. DIET SPECIAL — Mechanism only (low cost, field proven, available in quantity) add your own electronics.
2. TO GO — Cabinetized Version — comes in a handsome, well finished, gray case, for only a little extra lettuce.
3. BIG MECH — Mechanism (in a finished case) with its own power supply, with or without NCR electronics, packaged as a complete unit.
4. ON THE SIDE — NCR driven electronics, available with any selection.

For delivery information, prices, or literature, please contact:
NCR Engineering and Manufacturing
OEM Marketing
P.O. Box 627, Ithaca, New York 14850
(607) 273-6066.

"Have it your way" is a reg. T.M. of Burger King Corporation, Miami, Florida, and is used with permission.

Compare our ingredients and note the extra value of every unit served.



- Works as printer and/or plotter because of unique single wire design
- Multiple copy capability
- Prints up to 120 lines per minute
- Disposable ribbon cassette is operator changeable
- No messy spools or tricky threading

NCR

Engineering and Manufacturing — Ithaca

Circle 11 on reader service card

Circle 18 on reader service card →

OVENAIRE...

...now, more than ever, your best bet for crystal oscillators.

Ovenaire's oscillator capabilities have been enhanced by the acquisition of W.H. Ferwalt, Inc.

- **STATE-OF-THE-ART HIGH STABILITY CRYSTAL OSCILLATORS** with stabilities to 5×10^{-10}/day and 7×10^{-11}/°C.
- **OVENIZED CRYSTAL OSCILLATORS** 3×10^{-9}/°C at low cost.
- **TCXO's** with temperature stabilities to $\pm1\times10^{-7}$ 0 to 50°C.
- **DIP HYBRID CIRCUIT CRYSTAL OSCILLATORS** with temperature stabilities to ±20 ppm.

...and, as always, your best bet for crystal and component ovens.

- **ELECTRONIC CONTROL MINIATURE OVENS FOR:** HC-18U, HC-25U, HC-42U, HC-43U crystals TO5 & TO8 crystal, transistor or IC 14 Pin & 16 Pin DIP IC.

Plus a complete range of ovens for commercial and military applications.

OVENAIRE-AUDIO-CARPENTER
Division of Walter Kidde & Company, Inc.
706 Forrest St., Charlottesville, Va. 22901
804/977-8050 TWX 510-587-5461 KIDDE

Circle 22 on reader service card

FREE Washer Catalog and Sample Pack

Catalog lists 3500 sizes of non-standard washers and spacers available without die charge

All metal washers are flat and tumble de-burred. They are made immediately to your order from existing dies. Materials certified if needed.

Boker's complete stamping capability includes tooling, welding, metallurgical lab, assembly, and quality control. Let us give you a quick quote.

See our ads in Thomas Register under STAMPINGS and WASHERS.

Satisfied customers from coast to coast.

OD's from .086" to 1.936"
ID's from .027" to 1.637"
Thickness: .005" to .125"
Any stampable material

60th Anniversary Since 1919

BOKER'S, INC.
3104 Snelling Ave. So., Mpls., MN 55406 Phone 612-729-9365

Circle 24 on reader service card

The biggest problem with your IEEE bus...

So your new equipment conforms to IEEE standards. Great. But your system doesn't work. Not so great. Either your interface or your software isn't compatible. But which one?

Look no further. This is Model 488. The IEEE Bus Monitor/Analyzer from Interface Technology.

It records, analyzes, and controls. It stimulates, calibrates, tests, and verifies. In short, it does the thinking — and the searching — for you.

Call today for a demonstration of this remarkable time saver. Now that you're on the bus, you don't want to miss the boat.

...is finding why your bus has a problem.



interface TECHNOLOGY

852 North Cummings Road • Covina, California 91724 U.S.A. • (213) 966-1718

France MB Electronique • **Switzerland/Spain** Instrumatic AG • **W. Germany** Kontron Electronik GmbH • **UK** Wavetek Electronics Ltd. • **Japan** Tokyo Electronics Trading Co., Ltd.

Circle 28 on reader service card

Coming through...

with better ways to interface

NEW "GPIB" CABLES

Interface computer power with test and measurement hardware—without lots of time-consuming patchwork wiring.

Belden's new "General Purpose Interface Bus" cable assemblies will become essential tools for you in R/D, quality control and on-the-job trouble-shooting.

Interconnect up to 15 programmable instruments at once. In star or daisy chain networks. Cables work with counters, signal generators, calculators, digital multimeters—in fact, they can be used with any instrument equipped with standard IEEE 488 interfaces. That means hundreds of compatible products today and the hundreds more coming on-stream soon.

These new 24 conductor cables are built to last, too. Semi-rigid PVC insulation and PVC jacket offer good flex life. U.L. recognized self-extinguishing plastic connectors are designed to withstand constant make/break cycling. Contact pins featuring gold over nickel-plated beryllium copper deliver far better conductivity than designs using plain copper. Belden U.L. approved "GPIB" cable assemblies (with metric cadmium plated screws) are available right now in five standard lengths up to 16 m (52.5'). U.L. approved and CSA certified bulk put-ups are also available. Let Belden come through for you. Contact your local Belden distributor or Belden Corporation, Electronic Division, P. O. Box 1327, Richmond, Indiana 47374; 317-966-6661.

BELDEN

Coming through...

with new ideas for moving electrical energy

©1978 Belden Corporation

Circle 30 on reader service card

Products newsletter

Impact printer doesn't hit OEMs in the pocketbook

Taking up only 1.37 ft^2 of space, a fast impact printer for original-equipment manufacturers is priced at $995 in single quantities. It is called the Paper Tiger, and it rips through copy at rates of **100 to 198 characters/s, depending on which of the four pitches—8.3, 10, 12, or 16.5 characters/in.—a user selects.** Controlled by a Motorola M3870 microcomputer, it can recognize the last seven-by-seven-dot-matrix character on a line and immediately return to start a new one, making possible 400-line/min speeds. It prints a 96-character set, has an RS-232 interface, and comes from Integral Data Systems Inc. of Natick, Mass.

Compact unit tests memories at 25 MHz

Dubbed "The Colt," the latest memory tester from Pacific Western Systems of Mountain View, Calif., is a 25-MHz machine that sells in the $50,000 to $60,000 bracket. **Intel Corp., Santa Clara, Calif., is slated to get first crack at the tester, which is designed to check out both static and dynamic semiconductor memories at both the wafer stage and at final test.** The Colt is small enough to slide under the table that houses the prober or device handler. It is software-compatible with Pacific Western's Mustang-2 test system, already used by Intel for testing erasable programmable read-only memories and the new 2920 analog microprocessor.

German learning aid for 8085 processor to be sold here

Good sales on European markets have prompted Munich-based Advanced Micro Computer GmbH (AMC) to introduce its ECB85 microcomputer learning aid to the American market. The system, intended to familiarize users with 8085-based microcomputer applications [*Electronics*, Dec. 21, 1978, p. 4E], **comprises a single-board computer built around an 8085 and a host of peripherals.** It will be available for $825 from Advanced Micro Devices in Sunnyvale, Calif. U. S. deliveries are expected to begin "within a few months," says Erich Gelder, head of AMC in Munich.

How to capture random events

What makes digital-system troubleshooters turn prematurely gray is the random event that always occurs when no one is around. Hewlett-Packard's way of fighting aging is option 003 for its 1741A variable-persistence storage scope. **With this $75 feature, such random signals are automatically stored, redisplayed, and photographed by the model 197B camera ($1,100).** The 1741A scope goes for $4,250.

Eclipse computer gets militarized

Data General's Eclipse computer is now available in a fully militarized version from Rolm Corp., Santa Clara, Calif. Designated the MSE/30, **the rugged computer is aimed at military C^3 data-base management and logistics markets.** It supports AOS—Data General's advanced operating system—along with the data-base–oriented file-management system Infos, ANSI standard Cobol, Fortran, and PL/1.

4½-digit DMM measures 20 A

Keithley Instruments Inc., Cleveland, Ohio, has added a 20-A current-measuring range to its model 179 digital multimeter and dubbed the result the 179-20A. **Priced at $349, the 179-20A is claimed to be the only 20-A 4½-digit DMM available.** It can make continuous measurements on ac and dc currents up to 15 A and periodic measurements up to 20 A.

Hipotronics inc.

HIGH VOLTAGE DC POWER SUPPLIES AND POWER PACKS

Standard supplies from 1 kW to 50 kW

1 kW supply provides 120 kV @ 8 mA

Power Supplies
Complete range of unregulated high voltage dc supplies with voltage outputs from 1 kV to 1000 kV and current outputs from 10 mA to 50 Amps available in standard designs at economical prices. Fully instrumented and protected, these supplies are ideal for:

- Laboratory use
- Capacitor charging
- Laser supplies
- CRT supplies
- Marx generators
- Many more

5, 7.5 & 10 kV @ 5 mA OEM Power Packs

Power Packs
Miniaturized, oil-filled steel cans for OEM use. Voltages from 2.5 kV to 100 kV at 2, 5 & 10 mA. Low cost, high reliability.

Metered Power Packs
Same miniature power packs available with simplified or deluxe controls for rack-mounting. Short circuit current limit option makes these ideal for cap charging applications.

Write or call for complete details.

HIPOTRONICS

HIPOTRONICS, INC.
P.O. Drawer A, Brewster, NY 10509
(914) 279-8031 Twx 710-574-2420
Amex Symbol: HIP

New products/materials

Titanium and palladium etchants are for use in semiconductor and microelectronics applications. The titanium etchant, TFT, is useful from 20° to 50°C and can etch at a rate of 2.5 mil/min at 25°C. The clear material is compatible with negative and positive photoresists and is rinsed with water. TFP, the palladium etchant, has a temperature range from 40° to 60°C and can etch at a rate of 11 nm/s at 50°C. The aqueous solution is compatible with a variety of photoresists, including KPR, KMER, KTFR, and Riston, and can also be rinsed with water.

Shelf life for TFT is a year and for TFP six months. The latter etchant sells for $18 for 1 gallon and $15 each for 4 gallons. The former one sells for $22 per quart, $60 per gallon, and, in quantities of 4 gallons, $50 per gallon.

Transene Co. Inc., Route One, Rowley, Mass. 01969 [475]

An aerosol solvent removes grease or grime from electronic and electrical components and circuits. This trichlorotrifluoroethane compound, Contour Number 40, can be applied as a heavy wet spray. Evaporating quickly and leaving no film to retain dust or oil, it is suitable for such devices as switches, motors, precision

instruments, film equipment, and tools. It is packaged in a 16-oz can and a free sample is available when requested on company letterhead.

Contour Chemical Co., Special Products

Get your 1978 EBG while they last. 1979 edition not available until June.

The only book of its kind in the field.

If you haven't got it, you're not in the market.

To insure prompt delivery enclose your check with the coupon now.

Electronics Buyers' Guide
1221 Ave. of the Americas
New York, N.Y. 10020

Yes, please send me _____ copy(ies) of 1978 EBG.

☐ I've enclosed $25 per copy delivered in the USA or Canada.

☐ I've enclosed $35 per copy for delivery elsewhere ($47 if shipped by Air). Full money-back guarantee if returned in 10 days.

Name _____

Company _____

Street _____

City _____ State _____ Zip _____

The Quick Test.

SERIES 50

NO FAULT INSURANCE

Next.

In less than 4 seconds you can test up to 8,000 points on a bare board. And test the next board quicker than anyone else. And the next. That's testing hundreds of boards per hour.

The Series 50's high-speed scanning allows high throughput on all types of bare printed circuit boards — be they single or double-sided boards, inner-layer, multi-layer or flex circuits.

Quick and simple to operate, the Series 50 features easy self-programming from a known good board, extensive self-diagnostics, rapid "go-no-go" inspection, complete numeric or alpha numeric hard copy error messages and full memory storage on magnetic tape or diskettes.

Next. The Series 50 is modular and expandable. Choose the capability you need today; add additional capability as you require it. Low equipment and operating costs, modular design, easy operation and high test speeds make the Series 50 Family ideal for a variety of applications. You can test bare boards, backplanes, ceramic substrates and cable assemblies. Quickly, easily, accurately. Next time you think about throughput, think about the Series 50 Circuit Verifier line.

By ATEC, an Everett/Charles Company.

ATEC

ASSEMBLY AND TEST EQUIPMENT CORPORATION

2806 METROPOLITAN PLACE
POMONA, CALIFORNIA 91767

EC EVERETT/CHARLES, INC.

RADIATION COUNTERS

for registration of
- alpha radiation
- beta radiation
- gamma radiation
- X-rays
- cosmic rays
- neutrons

Exporter:
V/O TECHSNABEXPORT
32/34 Smolenskaya-Sennaya,
121200 Moscow, USSR
Tel. 244-32-85 · Telex 7628

Techsnabexport

Circle 36 on reader service card

BEAT TOUGH, tiny JOBS!

Snap-on 167-TM-B MIDGET SET



167 ¼-inch drive socket wrenches and handles for a wide range of electrical, electronic and other miniature production and maintenance work. Socket wrench openings from ⅛ inch to 9/16 inch. Other small sets available. See your *Snap-on* representative.

255

FOR ALL INDUSTRY
SNAP-ON TOOLS
8051-D 28th Avenue KENOSHA, WISCONSIN 53140

Circle 37 on reader service card

New products/materials

Division, 3 Draper St., Woburn, Mass. 01801 [476]

A dielectric recording paper for use with electrostatic printers, measuring equipment, and facsimile systems, will operate in an environment with from 0 to 100% relative humidity. According to Matsushita Electric Corp., this surpasses the performance of most other papers, since they are effective only in an area with 40% to 70% relative humidity.

The recording sheet is made up of a base paper, a 6-to-7-μm-thick conductive layer, and a 4-to-5-μm-thick dielectric layer. The dielectric layer is essentially a thin film of resins that can be easily charged when placed in contact with electrodes in the computer terminal, measuring device, or facsimile system. The conductive layer acts as an opposing electrode to hold the charge pattern on the dielectric layer. To form the images deposited by the electrodes, the sheet is passed

through an electrostatically charged toner. The images are then fixed on the paper either by heat or pressure. The image recorded on the paper will not fade or discolor with age.

Specifications for the paper are a resistivity of 10^7 ohms regardless of ambient humidity, a recording voltage of 300 to 700 V, a recording speed of 0 to 500 kHz, and a resolution of more than 8 lines/mm.

One roll of paper 20 in. wide by 328 ft long sells for approximately $36 to $39. Delivery time is scheduled for the beginning of the summer.

Matsushita Electric Corp. of America, One Panasonic Way, Secaucus, N. J. 07094 [477]














Variety show.

Conrac's variety show won't win an Emmy.

But OEM's think it's great just the same.

Where else could they find such a variety of reliable color and monochrome CRT monitors to meet their system needs?

Screen sizes range from a compact 9″ to a dramatic 25″. Resolution capabilities go up to 4,500,000 individual picture elements. Rack, cabinet, or even ceiling mount options are offered.

Models are available for every signal input: NTSC, PAL, SECAM and separate signals for RGB. Also composite, non-composite or external syncing pulses.

Whether your requirement is for simple alpha-numerics or complex graphics and computer-generated imagery, you can depend on Conrac's experience and depth of technology.

And since Conrac monitors are made in the U.S., we're always here to supply first-hand technical assistance and parts.

Call or write for more information today. We'll also send you a "tv guide" for OEM's — the Conrac CRT Monitor Guide.

Conrac Division, Conrac Corporation,
600 North Rimsdale Ave., Covina, CA 91722,
Tel. (213) 966-3511 Telex: 67-0437.

CONRAC

We're more than meets the eye.

Circle 39 on reader service card

MILLIONS OF OPERATIONS

with *Magnecraft's* Mercury Displacement Relay "MDR"

- ▶**MDR's routinely handle in-rush current up to 15 times rated loads.**
- ▶**Liquid Mercury Contact**—provides a new contact surface with every actuation. Mercury is perpetually self-renewing . . . it cannot pit, weld, disintegrate or oxidize.
- ▶**Hermetically Sealed Inert Gas Atmosphere**—the contactor tube is evacuated, then pressurized with an inert gas which extinguishes arcing, contributing to long contact life.
- ▶**Ultra Quiet Operation.**
- ▶**Contact Resistance** less than .003 ohms.
- ▶**(UL) and (CSA) approved**—up to 60 amps continuous current 480 volts AC.

47 DIFFERENT RELAYS
IN STOCK FOR IMMEDIATE DELIVERY.

Sam Goldfus
MDR Product Manager
MAGNECRAFT

SEE US AT
Electro 79
BOOTH 2719 & 2721

MAKE A LOCAL CALL . . . .

206-883-3550	303-841-3435	316-788-0621	602-894-2345
213-641-4255	305-831-8233	317-259-4431	609-933-2600
214-631-9450	312-963-6400	414-784-3390	612-933-2594
216-238-0300	313-398-5556	415-592-8333	617-969-8100
301-465-5944	315-472-5273	516-364-0310	803-233-4637

Magnecraft®
ELECTRIC COMPANY

5575 North Lynch Avenue Chicago, IL 60630
(312) 282-5500

Circle 40 on reader service card

AUGAT MADE ZERO-PROFILE SOCKETS POSSIBLE. NOW WE'VE MADE THEM PRACTICAL.

Not long ago Augat introduced the Holtite™ concept of solderless sockets, to give you zero-profile component plugability without conventional sockets or solder, and the unmatched dependability of machined beryllium contacts.

Now we've made the Holtite idea practical for almost every application – including ones where PC boards already contain soldered components. The Holtite System now offers a new,

Augat contacts, magnified 7X

low cost (just $695) pneumatic insertion machine which presses Holtite contacts into plated-through holes converting the holes into plug-in sockets. Contacts for this new system are preloaded in DIP patterns on a Mylar carrier strip supplied on reels. Typical insertion rate for the machine is 5,000 contacts/hour.

And if you need mass loading capability, we can lease you a machine that loads more than 50,000 contacts/hour.

The thing to remember is no matter what the size or nature of your application, the Holtite System can now offer you all the advantages of sockets: reduced test cycle times, less damage to ICs and PCs from soldering, easier component changes, and economical field maintainability. Holtite delivers all these benefits and still gives you card spacing as low as .400".

You don't have to change a thing to use Holtite; simply drill the holes to the recommended diameter. Prove it for yourself. Order one of our Holtite Prototype kits. With all the tools, contacts, instructions, and test reports you need to judge the system on your job.



The kit costs only $94.50. The reels, the insertion machine, and the trial kit are all available from Augat's worldwide distributors.



Or write Augat, Inc., 33 Perry Avenue, P.O. Box 779, Attleboro, Mass. 02703. Tel. (617) 222-2202.

AUGAT®

Augat interconnection products, Isotronics microcircuit packaging, and Alco subminiature switches.

Circle 41 on reader service card 303

Revolting developments ...from Rotron



New voltage options for key Rotron fans help simplify design of original equipment for both domestic and overseas markets, provide valuable new flexibility of application.

They can save you money. Time. Trouble. And they can give you a more widely acceptable product.

Low voltage versions of Muffin®, Whisper®, and Sprite® fans help you cope with international electrical codes... give added safety for special applications...avoid need for special wiring...maintain full volume/pressure performance.

Dual voltage fans operate on either 115 or 230 VAC, 50 or 60 Hz...fit switching power supplies without special wiring or transformer taps.

Extended Voltage Range (EVR) Fans meet varying national and international line voltages...have 50% greater tolerance to off-nominal voltages than standard fans.

See why the company that invented the precision airmover business is still inventing it, meeting new, world-wide needs of electronic equipment manufacturers. Get all the facts on Rotron's "Revolting Developments" today.

Rotron has a way with air

® ROTRON INCORPORATED

ROTRON INC.
AN EG&G COMPANY

Woodstock, N.Y. 12498 ☐ 914•679-2401 ☐ TWX 510-247-9033
Garden Grove, Cal. 92641 • 714•898-5649 • Rotron B.V., Oosterhout, Netherlands, Tel: 01620-32920, Telex: NL. 74174

4572

When you need rockers & toggles or more than rockers & toggles...

Come to the people who've always been specialists in having more good ways to solve problems: Dialight. What we've done in indicator lights, illuminated switches, readouts and LEDs, we're doing now in miniature rockers and toggles.

This new Dialight family of switches, which comes in a full range of sizes is, we're proud to point out, all-American made.

When you consider all the configurations of styles, sizes, life and safety ratings, colors and mountings, you'll find there are literally hundreds of thousands of design combinations. Such a number of possibilities can in itself be a problem, except that the new Dialight catalog is specifically designed to prevent confusion and help you quickly and easily find the most advantageous combination of features for your applications.

If you'd like to see what Dialight quality rockers and toggles can do for the looks, durability and economics of your products, contact us today for the Dialight "Meets Your Need" Book. Your free copy will include a list of stocking distributors in the U.S. and Canada.

DIALIGHT
A North American Philips Company

Made in the U.S.A. by DIALIGHT

Dialight meets your needs.

Dialight, 203 Harrison Place, Brooklyn, N.Y. 11237 (212) 497-7600

See us at Electro '79 - Booths 2641, 2643, 2645

Circle 42 on reader service card

Meet the new heavyweight champ of electronic component catalogs.

It weighs in with plenty of power. No lightweight, this newly revised Cambion general catalog. It delivers 272 pages of solid information. No fat – all muscle – packed with over 24,200 items: *Solder terminals, insulated terminals, coil forms, variable and fixed coils, connectors, pins, panel hardware and chassis hardware – just about the broadest line of components anywhere. Plus well over a hundred totally new products.*

You'll find this new champ – Catalog 800 – is conveniently organized for finding what you want fast. It has complete specs, engineering drawings, and applications information to assist you in your decision.

Put the new heavyweight to work for you today. Send for your FREE copy of Cambion catalog 800 – just off the press. You need the champ in your corner. It's a knockout.

CAMBION®
The Right Connection.

FREE...Cambion's new champ of component catalogs!

Cambridge Thermionic Corporation,
445 Concord Ave., Cambridge, MA 02138
☐ Please send me your new 272-page catalog absolutely FREE.

BONUS! ☐ I'd also like a FREE copy of your IC Packaging Hardware Catalog No. 121.

Send catalog(s) to address below:

Name _____ Position _____

Firm Name _____

Street _____

City _____ State _____ Zip _____

Acheson introduces the liquid component.

Electrodag® — for cost-effective control of both EMI and ESD.

To achieve electromagnetic compatibility you must control both EMI and ESD. And that's why Acheson Electrodag coatings should be a precise component *specified* in your initial design. Because Electrodag coatings provide *both* shielding and static bleed.

Highly effective, yet most economical, Acheson Electrodags are easy to apply—by spray, and even easier to cure. They air dry.

Now, compare the broad performance capabilities of Electrodag coatings with the *partial* solution offered by other technologies. Electrodag's ease of application versus the pretreatment, elaborate safety precautions and baking required with other metallic coating systems. All additional costs—for only a partial solution.

Among the wide range of Electrodag coatings you'll find one exactly right for your product. With the right conductivity, the right solvent, the right degree of shielding and ESD control.

Specify Electrodag—Acheson's liquid component for *complete* EMC at much lower cost.

For additional information send us the coupon below. Or call: (313) 984-5581. In Canada, call: (519) 752-5461.

Acheson
high technology coatings

Electrical Products Dept.
Acheson Colloids Co.
Port Huron, MI. 48060

Please send data on Electrodag coatings.

Name _____ Title _____

Company _____

Street Address _____

City _____ State _____ Zip _____

Circle 46 on reader service card

New literature

Test accessories. "1979 Electronic Test Accessories" catalogs dozens of new patch cords, cable assemblies, test socket adapters, test leads, banana plugs, phone jacks, and connecting cords. The 100-page booklet also outlines step-by-step procedures for putting together BNC cable and triaxial cable assemblies and provides tables for metric and temperature conversions. ITT Pomona Electronics, 1500 E. Ninth St., Pomona, Calif. 91766. Circle reader service number 421.

Frequency converters. A 15-page catalog of frequency-to-voltage converters includes application notes covering the converters' operation with standard optoisolated inputs and magnetic pickups. It also discusses their use in simple control applications. Prices for the devices are provided. D-B-Developments, 7709 Kilbourne Rd., Rome, N. Y.13340 [422]

Component subassemblies. A 70-page catalog describes a diverse line of attenuators, directional and hybrid couplers, oscillators, diode switches, tuners, and other devices. Specifications and prices are accompanied by drawings and photos. Engelmann Microwave, Skyline Drive, Montville, N. J. 07045 [424]

Converters and encoders. A 34-page catalog of synchro converters, displays, and encoders contains clear diagrams along with complete specifications and application information. Products not previously listed include synchro-to-digital converters and programmable solid-state limit switches. Computer Conversions Corp., 6 Dunton Ct., East Northport, N. Y. 11731 [426]

Rent, lease, or buy. This instrument catalog goes into the whys and wherefores of renting, leasing, or buying the equipment. It lists and



explains Idiom, a computer service for getting reliable up-to-date information on product availability, price, and delivery. The catalog discusses microprocessor development systems, programmable read-only memory programmers, amplifiers,

SERIES JX5100/5200/5300 FILTERS

. . . U.L. Recognized



GENERAL PURPOSE SUPPRESSORS

- For use in mini-computers, office machines, medical electronics, industrial controls, etc.
- 1 to 30 amperes . . . 125 or 250 VAC.
- Series JX5100 provides RFI control of line-to-ground noise.
- Series JX5200 highly-effective in controlling line-to-line interference.
- Series JX5300 power line RFI filters offer premium performance in low impedance applications.

Write for Engineering Bulletin 8211 to
Technical Literature Service, Sprague Electric Co.,
35 Marshall St., North Adams, Mass. 01247.

4SF-8157R1

THE BROAD-LINE PRODUCER OF ELECTRONIC PARTS

SPRAGUE® THE MARK OF RELIABILITY

TYPE 627P METFILM® 'K' CAPACITORS

THE SMALLER 400 Hz CAPACITOR

- All the advantages of polycarbonate-film dielectric, yet smaller than previously available capacitors designed for 150 V_{RMS} 400 Hz operation.
- Low dissipation factor, high insulation resistance, high stability, minimum capacitance change with temperature, low dielectric absorption.
- Operating temperature range, −55°C to +105°C without voltage derating. Hermetically-sealed with glass-to-metal solder-seal terminals.
- Capacitance values from .18 μF to 12 μF. Standard tolerances, ±10% and ±5%.

Write for Engineering Bulletin 2709 to:
Technical Literature Service, Sprague Electric Co.,
35 Marshall St., North Adams, Mass. 01247.

4SP-7159R1

THE BROAD-LINE PRODUCER OF ELECTRONIC PARTS

SPRAGUE® THE MARK OF RELIABILITY

Circle 60 on reader service card

Circle 63 on reader service card

analyzers, calibrators, component testers, counters, generators, oscilloscopes, and receivers. Write U. S. Instrument Rentals, 2121 S. E. Camino Real, San Mateo, Calif. 94403 [425]

Measurement systems. A line of instruments and systems for the analysis of audio-frequency spectra, distortion, frequency response, and very low-frequency phenomena is covered in a 16-page catalog. The products range from one- and two-channel real-time spectrum analyzers to advanced systems and fast-Fourier-transform analyzers for digital signal processing. Spectral Dynamics, a Scientific-Atlanta subsidiary, P. O. Box 671, San Diego, Calif. 92112 [427]

IC handlers. Five different integrated-circuit handlers are compared and their primary features discussed in a booklet. They include



ambient and elevated temperature dual in-line package types, an expanded-input DIP model, and a single in-line package (SIP) unit. Micro Component Technology Inc., P. O. Box 43013, St. Paul, Minn. 55164 [428]

Power supplies. More than 350 encapsulated ac-dc and dc-dc power-supply descriptions, specifications, prices, and photographs are included in a 20-page catalog. A glossary of terms also is provided. Wall Industries Inc., 175 Middlesex Turnpike, Bedford, Mass. 01730 [429]

Bubble memory. The TI0203 bubble-memory data manual includes an eight-page discussion on the operational fundamentals and advantages of the 92-kilobyte device. Specifications go beyond the bubble package to include integrated circuits it interfaces with. These are function-timing generator SN74LS361, sense amplifier SN75281, function driver SN75380, and coil driver SN75382. Thermistor TSP102 and Schottky-diode bridge VSB53, needed for bubble-memory system design, are also covered. Texas Instruments Inc., Inquiry Answering Service, P. O. Box 225012 MS-308 (Attn: LCC4430), Dallas, Texas 75265 [432]

TYPE 292P PACER® FILM CAPACITORS



PREMIUM CAPACITORS FOR IMPROVED PERFORMANCE

- Epoxy-coated version of the proven sleeved-case PACER® polyester-film, end-cap construction capacitor.
- Flame-retardant coating provides improved humidity resistance, life, and insulation resistance.
- Metal end-caps are welded to foil electrodes, eliminating problems associated with soldered construction. End-caps also block entrance of moisture into ends of the film section and assure excellent lead concentricity.
- Voltage ratings of 80 and 200 WVDC at 85°C. Capacitance values from .001 to .27 μF.

Write for Engineering Bulletin 2066.6 to
Technical Literature Service, Sprague Electric Co.
35 Marshall St., North Adams, Mass. 01247.

4SP-7154R1

THE BROAD-LINE PRODUCER OF ELECTRONIC PARTS

SPRAGUE® THE MARK OF RELIABILITY

Circle 64 on reader service card

TYPE 224M FABMIKA® CAPACITORS

THE ECONOMICAL HIGH-VOLTAGE MICA

- Film-wrapped reconstituted mica capacitors ideal for airborne electronics . . . also well-suited for ground equipment applications including radio transmitters, induction heating equipment, electrostatic precipitators.
- High dielectric strength, small size, high temperature performance, low temperature coefficient of capacitance.
- Capacitance values range from .0018 to 1.0 μF in voltage ratings from 1500 to 7500 WVDC.

Write for Engineering Bulletin 1735 to
Technical Literature Service, Sprague Electric Co.
35 Marshall St., North Adams, Mass. 01247.

4SP-7141R2

THE BROAD-LINE PRODUCER OF ELECTRONIC PARTS

SPRAGUE® THE MARK OF RELIABILITY

Circle 65 on reader service card

SPARTON ELECTRONICS



Sparton Electronics -- Our approach has always been a little different. It's our nature to experiment and innovate -- you see it in everything we do. But it's not just the innovation, it's the testing and research behind it. That's why we place such importance on you -- the engineer -- and that's why we have so much to offer. If you are an experienced EE or ME looking for more challenge and responsibility or maybe you just enjoy a small town atmosphere with easy access to almost any kind of recreation, check out Sparton Electronics.

IMMEDIATE OPENINGS:

Electronic Design Engineers - Responsible for the design of VHF-UHF receivers and transmitters, sonar receivers and transmitters, and various analog and digital circuits. Experience applicable to one or more of these areas required.

Mechanical Design Engineers - Responsible for the mechanical design of low-cost, high-quantity electromechanical and electronic equipment. Experience should include the design of injection moldings and die castings. Responsibilities consist of conceptual design, prototype build and qualification, and production support.

Call, or send resume and salary requirements to: Paul Cook, Employee Relations Manager

sparton electronics

2400 E. Ganson St
Jackson, Michigan 49202
Phone (517) 787-8600

AN EQUAL OPPORTUNITY EMPLOYER M/F

The Optimum System Approach.

It's the concept that we base our engineering on at the Space Information Systems Operation...a dynamic approach to design that allows us to build in specific capabilities and maximize flexibility and cost efficiency. Within the Space Information Systems Operation we have all the necessary resources to build and deliver an optimum system. We can provide requirements analyses, system design and engineering, hardware and software design and development, maufacturing, procurement, logistics support, system maintenance, system operation, maintenance and user documentation, and programmer, operator and analyst training.

We have this same attitude toward our employees, giving them maximum responsibilities across the entire development cycle, in a growth oriented environment. Additionally, we offer highly competitive salaries, outstanding benefits, and an uncongested working community...the optimum employment opportunity. What's more, Texas does not have a state income tax. Our current openings are for experienced Digital and Analog Design engineers and Minicomputer Systems engineers. For more information CALL COLLECT or send a resume to: *John Brown, Space Information Systems Operation, P.O. Box 58487, Houston, Texas 77058, (713) 488-1270.*

We are an equal opportunity employer, m/f.

Ford Aerospace & Communications Corporation

SENIOR SCIENTIST

Position available for Supervisor of U of M Chemistry Dept. Electronics Shop (Sr. Scientist). Stimulating opportunities to interact w/research personnel in applying state-of-the-art electronics to chemical instrumentation. Supervisor responsible for analog & digital design, interfacing w/computers, overseeing maintenance of wide variety of instrumentation. Excellent fringe benefits, incl. 18 days vac. + 9 U holidays. Educ. opportunities. Salary: 22K-29.6K. If you have min. 8 yrs. relevant post-EE degree exp. & study, write: U of M Personnel Dept., 2651 University Ave., St. Paul, MN 55114, or call J.E. Wertz, 612-373-2368.

UNIVERSITY OF MINNESOTA

An Equal Opportunity Employer and Educator

NATIONWIDE ELECTRONICS PLACEMENT

Digital Ckt Dsgn * Hardware Sys Dsgn
Analog Ckt Dsgn * Software Sys Dsgn
Quality Reliability * Test Equipment Mtnce
Entry Level through Management
All Fees are Exclusively Employer Paid
Resume Format Guide
Available Upon Request

E. J. STEPHEN ASSOCIATES
1601 Concord Pike, Suite 86, Wilmington, DE 19803
(302) 654-5350

ENGINEERS
ELECTRONICS & ELECTRICAL

Let our ENGINEERING professionals work with you in strict confidence
Free NATIONWIDE service-140 offices

RPM

RPM-Technical Div (agency)
6 E 45 St NYC 212-682-6150

We put the future in your hands when you become a TI design engineer.

Electronic engineers come to TI to get in on the future of technology. They stay because they find a future for themselves.

You don't start at ground-zero when you join TI, because everyone works on equal footing. Of course, there are differences in rank and responsibility. But everyone is on a first-name basis, right up to the president of the company.

So, if you have a good idea your first week on the job, you speak your mind. And you get heard. Or, if you need to ask your department head some questions, you ask. And you get answers.

There's nothing to slow down your initiative at TI. We've got a move-up environment that lets you prove how good you are fast. Everybody is evaluated regularly. And if you're good, you advance. No matter how new you are.

TI has developed a solid reputation for technological leadership through work in more than 15 major fields of science and engineering. So you'll have an infinite variety of mind-broadening projects to work on. And grow with.

And because TI is headquartered in Dallas, you'll work in one of the most progressive cities in the nation. You'll have a sunny, relaxed lifestyle at a cost way below the national urban average, with no state or city income tax whatsoever.

Right now, we are looking for some free thinking design engineers that have experience designing automatic semiconductor test systems and real time microcomputer-based machine control systems.

- Circuit designer (Analog & Digital)
- S/C test system designer
- Equipment controls designer
- Software specialist
- Test system application specialist
- Computer system designer

Contact Bill Rigsby
Staffing Manager
Dept. D3
Box 225012, M.S. 11
Dallas, Texas 75265

TEXAS INSTRUMENTS
INCORPORATED

An Equal Opportunity Employer

MS/PhD Engineers & Computer Scientists

Bell Laboratories

offers important professional challenges to:

INTEGRATED CIRCUIT DESIGNERS AND TEST ENGINEERS

Openings for both MOS and Bipolar Design in:

- LSI Digital Circuits
- LSI Linear Circuits
- Static and Dynamic Memories
- Microprocessors

Above openings are available at Reading and Allentown, PA; Murray Hill, N.J.

COMPUTER SCIENTISTS & ELECTRICAL ENGINEERS

- Operating Systems
- Compiler Design
- System Architecture
- Computer Networks
- Communications Processing
- Software and Firmware Design
- Distributed Computer Networks
- Analog and Digital Data Systems
- Electronic Switching Systems
- Transmission Systems

Above openings available in: New Jersey, Illinois, Pennsylvania, Georgia, Colorado, Ohio, Indiana, Massachusetts.

OUR PROFESSIONAL COMMUNITY

As the Research and Development Unit of the Bell System, our work spans the widest range of science and technology. At Bell Labs we employ 18,000 people in eight states. We've put together a staff of professionals with a worldwide reputation for excellence. Out of their efforts have come developments such as the information theory, electronic switching and other contributions in computer science and computer controlled real time systems. Such developments have helped make America's communications network the finest in the world.

THE TECHNICAL CHALLENGE

To keep it that way we are advancing the state-of-the-art on a variety of fronts. We are applying advanced electronics and computer techniques to virtually all phases of telecommunications. With such new technologies, we're developing new products and services, as well as sophisticated tools for operating the nationwide network efficiently and economically.

We offer salaries and benefits that rank among the best in industry; the latest and best laboratory equipment; excellent libraries and technical support; strong continuing education programs; and, most important, work that will keep you thinking in creative and productive ways.

If your background matches our needs, and you have a Master's or a PhD degree, we can use your expertise immediately. If you're interested, please write, stating your geographic preference and including resume and transcripts, to: Director of Technical Employment, Center 831-EL, Bell Laboratories, Murray Hill, N.J. 07974.

Bell Laboratories

An equal opportunity employer, m/f.

ENGINEERS

KAISER ELECTRONICS on the SAN FRANCISCO PENINSULA . . .

continues to expand its capability to produce the finest Airborne Display Systems in the world:

Our continuing commitment to the advancement of airborne CRT display systems' technology has created rare career opportunities for additional talented Engineers to blend their skills with ours. We require BSEE, BSME or higher and experience in any of the following areas:

- **MECHANICAL ENGINEERING**
- **ANALOG DESIGN**
- **DIGITAL DESIGN**
- **RELIABILITY ENGINEERING**
- **SOFTWARE ENGINEERING**
- **PROJECT ENGINEERING**
- **ENVIRONMENTAL TEST DESIGN**
- **OPTICS ENGINEERING**
- **SYSTEM ENGINEERING**
- **TEST EQUIPMENT DESIGN**

KAISER ELECTRONICS offers exceptional salary and benefits including Company-paid Medical (+ Major Medical)/Dental/Life/Disability Insurance, Profit Sharing, Retirement Plan, Educational Assistance & Credit Union . . . AND the opportunity to live and work on the beautiful San Francisco Peninsula in the heart of the electronics industry. We will move into brand new ultra modern facilities in San Jose in June 1979.

To arrange interview, call COLLECT to Michelle Gross, 415/494-8411, Ext. 269 or send resume including salary history & requirements to Staffing Manager, KAISER ELECTRONICS, 1681 Page Mill Road, P.O. Box 11275, Plant 3, Palo Alto, CA 94306. U.S. citizenship required. Equal Opportunity Employer M/F/H.

KAISER ELECTRONICS
A KAISER AEROSPACE & ELECTRONICS COMPANY

HARRIS Corporation—PRD Electronics Division

CALL IT "THE HORNET"... CALL IT THE F-18...

Call It An Extra Reason to Come With PRD on Long Island—World Leader in ATE—Now!

It's a magnificent aircraft, with a key role to play for years ahead. To keep Hornets ready to fly, Automatic Test Equipment is essential. For years PRD Electronics has set the pace in this intricate, fascinating field. Our equipment in stations around the globe and at sea has an outstanding performance record—not only for the F-18 but for approximately 80% of all new military aircraft, including F-14, E2C, S3A, CP-140 and A7E.

Be In On the Ground Floor of A New Generation of ATE

The system we are developing right now will be the backbone of PRD's activities in this field for the next five years and beyond... giving you even more opportunity to prosper and advance in your professional specialty. You'll also find the stimulating environment, the superb facilities, and the working atmosphere hard to top. Salaries and benefits are excellent.

PRD Electronics is a division of Harris, a corporation, diversified across the whole spectrum of advanced electronics, that has enjoyed strong, steady growth to over $850-million in sales. **Please send resume, indicating salary record and areas of interest, to: Mr. Tony Pfarrer, Manager, Employment, Harris Corporation, PRD Electronics Division, 6801 Jericho Turnpike, Syosset, New York 11791.**

SOFTWARE

PROJECT ENGINEERS Lead technical teams to define and develop control software and compiler software in support of advanced ATE systems. As such should be fully familiar with the disciplines of software development starting with language standardization, compiler design operating on a real time mini-based operating system with multitasking. BS Engr/Physics/Computer Science, Advanced degree desirable.

SENIOR ENGINEERS Responsible for detail design of programs and subsequent systems integration and validation. Should be capable of working from overall software specifications into systems analysis and subsequent coding conversions. Experience with mini-base systems as well as micro-processor designs and applications. BS Engr. Comp. Sci., Advanced Degree desirable.

ENGINEERS Working from detailed specifications capable of developing FORTRAN IV software modules. Executing under a mini-based real time operating system. Knowledge of Backus-Naur form of language definition a plus. BS Computer Science required.

SENIOR PROGRAMMER/ANALYSTS Using your familiarity with DBMS, be involved in design of application packages (TOTAL DBMS), research and design utilizing the DBMS theory, compiler, and language development and access methods. At least 2 years experience on a major DBMS system and overall experience not less than 4 years is needed, including scientific languages—FORTRAN, assembler, etc. BS in engineering, Math, Physics or CS of equivalent is essential, with higher degree preferred. Other disciplines will be considered if practical DP background is impressive.

PROGRAMMER/ANALYST Data communications person familiar with hardware/software. Capable of implementing network protocols.

HARDWARE DESIGN

PROJECT ENGINEERS • SENIOR ENGINEERS BSEE, 3-10 years experience with strong R&D background, hands-on experience current LSI and microprocessor technology, and leadership capability. Key positions in advanced development department, participation in state-of-the-art design activities.

TEST PROGRAMS

PROJECT ENGINEERS • SENIOR ENGINEERS • ENGINEERS
Responsibilities in these positions will be for engineering design and analysis of digital and analog circuitry, audio through microwave frequencies, with objective of translating circuit operation in computer programs for automatic fault detection and isolation. Background is essential in programming. ATE operation and circuit analysis, with at least 1-3 years experience in circuit design/analysis/development, 3-5 years in design and utilization of ATE and associated software. EE or Physics degree/equivalent is required.

PUBLICATIONS

TECHNICAL WRITERS & PROPOSAL WRITERS Several openings are available requiring 3 to 5 years experience in electronics technical writing. Degree preferred.

PRD INTERVIEWS DURING ELECTRO '79
April 24th to the 26th
Please stop by and talk to our Professional Recruitment Staff
At the
NEW YORK HILTON
6th Ave. Bet. 53rd & 54th St., NYC

HARRIS
COMMUNICATION AND INFORMATION PROCESSING

An Equal Opportunity Employer-Male and Female

IMAGING PHYSICIST

Advancing technology and growth have created an opening in our Tek Labs group for a Research Project Leader specializing in ink jet technology. Ideally we are looking for three to five years experience in the design and development of ink jet technology or related processes, and a PhD (or equivalent experience) in the physical sciences or engineering.

Tektronix develops and markets internationally recognized electronic measurement instruments as well as other related products. Located near Portland, Oregon, we are within a two-hour drive of the Cascade Mountains or Ocean Beaches. Salary is open and benefits include educational support, multiple insurance plans, and profit sharing.

For this opening, please call toll free (800) 547-1164 and ask for Gary Hecht or send your resume to Gary Hecht, Tektronix, Inc., Box 500, L79, Beaverton, Oregon 97077.

An Equal Opportunity Employer M/F/H.

Tektronix®
COMMITTED TO EXCELLENCE

Explore the Undersea World of Electric Boat

TOP JOBS FOR TOP PROFESSIONALS

The world's foremost designer and builder of submarines has career openings now for engineers with experience in these areas:

- **ELECTRONICS AND ELECTRICAL SYSTEMS**
- **FLUID AND MECHANICAL SYSTEMS**
- **COMPONENT PROCUREMENT**
- **COMMAND/CONTROL SYSTEMS**
- **SHIP CONTROL**
- **FIRE CONTROL, SONAR AND COMMUNICATIONS**
- **SOFTWARE DEVELOPMENT AND TEST**
- **STRUCTURAL AND PIPING DESIGN**
- **STRUCTURAL ANALYSIS**
- **ACOUSTICS AND VIBRATION**
- **NAVY OPERATIONS ANALYSIS**

SEND YOUR RESUME TODAY!

If you would like to know more about the exciting professional careers at Electric Boat, our superior compensation and benefit programs, and the opportunities to keep moving ahead in your profession, send your resume to John M Hardink, Professional Placement Manager.

U.S. Citizenship required — an Equal Opportunity Employer M&F

GENERAL DYNAMICS
Electric Boat Division
Groton, CT 06340

ELB152

ELECTRICAL ENGINEERS

Immediate Openings Nationwide positions . All fees and relocation paid by our client companies. Call collect or send resume to K. Schargus or S. Nemser.

Electronic schematics, semi-conductors, PC boards, circuit design, terminal systems, microwave, modems, multiplexers, instrumentation, DTL, TTL, HTL, MOS-logic, peripherals, kinematics, electro/optical, computer systems, acoustics and sonar.

American Personnel Service
240 State Street
New London, Conn. 06320
203-442-0395

FREE
Your dream job.

We hope you're happy in your current position, but there's always that ideal job you'd prefer if you knew about it.

That's why it makes sense to have your resume on file in the Electronics Manpower Register, a computerized data bank containing the qualifications of career-conscious ELECTRONICS readers just like yourself.

You'll benefit from nation-wide exposure to industry firms privileged to search the system, and since the computer never forgets, if you match up with their job requirements you'll be brought together in confidence.

To take advantage of this free service, mail your resume to the address below.

ELECTRONICS MANPOWER REGISTER
Post Office Box 900/New York, N.Y. 10020

ENGINEERS

Career Opportunities have never been better!

A broad spectrum of high-technology job categories at all levels. Immediate positions are available; an extraordinary diversity of product lines to choose from.

Engineering Positions

Available to personnel with the following interests or backgrounds:

- **ELECTRONIC DESIGN**
  Analog, Digital, RF Circuits, Microprocessors
- **SYSTEMS ENGINEERING/ANALYSIS**
  IFF, Communications, ECCM, Microwave Landing Systems
- **RESEARCH AND DEVELOPMENT**
  SAW Devices, Microwave Systems and Antennas
  Systems Analysis and Simulation
- **RELIABILITY/MAINTAINABILITY**
- **FIELD ENGINEERING — DIGITAL**
- **TEST ENGINEERING**
- **QUALITY CONTROL**
- **INDUSTRIAL ENGINEERING**
- **ENGINEERING PROGRAMMERS**

CONSIDER THE CHALLENGE...CONSIDER THE OPPORTUNITY... CONSIDER THE MANY BENEFITS OF WORKING FOR HAZELTINE, A WORLD LEADER IN INFORMATION ELECTRONICS FOR MORE THAN A HALF CENTURY.

Send your resume, indicating your salary requirements to : Employment Manager, Hazeltine Corporation, Greenlawn, New York 11740.

An Equal Opportunity Employer Committed to Affirmative Action—

HAZELTINE

ENGINEERS:

AMECOM Challenges You!

Put Your Ideas Up Against Our Best in EW/ECM Systems.

We work on the leading edge of EW and ECM systems, and our success is measured by the major programs in house with production follow-on to provide systems operating capability through the year 2000. If you are an innovative *Microprocessor* or *EW Software Engineer* we challenge you to work in the development of multifunction distributed microprocessors.

These positions range from Member of the Technical Staff to Senior Scientist with salaries to $35,000.

Find out more about the challenges waiting for you at AMECOM. Please send your resume including salary history, or better yet, call COLLECT to:

Philip T. Foster
(301) 864-5600

AMECOM also has openings for Telecommunications and RF Engineers at our College Park headquarters. We are located in a pleasant Maryland suburb close to the Nation's capital with your choice of city, suburban, waterfront or country living.

Amecom Division
LITTON SYSTEMS, INC.
5115 Calvert Rd., College Park, Md. 20740
An Equal Opportunity Employer M/F/H

FLIGHT TEST DATA SYSTEMS

McDonnell Aircraft Company has immediate openings in Flight Test Data Systems associated with the collection processing and presentation of Flight Test Data.

- **Technical Specialist** – To direct the software development of minicomputer systems. M.S. in computer science with E.E. basis. Familiarity with minicomputer operating systems, assemblers, and source file management, and the ability to deal with system hardware as well as software are required.
- **Senior Programmer and Programmer** – To write or direct the writing of minicomputer applications for Raytheon RDS-500, Data General Nova and H.P. Scientific Minicomputers. Experience with aforementioned systems is desirable but not required. M.S. or B.S. in E.E., Computer Science major. 3-5 years experience in minicomputer programming preferred.

Please send your resume in confidence to:

W. B. Kellenberger
Section Manager,
Professional Employment
(62-2A)
Department E-04
P.O. Box 516
St. Louis, Missouri 63166

MCDONNELL DOUGLAS CORPORATION

ENGINEERS—HARDWARE/SOFTWARE

Due to recent expansion and new business development activities, several clients within the Electronics and Computer industry have presented a number of requirements in the following disciplines:

- ★ **Digital Circuit Design (TTL, Schottky, ECL, CMOS, etc.)**
- ★ **Real-TIme Software Development**
- ★ **Analog Cirucit Design (RF)**
- ★ **Communications/Digital Switching Systems**
- ★ **Control Systems Design**
- ★ **Micro/Mini Computer Applications**

Please write/send your resume or call collect:

RECRUITING SERVICES, INC.

Eastern Division
2367 Auburn Ave.
Cincinnati, Ohio 45219
ATTN: Mr. William Cooke
513/721-3030

Western Division
3822 Campus Dr., Suite 140
Newport Beach, CA 92660
ATTN: Ed Renner
714-549-0853

ENGINEERS

We currently have numerous positions available for engineers throughout the Northeast. If you are in the salary range of 18-35K and have a desire to explore our career opportunities, please call or send resume to Mike Haburay at:
New England Recruiters
900 Chapel Street
New Haven, CT 06510
203/624-0161



The professional who practices commitment and is spurred by the need to excel will find no more compelling environment than that offered by GE Space.

The above locations are involved in substantial advanced state-of-the-art assignments demanding innovative approaches:

COMPUTER IMAGE GENERATION
(Daytona Beach, FLA)

We're now enhancing a simulation system that provides an unlimited range of flight conditions and ground maneuvers as well as new levels of realism.

Hardware Systems Design & Systems Engineers — BS/MS EE, experienced in design of large scale, real time digital systems including computer image generation systems and digital radar land mass simulators.

Digital Design Engineers — BS/MS EE or Computer Science with experience in microprocessor systems and/or special purpose digital control systems. Must be experienced in design of digital control systems such as ship controls and visual/radar simulation systems.

Visual Display Design Engineers — MS EE or Physics, experienced in design of display systems and related equipment involving CRTs, light valve projectors, dome screens, virtual optics and associated electronics.

CALL COLLECT OR WRITE: E. H. Mollinger, P.O. Box 2500, Daytona Beach, FL 32015 (904) 258-2115

LANDSAT D
(Beltsville, MD)

This next step of a long-term Earth Resources Survey Program offers the chance to be at the very heart of advanced work in digital image processing.

Data Systems Engineers — BS/MS EE, experienced in design, implementation and testing of minicomputer-based systems. Translate mission requirements into hardware and software specifications.

Digital Design Engineers — BS/MS EE, experienced in digital logic design with emphasis on high speed (50 MB/S and above) ECL design; and microprocessor application and firmware development.

CALL COLLECT OR WRITE: C. Gayle, 5030 Herzel Place, Beltsville, MD 20705 (301) 937-3500

LARGE-SCALE SYSTEMS
(Arlington, VA)

We're now involved in developing a wide variety of state-of-the-art applications for both commercial and government customers.

Computer Programmers — BS CS/Math, or EE, experienced in scientific applications.

System Analysts — experienced in technical leadership of scientific programming applications.

CALL COLLECT OR WRITE: C. Mudge, 1755 Jefferson Davis Highway, Arlington, VA 22202 (703) 979-6000

COMMAND & CONTROL SYSTEMS
(Sunnyvale, CA)

We're designing and developing C & C Systems for satellites. Work involves command assemblies, data base management and orbital analysis and prediction.

Software Validation and Test Engineers — BS CS or Math, experienced in scientific applications.

Math Analysts — Computer Applications — OR/Math/CS, experienced in operations research and simulation modeling.

Information System Analysis — BS/MS CE, Math, EE, experienced in design of computer programs for application to control of complex systems.

CALL COLLECT OR WRITE: C. Walker, 450 Persian Drive, Sunnyvale, CA 94086 (408) 734-4980

We offer excellent compensation, noted GE benefits, and the opportunity to work with the top people in the field.

GENERAL ELECTRIC

GE takes pride in being an equal opportunity employer, m/f

1

2

3


4


5


6

7

8


9


10


11

12

From Beef on 'weck... to Isaac Stern on violin

If you come to work at Calspan it'll be in a familiar discipline. Our expertise includes Full Scale Flight Research, Systems Analysis, Avionics Research, Environmental Engineering and much more.

But we're located in Western New York which might not be so familiar.

Here's a little orientation on the area:

1. It's the only place in the world where prime roast beef is served on a taste delight called kummelweck.
2. We have exciting NFL Football/NHL Hockey Teams.
3. Teddy Roosevelt became president here, two other presidents were born here and Mark Twain once wrote for one of our major papers.
4. Admiral Perry drove the British off Lake Erie here (and they haven't been back).
5. We have over 15,000 square miles of fresh water for recreation and easy access to the unspoiled Canadian vacationland.
6. And one of the world's Seven Wonders.
7. Our Real Estate Market is favorably priced for home ownership.
8. Excellent skiing is within half an hour (unfortunately the season is only from mid December to mid March).
9. The largest University in the New York State system is here, with schools in Science, Fine Arts, Medicine and (of course) Engineering.
10. Our night life includes Broadway theatre, ballet, cool jazz, hot rock and disco. And, just across the Canadian border are Shaw and Shakespeare Festivals.
11. And in addition to beef on 'weck, we have over a hundred restaurants (many of which Mobil would gladly give stars to).
12. We have one of the finest music halls in the world, a philharmonic orchestra to go with it, and visiting virtuosi like Isaac Stern. (Incidentally, our art gallery has one of the finest collections of moderns in the nation — plus permanent exhibitions of originals by older masters such as Picasso, Renoir and Degas.)

And you won't have time to read Shapiro's "Compressible Flow Theory" on the way home from work because work and home are usually less than a half hour apart.

Now that we've piqued your interest about living in Western New York, check the facing page about working here. You'll be working with some of the finest engineering and scientific talent anywhere and facing some of the nation's foremost technical challenges — the kind that Calspan and its predecessor, Cornell Aeronautical Laboratory, have so successfully addressed for over 32 years.

Calspan CORPORATION AN ARVIN COMPANY | **ADVANCED TECHNOLOGY CENTER**

4455 Genesee Street, Buffalo, New York 14225
An Equal Opportunity Employer

CAREER OPPORTUNITIES WITH CALSPAN CORPORATION

Career opportunities exist in these general areas:

• Electronic Design • Electronics Warfare • Avionics • Tactical Mission Analysis • Programming • Manufacturing Analysis/Quality Assurance • Operations Research • Systems Analysis

ELECTRONIC DESIGN

• Radar/Communications Equipment • Microwave and Signal Processing Circuitry • Display Equipment

ELECTRONICS WARFARE

• Survivability/Vulnerability: Nuclear (EMP, TREES, Hardness Criteria); Non-nuclear • Strategic Systems/Sub-systems Analysis

DEFENSIVE/OFFENSIVE AVIONICS

• System Effectiveness Simulation • ECM/ECCM • Receive/Transmit Requirements • Processing/Control Functions • Expendable Countermeasures • Thrust Definition • Tail Warning Systems • Thrust Simulation • Navigation/Guidance Sub-systems • Weapons Delivery Sub-systems • Terrain Following/Avoidance • Sensitivity Analysis • Performance Requirement Decisions

TACTICAL MISSION ANALYSIS

• Tactical Battlefield Systems • Air to Air/Ground Operations • Red/Blue Gaming

PROGRAMMING

• Simulation: Campaign, Weapons Effectiveness; ECM/ECCM System • CDC-6600 Series: NOS/BE • IBM 360/370: OS/MVT, MVS

MANUFACTURING ANALYSIS/QUALITY ASSURANCE

• Reliability/Maintainability • Military Specifications • Life Cycle Costing • System Safety • Avionics Systems • Mechanical/Aerodynamic Systems

OPERATIONS RESEARCH

• Performance Requirements Decisions • Systems Effectiveness Evaluation • Statistical Analysis

We also have openings for Economists, Materials Engineers, Chemists, Environmental Engineers, Psychologists, Statisticians and many others. Think of us this way. The "SPAN" in CALSPAN labels our wide range of high technology effort—and the spectrum of disciplines involved.

While most of our projects are conducted at our Advanced Technology Center in Buffalo, we also have openings at our Technical Centers in White Sands, N.M.; Dayton, Ohio; Washington, D.C.; San Diego, Los Angeles and Honolulu.

If your background and interests match ours, we'd like to hear from you.

Please send me your resume and you'll receive full consideration—in strict confidence.

E.B. RICKARD

Calspan CORPORATION AN ARVIN COMPANY | **ADVANCED TECHNOLOGY CENTER**

4455 Genesee Street
Buffalo, N.Y. 14225
An Equal Opportunity Employer

BOEING VERTOL TECHNOLOGY KEEPS THINGS MOVING

Our reputation as one of the industry's most innovative and efficient transportation manufacturers is borne out by our recent acquisition of long term projects. In order to meet and surpass our production goals, BOEING VERTOL has immediate openings for engineers at all levels of experience for the following positions:

ENGINEER LIAISON

BS or equivalent and electrical background. Minimum 4 years experience in Engineering Liaison, general design or both. Will prepare documentation of problems; analyze and write corrective action relating to documents or ENGINEERING ORDERS. Provide detail investigation and technical data or analysis on routine problems. Provide engineering assistance in various areas of manufacturing. Provide engineering interpretation for drawings and mock-up engineering guidance in fit and functional problems.

ELECTRICAL ELECTRONIC DESIGN

BS, MS, or equivalent, preferably in Electrical/Avionics design field. Minimum of 3-5 years of experience in aircraft electrical/avionics sub-system or component design. Perform specialized layouts and feasibility studies on highly complex installations and assemblies. Preparation of electrical lode analysis and responsible to review and check production documentation. These positions offer a salary commensurate with experience, an excellent benefits package, and the opportunity to work in one of Philadelphia's very attractive suburbs.

For more information send your resume with salary history to:

C. Murray
BOEING VERTOL
P. O. Box 16858, M/S P50-40
Philadelphia, Pa. 19142

Equal Opportunity Employer M/F

Job-seekers... be the first to know with McGraw-Hill's Advance Job Listings

By having our weekly ADVANCE JOB LISTINGS sent to your home every Monday you can be the first to know about openings both in and out of your field. AJL will enable you to contact anxious recruitment managers BEFORE their ads appear in upcoming issues of 21 McGraw-Hill publications. To receive a free sample copy, plus information about our low subscription rates, fill out and return the coupon below.

ADVANCE JOB LISTINGS / P.O. BOX 900 / NY 10020

PLEASE SEND A SAMPLE COPY
OF ADVANCE JOB LISTINGS TO

NAME ADDRESS

CITY STATE/ZIP

ANALOG ENGINEER

PCS, a leading manufacturer of industrial microcomputers, located near Ann Arbor, is now beginning the design of future product lines which offer state-of-the-art opportunities in advanced microcomputer control systems hardware and software engineering.

We are a full service microcomputer manufacturer representing extensive experience in designing, building and servicing industrial computer products used for machine and process control, water treatments, fluid metering, energy managements, numerical control, and other applications.

We have an immediate opening for an experienced Process Control/Industrial Analog Design Engineer with a BSEE, or MSEE preferred, or equivalent.

To the successful candidate, PCS offers:

- Opportunity for advancement
- Dynamic organization
- Excellent salary and benefits package

Submit your resume in confidence to:

A. Grisham
Office of the President
PCS
750 N. Maple Rd. • Saline, MI 48176
(313) 429-4971



Equal Opportunity Employer M F

CONTROL DESIGN ENGINEERS

D-M-E, the world leader in basic tooling for the injection plastics and die casting industries, has an outstanding opportunity for you.

Our electronic products group needs enthusiastic, creative individuals (degree preferred with 3-5 years experience) who want to work on the development of process control systems used in the plastic injection molding industry.

To be considered, applicants should possess some background in the following areas:

- design of digital and analog circuitry
- software programming (assembly and high level languages with real time programming experience)
- familiarity with micro processors or other computer systems
- "hands-on" experience with design and prototyping
- seasoned troubleshooting capabilities
- experience with machine tools or industrial controls and instrumentation

We offer a very competitive salary (including an incentive program), a strong benefits package and a challenging, professional environment in which to grow. To explore this opportunity further, send your confidential resume and salary history to:

MANAGER OF EMPLOYEE RELATIONS

D-M-E COMPANY
29111 Stephenson Highway
Madison Heights, Michigan 48071
(313) 398-6000

Equal Opportunity Employer M F

Tennessee Eastman Company's Research Laboratories in Kingsport, Tennessee, needs an experienced electronics engineer for a broad range of "hands-on" and developmental engineering. The work is related to the performance, reliability, and improvement of electronic instrumentation used for chemical and physical analyses and for the processing of materials. Duties include servicing scientific instrumentation, designing instrument-computer interfaces, and developing micro computer applications for automation.

Candidates should have a B.S. degree in Electrical Engineering and "hands-on" experience with instrumentation and computers. The ideal candidate will enjoy the challenges of analyzing instrument failures and restoring optimum performance as well as developing electronic systems for automation. Please send resume to: **Mr. M.F. Lowe, P.O. Box 511, Tennessee Eastman Company, Kingsport, TN 37662.**

An Equal Opportunity Employer

The Engineer's Index

Systems Engrs.
Data Processing
Electronics

Salaries to $46,000

Manufacturing Engrs.
ECM Engrs.
Tool Design Engrs.
Air Traffic Contrl. Syst. Engrs.
Rotating Devices Engrs.
Thermometric Engrs.
Digital CKT Design Engrs.
Power Systems Engrs.
Sr. Military Systems Engrs.
Field Engrs.(Electronic Equip.)
Digital Systems Engrs.
Production Control
Programmers/Mgrs.
QA and/or QC Engrs.
Technicians

Companies Assume Our Fees.
Submit Resume, Call or Visit:
THE ENGINEER'S INDEX
133 Federal Street, Suite 701
Boston, Massachusetts 02110
Telephone (617)482-2800

SCHOOLS

World Open University—A Non-Resident Graduate School—Division of Electrical, Electronics & Computer Engineering offers full graduate courses in areas: Applied Mathematics & Physics; Electronics Engineering; Electrical Circuits; Computers & Advanced Programming; Communications Systems; Control Systems; Energy-Power Systems; Nondestructive Testing—leading to M.S., Ph.D., Sc.D., Eng.D., Tech. D.—guided by full professors having a series of original contributions to inter-national learned societies. Request complete information to WOU, PO Box 5505, Orange, CA 92667, USA, enclosing $5 in US, or US $7 outside of US, for airmailing. Self-authored original paper reprints from national learned societies may get proper credits. WOU is racially nondiscriminatory. To mention Electronics in request.

FACULTY POSITIONS VACANT

Physics/Earth Sciences Anticipated Position—Assistant Professor, Full-time, 10 month position, Salary: $14,850, Fall 1979. Responsibilities: Teach Electronics for Physics and Pre-Engineering Students; Computer Electronics including integrated circuits, microprocessors, and interfacing techniques. To develop computer assisted instructions in Physics courses and develop courses in computer hardware to enhance computer science program. Qualifications: Ph.D. strongly preferred, will consider M.S. with appropriate experience or Engineering background. Resumes forwarded to: Dr. James A. DellaValle, Chairperson, Physics/Earth Sciences Dept., Central Conn. State College, New Britain, Connecticut 06050. Please include three(3) letters of recommendation. Deadline for application: June 1, 1979. EOE/Minorities, Females, Handicapped persons encouraged to apply.

Your Career Path Leads To Honeywell-Phoenix

Located in the heart of Arizona, not only will you have the opportunity to join the staff of a company that is the nucleus of tomorrow's computer technology, but you will also have the chance to live in an area that has everything to offer in recreational facilities with perfect weather in which to enjoy them.

Therefore, the people we're looking for must be familiar with today's processes and still be innovative enough to develop tomorrow's systems.

LOGIC ENGINEERS FOR ADVANCED COMPUTER HARDWARE DESIGN

Background should include succeessful performance as Logic Engineer, experience with the conceptual design and implementation of large scale central processors working closely with the systems architecture staff. Requires 5 years experience in the design of large scale processors with architectural exposure. Experience in the design of microprogrammed processors using latest technologies, (TTL, ECL, etc.) is very desirable. BS/MS or equivalent is desired also.

The roads lead in many directions in today's world. If you're ready to take one that will be the most beneficial to you, send your resume with salary requirements in complete confidence to:

HONEYWELL LARGE INFORMATION SYSTEMS
Manager, Recruitment & Placement
P.O. Box 6000
Mail Station Y-18
Phoenix, AZ 85005

Honeywell

A Equal Opportunity Employer M/F/H

Electrical Engineers Solid-State Power Conversion

The Advanced Energy Systems group of Exxon Enterprises, Inc., the new business development arm of Exxon Corporation, is seeking engineers with experience in all aspects of solid-state power conversion. We're a unique and dynamic organization with attractive opportunities and highly visible positions. Presently our needs include:

Senior Project Engineer

You'll be working on the development of advanced power conversion equipment with primary application to variable speed AC motor drives. Responsibilities include overall system design and the coordination of electronic design engineers. The successful candidate will have a working knowledge of variable speed motor controls, multi-variable feedback systems, and power semiconductors. Design experience with analog IC's and digital logic is required. Familiarity with microprocessor controllers a plus. You should have a minimum of 8 years experience and demonstrated a high level of achievement with minimum supervision. BS degree in EE required, MS desirable.

Electronic Design Engineers

We seek creative engineers with extensive hands-on experience developing power transistor switching circuits, dedicated analog and digital feedback control circuits, or microprocessor based real-time controllers. You will be working on the development of state-of-the-art inverter circuits and systems in small project teams, working under minimum supervision. Familiarity with electromagnetic machine fundamentals and computer-aided design is also desirable. BS degree in EE and minimum of 5 years experience is required, MS desirable.

Our new project facilities are located in Florham Park, New Jersey, a pleasant suburban location in proximity to both rural and metropolitan areas. If you're the type of engineer we seek, you'll find that our salary and benefit package is attractive and commensurate with your qualifications.

For consideration, please send us your resume and salary history in assured confidence to: Exxon Enterprises Inc., Department MD-3, P.O. Box 192, Florham Park, New Jersey 07932.

EXXON ENTERPRISES INC.

the accent is on enterprise...

We are an equal opportunity employer, m/f

ENGINEERS

ELECTRONICS ENGINEERS $15,000-$45,000. Choice entry-level to management positions immediately available in Pennsylvania & national locations. Reply in strict confidence to J. G. Weir, President, WEIR PERSONNEL SERVICES, 535 Court St., Reading, PA 19603 (215/376-8486).

DESIGN ENGINEERS to $38K. Central Penna. Design connectors/terminals, micro-processors. Outstanding relocation packages. Prompt confidential reply. MECK ASSOC. PERSONNEL, 1517 Cedar Cliff, Camp Hill, PA 17011 (717/761-4777).

ENGINEERS, $15K-$40K. West Coast & nationwide positions entry level thru mgmt. Design, Inst., Application, Test, etc. Reply in confidence. Call or send resume to GLENN ENGLISH AGENCY, 7840 Mission Center Ct., San Diego, CA 92108 (714/291-9220).

ENGINEERS, $17-$35,000+. We have access to hundreds of positions. Openings in design, applications, systems. Reply in strict confidence to Phil Riddick, RIDDICK ASSOCIATES, 9 Koger Center, Norfolk, VA 23502 (804/461-3994).

BSEE / ELECTRONIC DESIGN ENGINEERS, $15,000-$35,000. Immediate, desirable upstate New York & nationwide. Junior to senior project management. In confidence send resume or call James F. Corby, President, NORMILE PERSONNEL ASSOC., INC., 5 Leroy St., Box 110 Westview Station, Binghamton, NY 13905 (607/723-5377).

ENGINEERS. WHY not LIVE, WORK and PLAY in tax-free New Hampshire? Numerous career opportunities at all levels with salaries form $15,000 to $30,000++. Contact AVAILABILITY PERSONNEL CONSULTANTS, 160 South River Rd., Bedford, NH 03102 (603/669-4440).

all positions fee-paid

npc NATIONAL PERSONNEL CONSULTANTS

ENGINEERS

Take advantage of the most individualized job search in the Engineering field today. You pay absolutely NO FEE for our local or nationwide service. Forward your resume in confidence to:

ENGINEERING SEARCH
3152 Linwood Ave. Cinti. Oh 45208
all replies answered

This is our story...

Hughes Missile Systems Group is one of the largest and most progressive organizations within the Hughes family. We're international, encompassing an enormous spectrum of activities, from electro-optical technology and radars, to lasers, communication and computer science. And we have the people, environment and technological resources to compete in this highly visible market. We're expanding our present programs, and developing new ones, too. Join us in these areas:

Missile Systems Analysts
CAD for LSI
LSI/Design Engineers
Microwave Engineers
Mechanical Design Engineers
Product Engineers
Platform Design Engineers
Circuits Design Engineers
Systems Engineers
Electro-Optical Engineers
Subsystem Engineers
Aerodynamicists
Propulsion Engineers
RF Engineers
Scientific Programmers
Ordnance Engineers
Computerized Test Equipment Engineers
Structural Dynamicists
Electronic Packaging Engineers
Thermal Analysts
Missile System Software Designers
ECCM/IRCM Analysts
Operations Analysts-Weapons Systems
Digital Systems Design Engineers

Now we'd like to hear your story...

Send your resume to: Engineering Employment, Dept. EL, Hughes Missile Systems Group, Fallbrook at Roscoe, Canoga Park, CA 91304.

HUGHES
HUGHES AIRCRAFT COMPANY

U.S. Citizenship Required
Equal Opportunity M/F/HC Employer

We're looking for people to make our advanced technology obsolete.



Storage Technology Corporation is no ordinary company. We've built our reputation on innovation and advanced technology with a commitment to developing better products. We constantly strive to improve our technology. That's one reason why we are the world's largest manufacturer of high density tape data storage products and a major manufacturer of disk subsystems.

If you are an engineer who wants a creative, challenging career, one of the following openings may be just the opportunity you've been looking for.

MANUFACTURING ENGINEERS
INDUSTRIAL ENGINEERS
ELECTRICAL ENGINEERS
MANUFACTURING TEST ENGINEERS
QUALITY ENGINEERS
PRODUCT PERFORMANCE ENGINEERS
QUALITY TEST ENGINEERS
RELIABILITY ENGINEERS
LOGIC DESIGN ENGINEERS
MEMORY DESIGN ENGINEERS
POWER SYSTEMS DESIGN ENGINEERS
BLOCK MULTIPLEX 1/O DESIGN ENGINEERS
MICROCODE DIAGNOSTICS ENGINEERS
ARCHITECTUAL DESIGN (ADVISORY) ENGINEERS
TELECOMMUNICATIONS FIELD ENGINEERING SPECIALISTS
TELECOMMUNICATIONS ENGINEERS
TELECOMMUNICATIONS SOFTWARE ENGINEERS
MECHANICAL DESIGN ENGINEERS (TELECOMMUNICATIONS)
SYSTEMS ENGINEERS/DATA COMMUNICATIONS

Living in the Denver-Boulder area is just the beginning of the outstanding benefits of a career at Storage Technology Corporation. We offer an excellent salary and benefits package that includes health and insurance benefits, stock purchase plan and retirement.

Write or send your resume in complete confidence to the Professional Employment Department at the address listed below. Your correspondence will be answered promptly and courteously and we'll tell you what it's like to be part of our company, and why we can say with pride at STC, people count and technology truly is our middle name.

Dept. E/4-12
MD-13

STC

STORAGE TECHNOLOGY CORPORATION
2270 South 88th Street
Louisville, Colorado 80027
An equal opportunity employer.

EARTH STATION ENGINEERS

B.S. degree and minimum 5 years experience.

FACILITIES & CONSTRUCTION

Experience in design of Power Supply Systems for communications operating facilities. Hands-on experience in design, preparation of specs and estimates for installation of power switchboards, rectifier/battery systems emergency power, UPS, HVAC lite & Pow. distribution and controls for earth stations, microwave & central office. Mechanical and construction experience a plus.

FIELD OPERATIONS

Experience in multiplex wave installation or earth station involving engineering implementation and/or integration of installation of power systems.

These permanent positions carry an excellent salary and liberal benefits package with a major East Coast manufacturer.

For confidential interview, please send a complete resume including past experience and earnings to:

McWILLIAMS
TECHNICAL SERVICE INC.

BOX 146
OLD BRIDGE,
N.J. 08857

PROJECT ENGINEER

Design new research instrumentation.

Here's an opportunity to become deeply involved in developing new advanced equipment at Merck & Co. Inc . . . one of the largest and fastest growing companies in the pharmaceuticals and speciality chemicals industry. Concept-to-design-to-implementation responsibilities require an EE with 2-5 years experience in designing and assembling scientific instruments. Thorough familiarity with sophisticated research instrumentation—theory and methodology is required. Experience in adapting such instrumentation for use in solving specific bioelectronic problems is a plus.

Please send resume and salary history to Mr. Robert O'Connor,

MERCK

MERCK & CO., INC.
P.O. Box 2000, Rahway, NJ 07065.
An equal opportunity employer, m/f.

You'll make the right connections at GTE LENKURT

San Francisco Peninsula

ENGINEERS, DESIGNERS

Join a people-oriented TELECOMMUNICATIONS Company that is not only stable, but also growing rapidly to meet the expanding demand for a variety of communications systems.

Our customers depend on us for excellence in design, manufacture, and service of sophisticated video, voice and data communication systems. We offer a rewarding career, excellent advancement potential, interface with knowledgeable professionals.

DEVELOPMENT ENGINEERS

Electrical Engineers at all levels for projects in subscriber carriers, signalling and VF equipment design, PCM carrier and switching as well as digital microwave radio. Experience in either linear, digital or microprocessor control circuit design.

PCM DEVELOPMENT ENGINEER

As a key member of a product development team, you will have significant responsibilities for system and circuit design of high bit rate PCM equipment. This equipment will utilize State-of the-Art techniques including high speed digital circuits and microprocessors, and will be used with fiber optic and microwave radio systems. Applicants should have a minimum of 4 years digital design experience, preferably including ECL, and a BSEE degree. A background in PCM telecommunications equipment design is desirable.

PCM TERMINALS ENGINEERS

Responsible for circuit design of PCM voice/data channel bank equipment from concept to factory production. Position requires BSEE degree and experience in analog design. Prefer some digital experience or desire to learn digital design. Openings at all skill levels.

MICROPROCESSOR SOFTWARE ENGINEERING

For a Stored Program Digital Telecommunications Switching System. Should have a BS or MS degree in one or more of the following areas: Telephone Call Processing, Structured Software Design, Real Time Systems Design, Systems Diagnostics, PL/M.

TEST EQUIPMENT DESIGN ENGINEER

Position requires experience in digital and analog circuit design, preferably in the area of test equipment. Some programming background/TTL and ECL experience desirable. Ability to convert engineering test requirements into finished production test equipment.

Projects involve the design of test equipment for digital and analog carrier systems, microwave and digital radio systems, as well as microprocessor based products. Work includes design of calculator controlled and microprocessor based automatic and semi-automatic test systems as well as dedicated hardware test sets. BSEE or equivalent experience required. (Reply specifically to Job #JC1)

POWER ELECTRONICS ENGINEER

Position requires a BSEE with 2-5 years experience in power electronics and power processing. Knowledge of solid state components, power electronic circuits and power magnetics is required.

CUSTOM IC DEVELOPMENT ENGINEERS & DESIGNERS

BS/MS or PhD in Electrical Engineering to develop custom integrated circuits in Bipolar and N-Mos technologies. Analog and/or digital design and computer simulation desirable. Willing to train Engineer with solid experience in discrete circuit design. You will have full responsibility for the development of your telecommunication circuit.
Need Electrical Engineer to generate IC modeling test pattern and to develop automatic programs for high speed test systems. Solid background in linear or digital circuit analysis and aptitude in programming required.
Programmer or IC Designer to develop and maintain IC layout design rules and to generate software programs for digitizing and mask design.

EQUIPMENT MECHANICAL/ PC DESIGNERS

Must have knowledge of electromechanical packaging and/or printed circuit board layout for proprietary products. No degree necessary.

GTE Lenkurt offers excellent salaries and a comprehensive benefits package including Paid Vacations and 11 Paid Holidays; Medical/Dental/Life/Disability Insurance; Stock Purchase; Savings & Investment Program; 100% Tuition Refund; Pension Plan; Employee Store and Credit Union, and Relocation Assistance. We are an Equal Opportunity/ Affirmative Action Employer.

Please send your resume or a brief letter outlining your qualifications to DICK NELSON, Employment Manager, GTE Lenkurt, 1105 County Road, San Carlos, CA 94070. (415) 595-3000.

GTE LENKURT

A Part of General Telephone & Electronics Corporation

Product Development & Design Engineers BSME/EE

General Electric specializes in producing high quality appliances for the home. We offer engineers the opportunity to make original contributions . . . while working within a top professional team.

ELECTRONIC PRODUCT DEVELOPMENT ENGINEERS: BSEE

3-5 years product development experience. Background must include applying the latest circuit design and microelectronic design techniques.

DESIGN ENGINEERS:

BSME/EE 3-5 or more years of experience with mass produced products —preferably consumer—and knowledge of heat transfer, strength and cost of materials, UL Standard, design experience should include die casting, thermoplastics, thermostats, heaters, motors, and related devices.

Join us, and we'll provide you with a fully commensurate salary. Famous General Electric benefits, and an environment where individual success is seen and recognized.

Please send resume with salary requirements, identifying area of interest, to Ms. C. C. Ref. 78-D, St. Mark, General Electric Housewares & Audio Business Division, 1285 Boston Ave., Bridgeport, Ct. 06602.

GENERAL ELECTRIC

an equal opportunity employer m/f

If you currently earn between $15,000 - $36,000 we've got a better job for you . . . NOW!

Several new contract awards have created numerous, immediate, long term career opportunities for degreed, technical professionals. We are only interested in top caliber, creative individuals with proven records of success in engineering, management & consulting. Locations are nationwide.

Opportunities include technical/management consulting, project management, R&D, test and systems evaluation. Major contract areas include Communications, Satellites, Weapons, Intelligence, Computer, Energy and Aerospace systems. All positions require U.S. CITIZENSHIP, MINIMUM OF A BS degree (MS/Ph.D. preferred), and a minimum of one year experience in one or more of the specific areas listed below.

- **Minicomputers**
- **Microprocessors**
- **Software development**
- **Signal processing**
- **Digital systems**
- **Command & Control**
- **Radar Systems**
- **Communication Systems**
- **EW/SIGINT/ELINT**
- **Microwave Systems**
- **Electromagnetics**
- **Fire Control Systems**

If you want to join one of the fastest growing firms in the country, call Robert Beach, Vice President, collect at (301) 762-1100 or, if you prefer, send your detailed resume, in confidence. We'll make you an offer you can't refuse.

WALLACH . . . Your career connection

Equal Opportunity Employer Agcy.

WALLACH associates, inc.

1010 Rockville Pike
Box 6016
Rockville, Maryland 20852
(301) 762-1100

Job-seekers... be the first to know with McGraw-Hill's **Advance Job Listings**

By having our weekly ADVANCE JOB LISTINGS sent to your home every Monday you can be the first to know about openings both in and out of your field. AJL will enable you to contact anxious recruitment managers BEFORE their ads appear in upcoming issues of 21 McGraw-Hill publications. To receive a free sample copy, plus information about our low subscription rates, fill out and return the coupon below.

ADVANCE JOB LISTINGS / P.O. BOX 900 / NY 10020

PLEASE SEND A SAMPLE COPY OF ADVANCE JOB LISTINGS TO

NAME ADDRESS

CITY STATE/ZIP

ELECTRONIC ENGINEERS

There are many reasons why you should explore the world of electronics at

ROCKWELL INTERNATIONAL'S AUTONETICS DIVISIONS IN ANAHEIM, CALIF.

But the best reason is simply that our engineers will tell you it's a great place to work.

We are growing in a majority of the future electronic areas. We are located convenient to reasonably priced housing. We are involved in a broad variety of electronic projects, as shown below:

ACOUSTIC SIGNAL PROCESSING ☐ AIRBORNE GUIDANCE SYSTEMS ☐ ☐ AIRBORNE RADARS ☐ ANTISUBMARINE SYSTEMS ☐ ☐ AUTOMATIC TEST EQUIPMENT ☐ BUBBLE-DOMAIN MEMORIES ☐ ☐ ☐ CHARGE-TRANSFER DEVICES ☐ ☐ COMMAND AND CONTROL ☐ ☐ ☐ COMPUTERS ☐ CONTROL SYSTEMS ☐ ☐ ☐ COUNTERMEASURES ☐ ☐ ☐ DEVICE DEVELOPMENT ☐ ☐ DIGITAL ELECTRONICS ☐ ☐ ☐ DISPLAYS ☐ ☐ ELECTROMAGNETIC SYSTEMS ☐ ☐ ☐ ELECTROMECHANICS ☐ ☐ ELECTRONIC INTELLIGENCE ☐ ELECTRO-OPTICS ☐ ELECTRO-SENSOR SYSTEMS ☐ ☐ FIELD ENGINEERING AND LOGISTICS ☐ ☐ ☐ INERTIAL INSTRUMENTS ☐ ☐ ☐ INFRARED INSTRUMENTATION ☐ INTEGRATED MICROCIRCUITRY ☐ LASER TECHNOLOGY ☐ ☐ MAGNETICS MICROCIRCUITRY ☐ ☐ MANUFACTURING ENGINEERING ☐ MARINE ELECTRONICS ☐ ☐ MARINE NAVIGATION ☐ ☐ MATERIALS AND PROCESSES ☐ ☐ ☐ MICROMAGNETIC PHYSICS ☐ ☐ MICROWAVE PHYSICS ☐ MILITARY AVIONICS ☐ MISSILE SYSTEMS ☐ MOS/SOS/LSI ☐ ☐ MULTIPLEXING ☐ ☐ PATTERN RECOGNITION ☐ ☐ RADIATION HARDENING ☐ SEMICONDUCTOR DEVICES ☐ ☐ SHIP DYNAMICS AND CONTROL ☐ ☐ SOFTWARE ☐ ☐ SOLID-STATE PHYSICS ☐ ☐ SONAR SYSTEMS ☐☐ SPACE ELECTRONICS ☐ ☐ SURFACE ACOUSTIC WAVE DEVICES ☐ ☐ ☐ TACTICAL/STRATEGIC ELECTRONICS

If you would like us to explore career opportunities for you, mail us your resume. We'll take it from there. (U.S. citizenship required)

Rockwell International

Equal Opportunity Employer M/F

AUTONETICS DIVISIONS
Rockwell International
3370 Miraloma Avenue
Anaheim, CA 92803
ATTN: E41226 BA39

Marketing Representatives
(Avionics Systems Commercial Airline Sales/ Military Sales

At Lear Siegler, you won't find yourself tangled in a lot of red tape and corporate structure. On the contrary, you'll enjoy freedom - high visibility - and uncommon growth opportunities with a clear path to success. Right now we're looking for innovative individuals to join our rapidly growing group of sales professionals and market our quality avionics product to both commercial airline and military markets.

The successful candidates will be talented, aggressive and thoroughly knowledgeable in either the commercial airline or military markets. If you are seeking diversity, immediate recognition and top rewards, these opportunities are unmatched.

We offer a superior salary/benefits package, plus unlimited potential to grow with a leader. So bring your expertise to us. Forward your resume to:Bill Nottelmann, Manager, Professional and Technical Employment.

LEAR SIEGLER, INC.
INSTRUMENT DIVISION
4141 Eastern Avenue
Grand Rapids, Michigan 49508
We encourage minorities and females to apply.

Your Ultimate Choice

ELECTRONIC DEVELOPMENT PROJECT MANAGER

Salary area $39,000

Major designer/manufacturer of downhole and surface oil field equipment is seeking an engineer to head up initial $350,000 project to develop jumper cables from downhole sensors up the drill string with related trailer mounted spooling systems/mechanisms. If you have five or more years in design/development/fabrication of wireline electrical connectors, and a BSEE or BSME degree, this could be a ground floor opportunity for you. Excellent benefits, savings plan and incentive bonus.

For further information, please contact Jennifer Kellum or Bill Thayer at
(713) 772-7201
All Fees Assumed by Client Companies

M. david lowe
PERSONNEL SERVICES
433 Houston Natural Gas Building
1200 Travis, Houston, TX 77002

INSTRUMENTATION ENGINEERS

B.S.E.E., with 3 to 5 years experience to work in area of proprietary instrumentation development. Seeking expertise in design and analysis of solid state analog and digital circuitry; microprocessor applications; electro-optical devices/systems; and understanding of television technology. Competitive compensation and benefit programs in challenging, professional technical environment w/career growth opportunity. For immediate consideration please send resume with salary history in confidence to:

Anne M. Snell
Electronic Tube Division
GTE Sylvania Inc.
Johnston Street
Seneca Falls, N.Y. 13148
An Equal Opportunity Employer

NOTICE TO EMPLOYERS:

Why we can recommend our readers for the top jobs

The subscribers to this magazine have qualified professionally to receive it. They are also paid subscribers—interested enough in the technological content to have paid a minimum of $15 for a subscription.

As subscribers to ELECTRONICS, our readers have told you several things about themselves. They are ambitious. They are interested in expanding their knowledge in specific areas of the technology. And they are sophisticated in their need for and use of business and technology information.

Our readers are now in senior engineering or engineering management, or they are on the road toward those levels. In either case, they are prime applicants for the top jobs in almost any area.

If you are interested in recruiting the best people in electronics, these pages are open to you for your recruitment advertising.

Our readers are not "job-hoppers". To interest them you will have to combine present reward with challenge and opportunity for future career advancement.

The cost of recruitment advertising on these pages is $65 per advertising inch. For information call or write:

Electronics
Post Office Box 900, New York, NY 10020
Phone 212/997-2556

XEROX OPPORTUNITY UPDATE

Our Electronics Division in El Segundo is growing in so many directions that we've established this convenient way of keeping qualified people posted on openings. All the diversified areas of this advanced organization are focused on the development of innovative new components and subsystems that enable the worldwide growth of every Xerox product line. Career potential is outstanding for those qualified.

If you're interested in one of these positions, send your resume, including salary history, to the person indicated—who is a placement specialist in the area involved, and who will make sure you're reviewed by the right people. If you don't see a position listed for which you are qualified, check future "Updates" for added openings.

MICROELECTRONICS CENTER

Take a closer look at one of the most advanced, best equipped LSI/VLSI facilities in Southern California. Together, we can develop the semiconductor technologies to meet the demanding electronics challenges of tomorrow.

MOS/LSI Circuit Designers

MSEE or Phd (or equivalent) required.

- **to develop LSI/VLSI design technology and new design concepts**
- **to design and simulate advanced MOS circuits**

MOS/VLSI Device Design, Modeling & Process Development

PhD or MSEE (or equivalent) required.

- **to develop new device technology**
- **to model and optimize VLSI device designs**
- **to work on circuit simulation and new design concepts**
- **to carry out process development and simulation**

Also openings for:

- **Plastics Encapsulation Technician**
- **MOS/LSI Layout Designers**
- **MOS/LSI Technology Development Project Technicians and Associate Engineers**
- **Silicon Process Technicians**

For above positions, please send resume to: Thomas Householder, Dept. 329E

POWER SUPPLY TECHNOLOGY

You'll be working at the leading edge of this key technology with highly diversified assignments to meet the power requirements of new kinds of circuits.

Consulting Engineer

We seek an authority in power systems design and development for this position of technical leadership. Must be innovative with broad experience in analog systems and circuits. Familiar with computer modeling techniques. Interested in state-of-the-art developments in power systems and circuits to 2 KW high and low voltage.

Test Specialist

BSEE or equivalent and minimum 5 years experience in the area of product test and evaluation of electronic power systems and circuits. Should be capable of assuming project test responsibility from design qualification through project delivery and follow-on. Work will include writing test plans and reports, design and selection of test equipment, interface with Engineering and internal organizations, and communication with upper management.

PhD—Entry Level

PhD or equivalent—Electronics or Physics. You will work with and be involved in the design of electrochemical and electrophysical devices. Must be able to do imaginative circuit design. Experience in computer modeling, network synthesis and analysis.

Also openings for:

- **Documentation/Standards Engineer**
- **Power Supply Test Technicians**
- **Layout Drafters**

For above positions, please send resume to: Thomas Householder, Dept. 329E

COMPONENTS and PACKAGING

These are key positions calling for proven effectiveness in state-of-the-art components and packaging disciplines.

Semiconductor Component Test Engineer

Senior component test engineer needed to develop programs for VLSI and memory components on Sentry VII, Macrodata and/or Megatest test equipment. Several years ATE experience required and detailed understanding of advanced components characterization needed. BSEE or equivalent.

VLSI Device Engineer

Senior applications and evaluation specialist required to work on VLSI components. Will work on selection of VLSI parts for new systems and characterization of devices. Five to ten years of electronics experience required with recent experience on microprocessors and VLSI peripherals. MS or equivalent.

Senior Circuit Designer

Familiar with commercial logic families, but with special emphasis in analog circuit design and interface circuits (and devices) for controlling electromechanical devices. The person should be well versed in power-ground distributions and noise problems. The job has project responsibilities and leadership experience is useful. You must be well organized and goal oriented and familiar with industrial environment for large volume products. MSEE or equivalent preferred; 5 years experience minimum.

For above positions, please send resume to: Ruth Cattelle, Dept. 329E

DIGITAL SYSTEMS/ LSI DESIGN

Assignments involve the development of advanced digital electronics subsystems for a range of products.

LSI Systems/Logic

Experienced in systems/logic design and system integration of LSI based controllers. Responsibilities to include controller design using LSI devices, interface definition and development for controller I/O options required by the product definition. Degree in Electrical Engineering and Computer Sciences (or equivalent) is preferable.

Test Pattern Specialist

MS in Computer Science or EE (or equivalent) with 6 or more years experience in the field of test and diagnostics involving design verification, design for testability, digital printed circuit board test program development utilizing automated test techniques. Background in logic design highly desirable. Knowledge of commercial printed circuit board test equipment.

Microprocessor Architecture

8 years experience in design and development of computer related equipment. The candidate should have a strong technical background and leadership capability in developing complex digital systems products from a conceptual level through to production. Background should include computer architecture logic design, firmware design and good knowledge of software systems. Advanced degree in Computer Science or Electrical Engineering (or equivalent).

Also openings for:

- **Development Technicians**
- **Test Technicians**

For above positions, please send resume to: Thomas Householder, Dept. 329E

An affirmative action employer (male/female)

XEROX

701 S. Aviation Blvd., El Segundo, California 90245

Communications Systems Professionals ...

At ORI Our Growth Pays Off — for YOU!

ORI is an employee-owned company offering uncommon career opportunities for your professional and personal growth. We're searching for technical professionals as well as individuals capable of generating new business in the area of Communications Systems Engineering.

Functioning as a diversified technical consulting organization in space vehicles and communications systems (military and commercial), transportation systems, and information sciences, our rapid growth offers you involvement in any of these areas of your professional interest:

ANALYSIS, DESIGN OR SPECIFICATION of military and commercial communications systems and subsystems. Your work will include the analysis of coding and signalling performance and comparison of user requirements with system specifications.

COMMUNICATIONS SYSTEMS APPLICATIONS using networking theory on military C^3 studies. You'll be working on advanced system concepts for LANDMOBILE applications.

REAL TIME COMPUTING SYSTEMS and distributed processing for spacecraft operations control centers. You'll use your knowledge of large computing systems and systems architecture to direct a technical staff and solve customer problems both real time and off-line.

MISSION PLANNING of spacecraft operations. You need a knowledge of spacecraft systems, spacecraft control center operations, and mission planning of operations.

SPACECRAFT SYSTEMS ANALYSIS. Responsibilities require a knowledge in three of the following areas: communications, on-board computers, attitude control, propulsion, ground systems support, ground testing, spacecraft operations.

SYSTEMS RELIABILITY and quality assurance related to satellites and/or space shuttles.

At ORI, you will find compensation matched to your talents and responsibilities. We are an Employee Stock Ownership Trust — ESOT — offering an excellent benefits package including relocation expenses.

Let us tell you more about ORI and the professional challenges we have to offer. Please send your resume including salary history in confidence to: **Director of Employment, ORI, Inc., 1400 Spring Street, Silver Spring, MD 20910.** An Affirmative Action/Equal Opportunity Employer

ORI

ELECTRONIC ENGINEERS

State-Of-The-Art Digital Systems Applications

This is your chance to help form a new, vital Development/Design Team for GENERAL ELECTRIC's Power Systems Management Department located in Philadelphia. You will work on the latest concepts in digital systems for control and protection of power generation and transmission equipment, to maintain and expand GE's worldwide leadership in the Electrical Power field, through the 80's and into the 90's.

To qualify, you must possess a BSEE, (ME a plus) and a proven thorough knowledge of analog and digital circuitry. Background in systems design, programming and applied mathematics is highly desirable. Power Systems experience a plus.

GENERAL ELECTRIC offers an excellent salary structure, geared to your experience and potential, a full range of corporate benefits, exciting technical challenges and high visibility opportunities for advancement. Interested applicants should send their resume, in confidence or call COLLECT: PROFESSIONAL RELATIONS OFFICE, Dept. 10B04

GENERAL ELECTRIC

Switchgear Division
6901 Elmwood Ave., Dept. D
Philadelphia, Pa. 19142
215-726-3582

An Equal Opportunity Employer M/F

POSITIONS VACANT

Electrical Engineer/Instructor— Qualifications: Electrical Engineer, Bachelor's Degree, Master's Degree preferred. Three years of applied experience in the application, design or maintenance of electrical power. Control equipment, motor controls, or similar current consuming devices is required. Solid state and logic systems as they apply to electrical controls are desirable. Salary range: depending upon training and experience. To apply send resume, transcripts and salary requirements in confidence to: Edward R. Maclosky, Springfield Technical Community College, One Armory Square, Springfield, MA 01105. An Equal Opportunity Employer.

Electronic Engineer, Sun Belt, excellent opportunity, salary & benefits. Murkett Assoc., Box 527, Montgomery, AL 36101.

POSITIONS VACANT

Electrical Engineer/Instructor— Qualifications: Electrical Engineer, Bachelor's Degree, Master's Degree preferred. Three years of applied experience in the design or application of engineering principles on electronic equipment or equal. Solid state and computer background as they relate to the communications field is desirable. Salary range: depending upon training and experience. To apply send resume, transcripts and salary requirements in confidence to: Edward R. Maclosky, Springfield Technical Community College, One Armory Square, Springfield, MA 01105. An Equal Opportunity Employer.

EMPLOYMENT SERVICES

Electronic engineering growth positions with clients located nationally. Our service is enhanced by the fact that I am an EE with 20 years in industry and over 10 years in placing professionals on an employer fee paid basis. Send your resume to Joe Torcassi, Director, J. Anthony & Associates, PO Drawer AD, Lynchburg, OH 45142. 513/364-2305.

FACULTY POSITIONS VACANT

Junior Faculty And Research Positions In Semiconductor Device Technology. Applications are solicited for junior faculty and research staff positions in the Department of Electrical Engineering and Computer Science at M.I.T. in the general area of semiconductor-device and integrated-circuit technology. Faculty duties include teaching at the graduate and undergraduate levels, research, and supervision of theses. Research staff duties are primarily in research, with opportunities for teaching or thesis supervision when appropriate. As part of an expanding M.I.T. program in semiconductor device and integrated circuit technology, a new faculty or staff member will be expected to become a collaborative member of one or more existing research programs, and to develop original research programs in such areas as semiconductor device fabrication; characterization and modeling of submicrometer structures and devices; physical device limitations; design technologies for device and integrated circuits; or novel devices, integrated circuits, and integrated systems. Prior industrial experience will be helpful. Applicants should have an interest in working with groups at M.I.T. that seek to develop integrated circuits and systems for a wide range of disciplines, such as computer technology, signal and image processing, biomedical engineering and communications, and should be interested in developing working relationships with industrial organizations. Applicants should provide a resume and the names and addresses of three or more references. Applications should be sent to: Professor Stephen D. Senturia, Room 13-3010, Massachusetts Institute of Technology, Cambridge, Mass. 02139. Indicate citizenship and, if not a US citizen, describe your visa status. M.I.T. is an equal opportunity/affirmative action employer.

Applicants are invited for a faculty position in The Electrical Engineering Dept. at South Dakota State University, Brookings, SD to begin Aug. 16, 1979. Rank and salary are commensurate with background and ability. Acceptance of applications until position is filled. Contact Dr. V. Ellerbruch Head, or call 605-688-4526. An equal opportunity/affirmative action employer.

Anticipated faculty position in Bachelor of Technology Program Fall 1979. Teach courses in areas of digital electronics micro-processors, and computer interfacing. Ph.D. required for assistant professor appointment; industrial and teaching experience desired. Send resumes to: Dr. George DePuy, Director of Technology Programs, School of General Studies, SUNY-Binghamton, Binghamton, New York 13901. An equal opportunity employer.

3 Tenured Track Faculty positions available in the Department of Electronics and Computer Technology. Fall 1979. Send resumes to: Richard Lyons, Department of Electronics and Computer Technology, School of Technology, Indiana State University, Terre Haute, IN 47809. Applications received after June 1, 1979 cannot be assured consideration. Equal Opportunity/Affirmative Action Employer.

Get A View From The Top. Join Wang.

If you're a computer professional who wants to be on top, open your eyes to Wang. And set your sights on a company that's far above the rest.

At Wang, you'll see things happen. You'll also be encouraged to express your own ideas, and get the organizational support you need to have them realized.

Come make things happen, with the #2 company in the area of small business computers. Join Wang. We'll take your career to new heights.

In our Diagnostics Development group:

Supervisor - Manufacturing Test Development

As part of the department that has corporate responsibilities for diagnostic development, you will be instrumental in building a group that has diagnostic test development responsibilities for our manufacturing facilities. You will analyze manufacturing's software testing requirements and design and implement appropriate solutions. You will also interface with manufacturing engineering groups to develop hardware/software test systems.

This is a ground-floor opportunity in a rapidly growing department and a dynamic company. The ideal candidate will have a thorough understanding of computer architecture, 5 or more years of direct diagnostic experience, project and/or supervisory experience, and an understanding of manufacturing processes and testing requirements. A BSEE or equivalent experience and excellent written and verbal communications skills are required.

Diagnostic Programmer Analyst

Wang's growing diagnostic Software Development Department is looking for highly motivated individuals with a minimum of 3 years hardware/software experience to fill intermediate through senior level openings to design, code, debug, evaluate and release diagnostic programs for hardware systems and subsystems, ranging from a microprocessor-based subsystem to a medium sized general purpose virtual memory system.

The applicant should be versed in assembly language programming, knowledgeable of diagnostic testing strategy for subsystems, including CPUs, memories, and peripheral devices, acquainted with hardware/software compromises to obtain levels of hardware visibility that will ensure a product that we can test, diagnose and maintain.

We offer excellent salaries and benefits. Please send your resume, including salary history, to Merle Halverson, Wang Laboratories, Inc., One Industrial Avenue, Lowell, MA 01851.

We are an affirmative action employer

Computers

WANG

Word Processing

CAREER OPPORTUNITIES AT GOULD

Join The Search For The Technology of Tomorrow



Gould Ocean Systems is the world's leading pioneer in the field of oceanic technology, and is continually striving to stay #1. Significant growth coupled with forecasted expansion and a solid commitment to new product development has created exciting professional opportunities for imaginative engineering talent with Gould's fast-moving Ocean Systems Division. Immediate openings are now available for professionals with U.S. Citizenship in the following areas:

ELECTRICAL ENGINEER

To qualify, candidates must have at least 5 years experience in the design of test circuits for use in complex digital and analogy systems. Primary responsibility will involve the design and development of test circuits and specifications for performance testing. A BS in Electrical Engineering is required.

SENIOR ENGINEER

Prior work experience should include at least 7-10 years of power control engineering demonstrating strong leadership abilities as well as solid experience in Fortran IV and other computer aided analysis. Areas of responsibilities will include analyzing power systems used for undersea propulsion, generating system requirements and overseeing design integration and evaluation processes. A BSEE, MS or PhD in Electrical Engineering is required.

ELECTRICAL ENGINEER

For consideration, candidate must have experience in either hardware design or test program development, plus a background in automatic test equipment. Primary responsibilities will involve the analysis and synthesis of circuits for prototype development, the development of software and hardware test programs, as well as the generation of engineering documentation. A BS in Electrical Engineering is required.

ELECTRICAL ENGINEER

For consideration, candidates must have 0-3 years electronic experience in either hardware design or test program development, plus a solid background in automatic test equipment. Primary responsibilities will involve the analysis and synthesis of circuits for prototype development and the development of software and hardware test programs, as well as providing liaison with other departments to expedite realization of hardware and software products. A BS in Electrical Engineering is required.

If you're up to the large scale challenges and the exhilarating growth pace that have established Gould as an integrated technology company . . .you'll be rewarded with an exceptional salary, a full benefits package and highly-visible advancement opportunities. Submit letter or resume in confidence with earnings history and salary requirements to:

GOULD OCEAN SYSTEMS DIVISION
18901 Euclid Avenue
Cleveland, Ohio 44117

GOULD
Ocean Systems Division

An Equal Opportunity Employer, M/F/H.

FLIGHT TEST ENGINEERS

McDonnell Aircraft Company has immediate openings for engineers experienced in Flight Test data systems applications. Career opportunities include development, operation and support of Flight Test data systems on F-15, F-18, AV-8 and advanced aircraft projects in one or more of the following applications.

- **Mini-Computer Technology**
- **Computer Programming**
- **Flight Test Data Assessment**
- **System Design**
- **Airborne Instrumentation**
- **Installation Design — Electrical & Mechanical**
- **Electronic Circuit Design**
- **Micro-Processor Technology**

Please send your resume in confidence to:

W. B. Kellenberger, Section Manager
Professional Employment
Department E-04 • P. O. Box 516
St. Louis, Missouri 63166

MCDONNELL DOUGLAS CORPORATION

An Equal Opportunity Employer

ELECTRONIC ENGINEERS

ARE YOU WORTH A 17.5% INCREASE IN SALARY?

That is the average increase in salary for the technical professionals who we placed in new positions in 1978. Some received more! Most relocated to a more desirable geographic location or stayed in the same city in which they lived. Most importantly, all of them went into a position of either increased technical challenge, more responsibility, or better opportunity for career growth.

RCI is a technical search firm with an outstanding reputation representing a broad base of nationwide clients serving the Electronics Industry. If you are interested in advancing your career, call us or send your resume or a brief hand written description of your background including present salary and geographic preferences, in confidence to:

Tony Ray, Search Director-Room J
REGIONAL CONSULTANTS, INC.

213 West Ninth Street
Cincinnati, Ohio 45202
513/579-1513

The "Local National" Technical Search Firm
(representing EEO clients only)

Plug Into Our Electronics Opportunities.

When you plug into General Dynamics' Electronics Division, you get more than a challenging job, good pay and fringe benefits for you and your family. You get San Diego, one of the country's most beautiful cities. With miles of clean beaches, year-around golfing, sailing and tennis, and an average temperature of 68°, San Diego is one of America's most desired living areas.

As a Design Engineer you will find a broad selection of opportunities in a variety of technical areas: Automatic test equipment for the F-16. High-resolution, helicopter-borne radar systems. Satellite-based, world-wide navigational aids. Plus other projects for military and space programs.

If your career needs challenge, stimulation or just a change of scenery, contact us immediately.

AUTOMATIC TEST EQUIPMENT

Automatic test equipment design including analog measurement, analog stimulus and digital subsystems. Requires BSEE/MSEE and 2-5 years design experience. Analog design background preferred.

DISPLAY SYSTEMS DESIGN

Responsible for the configuration of display systems to meet customer requirements. Requires experience in areas of customer interface and proposal preparation, as well as display logic design or display analog circuit design.

ELECTROMAGNETIC COMPATIBILITY ENGINEER

Provide EMC support in development of electronic equipment and tracking navigation systems. Minimum of 2 years experience in system EMC analysis, EMC design, and equipment/system EMC testing is required; EMP and/or TEMPEST experience is desirable. Minimum BS degree with background in electromagnetic bonding.

RF DESIGN

Engineering specialist to head new airborne radar design group. Requires strong technical/proposal experience and analytical background. MSEE required.

Principal engineer for radar section requires technical/proposal and "hands on" experience. MSEE required.

HARDWARE/ SOFTWARE DEVELOPMENT

Work in field of digital image processing and display. Background in systems analysis such as error budget calculation helpful. Requires microprocessor familiarity and BSEE, Physics or Math degree.

DIGITAL DESIGN

Responsible for the design and special computer and transponder interfaces, display logic and microprocessor multifunction transponders used in sophisticated tracking systems.

All positions require at least a technical BS degree and 2-5 years experience.

Excellent benefit program includes life insurance and medical program, dental and prescription drug plans, savings/stock investment and retirement plans.

Qualified applicants, submit your resume, including recent salary history, to: GENERAL DYNAMICS Electronics Division, Drawer KE, P.O. Box 81127, San Diego, CA 92138.

GENERAL DYNAMICS
Electronics Division

An Equal Opportunity Employer M/F/H

Hardware/Firmware, Software, Product and Application Engineers

OUR GROWTH CAN BE YOUR GROWTH

At Allen-Bradley Systems Division, we apply "state-of-the-art" computer and microprocessor technology to industrial systems. This Division has grown four-fold since 1975 and is still growing...strong! As an important part of an international corporation, employing over 13,000 people, we emphasize stability and a sophisticated professional environment, which promotes your growth and ours.

Opportunities exist for engineering professionals in the following areas.

HARDWARE/FIRMWARE DESIGN ENGINEERS

We have a variety of challenging assignments for engineers able to take responsibility to design and develop programmable controllers and numerical control systems employing digital and analog design techniques. Your background should include a B.S.E.E., scientific or advanced degree with 2 + years of related experience. Involvement with computer and microprocessor design is highly desirable.

SOFTWARE ENGINEERS

Since receiving your engineering or scientific degree (E.E., Comp. Eng., Comp. Science, Math, or Physics), you have two or more years experience establishing a strong engineering orientation and an assembly language background, preferably with minicomputers. You are ready to assume project responsibility for software specifications, including design, test and documentation. Projects can include numerical control, communications and machine dependent software.

PRODUCT/MARKETING ENGINEERS

Draw upon your experience to identify market possibilities for new products. Duties include participation in research, exploration, identification and recommendations for product opportunities based on anticipated industry-wide requirements. Background should include B.S.E.E. with 2 or more years experience and understanding of microprocessor technology and applications.

APPLICATIONS ENGINEERS

Use your engineering skills to define customer control system requirements, determine design strategy and prepare proposals. Also implement control systems, participate in customer/sales training programs and be involved in new product planning and development. You presently have an engineering degree or equivalent experience in industrial control systems. Exposure to microprocessors and/or programming helpful.

If your experience and career goals match these professionally rewarding positions, you owe it to yourself to contact us. The total compensation plan is good, including generous benefits and the career growth possibilities are exceptional! Act NOW! Send your resume and salary history/requirements to:

William Henderson, Salaried Employment Supervisor

A-B QUALITY

ALLEN-BRADLEY CO.

Systems Division Dept. EM

747 Alpha Drive • Highland Heights, Ohio 44143

Quality in the best tradition.

An Equal Opportunity Employer M/F

McGraw-Hill

Would you hire an engineer who couldn't understand this magazine?

Of course not. ELECTRONICS is the technical publication for technical people. If they can't understand it, they can't receive it. That's why, when you're looking for qualified engineers, you should consider our Classified Section.

For only $46.00 per inch your recruitment advertising will reach 46,000 pre-screened engineers—that's just $1 per thousand!—as they're reading to combat job obsolescence, while they're thinking about their future and bettering themselves.

There's no charge for typesetting and free layout service is provided.

For more information call or write:

ELECTRONICS

Post Office Box 900
New York, N.Y. 10020
Phone: 212/997-2556

Electronics advertisers

•	Accel	8E
	Acheson Colloids	307
■	Ad-Vance Magnetics, Inc.	197
■	AEG-Telefunken	93
	Aeroflex Laboratories, Inc.	89
	Ailtech	172-173
■	Alco Electronic Products (Sub. of Augat)	258
■	American Optical Scientific Instruments Div.	242
■	Amp Inc.	18-19
	Analog Devices	155-157
	Ansley (Thomas & Betts)	257
■	AP Products	248
	A.P.E.M.	53
	AQ Systems Inc.	262
‡	Aromat	195
	Assembly & Test Equipment Corp.	299
	Associated Environmental Systems	244
■	Augat, Inc.	303
■	Bel Fuse Inc.	6
	Belden Corporation	296
	The Bendix Corporation Electrical Comp. Div.	269
■•	B & K Precision Dynascan Corporation	193
	Berg Electronics	174-175
	Berquist Company	26
	Bokers, Inc.	295
■	Bourns Inc.	2nd cover
■	Bud Industries	190,192,194
•■	Burr Brown Research Corporation	186
■	Cambridge Thermionic Corp.	306
	CEC Division/Bell & Howell Co.	190
	Centralab Electronics Division	184-185
	Ceramaseal, Inc.	232
■	Cherry Electrical Products	32
•	Citel	53
	C & K Components	276
■	Clairex Electronics	4th cover
	Computer Automation, Inc. Industrial Prod. Div.	225
	Computique	8
	Conrac Corporation	301
■	Continental Specialties	47,232A&B
■	Corning Glass Works Fotoform Dept.	227
	Cramer	235
■	Creative Micro-Systems	61
■	Custom Electronics	240
•■	Custom Electronics	185
	Data General Corporation	128,129,212,213
	Data Instruments	338
	Data I/O Corporation	234
■	Data Precision	262
■	Data Translation	49
■	Delevan Division, American Precision Industries	198
■	Dialight	305
	Digital Equipment Corporation OEM.11 Group	176-177
•	Dionex Gas Plasma Systems	195
	Dit-MCO	277
	D. M. E.	338
•	Ducati Elettrotecnica Microfarad	66
	Dyna/Pert Division USM Corporation	231
‡	EAO Switch Corporation	263
	EG & G Wakefield	232
	Eastman Kodak Co. Graphic Markets Division	171
	Ebauches SA	266
•	EIP a Division of Danalab	206,207
	Elco Corporation	245
‡	E-Mask	69
	Electromask Inc.	59
	Electromatic Component Ltd.	3rd cover
	Electro Scientific Industries	247
	Electronic Navigation Industries	6
	Elorg Electronorgtechica	196
	EM Laboratories Inc.	259
■	EMI Technology	237
	EMM SESCO	271
■	Exact Electronics	199
	Fairchild Test Systems	98-99
•	FEME S.p.A.	4E
■	John Fluke Mfg Co.	12,13,91,158,159
•	Fujitsu Limited	55
	Gates Energy Products, Inc.	139
	General Electric Company Semiconductor Dept.	178
‡	General Electric Instrument Rental Division	200
	General Electric Lexan Industrial	275
■	General Instrument Microelectronics	264
	GE Plastics	219
■	Genrad Inc.	204,205
	Gould-Biomation	15,35
	Gould, Inc./Instrument Systems Div./T & M	28,29
	Grayhill, Inc.	96
‡	Guildline Instruments, Inc.	191
■	Hamlin	216
‡	Harris Semiconductor	38
‡	Heath Co. Schlumberger	43
	Hewlett-Packard	1,2,7
■	Hipotronics Inc.	298
	Houston Instrument	104
	I Corporation	238
	Intel-Microcomputer Components	20,21,73
	Interface Technology	295
	International Crystal Mfg. Co.	220
	International Electronic Research Corp.	222
	Intersil	10-11
•	Italtel/SIT	1E
‡■	ITT Cannon Electric	208
	ITT Schadow Inc	252
	ITT North Microsystems Division	253
■	Jensen Tools & Alloys	256
■	Keithley Instruments	132
■	Kepco Inc.	5
‡	Kollmorgen Corporation Multiwire Division	206-207
‡	Kontron Electronic Inc.	53-55
	Lambda Electronics Corporation	281-294
‡	Landis & Gyr (Sodeco)	71
‡	Leasametric	66
	Litronix	22-23
	Logitek Inc.	92
	Lomac Corporation	279
	Lumonics Research	258
■	Magnecraft Electric Company	302
	Mallory Capacitor Co	239

	Matrox Electronic Systems	278
*	Matsushita Electric Trading Company	38
	MDB Systems	218
■	Micro Component Technology	203
	Micro Networks Corporation	43
■	Microswitch Division of Honeywell	243
	3M Co. Electronics Division	153
	Mitel Semiconductor Inc.	52
	Mostek Corporation	27
■	Motorola Semiconductor Products	45
	Computer Professional Book Club	249
‡	Murata Corporation of America	193
*	Murata Mfg. Co. Ltd.	193-200
	National Plastics Exposition	250
■	National Semiconductor Corp.	36-37
	NCR	280
‡	NEC Microcomputers	78-79
*	NEOHM SPA	191
	Nicolet Instrument Corporation	101
■	Non-Linear Systems, Inc.	240
	Northern Ireland Ind. Devel. Organization	261
	Oak Industries Inc.	84
	Ohio Scientific	273
■	O.K. Machine & Tool Co.	251
	Ovenaire (Division of Walter Kidde & Co.)	295
‡	Panasonic Industrial Div.	65
■	Pearson Electronics	267
■	Permag Corporation	224
*	Philips ELA	71
*	Philips Elcoma Market Promotion	71,78,79
■	Philips TMI	2E
‡	Philips TMI	145
	Plastics Engineering Company	188
	Powercube Corporation (Div of Unitrode)	87
■	Power-One Inc	9
	Practical Automation	260
	Precision Filters	254-255
■	Projects Unlimited	246
	Pro-Log	25
	Radcliffe Auction Co.	6
	PTK Corporation	224
	RCA Solid State	62
‡	Rental Electronics	186-187
	Eduard Rhein Stiftung	51
	Robinson Nugent Inc.	189
	Rockwell Microelectronic Device Division	236
	Rogers Corporation	221
*	Rohde & Schwarz	65,69
‡	Rohm Corporation	211
	Rotron Inc (Commercial Product Division)	304
	Savoy Electronics	8
	Semikron	197
*	Sfernice	4E
‡	Sharp Corporation	210
*	Siemens AG Munich	60
	Sigma Instruments Inc.	54
	Signetics Corporation	183
	Snap-on Tools Corporation	300
	Solid State Scientific	228
	Spectrol Electronics	83
	Sprague Electric	308-309
■	Sprague-Goodman Electronics	192
■	Stackpole Carbon Co.	217
	Standex Electronics	264
	Statek Corporation	181
	Storage Technology Corporation	233
	Synertek	118-119
	Tau-Tron Inc.	230
	Techsnabexport	300
	Tecknit (Technical Wire)	241
■	Tecnetics	16
	Tektronix MDA	102-103
■	Tektronix	95,223
*	Tektronix Datatek NV	1E
	Teledyne Philbrick	260
■	Teledyne Relays	17
‡	Telequipment	265,267
	Telesensory Systems Inc.	256
*	Tencor Instruments	211
	Teradyne Inc.	80,146,147
	Texas Instrument Components	229
	Textool Products Inc.	14
	Thomson Sescosem	6E,7E
	E.H. Titchener & Company	268
	TRW Cinch Connectors	30-31
■	TRW Electric Components	76-77
	Ulrich Planfiling Equipment Corporation	338
■	United Systems Corporation	202
‡	US Instrument Rentals	140
	Verbatim Corporation	214,215
	Viking Industries	201
	Voltek Corporation	226
■	Wavetek Indiana	117
	Weckesser Company Inc.	246
	White Industrial Products S. S.	194
	Wilhelm Westermann	8
	Wiltron	160-161
	Xerox Corporation	97
*	Zeltron	208
‡■	Carl Zeiss Inc	151
	Zilog	74-75

Classified and employment advertising

F. J. Eberle, Manager 212-997-2557

Allen-Bradley Co.	334
American Personnel	314
Bell Labs	312
Boeing Vertol	319
Calspan	318,319
D-M-E Company	320
Engineers Index, The	320
Engineering Search	322
Exxon Enterprises, Inc	322
Ford Aerospace Corp.	310
General Dynamics	314,333
General Electric	317,326,330
Gould Ocean Systems Div.	332
GTE Lenkurt	325
GTE Sylvania Inc.	328
Harris (PRI)	313
Hazeltine	315
Honeywell	321
Hughes Aircraft	323
Kaiser Electronics	312
Lear Siegler	328
Litton Systems, Inc.	316
Lowe, M. David	328
McDonnell Douglas	316,332
McWilliams Tech Service Inc.	324
Merck & Co.	324
Minnesota University of	310
National Personnel Consultants	322
New England Recruiters	316
ORI, Inc.	330
PCS	320
Recruiting Services, Inc.	316
Regional Consultants, Inc.	332
RPM	310
Rockwell International	327
Spartan Elec. Corp.	310
Stephen, E.J. Assoc.	310
Storage Technology Corp.	324
Tektronix	314
Tennessee Eastman Co.	320
Texas Instruments Inc.	311
Wallach Assoc., Inc.	326
Wang Labs Inc.	331
Xerox	329

■ For more information of complete product line see advertisement in the latest Electronics Buyers Guide

* Advertisers in Electronics International

‡ Advertisers in Electronics domestic edition

Advertising Sales Staff

Advertising sales manager: Paul W. Reiss
1221 Avenue of the Americas, New York, N.Y. 10020
[212] 997-4371
Atlanta, Ga. 30309: Michael Charlton
100 Colony Square, 1175 Peachtree St., N.E.
[404] 892-2868
Boston, Mass. 02116: Frank Mitchell
607 Boylston St.
[617] 262-1160
Chicago, Ill. 60611
645 North Michigan Avenue
Jack Anderson [312] 751-3739
Robert M. Denmead [312] 751-3738
Cleveland, Ohio 44113: William J. Boyle
[716] 586-5040
Costa Mesa, Calif. 92626: Robert E. Boedicker
3001 Red Hill Ave. Bldg. #4 Suite 242
[714] 557-6292
Dallas, Texas 75201: John J. Uphues
2001 Bryant Tower, Suite 1070
[214] 742-1747
Denver, Colo. 80203: Harry B. Doyle, Jr.
123 Speer Blvd. #400
[303] 837-1010
Detroit, Michigan 48202: Jack Anderson
1400 Fisher Bldg.
[313] 873-7410
Fort Lauderdale, Fla. 33306: Michael Charlton
3000 N.E. 30th Place
[305] 563-9111
Houston, Texas 77002: John J. Uphues
601 Jefferson Street, Dresser Tower
[713] 659-8381
Los Angeles, Calif. 90010: Robert J. Rielly
Robert E. Boedicker, 3200 Wilshire Blvd., South Tower
[213] 487-1160
Minneapolis, Minn. 55435: Robert M. Denmead
4015 W. 65th St.
[312] 751-3738
New York, N.Y. 10020
1221 Avenue of the Americas
John Gallie [212] 997-3616
Matthew T. Reseska [212] 997-3617
Philadelphia, Pa. 19102: Matthew T. Reseska
Three Parkway
[212] 997-3617
Pittsburgh, Pa. 15222: Matthew T. Reseska
4 Gateway Center
[212] 997-3617
Rochester, N.Y. 14534: William J. Boyle
Power Mill Office Park, 1163 Pittsford-Victor Rd.,
Pittsford, N.Y. 14534
[716] 248-5620
San Francisco, Calif. 94111: Don Farris
Dean Genge, 425 Battery Street,
[415] 362-4600
Paris: Patrick Mouillard
17 Rue-Georges Bizet, 75116 Paris, France
Tel: 720-73-01
United Kingdom & Scandinavia: Robert Ghey
34 Dover Street, London W1
Tel: 01-493-1451
Scandinavia: Andrew Karnig and Assoc.
Kungsholmsgatan 10
112 27 Stockholm, Sweden
Tel: 08 51 68 70 Telex: 179 51
Milan: Ferruccio Silvera
1 via Baracchini, Italy
Phone 86-90-656
Brussels:
23 Chaussee de Wavre
Brussels 1040, Belgium
Tel: 13-73-95
Frankfurt/Main: Fritz Krusebecker
Liebigstrasse 27c, Germany
Phone 72 01 81
Tokyo: Akio Saijo, McGraw-Hill
Publications Overseas Corporation,
Kasumigaseki Building 2-5, 3-chome,
Kasumigaseki, Chiyoda-Ku, Tokyo, Japan
[581] 9811

Business Department

Thomas M. Egan
Production Director
[212] 997-3140
Carol Gallagher
Production Manager International
[212] 997-2045
Betty Preis
Production Manager Domestic
[212] 997-2908
Thomas Kazich
Production Manager Related Products
[212] 997-2044
Marieanne Meissner, Production Assistant
(212) 997-2843
Frances Vallone
Reader Service Manager
[212] 997-6057

Electronics Buyers' Guide

H.T. Howland, General Manager
[212] 997-6642
Regina Hera, Directory Manager
[212] 997-2544
Thomas Kazich, Production Manager
[212] 997-2044
Marieanne Meissner, Production Assistant
[212] 997-2843
Frances Vallone, Reader Service Manager
[212] 997-6057

Classified and Employment Advertising

Frank Eberle, Manager
[212] 997-2557

REPRINTS AVAILABLE FROM *ELECTRONICS*

No. of copies wanted

Books

____ R-903 Personal Computing: Hardware and Software Basics—Electronics Book Series 266 pp $11.95

____ R-819 McGraw-Hill's Compilation of Data Communications Standards—89 standards from 5 organizations 1133 pp $165.00

____ R-803 New Product Trends in Electronics 1977—Electronics Book Series 333 pp $14.95

____ R-732 Memory Design: Microcomputers to Mainframes—Electronics Book Series 180 pp $12.95

____ R-726 Design Techniques for Electronics Engineers: 293 time-saving ideas in 48 chapters—Electronics Book Series 370 pp $15.95

____ R-711 Circuits for Electronics Engineers: 306 circuits in 51 functional groups—Electronics Book Series 396 pp $15.95

____ R-31D Designer's Casebook Number 1 106 pp $5.50

____ R-704 Thermal Design in Electronics 52 pp $5.00

____ R-701 Applying Microprocessors—Electronics Book Series 191 pp $9.95

____ R-608 Basics of Data Communications—Electronics Book Series 303 pp $12.95

____ R-602 Large Scale Integration—Electronics Book Series 208 pp $9.95

____ R-520 Microprocessors—Electronics Book Series 154 pp $8.95

____ R-011 Computer-aided Design 135 pp $4.00

Articles

____ R-901 1979 world market survey and forecast 24 pp $4.00

____ R-829 Special report: New networks tie down distributed processing concepts 16 pp $3.00

____ R-827 Tackling the very large-scale problems of VLSI: a special report 15 pp $3.00

____ R-825 1978 technology update special issue $4.00

____ R-821 Codecs answer the call 18 pp $4.00

____ R-817 How bit-slice families compare 18 pp $3.00

____ R-816 Packaging technology responds to the demand for higher densities 9 pp $3.00

____ R-815 Higher power ratings extend V-MOS FETs' dominion 8 pp $2.00

____ R-813 Data-link control chips: bringing order to data protocols 10 pp $3.00

____ R-811 Multiplexing liquid-crystal displays 10 pp $3.00

____ R-809 New methods and materials stir up printed wiring 10 pp $3.00

____ R-807 Here come the big, new 64-K ROMs 14 pp $3.00

____ R-805 Why and how users test microprocessors 8 pp $3.00

____ R-801 World market report 1978 24 pp $4.00

____ R-734 Microcomputer families expand 20 pp $4.00

____ R-730 Special report—Automotive electronics gets the green light 10 pp $3.00

Charts

____ R-823 Communications satellites $3.00

____ R-516 Electronic symbols $2.00

____ R-213 Electromagnetic spectrum (updated 1976) $3.00

____ R-326 Optical spectrum (6-page report and chart) $3.00

Payment must accompany your order

Make check or money order payable to Electronics Reprints. All orders are shipped prepaid by parcel post. Allow two to three weeks for delivery. For additional information call (609) 448-1700 ext. 5494.

USE THIS PAGE AS YOUR ORDER FORM

Cost of orders $_____
Plus 10% handling charge $_____
TOTAL AMOUNT ENCLOSED $_____

Mail your order to:
Janice Austin
ELECTRONICS REPRINTS
P.O. Box 669
Hightstown, N.J. 08520

SEND REPRINTS TO

Name_____

Company_____ Dept._____

Street_____

City_____ State_____ Zip_____

Mini Planfile.
Take the fat out of filing flat.

Save Money. Save Space.
It would take 12 expensive flat drawers to match the capacity of a single Ulrich Mini Planfile. And, you'll find Ulrich Planfiles take less of your work area, are extremely well built, protect drawings, mylar and prints better, allow you to locate material faster and cost you LESS than flat files of comparable capacity.
Don't risk loss or damage of valuable materials.
Now there's a better way to file.
Write for our free brochure.



2120 Fourth Avenue
Lakewood,
New York 14750

Telephone
716/763-1815

ULRICH
PLANFILING
EQUIPMENT
CORPORATION

Circle 67 on reader service card

1969-1979

Since ten years D.M.E.
A French manufacturer of high-resolution OPTICAL Shaft encoders
OTHER PRODUCTS : linear and circular gratings, incremental and absolute encoded scales, gratings for electronic microscopes, optical spider-lines and micromiters evaporation masks.



Le Dessin en Matériel Electronique
D M E
Tracé au coordinatographe

DME
75011 PARIS FRANCE
8, rue de la Forge Royale
Tel 370.87.96
telex 250 303 PUBLIC

Circle 68 on reader service card

New Pressure Transducer Catalog

If you measure pressure, you'll want this condensed catalog. It describes a wide range of pressure transducers and related instruments. All units are built to exacting quality standards for reliable, trouble-free operation in the toughest environments. And at prices you have to like. Send for catalog of stock models.

DATA INSTRUMENTS INC.
Successor to TYCO Instrument Division

4 Hartwell Place, Lexington, Mass. 02173
617-861-7450 TWX 710-326-0672

Circle 70 on reader service card

We are looking for reps all over the world.

Innovation almost beyond imagination!

S-SYSTEM BY ELECTROMATIC OF DENMARK. Also includes Infra-red Photoelectric Relays. We offer you 22 different types of transmitters and receivers ranging from 1'' to 300'.
Let us show you!

Distributor Inquiries Invited.

ELECTROMATIC COMPONENTS LTD.
742 West Algonquin Road
Arlington Heights, Illinois 60005
(312) 364-0100 TWX 910-222-3452

Outside the United States, contact your Local ELECTROMATIC Sales Office located in 43 countries World Wide

Circle Number 902 on Reader Service Card

P-SERIES PHOTOCELLS from Clairex

Low in cost....high in performance



We produce 24 standard types of P-series photocells, but if you can't use a standard type, we'll design a custom cell to meet your specific requirements. This is only one reason we have been known as the "light touch in automation and control" for 25 years.

Give us your "light" problems. We'll develop the solution. Call (914) 664-6602 or write Clairex®, 560 South Third Avenue, Mount Vernon, N.Y. 10550.

CLAIREX ELECTRONICS

A Division of Clairex Corporation

Circle 901 on reader service card